
INSTALLATION RESTORATION PROGRAM

SITE INVESTIGATION REPORT APPENDICES A through J

FINAL

151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

NOVEMBER 1997



19980311 014

DTIC QUALITY INSPECTED 4

HAZARDOUS WASTE REMEDIAL ACTIONS PROGRAM
Environmental Restoration and Waste Management Programs
Oak Ridge, Tennessee 37831-7606
managed by MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the U.S. DEPARTMENT OF ENERGY under contract DE-AC05-84OR21400

FINAL
INSTALLATION RESTORATION PROGRAM
SITE INVESTIGATION REPORT
APPENDICES A through J

151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Submitted to:
AIR NATIONAL GUARD READINESS CENTER
ANDREWS AIR FORCE BASE

Submitted by:
HAZARDOUS WASTE REMEDIAL ACTIONS PROGRAM
MARTIN MARIETTA ENERGY SYSTEMS, INC.
Oak Ridge, Tennessee 37831

for the:
U.S. DEPARTMENT OF ENERGY

Prepared by:
PARSONS ENGINEERING SCIENCE, INC.
SALT LAKE CITY, UTAH 84040

NOVEMBER 1997

VOLUME II
LIST OF APPENDICES


APPENDIX A	Water Rights Search
APPENDIX B	Field Change Requests
APPENDIX C	Monitoring Well Development and Sampling Forms
APPENDIX D	Chain-of-Custody Forms
APPENDIX E	Data Validation Summary
APPENDIX F	Piezometer Construction Details and Logs
APPENDIX G	Monitoring Well Construction Details and Logs and Soil Boring Logs
APPENDIX H	Target Compounds and Detection Limits
APPENDIX I	Hydrogeological Methods and Data
APPENDIX J	Soil Gas Correlation

APPENDIX A
WATER RIGHTS SEARCH

UTAH DIVISION OF WATER RIGHTS
WATER RIGHT POINT OF DIVERSION PLOT CREATED WED, APR 28, 1993, 2:17 PM
PLOT SHOWS LOCATION OF 32 POINTS OF DIVERSION

PLOT OF AN AREA WITH A RADIUS OF 5280 FEET FROM A POINT
N 1990 FEET, W 2200 FEET OF THE SE CORNER,
SECTION 28 TOWNSHIP 1N RANGE 1W SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 2000 FEET



UTAH DIVISION OF WATER RIGHTS
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	QUANTITY CFS	AND/OR AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER DEPTH YEAR LOG NORTH EAST	POINT OF DIVERSION DESCRIPTION CNR SEC TWN RNG B&M	U N	A P	P T	S U P R	E E U G T E
0 59 163		.0150	.00	3 654 1940 Y N 735 E 140	SW 21 1N 1W SL	X			X	
		WATER USE(S): IRRIGATION DOMESTIC		City and County Building		PRIORITY DATE: 08/24/1940		Salt Lake City		UT
1 59 3650		.0150	.00	2 300 N N 25 E 900	S4 21 1N 1W SL	X			X	
		WATER USE(S): STOCKWATERING		136 South 7th East		PRIORITY DATE: / /1891		Salt Lake City		UT 84107
1 59 3564		.0150	.00	2 300 N N 25 E 900	S4 21 1N 1W SL	X			X	
		WATER USE(S): STOCKWATERING		3819 South 20th East		PRIORITY DATE: / /1891		Salt Lake City		UT
1 59 2715		.0220	.00	2 300 1891 N N 25 E 900	S4 21 1N 1W SL	X			X	
		WATER USE(S): STOCKWATERING		962 South 5th East		PRIORITY DATE: / /1891		Salt Lake City		UT 84105
2 59 3561		.0330	.00	N N 15 E 1260	S4 21 1N 1W SL	X			X	
		WATER USE(S): STOCKWATERING		3819 South 20th East		PRIORITY DATE: / /1891		Salt Lake City		UT
2 59 3563		.0220	.00	N N 15 E 1260	S4 21 1N 1W SL	X			X	
		WATER USE(S): STOCKWATERING		962 South 5th East		PRIORITY DATE: / /1891		Salt Lake City		UT
2 59 3562		.0220	.00	N N 15 E 1260	S4 21 1N 1W SL	X			X	
		WATER USE(S): STOCKWATERING		136 South 7th East		PRIORITY DATE: / /1891		Salt Lake City		UT
3 59 2579		.0110	.00	2 168 1916 N S 1140 W 185	N4 27 1N 1W SL	X			X	
		WATER USE(S): IRRIGATION DOMESTIC		Ponderosa One Limited Partnership (c/o J 4110 North Scottsdale Road, Suite 320		PRIORITY DATE: 00/00/1916		Scottsdale		AZ 85251
4 59 5386		.1000	.00	48 10 - 25 S 1700 E 2000	NW 27 1N 1W SL	X			X	
		WATER USE(S): IRRIGATION		1133 North Satori Circle		PRIORITY DATE: 03/03/1993		Salt Lake City		UT 84116
5 59 691		.0067	.00	2 400 1949 Y S 1780 W 875	N4 27 1N 1W SL	X			X	
		WATER USE(S): STOCKWATERING OTHER		1595 West 4th North		PRIORITY DATE: 11/09/1948		Salt Lake City		UT 84116
5 59 1396		.0150	.00	2 100 - 300 N N 756 E 1765	W4 27 1N 1W SL	X			X	
		WATER USE(S): IRRIGATION DOMESTIC STOCKWATERING		351 South State		PRIORITY DATE: 10/09/1958		Salt Lake City		UT
6 59 4467		.0150	.00	4 475 S 2066 E 144	N4 27 1N 1W SL	X			X	
		WATER USE(S): DOMESTIC		Box 10		PRIORITY DATE: 05/02/1977		Modena,		UT 84753
7 59 2751		.0090	.00	2 197 1900 Y N 430 E 1910	W4 27 1N 1W SL	X			X	
		WATER USE(S): IRRIGATION DOMESTIC STOCKWATERING		1099 North 1800 West		PRIORITY DATE: / /1900		Salt Lake City		UT 84116
8 59 4906		.1181	.00	2 275 N 10 E 770	W4 27 1N 1W SL	X			X	
		WATER USE(S): IRRIGATION		1004 Morton drive		PRIORITY DATE: 08/20/1982		Salt Lake City		UT 84116
9 59 4906		.1181	.00	2 460 S 50 E 900	W4 27 1N 1W SL	X			X	
		WATER USE(S): IRRIGATION		1004 Morton drive		PRIORITY DATE: 08/20/1982		Salt Lake City		UT 84116
A 59 316		.0150	.00	2 225 1942 Y S 200 E 730	W4 27 1N 1W SL	X			X	
		WATER USE(S): DOMESTIC STOCKWATERING		1896 West 8th North		PRIORITY DATE: 06/09/1942		Salt Lake City		UT

UTAH DIVISION OF WATER RIGHTS
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	QUANTITY CFS	AND/OR AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER DEPTH	YEAR LOG	NORTH	EAST	POINT OF DIVERSION DESCRIPTION CNR SEC TWN RNG B&M	U N	A P	T P	S E	U P	R T	E E
B 59 1395		.0150	.00	2 228	1979 Y S	320	E 1805	W4 27 1N 1W SL PRIORITY DATE: 10/09/1958 Salt Lake City						X	X
C 59 3432		.0150	.00	2 275	1890 N S	560	E 1430	W4 27 1N 1W SL PRIORITY DATE: 00/00/1890 Salt Lake City						X	X
D 59 3433		.0150	.00	2 275	1890 N S	560	E 1590	W4 27 1N 1W SL PRIORITY DATE: 00/00/1890 Salt Lake City						X	X
E 59 1220		.0330	.00	2 249	1955 Y N	1630	E 1737	SW 27 1N 1W SL PRIORITY DATE: 06/23/1955 Salt Lake City						X	X
F 59 2372		.0130	.00	2 180	1910 N N	1470	E 2390	SW 27 1N 1W SL PRIORITY DATE: 00/00/1910 Salt Lake City						X	X
G 59 2722		.0220	.00	2 200	1896 N N	1340	E 1345	SW 27 1N 1W SL PRIORITY DATE: / /1896 Salt Lake City						X	X
H 59 2145		.0450	.00	4 200	1904 N N	1280	E 735	SW 27 1N 1W SL PRIORITY DATE: / /1904 Salt Lake City						X	X
I 59 3686		.0110	.00			N N	900	E 55	S4 27 1N 1W SL PRIORITY DATE: / /1935 Salt Lake City					X	X
I 59 2539		.0160	.00	2 234	1927 N N	750	E 70	S4 27 1N 1W SL PRIORITY DATE: 09/00/1927 Salt Lake City						X	X
J 59 2898		.0110	.00	2 150	1920 N N	167	W 131	S4 27 1N 1W SL PRIORITY DATE: / /1920 Salt Lake City						X	X
K 59 1355		.0150	.00	2 231	1958 Y N	150	W 825	S4 27 1N 1W SL PRIORITY DATE: 01/29/1958 Salt Lake City						X	X
L 59 3112		.0220	.00	2 260	1922 N N	50	E 1120	SW 27 1N 1W SL PRIORITY DATE: / /1922 Salt Lake City						X	X
M 59 3111		.0180	.00	2 420	1923 N S	265	E 30	NW 34 1N 1W SL PRIORITY DATE: / /1923 Salt Lake City						X	X
N 59 1346		.0150	.00	2 126	1957 Y N	655	E 295	W4 34 1N 1W SL PRIORITY DATE: 09/25/1957 Salt Lake City						X	X
O 59 1494		.0150	.00	2 350	1946 Y N	620	E 360	W4 34 1N 1W SL PRIORITY DATE: 03/22/1946 Salt Lake City						X	X
O 59 1337		.0150	.00	2 183	1957 Y N	614	E 385	W4 34 1N 1W SL PRIORITY DATE: 08/07/1957 Salt Lake City						X	X

30-50
mv-1-16-50
vgh-1-30-50
1-23-50
t)27bdb-1

PAGE _____
(Leave Blank)

Report No. 7448
Filed Dec. 27, 1949
Rec. By MV
Ret'd

Report of Well and Tunnel Driller STATE OF UTAH

(Separate report shall be filed for each well or tunnel)

GENERAL INFORMATION:

Report of well or tunnel driller is hereby made and filed with the State Engineer, in compliance with Sec. 100-3-22, Utah Code Annotated, 1943. (This report shall be filed with the State Engineer within 30 days after the completion or abandonment of well or tunnel. Failure to file such report constitutes a misdemeanor.)

1. Name and address of person, ~~company or corporation owning or~~ drilling well or ~~tunnel~~
(Strike words not needed)
J. E. Kilpack 63 East 2700 South, Salt Lake City, Utah
2. Name and address of owner of well or ~~tunnel~~ Adelbert Elkins,
(Strike Words not needed)
1740 West 17th North, S.L. City
3. Source of supply is in _____ Salt Lake _____ County;
_____ drainage area; _____ artesian basin
(Leave blank) (Leave blank)
4. The number of approved application to appropriate water is 20327
5. Location of well or ~~mouth of tunnel~~ is situated at a point
S. 1715 ft. & W. 710 ft. from N¹ Cor. Sec. 27, T1N, R1W, SIM.
(Describe by rectangular co-ordinates or by one course and distance with reference to U. S. Government Survey
Corner - Copy description from well owner's approved application)
6. Date on which work on well or ~~tunnel~~ was begun July 20, 1949
(Strike words not needed)
7. Date on which work on well or ~~tunnel~~ was completed or abandoned August 1, 1949
(Strike words not needed)
8. Maximum quantity of water measured as flowing, ~~pumped~~ on completion of
(Strike words not needed)
well or ~~tunnel~~ in sec. ft. _____; or in gals. per minute 10 Date Aug. 1, 1949

DETAIL OF COLLECTING WORKS:

9. WELL: It is drilled, ~~deep~~ flowing or ~~pump~~ well. Temperature of water _____ °F.
(Strike words not needed)
 - (a) Total depth of well is 400 ft. below ground surface.
 - (b) If flowing well, give water pressure (hydrostatic head) above ground surface 6 ft.
 - (c) If pump well, give depth from ground surface to water surface before pumping _____
_____ ; during pumping _____
 - (d) Size and kind of casing 2" new Black pipe
(If only partially cased, give details)
 - (e) Depth to water-bearing stratum 385 ft.
(If more than one stratum, give depth to each)
 - (f) If casing is perforated, give depth from ground surface to perforations 380 ft.
 - (g) Log of well 0 to 12 clay; 12 to 30 sand; 30 to 159 clay; 150 to 169 sand;
169 to 175 clay; 175 to 259 clay streaks sand; 259 to 277
hard sand; 277 to 295 clay; 295 to 297 hard pan; 297 to 345 clay; 345 to
382 hard pan; 382 to 385 clay; 386 to 400 sand;
 - (h) Well was equipped with cap, valve, or valve to control flow.
(Strike words not needed)

(Over)

PHOTOSTATED

3-7-59 108
Exam. & Recorded 12-24-58 E.C.T.
Exam. for filing 12-29-58 E.C.T.
Final Copy checked
Indexed 1-31-59
Well No. 16-1-125, -40

PAGE

(Leave Blank)

Report No. 13731
Filed
Rec. By. 1-12-59
Ret'd

Report of Well and Tunnel Driller

STATE OF UTAH

(Separate report shall be filed for each well or tunnel)


GENERAL INFORMATION: 12-5-16, 51

Report of well or tunnel driller is hereby made and filed with the State Engineer, in accordance with the laws of Utah. (This report shall be filed with the State Engineer within 30 days after the completion or abandonment of well or tunnel. Failure to file such reports constitutes a misdemeanor.)

- Name and address of person, company or corporation boring or drilling well or tunnel.
(Strike words not needed)
H. J. Harkness 1250 So. 3rd St. Salt Lake City
- Name and address of owner of well or tunnel.
(Strike words not needed)
Madison D. Piche 457 North 1850 West S.L.C. 1100
- Source of supply is in..... County;
..... drainage area;..... artesian basin
(Leave blank) (Leave blank)
- The number of approved application to appropriate water is..... 20283
- Location of well or mouth of tunnel is situated at a point.....
1808.55 ft. from NW 1/4 Cor. Sec. 27, T.1N. R.1W. S.14
307.5 ft. from NW 1/4 Cor. Sec. 27, T.1N. R.1W. S.14
(Describe by rectangular co-ordinates or by one course and distance with reference to U. S. Government Survey Corner - Copy description from well owner's approved application)
- Date on which work on well or tunnel was begun..... Oct 13, 1958
(Strike words not needed)
- Date on which work on well or tunnel was completed or abandoned.....
(Strike words not needed)
- Maximum quantity of water measured as flowing, pumped or..... on completion of
(Strike words not needed)
well or tunnel in sec. ft.....; or in gals. per minute..... 35 Date.....

DETAIL OF COLLECTING WORKS:

- WELL: It is drilled, dug, flowing or pump well. Temperature of water.....°F.
(Strike words not needed)
(a) Total depth of well is..... 164 ft. below ground surface.
(b) If flowing well, give water pressure (hydrostatic head) above ground surface..... 6 ft.
(c) If pump well, give depth from ground surface to water surface before pumping.....
.....; during pumping.....
(d) Size and kind of casing..... 2" (If only partially cased, give details)
(e) Depth to water-bearing stratum..... (If more than one stratum, give depth to each)
(f) If casing is perforated, give depth from ground surface to perforations.....
(g) Log of well.....
0-11 clay 11-18 gravel 18-60 clay
60-65 sand 65-85 clay 85-135 clay & sand
135-150 sand 150-164 gravel
pumped 135 to P.M.
(h) Well was equipped with app, valve, or..... to control flow.
(Strike words not needed)



(Over)

2142 N.T.F.
certified N.T.F. 9-1-42
ling 9.0.44 1-8-43
signed 1-11-42
Assigned
1-11-42
ell
4

PAGE _____
(Leave Blank)

Report No. 2682
Filed Aug. 27, 1942
Rec. By: Counter P.C.
Ret'd _____

Report of Well and Tunnel Driller STATE OF UTAH

(Separate report shall be filed for each well or tunnel)

GENERAL INFORMATION:

Report of well or tunnel driller is hereby made and filed with the State Engineer, in accordance with Sections 100-3-22, Revised Statutes of Utah 1933, as amended by Session Laws of 1935. (This report shall be filed with the State Engineer within 30 days after the completion or abandonment of well or tunnel. Failure to file such report constitutes a misdemeanor.)

1. Name and address of person, ~~company or corporation boring~~ or drilling well ~~or tunnel~~
(Strike words not needed)
Sylvester Kilpack, 4353 So. State St., Murray, Utah
2. Name and address of owner of well ~~or tunnel~~ Geneve
(Strike words not needed) 483 7th Ave.,
Keith Holbrook, 19th West, 8th North Salt Lake City, Utah
3. Source if supply is in _____ Salt Lake _____ County;
_____ drainage area; _____ artesian basin
(Leave blank) (Leave blank)
4. The number of approved application to appropriate water is A-14818
5. Location of well ~~or mouth of tunnel~~ is situated at a point S. 253 ft. and E. 71.7 ft.
from the W 1/4 Cor. of Sec. 27, T. 1 N., R. 1 W., SLB&M.
- (Describe by course and distance with reference to U. S. Government Survey Corner — Copy description from well owner's approved application)
6. Date on which work on well ~~or tunnel~~ was begun July 11, 1942
(Strike words not needed)
7. Date on which work on well ~~or tunnel~~ was completed ~~or abandoned~~ Aug. 1, 1942
(Strike words not needed)
8. Maximum quantity of water flowing, ~~pumped or dipped~~ on completion of well ~~or tunnel~~ in sec.
(Strike words not needed)
ft. _____; or in gals. per minute 3; Date 8-1-42

DETAIL OF COLLECTING WORKS:

9. WELL: It is a drilled, ~~dug~~, flowing ~~or pump~~ well. Temperature of water _____ °F.
(Strike words not needed)
 - (a) Total depth of well is 225 ft. below ground surface.
 - (b) If flowing well, give water pressure (hydrostatic head) above ground surface 3 ft.
 - (c) If pump well, give depth from ground surface to water surface before pumping _____; during pumping _____
 - (d) Size and kind of casing 2" new black pipe.
(If only partially cased, give details)
 - (e) Depth to water bearing stratum 220
(If more than one stratum, give depth to each)
 - (f) If casing is perforated, give depth from ground surface to perforations 223
 - (g) Log of well 3" soil; 3'-85' clay; 85-92 sand; 92-98 clay; 98-103 sand;
103-147 clay; 147-185 sand; 185-220 clay; 220-225 fine gravel.

VED STATE
EER COUNTER
T 27, 1942


- (h) Well was equipped with cap, valve, or _____ Valve _____ to control flow.
(Strike words not needed)

(Over)

UTAH DIVISION OF WATER RIGHTS
WATER RIGHT POINT OF DIVERSION PLOT CREATED WED, APR 28, 1993, 2:35 PM
PLOT SHOWS LOCATION OF 4 POINTS OF DIVERSION

PLOT OF AN AREA WITH A RADIUS OF 15840 FEET FROM A POINT
N 1900 FEET, W 2200 FEET OF THE SE CORNER,
SECTION 28 TOWNSHIP 1N RANGE 1W SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 6000 FEET



UTAH DIVISION OF WATER RIGHTS
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	QUANTITY CFS	AND/OR AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER DEPTH YEAR LOG	POINT OF DIVERSION DESCRIPTION NORTH EAST CNR SEC TWN RNG B&M	U A P T S U P R N P E E U G T E N P R R R W P D
0 59 4513		100.0000		.00 SLC Sewer Outlet and/or Canal S 220 W 45 NE 22 1N 1W SL X	PRIORITY DATE: 06/24/1977 Salt Lake City UT	X
WATER USE(S): MUNICIPAL POWER OTHER Salt Lake City Corporation (Public Utili 1530 South West Temple Street,						
1 59 1735		.5000		.00 Underground Water Drain N 714 W 101 S4 22 1N 1W SL X	PRIORITY DATE: 10/21/1964 Salt Lake City UT 84110	X
WATER USE(S): IRRIGATION MUNICIPAL OTHER Western Horizon Homes Inc. P.O. Box 1499						
2 57 3569		3.0000		.00 N S 2536 E 2711 NW 25 1N 1W SL X	PRIORITY DATE: 00/00/1850 Salt Lake City UT 84115	X X
WATER USE(S): MUNICIPAL OTHER Salt Lake City Corporation Dept. of Wate 1530 South West Temple						
3 59 3437		.0000	100000.00	Jordan River S 1300 E 200 NW 4 1S 1W SL X	PRIORITY DATE: 11/02/1967 Orem UT 84058	X
WATER USE(S): IRRIGATION DOMESTIC STOCKWATERING MUNICIPAL OTHER Central Utah Water Conservancy District 355 West 1300 South						

WRNUM: 59-4513 APPLICATION/CLAIM NO.: A49381 CERT. NO.:

OWNERSHIP*****

NAME: Salt Lake City Corporation (Public Utilities) OWNER MISC:
 ADDR: 1530 South West Temple Street
 CITY: Salt Lake City STATE: UT ZIP: INTEREST:

LAND OWNED BY APPLICANT? Yes

DATES, ETC.*****

Filing: 06/24/1977 Priority: 06/24/1977 Advertise Paper: Date: 09/01/1977 Protested? N Appr/Rej: / /
 Proof Due: / / Ext Filed: / / Elec/Proof: Filed: / / Cert. or WUC Issued: / /
 Lap, Etc.: / /

PD Book No. Type of Right: APPL Status: UNAP Source of Info: APPL Map: Date Verified: / / Initials:
 PD REMARKS REFERENCE -- Name: Interest: Flow: Type of Right: Priority: Source:

LOCATION OF WATER RIGHT*****

FLOW: 100.0 cfs SOURCE: SLC Sewer Outlet and/or Canal
 TRIBUTARY 1: TRIBUTARY 2:
 COUNTY: Salt Lake COMMON DESCRIPTION: DRAINAGE AREA: Lower Jordan River-West

POINTS OF DIVERSION -- SURFACE:
 (1) S 2200 ft E 200 ft from NW cor, Sec 10, T 1N, R 1W, SLBM
 Diverting Works: Source:
 (2) S 220 ft W 45 ft from NE cor, Sec 22, T 1N, R 1W, SLBM
 Diverting Works: Source:

USES OF WATER RIGHT*****

CLAIMS USED FOR PURPOSE DESCRIBED: 4513
 Referenced To: Claims Groups: Type of Reference -- Claims: Purpose: Remarks:
 ###MUNICIPAL: Salt Lake City Corporation PERIOD OF USE: 01/01 TO 12/31
 ###POWER: Unnamed Steam Generation Power Plant, rated at . PERIOD OF USE: 01/01 TO 12/31
 ###OTHER General Industrial Uses. PERIOD OF USE: 01/01 TO 12/31

***** END OF DATA *****

WRNUM: 59-1735 APPLICATION/CLAIM NO.: A36492 CERT. NO.:

OWNERSHIP*****

NAME: Western Horizon Homes Inc. OWNER MISC:
 ADDR: P.O. Box 1499
 CITY: Salt Lake City STATE: UT ZIP: 84110 INTEREST:

LAND OWNED BY APPLICANT?

DATES, ETC.*****

Filing: 10/21/1964 Priority: 10/21/1964 Advertise Paper: Date: / / Protested? Appr/Rej: / /
 Proof Due: / / Ext Filed: / / Elec/Proof: Filed: / / Cert. or WUC Issued: / /
 Lap, Etc.: / /

PD Book No. Type of Right: APPL Status: UNAP Source of Info: APPL Map: Date Verified: / / Initials:
 PD REMARKS REFERENCE -- Name: Interest: Flow: Type of Right: Priority: Source:

LOCATION OF WATER RIGHT*****

FLOW: 0.5 cfs SOURCE: Underground Water Drain
 TRIBUTARY 1: TRIBUTARY 2:
 COUNTY: Salt Lake COMMON DESCRIPTION: DRAINAGE AREA: Lower Jordan River-West

POINT OF DIVERSION -- UNDERGROUND:
 (1) N 714 ft W 101 ft from S4 cor, Sec 22, T 1N, R 1W, SLBM DIAM: ins. DEPTH: to ft. YEAR DRILLED: WELL LOG?

PLACE OF USE OF WATER RIGHT*****

	NORTH-EAST4 NE NW SW SE	NORTH-WEST4 NE NW SW SE	SOUTH-WEST4 NE NW SW SE	SOUTH-EAST4 NE NW SW SE
Sec 22 T 1N R 1W SLBM	* : : : *	* : : : *	* X: X: X: X*	* : : : *
Sec 27 T 1N R 1W SLBM	* : : : *	* X: X: X: X*	* X: X: X: X*	* : : : *

USES OF WATER RIGHT*****

CLAIMS USED FOR PURPOSE DESCRIBED: 1735
 Referenced To: Claims Groups: Type of Reference -- Claims: Purpose: Remarks:

###IRRIGATION *---NORTH EAST QUARTER--*---NORTH WEST QUARTER--*---SOUTH WEST QUARTER--*---SOUTH EAST QUARTER--* Section
 Tot Irr. Acrg.: 23.75* NE NW SW SE * NE NW SW SE * NE NW SW SE * NE NW SW SE * Totals
 Sec 22 T 1N R 1W SLBM * : : : * : : : * : : : * : : : * 0.00
 Sec 27 T 1N R 1W SLBM * : : : * X: X: X: X* X: X: X: X* : : : * 0.00
 or a Total of .00 acres. Sole Supply: acres Diversion Limit: PERIOD OF USE: 04/01 TO 10/31
 ###MUNICIPAL: Rose Park PERIOD OF USE: 01/01 TO 12/31
 ###OTHER Subdivision development including swimming pools, parks, playgrounds, etc. PERIOD OF USE: 01/01 TO 12/31

***** END OF DATA *****

WRNUM: 57-3569 APPLICATION/CLAIM NO.: U1042 CERT. NO.:

OWNERSHIP*****

NAME: Salt Lake City Corporation Dept. of Water Supply OWNER MISC:
 ADDR: 1530 South West Temple
 CITY: Salt Lake City STATE: UT ZIP: 84115 INTEREST: 100%

LAND OWNED BY APPLICANT?

DATES, ETC.*****

Filing: 12/02/1935 Priority: 00/00/1850 Advertise Paper: Date: / / Protested? Appr/Rej: / /
 Proof Due: / / Ext Filed: / / Elec/Proof: Filed: / / Cert. or WUC Issued: / /
 Lap, Etc.: / /

PD Book No. Type of Right: UGWC Status: Source of Info: UGWC Map: Date Verified: 02/24/1992 Initials: JC
 PD REMARKS REFERENCE -- Name: Interest: Flow: Type of Right: Priority: Source:

LOCATION OF WATER RIGHT*****

FLOW: 3.0 cfs SOURCE: Wasatch Springs Underground Water
 TRIBUTARY 1: TRIBUTARY 2:
 COUNTY: Salt Lake COMMON DESCRIPTION: DRAINAGE AREA: Lower Jordan River-East

POINT OF DIVERSION -- UNDERGROUND:
 (1) S 2536 ft E 2711 ft from NW cor, Sec 25, T 1N, R 1W, SLBM DIAM: ins. DEPTH: to ft. YEAR DRILLED: WELL LOG? N

REMARKS:

No consumptive use for the municipal purposes.

USES OF WATER RIGHT*****

CLAIMS USED FOR PURPOSE DESCRIBED: 3569
 Referenced To: Claims Groups: Type of Reference -- Claims: Purpose: Remarks:
 ###MUNICIPAL: Salt Lake City Corporation PERIOD OF USE: 01/01 TO 12/31
 ###RECREATION Bath houses PERIOD OF USE: 01/01 TO 12/31

OTHER COMMENTS*****

The water supply was originally obtained from a natural spring and was later augmented by the driving of tunnels.

***** END OF DATA *****

WRNUM: 59-3437 APPLICATION/CLAIM NO.: A38519 CERT. NO.:

OWNERSHIP*****

NAME: Central Utah Water Conservancy District OWNER MISC:
 ADDR: 355 West 1300 South
 CITY: Orem STATE: UT ZIP: 84058 INTEREST:

LAND OWNED BY APPLICANT?

DATES, ETC.*****

Filing: 11/02/1967 Priority: 11/02/1967 Advertise Paper: Date: 09/16/1971 Protested? PH Appr/Rej: / /
 Proof Due: / / Ext Filed: / / Elec/Proof: Filed: / / Cert. or WUC Issued: / /
 Lap, Etc.: / /

PD Book No. Type of Right: APPL Status: UNAP Source of Info: APPL Map: Date Verified: 05/18/1992 Initials: ELA

PD REMARKS REFERENCE -- Name: Interest: Flow: Type of Right: Priority: Source:

LOCATION OF WATER RIGHT*****

FLOW: 100000.0 acre-feet SOURCE: Jordan River

TRIBUTARY 1: TRIBUTARY 2:

COUNTY: Salt Lake COMMON DESCRIPTION: DRAINAGE AREA: Lower Jordan River-West

POINTS OF DIVERSION -- SURFACE:

- (1) N 1400 ft W 150 ft from SE cor, Sec 23, T 1S, R 2W, SLBM
 Diverting Works: Source:
- (2) N 2000 ft E 2350 ft from SW cor, Sec 11, T 2S, R 1W, SLBM
 Diverting Works: Source:
- (3) N 2400 ft W 1600 ft from SE cor, Sec 11, T 3S, R 1W, SLBM
 Diverting Works: Source:

POINTS OF REDIVERSION

- (1) S 1300 ft E 200 ft from NW cor, Sec 4, T 1S, R 1W, SLBM
 Diverting Works: Source:
- (2) N 2000 ft W 3300 ft from SE cor, Sec 17, T 2N, R 1W, SLBM
 Diverting Works: Source:
- (3) N 50 ft E 1050 ft from SW cor, Sec 28, T 2N, R 1W, SLBM
 Diverting Works: Source:
- (4) S 50 ft W 120 ft from NE cor, Sec 29, T 2N, R 1W, SLBM
 Diverting Works: Source:
- (5) N 1490 ft E 550 ft from SW cor, Sec 1, T 2S, R 1W, SLBM
 Diverting Works: Source:
- (6) N 990 ft E 2000 ft from SW cor, Sec 14, T 2S, R 1W, SLBM
 Diverting Works: Source:
- (7) S 200 ft W 1200 ft from NE cor, Sec 14, T 2S, R 1W, SLBM
 Diverting Works: Source:
- (8) S 1500 ft E 500 ft from NW cor, Sec 23, T 2S, R 1W, SLBM
 Diverting Works: Source:
- (9) S 200 ft E 2500 ft from NW cor, Sec 11, T 3S, R 1W, SLBM
 Diverting Works: Source:
- (10) ft E 1500 ft from SW cor, Sec 13, T 3S, R 1W, SLBM
 Diverting Works: Source:
- (11) N 2000 ft E 3500 ft from SW cor, Sec 35, T 3S, R 1W, SLBM
 Diverting Works: Source:

PLACE OF USE OF WATER RIGHT*****

	NORTH-EAST4 NE NW SW SE	NORTH-WEST4 NE NW SW SE	SOUTH-WEST4 NE NW SW SE	SOUTH-EAST4 NE NW SW SE
ALL T 1N R 1E SLBM	*			
ALL T 1N R 1W SLBM	*			
ALL T 1N R 2W SLBM	*			
ALL T 1S R 1E SLBM	*			
ALL T 1S R 1W SLBM	*			
ALL T 1S R 2W SLBM	*			
ALL T 1S R 3W SLBM	*			
ALL T 2S R 1E SLBM	*			
ALL T 2S R 1W SLBM	*			
ALL T 2S R 2W SLBM	*			
ALL T 2S R 4E SLBM	*			
ALL T 2S R 5E SLBM	*			
ALL T 2S R 6E SLBM	*			
ALL T 3S R 1E SLBM	*			
ALL T 3S R 1W SLBM	*			
ALL T 3S R 2W SLBM	*			
ALL T 3S R 4E SLBM	*			
ALL T 3S R 5E SLBM	*			
ALL T 3S R 6E SLBM	*			
ALL T 3S R 7E SLBM	*			
ALL T 4S R 1E SLBM	*			
ALL T 4S R 1W SLBM	*			
ALL T 4S R 2E SLBM	*			
ALL T 4S R 2W SLBM	*			
ALL T 4S R 4E SLBM	*			
ALL T 4S R 5E SLBM	*			
ALL T 4S R 6E SLBM	*			
ALL T 5S R 1E SLBM	*			
ALL T 5S R 1W SLBM	*			
ALL T 5S R 2E SLBM	*			
ALL T 5S R 3E SLBM	*			
ALL T 6S R 1E SLBM	*			
ALL T 6S R 1W SLBM	*			
ALL T 6S R 2E SLBM	*			
ALL T 6S R 3E SLBM	*			
ALL T 7S R 1E SLBM	*			
ALL T 7S R 1W SLBM	*			
ALL T 7S R 2E SLBM	*			
ALL T 7S R 3E SLBM	*			
ALL T 8S R 1E SLBM	*			
ALL T 8S R 1W SLBM	*			
ALL T 8S R 2W SLBM	*			
ALL T 9S R 1W SLBM	*			
ALL T 9S R 2W SLBM	*			
ALL T 10S R 1W SLBM	*			
ALL T 11S R 1W SLBM	*			

USES OF WATER RIGHT*****

CLAIMS USED FOR PURPOSE DESCRIBED: 3437

Referenced To: Claims Groups:

Type of Reference -- Claims: Purpose: Remarks:

###IRRIGATION *---NORTH EAST QUARTER---*---NORTH WEST QUARTER---*---SOUTH WEST QUARTER---*---SOUTH EAST QUARTER---* Section
 Tot Irr. Acrg.: 50000.00* NE NW SW SE * NE NW SW SE * NE NW SW SE * Totals
 or a Total of .00 acres. Sole Supply: acres Diversion Limit: PERIOD OF USE: 04/01 TO 10/31

###STOCKWATERING: 0 Equivalent Livestock Units

Diversion Limit:

PERIOD OF USE: 01/01 TO 12/31

The water will be used to incidental stockwatering purposes.

###DOMESTIC:

Diversion Limit:

PERIOD OF USE: 01/01 TO 12/31

The water will be used for domestic purposes outside of the municipalities along the Wasatch Front from Provo City on the south to Salt Lake City on the north, in Heber Valley and Kamas Valley, and in Goshen Valley.

###MUNICIPAL: Municipalities along Wasatch Front

PERIOD OF USE: 01/01 TO 12/31

###OTHER

The water will be used for fish & wildlife, recreation, and other project uses.

PERIOD OF USE: 01/01 TO 12/31

OTHER COMMENTS*****

Application protested by: Utah Power & Light Company; Kennecott Copper Corporation; Division of Wildlife Resources.

SEGREGATION HISTORY*****

This Right as originally filed:

FLOW IN CFS	QUANTITY IN ACRE-FEET	W A T E R U S E S	
		IRRIGATED ACREAGE	STOCK DOMESTIC (ELUs) (FAMILIES)
	200000.0	125000.00	

The following Water Rights have been Segregated from this Water Right:

(1) WRNUM: 59- 4616 APPL#: A38519a	100000.0	75000.00
NAME: Central Utah Water Conservancy District		
FILED: 02/10/1978 STATUS: UNAP APPR/REJ: / /		

	CFS	ACRE-FEET	IRRIGATED ACREAGE	STOCK ERROR	DOMESTIC (ELUs) (FAMILIES) ERROR
59-3437 currently has: ----->					
ALL STOCK-ERROR has been SEGREGATED OFF.		100000.0	50000.00		
ALL DOMESTIC-ERROR has been SEGREGATED OFF.					
ALL MUNICIPAL-ERROR has been SEGREGATED OFF.					
ALL OTHER-ERROR has been SEGREGATED OFF.					

***** END OF DATA *****

APPENDIX B
FIELD CHANGE REQUESTS

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 12. PAGE 1 OF 13. PROJECT UTANG INSTALLATION RESTORATION PROGRAM4. PROJECT NUMBER UT014.14.025. APPLICABLE DOCUMENT SITE INVEST. SAMPLING AND ANALYSIS PLAN

6. DESCRIPTION OF CHANGE:

The requirement to analyze soil gas samples obtained at various sites around the UTANG Base for TCE according to the standards set forth in the IRP must either be changed to a qualitative rather than quantitative method, or abandoned altogether.

7. REASON FOR CHANGE:

TCE is difficult to detect using the CP-Sil 5 column supplied with the Photovac 10S70 Gas Chromatograph (GC) because the column length is short and the photoionization detector (PID) is very sensitive to double bonds. The short column and the PID work very well with BTEX compounds because they have numerous double bonds and are at least 100 times more sensitive to the PID than TCE. Also according to the PA 1989 all TCE used at the base was poured down the sanitary sewer until 1970 when use of TCE was discontinued. After a period of time TCE undergoes reductive dehalogenation which is the removal of one Cl atom and the addition of one H atom. It degrades into DCE, DCA, vinyl chloride and finally into chloroethane. TCE has a 300-day half life in a naturally occurring soil-groundwater system (Dragun, 1988).


8. RECOMMENDED DISPOSITION:

We propose to run a TCE standard using a neat solution of TCE mixed with zero air and observe the retention time for comparison.

9. PRESENT & COMPLETED WORK IMPACT:

After we have determined the retention time we can go back over the chromatograms and determine if any of the unknown retention times are within the allowable percentage ranges to be considered TCE. With this information we would also be able to determine "ball-park" concentrations of TCE in the previously run samples.

10. REQUESTED BY:


Field/Project Manager

Nov 17-1992
Date

11. FINAL DISPOSITION:

CHANGE ACCEPTED AS WRITTEN.

12. APPROVAL:


HAZWRAP Project Manager

NOV-20-1992
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 2
2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM
4. PROJECT NUMBER UT 014.14.02
5. APPLICABLE DOCUMENT SITE INVESTIGATION SAMPLING AND ANALYSIS PLAN

6. DESCRIPTION OF CHANGE:

The requirement to calibrate the PHOTOVAC 10S70 portable gas chromatograph (GC) utilizing a three point calibration curve and detection limit analyses (UANG IRP page 3-30) is impossible to execute. Therefore, this requirement must be suspended.

7. REASON FOR CHANGE:

The PHOTOVAC series of portable gas chromatographs are operated using four different libraries capable of storing 25 compounds each. A calibration standard containing 1 part per million (ppm) of several compounds could be stored in Library 1, a 10 ppm standard could be stored in Library 2, and a 50 ppm standard could be stored in Library 3. But three standards could not be placed into the same library to perform a three point calibration of that instrument and achieve accurate results.

8. RECOMMENDED DISPOSITION:


We advise that a calibration standard of one concentration be installed into Library 1, a standard of another concentration in Library 2, and so on. After the instrument is calibrated with each standard the results obtained when a standard of "unknown concentration" is analyzed, will be compared to the concentration of the actual calibration standard. If the percent difference of the "unknown standard" is within 20% of the actual standard then the GC will be considered calibrated for that standard. If the result obtained is not within 20% of the actual concentration of the calibration standard the "unknown standard" will be analyzed until the results indicate it is within the limits.

9. PRESENT & COMPLETED WORK IMPACT:

This change will not affect any of the past or present sample analysis or calibration results as this is the only acceptable method of operation. All results utilizing this method indicate that it is working and samples analyzed with the photoionization detector (PID) correlate almost exactly with total organic results obtained with the GC.

10. REQUESTED BY:

GAW


Field/Project Manager

12-7-92

Date

11. FINAL DISPOSITION

AFTER DISCUSSION WITH ANGEL & HAWWRAP STAFF,
THE CHANGE IS ACCEPTED.

12. APPROVAL:


HAZWRAP Project Manager

10 DEC '93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 3

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.02

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN- SAMPLE DESIGNATION AND DOCUMENTATION

6. DESCRIPTION OF CHANGE:

Due to the current field books being soft bound and the requirement in section 2-48 that the documents be hardboard bound, we request a procedural waiver to use the bound notebooks with a polyethylene cover and sequentially numbered pages already purchased. The notebooks meet all requirements except for hardcovers because they are bound with a durable waterproof polyethylene cover.

7. REASON FOR CHANGE:

The requirement that the site logbook, field logbook, and field equipment logbook (see page 2-48) be a bound book with a hard cover and sequentially numbered pages has been changed since we could not purchase the hard covered notebooks at the time of the field program, therefore these were used with the belief that they met HAZWRAP requirements.

8. RECOMMENDED DISPOSITION:

We believe that due to the fact that the notebooks have a soft cover should not have a bearing on their contents or the durability of the notebook and therefore no change in the notebooks should be made.

9. PRESENT & COMPLETED WORK IMPACT:

This will have no impact on the present or completed work on the site.

10. REQUESTED BY:

[Signature]
Field/Project Manager

12-7-92
Date

11. FINAL DISPOSITION:

APPROVED - A CHANGE TO OUR REQUIREMENTS HAS BEEN
REQUESTED. HARD COVERED FIELD LOG BOOKS ARE NOT
REQUIRED - POLYETHYLENE COVER IS ADEQUATE.

12. APPROVAL:

[Signature]
HAZWRAP Project Manager

10 DEC '92
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 4

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.02

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN- SAMPLING PROCEDURES

6. DESCRIPTION OF CHANGE:

The requirement to composite the sample remaining in the California rings after removal of the VOA sample using a cut and quartering technique should be changed because a representative sample is not always obtained from the remaining material (pg 2-43).

7. REASON FOR CHANGE:

We feel that if contamination is detected in a discrete zone within a 2 -1/2 foot split spoon sampler and a single 3-inch VOA sample is removed the remaining 27 inches of material should not be composited because a biased sample might result from this method.

8. RECOMMENDED DISPOSITION:

If a discrete interval is sampled we feel strongly that the next discrete interval immediately following the VOA sample should be analyzed for the remaining constituents. In order to obtain a more accurate indication of the subsurface contaminants present at the site.

9. PRESENT & COMPLETED WORK IMPACT:

This will only have an impact on the first few samples collected at the Waste POL Area- Site 2. The method described above has been used for sample collection on the remaining samples.

10. REQUESTED BY: GAW

[Signature]
Field/Project Manager

12-7-92
Date

11. FINAL DISPOSITION:

AFTER DISCUSSION WITH THE AUGRE AND HAZWRAP
STAFF, THIS CHANGE IS APPROVED.

12. APPROVAL:

[Signature]
HAZWRAP Project Manager

[Signature]
10 DEC 93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 5

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-change from SW-846 Method 8240 to SW-846 Method 8010/8020 for soil analysis.

6. DESCRIPTION OF CHANGE:

The requirement that soil samples be analyzed according to EPA SW-846 Method 8240 for volatiles in the SITE INVESTIGATION SAMPLING AND ANALYSIS PLAN FOR THE 151ST AIR REFUELING GROUP UTAH AIR NATIONAL GUARD (MARCH 1992) should be revised to include EPA SW-846 Method 8010/8020 for samples so that results of the analyses will correspond to analytical results of ground water samples. This is in reference to the memo from Richard Westmoreland HAZWRAP Analytical Chemist, dated 5 November 1992.

7. REASON FOR CHANGE:

The change is made in order to comply with the memo from Richard Westmoreland, dated 5 November 1992. The ground water samples will be analyzed using EPA Method SW-846 8010/8020 which is a GC method that quantifies the concentration of certain organic compounds, depending on the concentration of the compound to very low levels; 1 part per billion (ppb). The EPA Method SW-846 8240 is a GC/MS method that qualifies the compounds but may only have a level of accuracy to 5 ppb. Therefore, due to the regulations governing ground water the 8010/8020 method is required. Since not all the compounds analyzed for are the same with each method it makes more sense to use the same method on both soil and ground water samples so that correlation between contaminants can be documented.


8. RECOMMENDED DISPOSITION:

We recommend that the EPA SW-846 Method 8010/8020 be performed on all soil and ground water/surface water samples in lieu of EPA SW-846 Method 8240.

9. PRESENT & COMPLETED WORK IMPACT:

This will have an impact on some samples collected to date. The soil samples collected between 4 December and up to and including 9 December 1992 will be analyzed using Method 8240. The soil and water samples collected on and after 10 December 1992 will be analyzed using Method 8010/8020.

10. REQUESTED BY:

 12-23-92
Field/Project Manager Date

11. FINAL DISPOSITION:

APPROVED AND COORDINATED WITH THE ANGPO.

12. APPROVAL:

 JAN 5, 1993
HAZWRAP Project Manager Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 6

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-extending length of time between sampling events

6. DESCRIPTION OF CHANGE:

The requirement that each sampling event stopped by a hiatus of 24 hours or longer should be revised to include storms (when you are unable to sample due to adverse weather conditions but the sampling team does not demobilize), weekends (48 hours) when the sampling team does not leave the area, and equipment is not demobilized.

7. REASON FOR CHANGE:

If a rain or snow storm causes a break in the sampling process of several days during the week it is not considered another sampling event, if the samplers continue sampling after the storm abates. Therefore, if the samplers take a break over the weekend (48-hours) and do not demobilize it should not be considered another sampling event.

8. RECOMMENDED DISPOSITION:

We petition that a sampling event be amended to incorporate a break for the weekend between sampling sites. As stated in Document No.: HZ/RAP-102-1 page 25 of 109 section 3.7 FIELD QUALITY CONTROL SAMPLES "A sampling event is considered to be from the time the sampling personnel arrive at the site until these personnel leave for more than 24 h". We feel it is not justified to require a second Quality Control sample after the weekend, a break of 48 hours, because the sampling procedure has not changed and the field team has not demobilized. Therefore, nothing has changed that would alter the integrity of the sample collection procedures or the sample itself.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on any samples collected to this date. If we start ground water sampling one week and continue to collect ground water samples the following week, both should be considered part of the same sampling event and not two different sampling events. Yet if we follow the HAZWRAP procedures they become two different events and need the QA/QC samples and the added cost associated with the two different events.

10. REQUESTED BY:

[Signature] 12-23-92
Field/Project Manager Date

11. FINAL DISPOSITION:

APPROVED - MODIFICATION OF HZ/RAP-102-1 REGARDING
THE DEF OF "SAMPLING EVENT." HAS BEEN MAKE AND MAY
BE INCOMP. WITH NEXT REVISION.

12. APPROVAL:

[Signature] 5 JAN '93
HAZWRAP Project Manager Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 7

2. PAGES 1 OF 2

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-SOIL BORING,
PIEZOMETER, AND MONITORING WELL INSTALLATION AND
ABANDONMENT

6. DESCRIPTION OF CHANGE:

The requirement written on page 2-40 of the FINAL UANG -SITE INVESTIGATION SAMPLING AND ANALYSIS PLAN. States "The screens will be placed so that approximately 5 feet of screen extend above the static water level. The bottom of the screens will extend to about 10 feet below the static water table. This length will allow for fluctuations in the water table". Under the circumstances present at the Utah Air National Guard Base, this method would result in the screen starting at just below the ground surface and continuing to a depth of 17.5 feet below ground surface. Therefore, we recommend changing the length of the screen to 10 feet and include 3-5 feet of riser to the ground surface. We intend to keep the 2-foot sediment trap at the base of the screen. Due to the depth below ground surface of the static water table, some monitoring well locations will need to have a reduction in the amount of sand pack placed around the riser. As stated in the plan " The sand pack will be placed around the screen from approximately 1 foot below the bottom of the end cap to a minimum of two feet above the top of the screen. A minimum of two feet of pellitized, granular or flake bentonite will be placed above the filter pack". We recommend that a minimum of one foot of sand be placed above the top of the screen. At the time of well placement, ground water will be withdrawn in the wells with one foot of sand, then the sand will be added as necessary to assure that 1 foot of sand will be present above the screen.

7. REASON FOR CHANGE:

The reason we intend to make the change is that the screen would extend to the ground surface if we followed the protocol stated above and we would not be able to create an impenetrable surface seal, increasing the possibility of contaminated surface water entering the monitoring well. We recommend that two feet of screen extend above the static water table, followed by 1 foot of sand pack, and 2 feet of pellitized, granular or flake bentonite and cement/bentonite grout to the surface. This method is being used because the static water level was encountered at a depth of 5 feet below ground surface in some piezometers. In locations where the static ground water is encountered at depths greater than 5 feet below ground surface, monitoring wells will be constructed using the minimum amount of sand, bentonite and cement/bentonite grout as originally stated in the SAP.

8. RECOMMENDED DISPOSITION:


We petition that the work plan be altered to incorporate the above changes.

1. FIELD CHANGE NO. 7
2. PAGES 2 OF 2

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on any present or future activities on site.


10. REQUESTED BY:

 12-28-92
Field/Project Manager Date

11. FINAL DISPOSITION:

COORDINATED WITH TECHNICAL OPERATIONS AND
APPROVED.

12. APPROVAL:

 5 JAN 93
HAZWRAP Project Manager Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 8

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT SITE INVESTIGATION SAMPLING AND ANALYSIS PLAN-FIELD SAMPLING PLAN-BASE WIDE PIEZOMETERS

6. DESCRIPTION OF CHANGE:

In the original SAP it requires the installation of six piezometers. We would like to modify the SAP and install a total of ten piezometers to better understand the static water table on the Utah Air National Guard Base (UANG).

7. REASON FOR CHANGE:

The reason we recommend the change is that we suspect the City Drain has a dramatic influence on the static water table at the UANG Base and we cannot determine the full affect the City Drain has on the static water table unless we strategically install several more piezometers on the perimeter and east central locations of the base.

8. RECOMMENDED DISPOSITION:

We petition that the work plan be altered to incorporate the above changes.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on any present or future activities on site, except to better define the static ground water table underlying the UANG Base.

10. REQUESTED BY:

Robert W. Hayes
Field/Project Manager

1-8-93
Date

11. FINAL DISPOSITION:

AFTER COORDINATION, OVERALL PROJECT SCOPE IS NOT EXPECTED TO BE IMPACTED AND THE CHANGE PROVIDES MORE INFORMATION. THE CHANGE IS APPROVED AS STATED.

12. APPROVAL:

WANG SOF
HAZWRAP Project Manager

13 JAN 93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 9

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 2-WASTE POL SPILL NEAR BUILDING 1527

6. DESCRIPTION OF CHANGE:

The number of soil borings according to section 2.2.3.2 states that three soil borings will be installed and six soil samples will be collected for analysis. We request three more soil borings for a total of six. The SAP allows for one more soil boring in the optional activities (2.2.3.3). The two additional borings requested come from sites where optional work is not required.

7. REASON FOR CHANGE:

The reason to add more soil borings is to obtain a better understanding of the extent of potential contamination present at Site 2. In so doing we will be able to better define the extent of the contamination at this location and save future mobilization, drilling and sampling costs.

8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS. It should also define the extent of the contamination detected in the first three soil borings.

10. REQUESTED BY:

Robert W. Hayes
Field/Project Manager

1-8-93
Date

11. FINAL DISPOSITION:

APPROVED AS WRITTEN. NO OVERALL PROJECT SCOPE
IS ANTICIPATED.

12. APPROVAL:

[Signature]
HAZWRAP Project Manager

16.15 JAN 93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 10

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 3-DRUM BURIAL AREA

6. DESCRIPTION OF CHANGE:

The number of soil borings according to section 2.2.4 states that in the event that contamination is detected in the soil samples, four optional soil borings may be installed and eight soil samples collected. We recommend that an additional add two more soil borings for a total of six to investigate the site. The two additional borings requested should come from the ANG optional site investigation program.

7. REASON FOR CHANGE:

The reason to add more soil borings is to obtain a better understanding of the extent of potential contamination present at Site 3. A total of 14 barrels were discovered in the area originally defined in the SAP. Another grouping of barrels was discovered near the original site and the additional two borings will be used to investigate this new area. Also, the City of Salt Lake operates a large fire training area adjacent to the drum burial area and contamination from the fuel burned and floating on the fire training area surface might be impacting the soils in the vicinity of SITE 3. In so doing we should be able to better define the extent of the contamination at this location and save future mobilization, drilling and sampling costs.


8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS. They should also define the extent of the contamination detected in one of the four original soil borings.

10. REQUESTED BY:


Field/Project Manager

1-8-93

Date

11. FINAL DISPOSITION:

NO OVERALL CHANGE IN PROJECT SCOPE ANTICIPATED.
CHANGE IS APPROVED.

12. APPROVAL:


HAZWRAP Project Manager

15 JAN 93

Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 11

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 4-FIRE TRAINING AREA 1

6. DESCRIPTION OF CHANGE:

The number of soil borings according to section 2.2.5.2 states that four soil borings will be advanced and eight soil samples will be collected. We intend to add six more soil borings for a total of ten. The SAP allows for two more soil borings in the optional activities, section 2.2.5.3. The four additional borings requested come from sites where optional work is not required.

7. REASON FOR CHANGE:

The reason to add more soil borings is to obtain a better understanding of the extent of potential contamination present at Site 4. We have delineated the southern, and eastern extent of the site. Yet we continue to drill additional soil borings to the west and north of the site and results from them indicate the presence of several hydrocarbon compounds. If we install an additional four borings we should be able to define the north and west extent of Site 4. In so doing we will be better able to define the extent of the contamination at this location and save future mobilization, drilling and sampling costs.

8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS.

10. REQUESTED BY:

John W. Gauer
Field/Project Manager

1-11-93
Date

11. FINAL DISPOSITION:

NO CHANGE IN PROJECT SCOPE IS ANTICIPATED.
CHANGE IS APPROVED.

12. APPROVAL:

W. A. T. ZOR
HAZWRAP Project Manager

15 JAN '93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 12

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 5-FIRE TRAINING AREA 2

6. DESCRIPTION OF CHANGE:

The number of soil borings required for Site 5 investigation, according to section 2.2.6.1 states that four soil borings will be advanced and eight soil samples will be collected. We request three additional soil borings for a total of seven. The SAP allows for two more soil borings in the optional activities, section 2.2.6.3. The one additional boring requested should come from a site where optional work is not required.

7. REASON FOR CHANGE:

The reason to add more soil borings is to obtain a better understanding of the extent of potential contamination present at Site 5. In so doing we will be better able to define the extent of the contamination at this location and save future mobilization, drilling and sampling costs.

8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS.

10. REQUESTED BY:

[Signature]
Field/Project Manager

1-11-93
Date

11. FINAL DISPOSITION:

NO ANTICIPATED SCOPE INCREASE FOR THIS PROJECT.
CHANGE IS APPROVED.

12. APPROVAL:

[Signature]
HAZWRAP Project Manager

15 JAN '93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 13

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 7-OIL SLUDGE LAGOON

6. DESCRIPTION OF CHANGE:

The number of soil borings according to section 2.2.8.1 states that three soil borings will be advanced and six soil samples will be collected. We request seven more soil borings for a total of 10. The SAP does not allow for any soil borings in the optional activities, section 2.2.8.3. The seven additional borings requested should come from sites where optional work is not required.

7. REASON FOR CHANGE:

The reason to add more soil borings is to obtain a better understanding of the extent of potential contamination present at Site 5. In so doing we will be better able to define the extent of the contamination at this location and save future mobilization, drilling and sampling costs.

8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS.

10. REQUESTED BY:


Field Project Manager

1-11-93
Date

11. FINAL DISPOSITION:

NO INCREASED SCOPE IS EXPECTED. CHANGE IS
APPROVED AS STATED.

12. APPROVAL:


HAZWRAP Project Manager

15 JAN '93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 14

2. PAGES 1 OF 1

3. PROJECT UANG INSTALLATION RESTORATION PROGRAM

4. PROJECT NUMBER UT 014.14.03

5. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 3-DRUM BURIAL AREA

6. DESCRIPTION OF CHANGE:

The number of monitoring wells according to section 2.2.4 states that one downgradient monitoring well will be advanced and one groundwater sample will be collected. We intend to add one more monitoring well for a total of two. The SAP allows for one monitoring well in the optional activities, section 2.2.4. The one additional monitoring well requested will come from a site where optional work is not required.

7. REASON FOR CHANGE:

The reason to add more soil borings is to obtain a better understanding of the extent of potential contamination present at Site 3. A total of 14 barrels were discovered in the area originally defined in the SAP. Also, the City of Salt Lake operates a large fire training area adjacent to the drum burial area, and adjacent to a concrete pad located north of the UANG property. This fire training area contains a mixture of fuel and water at the surface and may be impacting the groundwater in the vicinity. Information obtained from a static water table map indicates that groundwater flows in a southeasterly direction toward the City Drain. We request that a monitoring well be installed between the fire training area and drum burial area, and the second monitoring well on the southeast side of the main drum burial area. In so doing we will be better able to define the extent of the contamination at this location and save future mobilization, drilling and sampling costs.


8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS.

10. REQUESTED BY:


Field/Project Manager

1-11-93
Date

11. FINAL DISPOSITION:

NO CHANGE IN SCOPE - APPROVED AS WRITTEN.

12. APPROVAL:


HAZWRAP Project Manager

15 JAN 93
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 152. PAGES 1 OF 13. PROJECT UANG INSTALLATION RESTORATION PROGRAM4. PROJECT NUMBER UT 014.14.035. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 2

6. DESCRIPTION OF CHANGE:

The number of sampling locations per boring according to section 2.2.3.2 states that during confirmation and optional sampling programs, two soil samples will be collected from each boring. We intend to collect only one sample from the deep zone in soil borings SB4, SB5 and SB6 in order to determine the vertical extent of contamination at this site.

7. REASON FOR CHANGE:

Made-land (man made) makes up the top four (4) feet of the site. Due to the potential for the made-land to be placed "post-contamination", and the contaminants of concern at this site to be solvents (exhibiting a specific gravity greater than water), it is not economical to collect and analyse a sample from the upper four feet of the borings. Therefore, only one soil sample will be collected from each boring at the interval between the made-land/native soil interface and the static water level, noted during drilling.


8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS.

10. REQUESTED BY:


Field/Project Manager

12-11-92
Date

11. FINAL DISPOSITION:

Coord'd with Lee Perry, NGB, and approved as
written.

12. APPROVAL:


HAZWRAP Project Manager

Dec 14, 1992
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 162. PAGES 1 OF 13. PROJECT UANG INSTALLATION RESTORATION PROGRAM4. PROJECT NUMBER UT 014.14.035. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 3

6. DESCRIPTION OF CHANGE:

The number of sampling locations per boring according to section 2.2.4 states that during confirmation and optional sampling programs, two soil samples will be collected from each boring. We intend to collect only one sample from the deep zone in soil borings SB4 and SB5 in order to determine the vertical extent of contamination at this site.

7. REASON FOR CHANGE:

Made-land (man made) makes up at least the top four (4) feet of the site. Due to the potential for the made-land to be placed "post-contamination", and the contaminants of concern at this site to be "off-spec" JP-4 and solvents it is not economical to collect and analyse a sample from the upper four feet of the borings. Therefore, only one soil sample will be collected from each boring at the interval between the made-land/native soil interface and the static water level, noted during drilling.

8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS.

10. REQUESTED BY:

[Signature]
Field/Project Manager

12-11-92
Date

11. FINAL DISPOSITION:

Coord'd with Lee Barry, NGR, and approved as
written.

12. APPROVAL:

[Signature]
HAZWAP Project Manager

DEC 14, 1992
Date

Form 9

FIELD CHANGE REQUEST FORM

1. FIELD CHANGE NO. 172. PAGES 1 OF 13. PROJECT UANG INSTALLATION RESTORATION PROGRAM4. PROJECT NUMBER UT 014.14.035. APPLICABLE DOCUMENT FIELD SAMPLING PLAN-CONFIRMATION
ACTIVITIES AT SITE 7

6. DESCRIPTION OF CHANGE:

The number of sampling locations per boring according to section 2.2.8.2 states that during confirmation and optional sampling programs, two soil samples will be collected from each boring. We intend to collect only one sample from the deep zone in soil borings SB4, SB6, SB8 and SB10 in order to determine the vertical extent of contamination at this site.

7. REASON FOR CHANGE:

Made-land (man made) makes up the top four (4) feet of the site. Due to the potential for the made-land to be placed "post-contamination", and the contaminants of concern at this site to be waste oil, and other wastes including paints, thinners, fuels, and solvents it is not economical to collect and analyse a sample from the upper four feet of the borings. Therefore, only one soil sample will be collected from each boring at the interval between the made-land/native soil interface and the static water level, noted during drilling.


8. RECOMMENDED DISPOSITION:

We recommend that the Field Sampling Plan be amended to reflect this change.

9. PRESENT & COMPLETED WORK IMPACT:

This will not have an impact on past work but might help save future costs associated with an RI/FS.

10. REQUESTED BY:


Field/Project Manager

12-11-92
Date

11. FINAL DISPOSITION:

COORD'D WITH LEE PERRY, NGR, AND APPROVED AS
WRITTEN

12. APPROVAL:


HAZWRAP Project Manager

DEC 14 1992
Date

APPENDIX C
MONITORING WELL DEVELOPMENT
AND SAMPLING FORMS

APPENDIX C

TABLE OF CONTENTS

Monitoring Well Development Forms - 1993	C-1
Groundwater Sampling Forms - 1993.....	C-19
Monitoring Well Development Forms - 1995	C-31
Groundwater Sampling Forms - 1995.....	C-36
Groundwater Sampling Forms - 1995 Resampling	C-53

Monitoring Well Development Forms

1993

WELL DEVELOPMENT LOG		Well No.: <u>MW1</u>	Page <u>1</u> of <u>1</u>
Installation: <u>UTANG</u>		Site: <u>86</u>	
Project No.: <u>U014.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENGINEERING - SCIENCE</u>		Dev. Contractor: <u>A.C. EXPLORATION</u>	
Dev. Start: Date <u>1-21-93</u> Time <u>15:20</u>	Dev. End: Date <u>1-21</u> Time <u>16:45</u>	Csg Dia:	
Developed by: <u>DAVE MOTT</u>		Dev. Rig (<input checked="" type="checkbox"/> N)	

Dev. Method move water through sand pack to remove fine silt & sand particles; resulting in a reduction in turbidity

Equipment: Compressor: INgersoll - RAND 37.5, Surge Block, water trap

Pre-Dev. SWL 4.82 ft Maximum drawdown during pumping 3.54 ft of 0.5 gpm

Range and Average discharge rate Average: 0.5 gpm Range: 0.5 - 1.0 gpm

Total quantity of material bailed 5 gal

Total quantity of water discharged by pumping 17 gal

Disposition of discharge water free of suspended solids ~~free of solids~~ DFB

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
1:25	22 gal	8.36	-	Light brown	12.3	8.1	1740 _{MS}	220 mV
					12.7	8.0	1725 _{MS}	226 mV
					12.4	8.0	1696 _{MS}	224 mV

Comments: _____

Reviewed by: Darin Best

Developed by: <u>Steve Dave Motl / Vallas</u>	Dev. Rig <u>(Y/N)</u>
<u>Explanation of Method:</u>	

Dev. Method Explanation of Method Surge Block - moves water through sand pack to remove fine silt & clay particles. - to remove most turbidity.

Type of Equipment: - Compressor, Surge Block

Pre-Dev. SWL 16.72 Maximum drawdown during pumping _____ ft of _____ gpm

Range and Average discharge rate 25 gpm

Total quantity of material bailed 5 gallons

Total quantity of water discharged by pumping 25 gallons

Disposition of discharge water cloudy, some sand, silt

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/ Color	Temp. °C	pH	Conductivity	Remarks
2.5 hrs	20	15.35		Brown				

Comments: _____

Reviewed by: _____

WELL DEVELOPMENT LOG		Well No.: MW1	Page 1 of 1
Installation: UTANG		Site: S1	
Project No.: UTO14.13	Client/Project: HAZWRAP		
HAZWRAP Contractor: ENGINEERING-SCIENCE	Dev. Contractor: P.C. EXPLORATION		
Dev. Start: Date 1-21-93 Time 12:15	Dev. End: Date 1-21 Time 15:05	Csg Dia:	
Developed by: DAVE MOTT / PHIL BRENETT		Dev. Rig (Y/N)	

Dev. Method: Move water through sand pack to remove fine silt & sand particles; resulting in a reduction in turbidity

Equipment: Compressor: INEERSOLL-RAND 375; Surge Block; ~~Water trap~~

Pre-Dev. SWL 5.42 Maximum drawdown during pumping ~~DFB~~ 1.80 ft of 2 gpm

Range and Average discharge rate 2 ± 1 gpm

Total quantity of material bailed 5 gal

Total quantity of water discharged by pumping 40 gal

Disposition of discharge water ~~DFB~~ free of suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
0:50	73.6 45 gal	7.22	—	Light brown	13.6	8.7	1818 μ S	62 mV DFB
			—		13.9	8.7	1769 μ S	102 mV
			—		13.8	8.7	1723 μ S	90 mV

Comments:

Reviewed by: Darin Bost

WELL DEVELOPMENT LOG		Well No.: <u>mw1</u>	Page <u>1</u> of <u>2</u>
Installation: <u>UTAN6</u>		Site: <u>52</u>	
Project No.: <u>UTOH.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENGINEERING-SCIENCE</u>		Dev. Contractor: <u>P.C. EXPLORATION</u>	
Dev. Start: Date: <u>1-22-93</u> Time <u>12:15</u>	Dev. End: Date: <u>1-22-93</u> Time <u>13:15</u>	Csg Dia:	
Developed by: <u>DAVE MOTT / PHIL BRUNETT</u>		Dev. Rig (Y/N)	

Dev. Method raise water through sand pack to remove fine silt and sand, reducing the turbidity.

Equipment: surge block, bailer

Pre-Dev. SWL 4.5 Maximum drawdown during pumping _____ ft of _____ gpm
Range and Average discharge rate _____ gpm
Total quantity of material bailed 20 gal
Total quantity of water discharged by pumping _____
Disposition of discharge water _____

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
1:00	20	—	—	—	—	—	—	water testing will begin during the next well development

Comments: _____

Reviewed by: Dan Brat

WELL DEVELOPMENT LOG		Well No.: <u>MCV 1</u>	Page <u>2</u> of <u>2</u>
Installation: <u>UTAWB</u>		Site: <u>52</u>	
Project No. <u>UT014.13</u>	Client/Project: <u>HAZWAP</u>		
HAZWAP Contractor: <u>ENGINEERING-SCIENCE</u>		Dev. Contractor:	
Dev. Start: Date <u>1-26-95</u> Time <u>13:30</u>	Dev. End: Date <u>1-26-95</u> Time <u>14:40</u>	Csg Dia:	
Developed by: <u>DARREN BROST</u>		Dev. Rig (Y/N)	

Dev. Method Draw water into well by boiling to remove fine sand & silt particles from the sand pack.

Equipment: boiler

Pre-Dev. SWL 3.91 Maximum drawdown during pumping _____ ft of _____ gpm
 Range and Average discharge rate _____ gpm
 Total quantity of material bailed 20 gal
 Total quantity of water discharged by pumping _____
 Disposition of discharge water Clear of suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
5:00 am	10	8.19	-	13.4 brown	11.0	8.2	1720 MS	143 mV
					11.4	8.2	1688	143
					11.8	8.2	1715	145
					11.8	8.2	1760	146
					11.8	8.2	1745	145
					11.9	8.2	1730	143

Comments: _____

Reviewed by: Darren Brost

WELL DEVELOPMENT LOG		Well No.: MW1	Page <u>1</u> of <u>1</u>
Installation: UTANG		Site: S3	
Project No.: UTO14.13		Client/Project: HAZWRAP	
HAZWRAP Contractor: ENGINEERING - SCIENCE		Dev. Contractor: P.C. EXPLORATION	
Dev. Start: Date 1-21-98 Time 12:20	Dev. End: Date: 1-21-98 Time 13:36	Csg Dia:	
Developed by: DAVE MOTT / PHIL BRENETT		Dev. Rig (Y/N)	

Dev. Method MOVE water through sand pack to remove fine silt & sand particles, resulting in a reduction in turbidity

Equipment: Compressor: INGERSOLL - RAND 375; SAGE Black; Water trap.

Pre-Dev. SWL 4.10 ft Maximum drawdown during pumping — ft of 2 gpm
 Range and Average discharge rate 2 ± 1 gpm
 Total quantity of material bailed 10 gal
 Total quantity of water discharged by pumping DFB 20 40 gal
 Disposition of discharge water Sandy, Silt, DFB
Free of suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
DFB 1.16	50 gal	4.1 ft	—	light brown, sandy	13.0	7.5	—	151 mV
			—	"	12.7	7.5	—	113 mV
			—	"	12.6	7.6	—	109 mV

Comments: _____

Reviewed by: Darin Best

WELL DEVELOPMENT LOG		Well No.: <u>WU 2</u>	Page <u>1</u> of <u>2</u>
Installation: <u>UTANL</u>		Site: <u>S3</u>	
Project No.: <u>U014.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENGINEERING - SCIENCE</u>		Dev. Contractor: <u>AL. EXPLORATION</u>	
Dev. Start: Date <u>1-22-93</u> Time <u>9:00</u>	Dev. End: Date: <u>1-22-93</u> Time <u>10:15</u>	Csg Dia:	
Developed by: <u>DAVE MOTT / PHIL BRUBITT</u>		Dev. Rig (Y/N)	

Dev. Method move water through the sand pack by surging to remove fine silt and sand from the sand pack.

Equipment: Surge, bailer.

Pre-Dev. SWL 7.5 ft Maximum drawdown during pumping _____ ft of _____ gpm
Range and Average discharge rate _____ gpm
Total quantity of material bailed 20
Total quantity of water discharged by pumping _____
Disposition of discharge water _____

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
1:15	20	—	—	—	—	—	—	water testing will be conducted during the next well development.

Comments: _____

Reviewed by: Dustin Brant

WELL DEVELOPMENT LOG		Well No.: <u>MW 2</u>	Page <u>2</u> of <u>2</u>
Installation: <u>UTAH</u>		Site: <u>S3</u>	
Project No.: <u>UTOH.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENGINEERING - SCIENCE</u>		Dev. Contractor:	
Dev. Start: Date <u>1-26-93</u> Time <u>09:55</u>	Dev. End: Date <u>1-26</u> Time <u>10:45</u>	Csg Dia:	
Developed by: <u>DARREN BROS</u>		Dev. Rig (Y/N)	

Dev. Method Draw water into well by bailing to remove fine sand & silt particles from the sand pack.

Equipment: bauler

Pre-Dev. SWL 6.23 ft Maximum drawdown during pumping _____ ft of _____ gpm
Range and Average discharge rate _____ gpm
Total quantity of material bailed 10
Total quantity of water discharged by pumping _____
Disposition of discharge water Clear of suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
5:00 am	10	9.24	-	dark brown	9.3	7.3	1843 HS	133 - ✓
					11.0	7.2	1852	73
					11.0	7.3	1843	57
					11.0	7.3	1841	5.3

Comments: _____

Reviewed by: Darren Bros

WELL DEVELOPMENT LOG		Well No.: <u>mw 1</u>	Page <u>1</u> of <u>2</u>
Installation: <u>UTANL</u>		Site: <u>54</u>	
Project No.: <u>UT014.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENGINEERING - SCIENCE</u>		Dev. Contractor: <u>P.C. EXPLORATION</u>	
Dev. Start: Date <u>1-22-93</u> Time <u>11:15</u>	Dev. End: Date <u>1-22</u> Time <u>12:00</u>	Csg Dia:	
Developed by: <u>DAVE MITCHELL</u>		Dev. Rig (Y/N)	

Dev. Method moved water through sand back to remove fine silt & sand. resulting in a reduction in turbidity

Equipment: Large block, bailer

Pre-Dev. SWL 4.0 Maximum drawdown during pumping _____ ft of _____ gpm
Range and Average discharge rate _____ gpm
Total quantity of material bailed 15 gal
Total quantity of water discharged by pumping _____
Disposition of discharge water _____

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
45 min	15 gal	—	—	—	—	—	—	water testing will be conducted during the next well development

Comments: _____

Reviewed by: Darin Best

WELL DEVELOPMENT LOG		Well No.: <u>MW1</u>	Page <u>2</u> of <u>2</u>
Installation: <u>UTANG</u>		Site: <u>54</u>	
Project No.: <u>UTO14.13</u>	Client/Project: <u>HAZWARP</u>		
HAZWARP Contractor: <u>ENGINEERING-SCIENCE</u>		Dev. Contractor:	
Dev. Start: Date <u>1-26-93</u> Time <u>16:30</u>	Dev. End: Date: <u>1-26</u> Time <u>17:50</u>	Csg Dia:	
Developed by: <u>DARREN DROST</u>		Dev. Rig (Y/N)	

Dev. Method Draw water into well by bailing to remove fine sand & silt particles from the sand pack.

Equipment: Bailer

Pre-Dev. SWL 4.59 Maximum drawdown during pumping _____ ft of _____ gpm
 Range and Average discharge rate _____ gpm
 Total quantity of material bailed 10
 Total quantity of water discharged by pumping _____
 Disposition of discharge water No suspended solids.

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
	<u>10</u>	<u>5.87</u>	<u>—</u>	<u>light brown</u>	<u>5.8</u>	<u>7.6</u>	<u>427</u>	<u>183</u>
					<u>5.9</u>	<u>7.5</u>	<u>440</u>	<u>180</u>
					<u>5.8</u>	<u>7.5</u>	<u>447</u>	<u>185</u>

Comments: _____

Reviewed by: Darren Drost

WELL DEVELOPMENT LOG		Well No.: <i>mw 1</i>	Page <i>1</i> of <i>2</i>
Installation: <i>UTANG</i>		Site: <i>55</i>	
Project No.: <i>UT 014.13</i>	Client/Project: <i>HAZWRAP</i>		
HAZWRAP Contractor: <i>ENGINEERING - SCIENCE</i>		Dev. Contractor: <i>P.C. EXPLORATION</i>	
Dev. Start: Date <i>1-22-93</i> Time <i>10:30</i>	Dev. End: Date <i>1-22</i> Time <i>11:00</i>		Csg Dia:
Developed by: <i>DAVE MOTT & PHIL BRUNETT</i>			Dev. Rig (Y/N)

Dev. Method: *move water through the sand pack by surging pressurizing
fine silt and sand (fine) being removed from the sand pack.*

Equipment: *surge block, boiler*

Pre-Dev. SWL *3.5 ft* Maximum drawdown during pumping *—* ft of *—* gpm
Range and Average discharge rate *—* gpm
Total quantity of material bailed *20 gal*
Total quantity of water discharged by pumping *—*
Disposition of discharge water *—*

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/ Color	Temp. °C	pH	Conductivity	Remarks
<i>30</i>	<i>20</i>	<i>—</i>	<i>—</i>	<i>—</i>	<i>—</i>	<i>—</i>	<i>—</i>	<i>water testing will be conducted during the next well development.</i>

Comments: _____

Reviewed by: *Daniel Bost*

WELL DEVELOPMENT LOG		Well No.: <u>DIW 1</u>	Page <u>2</u> of <u>2</u>
Installation: <u>UTANG</u>		Site: <u>SS</u>	
Project No.: <u>UT014.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENVIRONMENTAL SERVICE</u>		Dev. Contractor: <u>P</u>	
Dev. Start: Date <u>1-25-91</u> Time <u>16:00</u>	Dev. End: Date <u>1-25</u> Time <u>16:30</u>	Csg Dia:	
Developed by:		Dev. Rig (Y/N)	

Dev. Method Drawing water into well by bailer to remove fine silt and sand from the sand pack.

Equipment: teflon bailer.

Pre-Dev. SWL 7.48 Maximum drawdown during pumping _____ ft of _____ gpm
 Range and Average discharge rate _____ gpm
 Total quantity of material bailed 8
 Total quantity of water discharged by pumping _____
 Disposition of discharge water free of suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
30 min	8 gal	7.56		light brown	8.02	7.4	1790	-46 mV
					9.70	7.4	1775	-58 mV
					9.80	7.5	1772	-91 mV
					9.72	7.5	1770	-84 mV

Comments: _____

Reviewed by: Darin Bant

WELL DEVELOPMENT LOG		Well No.: <i>mw 1</i>	Page <i>1</i> of <i>1</i>
Installation: <i>UTANG</i>		Site: <i>56</i>	
Project No.: <i>UT014.13</i>	Client/Project: <i>HAZWRAP</i>		
HAZWRAP Contractor: <i>ENGINEERING - SCIENCE</i>		Dev. Contractor: <i>P.C. EXPLORATION</i>	
Dev. Start: Date: <i>1-22-93</i> Time: <i>14:20</i>	Dev. End: Date: <i>1-22</i> Time: <i>14:40</i>	Csg Dia:	
Developed by: <i>DAVE MITT / PHIL BRENETT</i>		Dev. Rig (Y/N)	

Dev. Method *Move water through sand pack to remove fine silt & sand particles; resulting in a reduction in turbidity*

Equipment: *Surge block, bailer*

Pre-Dev. SWL *5.85 ft* Maximum drawdown during pumping _____ ft of _____ gpm
 Range and Average discharge rate _____ gpm
 Total quantity of material bailed *20 gal*
 Total quantity of water discharged by pumping _____
 Disposition of discharge water *free of suspended solids*

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
<i>14:30</i>	<i>10</i>	<i>7.38</i>	<i>—</i>	<i>light</i>	<i>14.2</i>	<i>8.0</i>	<i>—</i>	<i>211 mV</i>
<i>14:40</i>	<i>10</i>	<i>6.77</i>	<i>—</i>	<i>brown</i>	<i>14.9</i>	<i>7.9</i>	<i>—</i>	<i>266 mV</i>
					<i>14.7</i>	<i>8.1</i>	<i>—</i>	<i>249 mV</i>

Comments: *PID was 0 ppm*

Reviewed by: *Dave Bennett*

WELL DEVELOPMENT LOG		Well No.: <i>MW2</i>	Page <i>1</i> of <i>1</i>
Installation: <i>UTAN6</i>		Site: <i>56</i>	
Project No.: <i>UT014.13</i>		Client/Project: <i>HAZWRAP</i>	
HAZWRAP Contractor: <i>ENGINEERING - SCIENCE</i>		Dev. Contractor: <i>P.C. EXPLORATION</i>	
Dev. Start: Date <i>1-22-93</i> Time <i>14:50</i>		Dev. End: Date <i>1-22</i> Time <i>15:40</i>	
Csg Dia:		Dev. Rig <i>(Y/N)</i>	
Developed by: <i>DAVE MOTT / PAUL BREWETT</i>			

Dev. Method *Mane water through sand pack to remove fine silt & sand particles; resulting in a reduction in turbidity*

Equipment: *Surge block, bailer*

Pre-Dev. SWL *7.59* Maximum drawdown during pumping _____ ft of _____ gpm
 Range and Average discharge rate _____ gpm
 Total quantity of material bailed *15 gal*
 Total quantity of water discharged by pumping _____
 Disposition of discharge water *free of suspended solids*

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
<i>15:15</i>	<i>16</i>	<i>14.30</i>	<i>-</i>	<i>light brown</i>	<i>14.3</i>	<i>8.0</i>	<i>1997</i>	<i>190</i>
<i>15 min wait</i>					<i>14.2</i>	<i>8.1</i>	<i>1991</i>	<i>185</i>
					<i>14.3</i>	<i>8.2</i>	<i>1993</i>	<i>174</i>
<i>15:40</i>	<i>40 gal</i>	<i>Initial 9.65</i> <i>Final 14.29</i>						

Comments: _____

Reviewed by: *Darin Brewett*

WELL DEVELOPMENT LOG		Well No.: <u>MW3</u>	Page <u>1</u> of <u>2</u>
Installation: <u>UTAN 6</u>		Site: <u>56</u>	
Project No.: <u>UT014.13</u>	Client/Project: <u>HAZW RAP</u>		
HAZW RAP Contractor: <u>ENGINEERING - SCIENCE</u>		Dev. Contractor: <u>A.C. EXPLORATION</u>	
Dev. Start: Date <u>1-22-93</u> Time <u>15:54</u>	Dev. End: Date <u>1-22-93</u> Time <u>16:20</u>	Csg Dia:	
Developed by: <u>DAVE MOTT/PHIL BARNETT</u>		Dev. Rig (Y/N)	

Dev. Method Flow water through sand pack to remove fine silt & sand particles, resulting in a reduction in turbidity.

Equipment: Sump block, hoses

Pre-Dev. SWL 7.73 Maximum drawdown during pumping _____ ft of _____ gpm
Range and Average discharge rate _____ gpm
Total quantity of material bailed 10 gal
Total quantity of water discharged by pumping _____
Disposition of discharge water Suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
16:06	<u>1</u>	<u>18.52</u>			<u>10.0</u>	<u>7.2</u>	<u>1887</u>	<u>256</u>
					<u>11.5</u>	<u>7.2</u>	<u>1886</u>	<u>257</u>
16:20	<u>3</u>				<u>11.5</u>	<u>7.3</u>	<u>1889</u>	<u>252</u>

Comments: _____

Reviewed by: Darin Burt

WELL DEVELOPMENT LOG		Well No.: MW1	Page <u>1</u> of <u>2</u>
Installation: <u>UTANG</u>		Site: <u>57</u>	
Project No.: <u>UTO14.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENGINEERING SCIENCE</u>		Dev. Contractor: <u>P.C. EXPLORATION</u>	
Dev. Start: Date <u>1-23-93</u> Time <u>11:15</u>	Dev. End: Date <u>1-22</u> Time <u>12:00</u>	Csg Dia:	
Developed by: <u>PHIL BRUNETT</u>		Dev. Rig (Y/N)	

Dev. Method Have water through sand pack to remove fine silt and sand. resulting in a reduction in turbidity

Equipment: Surge block, bailer

Pre-Dev. SWL 4.0 Maximum drawdown during pumping _____ ft of _____ gpm
 Range and Average discharge rate _____ gpm
 Total quantity of material bailed 15 gal
 Total quantity of water discharged by pumping _____
 Disposition of discharge water _____

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
45min	15	—	—	—	—	—	—	water testing will be conducted at the next well development

Comments: _____

Reviewed by: Darin Brunst

WELL DEVELOPMENT LOG		Well No.: <u>111W1</u>	Page <u>2</u> of <u>2</u>
Installation: <u>UTANL</u>		Site: <u>S7</u>	
Project No.: <u>01014.13</u>	Client/Project: <u>HAZWRAP</u>		
HAZWRAP Contractor: <u>ENGINEERING - SCIENCE</u>		Dev. Contractor:	
Dev. Start: Date: <u>12-26-93</u> Time <u>15:20</u>	Dev. End: Date: <u>1-26</u> Time <u>16:05</u>	Csg Dia:	
Developed by: <u>DARIEN BROST</u>		Dev. Rig (Y/N)	

Dev. Method Draw water into well by bailing to remove fine sand & silt
Articles from the sand pack.

Equipment: bailey

Pre-Dev. SWL 5.68 Maximum drawdown during pumping — ft of — gpm
Range and Average discharge rate — gpm
Total quantity of material bailed 8
Total quantity of water discharged by pumping —
Disposition of discharge water Clear of suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
	8	15.69	-	Clear	13.5	7.8	1153	123
				Very light brown	14.4	7.8	1168	95
				BFB	14.4	7.9	1153	64
					14.5	7.9	1151	53
					14.5	7.9	1154	54

Comments: _____

Reviewed by: Darien Brost

WELL DEVELOPMENT LOG		Well No.: <u>MW2</u>		Page <u>1</u> of <u>1</u>	
Installation: <u>UTAW6</u>				Site: <u>S7</u>	
Project No.: <u>UTO14.13</u>		Client/Project: <u>HAZWRAP</u>			
HAZWRAP Contractor: <u>ENGINEERING-SCIENCE</u>			Dev. Contractor: <u>A.C. EXPLORATION</u>		
Dev. Start: Date	Time <u>10:30</u>	Dev. End: Date	Time <u>11:15</u>	Csg Dia: <u>2"</u>	
Developed by: <u>DAVE MOTT / Phil Brunett</u>				Dev. Rig <u>(YN)</u>	

Dev. Method move water through sand pack to remove fine silt & sand particles; resulting in a reduction in turbidity

Equipment: Compressor: INGERSOLL-RAND 375, Surge Block; Water trap

Pre-Dev. SWL 4.5 ft Maximum drawdown during pumping ~~4.5~~ ft of 1.5 gpm

Range and Average discharge rate 1.5 ± 1 gpm gpm

Total quantity of material bailed 20 gal

Total quantity of water discharged by pumping 5 gal

Disposition of discharge water cloudy, sand, silty DFB
free of suspended solids

Time	Volume Removed (gal)	Water Level ft. BTOC	Turbidity	Clarity/Color	Temp. °C	pH	Conductivity	Remarks
45 min	25	4.5 ft	—	dark silty water little sand. Brown	14.2	7.8	1793 μS	236 mV

Comments: _____

Reviewed by: Darin Root

Groundwater Sampling Forms

1993

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 1-28-93	Time: 11:15 - 13:50	Sample Number: BG-mw1
Location: UANG-		
Well No.: BG 1	Sketch on Back (Yes/No): <input checked="" type="checkbox"/>	
Total Depth: 16.48	Number of Screened Interval(s): 1	
Depth to Top of Screen:		
Screen Length: 10'		
Well Secure (Yes/No): <input checked="" type="checkbox"/>	Comments:	
Sampler: Teflon bailer Darien Prost		
Organic Vapor Detector Serial No. 2840.8 NA090212	Other present: Robert Graven	
Background Organic Vapor Reading: 0	Reading: 40.8	
Weather: Wind: —	Precipitation: Light mist	Air Temperature: ~20°F
Water Level Measurement: Serial No.:		
Well Labeled (Yes/No): <input checked="" type="checkbox"/>	Elev. Ref. for Water Level:	
Comments:		
Odor: No		
Water Level Measurement Method: 5.88 ft DPA measure from top of PVC casing (north end)		
Depth to Product 1st: NA	Depth to Interface/Water: NA 5.88 ft	Product Thickness: NA
Purge Volume Computation Data:		
Inside Casing Diameter(d.): 2 in	Borehole Diameter (dH): 10 1/4 in	
Outside Casing Diameter(d.): NA 2-3/4" O.D.	Total Well Depth (TD): 16.48 ft	
Depth to Water from GS: 5.88 ft	Depth to Seal Base(s): —	
Calculated Well Volume: 1.73 gal	Required Purge Volume: 5.19 → 8.65 ft	
Actual Purge Volume: 7 gal	Purge Method: bailing	
Serial No's. Cond. 1009 Hanna	ph 7.3 Hanna - wtr. tester	Temp. 8.1 Hanna water test
Cond. μ mhos/cm	ph	Temp.
Initial		
Purged cycle		
Sample	1090	7.3
		8.1
		337 mv
Sample Type: 8010(2-40ml) 8020(2-40ml) 8270(2-1L) 8080(2-1L) PPM-1500ml		
Turbid (Yes/No): slightly - light brown		
Sample Filtered: yes - pressure bailer		
Reviewed by: R.W. Graven		
Form Complete (Yes/No): <input checked="" type="checkbox"/>	Decon. Complete (Yes/No): <input checked="" type="checkbox"/>	

51

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-19-93	Time: 1540 - 1745	Sample Number: 51-MWI-3
Location: Site 1		
Well No.: MW1	Sketch on Back (Yes/No):	
Total Depth: 17.05'	Number of Screened Interval(s): 1	
Depth to Top of Screen: 9.05'		
Screen Length: 10'		
Well Secure (Yes/No):	Comments:	
Sampler: RWG PA		
Organic Vapor Detector Serial No.: PA910420	Other present:	
Background Organic Vapor Reading: 1.8 ppm CO ppm	Reading: 1.8 ppm	
Weather: Wind: 5-10 mph	Precipitation: snowing	Air Temperature: 30's
Water Level Measurement: Serial No.:		
Well Labeled (Yes/No):	Elev. Ref. for Water Level:	
Comments:		
Odor: none detected 2 H ₂ S (slight)		
Water Level Measurement Method: slope Indicator water level Indicator		
Depth to Product 1st: NA	Depth to Interface/Water: NA	Product Thickness: NA
Purge Volume Computation Data: $17.05 - 5.98 = 11.07 \times 1.63 = 1.80$		
Inside Casing Diameter(d.): 2"	Borehole Diameter (dH): 10.25"	
Outside Casing Diameter(d.): ?	Total Well Depth (TD): 17.05'	
Depth to Water from GS: 5.98 - 6.06 PTS	Depth to Seal Base(s):	
Calculated Well Volume: 1.80 gallons		
Required Purge Volume: $1.80 \times 5 = 9.0$ gallons		
Actual Purge Volume: 9.5 gallons		
Purge Method: bailer		
Serial No's. Cond.	ph Hanna wt. testr	Temp. Hanna wtr. testr
Redox.		
Cond.	ph	Temp.
Initial	1740	8.5
Purged cycle	1754	8.5
	1794	8.5
Sample	1793	8.6
Temp.	10.2	10.2
	10.2	10.5
	10.5	10.5
	10.5	10.5
Redox mv	100	062
	-093	-110
Sample Type: Pesticides Method 8080 and duplicate 4-950ml amber Bz 4/4		
Turbid (Yes/No): marginal		
Sample Filtered: no		
Reviewed by: RWG		
Form Complete (Yes/No): RWG	Decon. Complete (Yes/No): RWG	

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2/10/93	Time: 1215	Sample Number: WANE S2-MW1(MS/MSD)		
Location: site 2 WANE				
Well No.: MW-1 (resample MS/MSD)	Sketch on Back (Yes/No):			
Total Depth: 17 ft	Number of Screened Interval(s): 1			
Depth to Top of Screen: 5.0'				
Screen Length: 10 ft				
Well Secure (Yes/No): yes	Comments: fresh mount			
Sampler: Mitch Jensen	Other present: Robert Graves			
Organic Vapor Detector Serial No.: DA 910420	Reading: NA			
Background Organic Vapor Reading: NA sawing				
Weather: Wind: none	Precipitation: snow	Air Temperature: $\approx 36^{\circ}\text{F}$		
Water Level Measurement: Serial No.: B-1632				
Well Labeled (Yes/No): yes	Elev. Ref. for Water Level: 4213.18 MSL			
Comments: initial water is clear, final water nearly clear				
Odor:				
Water Level Measurement Method: water level indicator				
Depth to Product 1st NA	Depth to Interface/Water 3.98	Product Thickness NA		
Purge Volume Computation Data: $17 - 3.98 \approx 13 \text{ ft}; 13 \times .163 \text{ gal/ft} = 2.1 \text{ gal}$				
Inside Casing Diameter(d.): 2 inch I.D.	Borehole Diameter (dH): 10.25"			
Outside Casing Diameter(d.): 2 3/8" O.D.	Total Well Depth (TD): 17 ft			
Depth to Water from GS: 3.98 ft	Depth to Seal Base(s): 2.0'			
Calculated Well Volume: 2.1 gal				
Required Purge Volume: $5 \times 2.1 = 10.5 \text{ gallons}$				
Actual Purge Volume: 10 gallons				
Purge Method: footer bailer				
Serial No's. Cond. CSI 9009	ph CSI 9009	Temp. CSI 9009		
Redox.				
Cond. time	micro/cm	ph	Temp.	Redox mv
Initial 1225	1492	7.6	10.3°C	140
Purged cycle 1256	1890	8.0	10.3	161
1300	1864	7.8	10.5	172
Sample 1305	1802	8.0	9.5	173 WL 6.6 ft BGS
Sample Type: VOA, SVWA one ppm, triple volume for MS/MSD				
Turbid (Yes/No): No				
Sample Filtered: yes				
Reviewed by: Robert W Graves				
Form Complete (Yes/No)		Decon. Complete (Yes/No):		

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2/2/93	Time: 1430	Sample Number: 93-MW1
Location: S143		
Well No.: MW-1	Sketch on Back (Yes/No):	
Total Depth: 20' 19'	Number of Screened Interval(s): 1	
Depth to Top of Screen: 8.0'		
Screen Length: 10'		
Well Secure (Yes/No): yes	Comments:	
Sampler: Denton Frost		
Organic Vapor Detector Serial No.: PA910420	Other present: Mitch Jensen	
Background Organic Vapor Reading: 10.2 ppm	Reading: 12.0 ppm	
Weather: Wind: slight breeze	Precipitation: none	Air Temperature: ~35°F
Water Level Measurement: Serial No.: B-1632		
Well Labeled (Yes/No): yes	Elev. Ref. for Water Level: Top of above ground casing 4209.65 MSL	
Comments:		
Odor: none		
Water Level Measurement Method: electronic oil/water interface probe		
Depth to Product 1st NA	Depth to Interface/Water NA	Product Thickness NA
Purge Volume Computation Data:		
Inside Casing Diameter(d.): 2 inch I.D.	Borehole Diameter (dH): 16.25 inch	
Outside Casing Diameter(d.): 2 3/8" O.D.	Total Well Depth (TD): 19.4 ft at top of casing above ground	
Depth to Water from ^{top of casing} (above ground): 5.78 ft	Depth to Seal Base(s): 2.0'	
Calculated Well Volume: $(19.4 - 5.78) \times 0.163 = 2.2 \text{ gal}$		
Required Purge Volume: $5 \times 2.2 = 11.1 \text{ gal}$		
Actual Purge Volume: unknown		
Purge Method: bailer (teflon)		
Serial No's. Cond. CSI 9009	ph CSI 9009	Temp. CSI 9009
Cond.	μmhos/cm MS/cm	ph
Initial 1446	1892	7.2
Purged cycle 1533	1836	7.4
1538	1818	7.4
1546	1797	7.4
Sample		
Temp.		Redox mv
7.1 °C		187
6.4		034 WL 5.87 ft
7.0		033
5.5		033
Sample Type: VOA & SUOA, collected deep called MW-3		
Turbid (Yes/No): yes		
Sample Filtered: NA		
Reviewed by: R.W. J. navel		
Form Complete (Yes/No)		Decon. Complete (Yes/No):

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: <u>Feb 2, 1993</u>	Time: <u>1505</u>	Sample Number: <u>S3-MW2</u>		
Location: <u>MW2 site 3</u>				
Well No.: <u>MW2</u>	Sketch on Back (Yes/No):			
Total Depth: <u>23.2 ft to top of casing</u>	Number of Screened Interval(s): <u>1</u>			
Depth to Top of Screen: <u>7.0'</u>				
Screen Length: <u>10 ft</u>				
Well Secure (Yes/No): <u>yes</u>	Comments: <u>well is above ground</u> <u>and WL measurements are from casing</u>			
Sampler: <u>Mitch Jensen</u>		Other present: <u>Darien Brosf</u>		
Organic Vapor Detector Serial No.: <u>PA 910420</u>	Reading: <u>7.9 ppm</u>			
Background Organic Vapor Reading: <u>6.7 ppm</u>				
Weather: Wind: <u>light breeze</u>	Precipitation: <u>none</u>	Air Temperature: <u>< 40°F</u>		
Water Level Measurement: Serial No.: <u>B-1632</u>				
Well Labeled (Yes/No): <u>yes</u>	Elev. Ref. for Water Level: <u>4209.51 MSL</u>			
Comments:				
Odor: <u>none</u>				
Water Level Measurement Method: <u>water level indicator</u>				
Depth to Product 1st <u>NA</u>	Depth to Interface/Water <u>9.2'</u>	Product Thickness <u>NA</u>		
Purge Volume Computation Data:				
Inside Casing Diameter(d.): <u>2 inch I.D.</u>	Borehole Diameter (dH): <u>10.25 inches</u>			
Outside Casing Diameter(d.): <u>2 3/8" O.D.</u>	Total Well Depth (TD): <u>23.2 ft</u>			
Depth to Water from GS: <u>9.2 ft top of casing</u>	Depth to Seal Base(s):			
Calculated Well Volume: <u>.163 gal/ft (23.2 - 9.2) = 2.3 ft</u>				
Required Purge Volume: <u>5 x 2.3 = 11.5 ft</u>				
Actual Purge Volume: <u>12 gallons</u>				
Purge Method: <u>bailer</u>				
Serial No's. Cond. <u>CSI 9009</u>	ph <u>CSI 9009</u>	Temp. <u>CSI 9009</u>		
Redox.				
Cond.	µmhos/cm	ph		
Temp.	Redox mv			
Initial	<u>1855</u>	<u>7.4</u>	<u>6.9°C</u>	<u>028 mv</u>
Purged cycle				
1700	<u>1765</u>	<u>7.4</u>	<u>6.9</u>	<u>009 mv</u>
1704	<u>1702</u>	<u>7.4</u>	<u>7.9°C</u>	<u>018 mv</u>
1708	<u>1742</u>	<u>7.4</u>	<u>8.2°C</u>	<u>011 mv</u>
Sample				
Sample Type: <u>HOA and SUOA</u>				
Turbid (Yes/No): <u>yes</u>				
Sample Filtered: <u>NA</u>				
Reviewed by: <u>RW Grasen</u>				
Form Complete (Yes/No)		Decon. Complete (Yes/No):		

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-3-93	Time: 1020	Sample Number: 54-MW1
Location: LANG site 4		
Well No.: MW-1	Sketch on Back (Yes/No):	
Total Depth: 17.0 ft	Number of Screened Interval(s): 1	
Depth to Top of Screen: 5.0'		
Screen Length: 10 ft		
Well Secure (Yes/No): yes	Comments:	
Sampler: Mitch Jensen		
Organic Vapor Detector Serial No.: PA910420	Other present: NA	
Background Organic Vapor Reading: 3.7 ppm	Reading: 13.5 ppm	
Weather: Wind: slight NW breeze	Precipitation: none	Air Temperature: 32-35°F
Water Level Measurement: Serial No.: B-1632		
Well Labeled (Yes/No): yes LANG 54 MW1	Elev. Ref. for Water Level: North edge of casing of well 4269.11 MSL	
Comments:		
Odor: none		
Water Level Measurement Method: water level Indicator		
Depth to Product 1st: NA	Depth to Interface/Water: NA 4.95	Product Thickness: NA
Purge Volume Computation Data: $0.163 \text{ gal/ft} (17 - 4.95) = 1.96 \text{ gallons}$		
Inside Casing Diameter(d.): 2 inch I.D.	Borehole Diameter (dH): 10.25"	
Outside Casing Diameter(d.): 2-3/8" O.D.	Total Well Depth (TD): 17.0 ft	
Depth to Water from GS: 4.95 ft	Depth to Seal Base(s): 2.0'	
Calculated Well Volume: 1.96 gallons		
Required Purge Volume: $5 \times 1.96 = 9.8 \text{ gallons}$		
Actual Purge Volume: 10 gallons		
Purge Method: 4 cfm bailer		
Serial No's. Cond. CST 9009	ph CST	Temp.
Cond. $\mu\text{mhos/cm}$ 45/cm	ph	Temp.
Initial		
Purged cycle		
Sample		
Sample Type:		
Turbid (Yes/No): yes		
Sample Filtered: no		
Reviewed by: Robert W. Greaver		
Form Complete (Yes/No)		Decon. Complete (Yes/No):

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-4-93	Time: 0930	Sample Number: 55-MW1
Location: U1A N685 2145		
Well No.: MW-1	Sketch on Back (Yes/No):	
Total Depth: 20.0'	Number of Screened Interval(s): 1	
Depth to Top of Screen: 5'		
Screen Length: 10 ft		
Well Secure (Yes/No): yes	Comments: Measured 1' depth from casing Well is above ground	
Sampler: Mitch Jensen		Other present: Bob Carver
Organic Vapor Detector Serial No.: PA 910420	Reading: 0 ppm	
Background Organic Vapor Reading: 0 ppm		
Weather: Wind: slight N breeze	Precipitation: light rain/snow	Air Temperature: ~35°F
Water Level Measurement: Serial No.: B-1632		
Well Labeled (Yes/No): yes	Elev. Ref. for Water Level: 4208.02' MSL	
Comments: initial water clear, bail water gray brown w/ sediment, final water not clear		
Odor: none detected		
Water Level Measurement Method: water level indicator		
Depth to Product 1st: N/A	Depth to Interface/Water 7.65'	Product Thickness N/A
Purge Volume Computation Data: $(19.55 - 7.65) \times .163 \text{ gal/ft} = 11.9 \times .163 = 1.94$		
Inside Casing Diameter(d.): 2 inch I.D.	Borehole Diameter (dH): 10.25-inch	
Outside Casing Diameter(d.): 2 3/8" O.D.	Total Well Depth (TD): 19.55 ft	
Depth to Water from GS: 7.65 ft	Depth to Seal Base(s): 20'	
Calculated Well Volume: 1.94 gallons		
Required Purge Volume: $5 \times 1.94 \text{ gallons} = 9.7 \text{ gallons}$		
Actual Purge Volume: ~10 gallons		
Purge Method: teflon bailer		
Serial No.'s. Cond. CSI 9009	ph CSI 9009	Temp. CSI 9009
Redox.		
Cond: trace	ph: 7.4	Temp: 5.2
Initial 0952	1712	068
Purged cycle 1036	1689	-130 WL 7.65'
1040	1732	-093
Sample 1045	1750	-113
Sample Type: 2 - 40 ml vials for 8010/8020; 2 - 1 liter bottles for 8010		
Turbid (Yes/No): yes		
Sample Filtered: No		
Reviewed by: Robert W. Grever		
Form Complete (Yes/No)		Decon. Complete (Yes/No):

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-4-93	Time: 1028 - 1212	Sample Number: 56-MW1-	
Location: Utah Air National Guard			
Well No.: 56-MW1	Sketch on Back (Yes/No):		
Total Depth: 17.03	Number of Screened Interval(s): 1		
Depth to Top of Screen: 5.03			
Screen Length: 10'			
Well Secure (Yes/No):	Comments:		
Sampler: Robert W Graves			
Organic Vapor Detector Serial No.: PA910420	Other present:		
Background Organic Vapor Reading: 2.6	Reading: 4.5		
Weather: Wind: 8 to 10 mph NW	Precipitation: minor-snow	Air Temperature: 30°F	
Water Level Measurement: Serial No.: B-1632			
Well Labeled (Yes/No): y	Elev. Ref. for Water Level: 4210.93' msl		
Comments:			
Odor: none observed			
Water Level Measurement Method: water level indicator			
Depth to Product 1st: NA	Depth to Interface/Water: 5.78'	Product Thickness: NA	
Purge Volume Computation Data: $11.25' \times 0.163 = 1.83375 \rightarrow 1.8 \text{ galls/gauging}$			
Inside Casing Diameter(d.): 2" I.D.	Borehole Diameter (dH): 10.25"		
Outside Casing Diameter(d.): 2 3/4"	Total Well Depth (TD): 17.03'		
Depth to Water from GS: 5.78' / 5.82	Depth to Seal Base(s): 3.03'		
Calculated Well Volume: 1.8 gallons / casing length			
Required Purge Volume: $1.8 \times 5 = 9.0 \text{ gallons}$			
Actual Purge Volume: 9.0 gallons			
Purge Method: bailing			
Serial No's. Cond. CSI 9009	ph CSI 9009	Temp. CSI 9009	
Redox.			
Cond.	µmhos/cm	ph	
Temp.	Redox mv		
Initial	1732	8.0	14.40
Purged cycle	1735	8.01	13.5
	1728	8.1	13.5
Sample			171
Sample Type: water - 8010, 8020, 8270			
Turbid (Yes/No): Yes			
Sample Filtered: Not			
Reviewed by: R.W. Graves			
Form Complete (Yes/No)		Decon. Complete (Yes/No):	

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-4-93		Time: 1330		Sample Number: 56-MW2	
Location: UANG SDC 6					
Well No.: MW-2			Sketch on Back (Yes/No):		
Total Depth: 17.0			Number of Screened Interval(s): 1		
Depth to Top of Screen: 5.0					
Screen Length: 10 ft					
Well Secure (Yes/No):			Comments: flush mount well on flight line before planer		
Sampler: Mitch Jensen			Other present:		
Organic Vapor Detector Serial No.: PA910420			Reading: 34.9 ppm		
Background Organic Vapor Reading: 144 ppm					
Weather: Wind: 10-15 mph NW		Precipitation: none		Air Temperature: mid thirties	
Water Level Measurement: Serial No.: B-1632					
Well Labeled (Yes/No):			Elev. Ref. for Water Level: 4209.22 MSL		
Comments: initial water light amber and frothy suspended solids, final water clearer					
Odor: none detected					
Water Level Measurement Method: water level indicator					
Depth to Product 1st: NA		Depth to Interface/Water: 7.1'		Product Thickness: NA	
Purge Volume Computation Data: $(16.95 - 7.1) \times .163 \text{ gal/ft} = 1.6 \text{ gal}$ $lw = 9.85'$					
Inside Casing Diameter(d.i.): 2" I.D.		Borehole Diameter (dH):			
Outside Casing Diameter(d.o.): 2 3/8" O.D.		Total Well Depth (TD): 16.95 ft			
Depth to Water from GS: 7.1 ft / 11.4' after 10 gal		Depth to Seal Base(s): 2.0' ft			
Calculated Well Volume: 1.6 gallons					
Required Purge Volume: 1.6 gallons $5 \times 1.6 = 8 \text{ gallons}$					
Actual Purge Volume: $5 \times 1.6 = 8 \text{ gallons}$ 8 to 9 gallons					
Purge Method: Teller bailer.					
Serial No's. Cond. CBI 9009		ph CBI 9009		Temp. CBI 9009	
Redox.					
Gond. μm	res/cu μm mS/cm	ph	Temp. $^{\circ}\text{C}$	Redox mv	
Initial 1414	1893	8.4	11.0	138	
Purged cycle 1440	1817	8.6	11.0	- 021 MSL 11.4'	
1450	1836	8.4	11.1	- 029	
Sample 1456	NA	NA	NA	lw = 8.9	
1575	NA	NA	NA		
Sample Type: 2-40 ml vial for 8000/8020, 2-16 amber glass for 8270					
Turbid (Yes/No): No					
Sample Filtered: No					
Reviewed by: R. J. W. J. Haver					
Form Complete (Yes/No):			Decon. Complete (Yes/No):		

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-4-93	Time: 1341	Sample Number: 56-MW3		
Location: UANG				
Well No.: 56-MW3	Sketch on Back (Yes/No):			
Total Depth: 19.91 BTOL	Number of Screened Interval(s): 1			
Depth to Top of Screen: 5.0'				
Screen Length: 10'				
Well Secure (Yes/No):	Comments: Above ground casing			
Sampler: Robert Graves				
Organic Vapor Detector Serial No.: 7A91042D	Other present: Mitch Jensen			
Background Organic Vapor Reading: Malfunction due to water vapor in Monitoring well.	Reading: 0.0			
Weather: Wind: 10 mph NW	Precipitation: None	Air Temperature: 38°		
Water Level Measurement: Serial No.: B-1632				
Well Labeled (Yes/No):	Elev. Ref. for Water Level: 4208.85 MSL			
Comments:				
Odor: Not observed				
Water Level Measurement Method: Oil/water interface probe				
Depth to Product 1st: NA	Depth to Interface/Water: 10.44	Product Thickness: NA		
Purge Volume Computation Data: $19.91 - 10.44 = 9.47 \times 1.63 = 15.3461 \rightarrow 1.5$				
Inside Casing Diameter(d.): 2" I.D.	Borehole Diameter (dH): 10.25"			
Outside Casing Diameter(d.): 2 3/8" O.D.	Total Well Depth (TD): 19.91'			
Depth to Water from GS: 10.44' / 10.43'	Depth to Seal Base(s): 2.0'			
Calculated Well Volume: 1.5 gallons				
Required Purge Volume: $1.5 \times 5 = 7.5$ gallons				
Actual Purge Volume: ~ 8 gallons				
Purge Method: teflon batten - 5 casing volumes				
Serial No's. Cond. CST 1009	ph CST 9009	Temp. CST 9009		
Cond.	µmhos/cm 215/cm	ph		
Temp.	Redox mv			
Initial	1809	7.4	9.2	167
Purged cycle 1452	1739	7.8	8.2	103
1457	1741	7.0	8.9	131
Sample	1684	7.4	6.8	096
Sample Type: 8010, 8020, 8210				
Turbid (Yes/No): 1st brown				
Sample Filtered: No				
Reviewed by: Robert W. Graves				
Form Complete (Yes/No)		Decon. Complete (Yes/No):		

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-3-97		Time: 1350		Sample Number: 27-MW1	
Location: URG 57					
Well No.: MW1			Sketch on Back (Yes/No):		
Total Depth: 16.95 ft			Number of Screened Interval(s): 1		
Depth to Top of Screen: 5.0 ft.					
Screen Length: 10 ft					
Well Secure (Yes/No): Yes			Comments: Fresh mouth well		
Sampler: Mitch Jensen			Other present:		
Organic Vapor Detector Serial No.: PA 910420			Reading: 16.5 ppm		
Background Organic Vapor Reading: 3.3 ppm					
Weather: Wind: calm		Precipitation: none		Air Temperature: ~ 40°F	
Water Level Measurement: Serial No.: B-1632					
Well Labeled (Yes/No): Yes			Elev. Ref. for Water Level: 4209.39 MSL		
Comments: water level 13.35 ft after bailing 4 gallons (time 1427) 12.2 ft after 8 gallons					
Odor: none detected					
Water Level Measurement Method: water level indicator					
Depth to Product		Depth to Interface/Water		Product Thickness	
1st NA		NA 5.45'		NA	
Purge Volume Computation Data: $(16.95 - 5.45) \times 1.163 \text{ gal/ft} = 1.37 \text{ gal}$					
Inside Casing Diameter(d.): 2 inch			Borehole Diameter (dH): 10 1/4 inch		
Outside Casing Diameter(d.): NA			Total Well Depth (TD): 16.95 ft		
Depth to Water from GS: 5.45 ft			Depth to Seal Base(s): 2.0 ft.		
Calculated Well Volume: 1.87 gal					
Required Purge Volume: $5 \times 1.87 = 9.4 \text{ gallons}$					
Actual Purge Volume: 8 gallons					
Purge Method: follow bailer					
Serial No's. Cond. CSI 9009		ph CSI 9009		Temp. CSI 9009	
Redox.					
Cond.	time	µmhos/cm	NS/cm	ph	Temp.
Initial	1410 Lm	1173		7.8	12.7°C
Purged cycle	1440	1097		8.0	10.5°C
	1551	1114		8.0	10.7°C
Sample					Redox mv
					-003
					082
					084
Sample Type: 2 40 ml vials for 8010/9020, 2-11.4v number for SW204 11.4v PP for metals					
Turbid (Yes/No): Yes					
Sample Filtered: metals sample filtered w/ pressure filter					
Reviewed by: R. W. Graves					
Form Complete (Yes/No)			Decon. Complete (Yes/No):		

GROUND-WATER SAMPLING FORM

ATTACHMENT 9.1
FP 5-5

Date: 2-3-93	Time: 1103 -1503-1720	Sample Number: AANG 57-MW2-
Location: Utah Air National Guard		
Well No.: UANG 57-MW2	Sketch on Back (Yes/No):	
Total Depth: 16.63'	Number of Screened Interval(s): 1	
Depth to Top of Screen: 4.63		
Screen Length: 10'		
Well Secure (Yes/No):	Comments:	
Sampler: Robert W Graves		
Organic Vapor Detector Serial No.: DA 910420	Other present: N/A	
Background Organic Vapor Reading: 0.0 ppm	Reading: NA	
Weather: Wind: 10 mph NW	Precipitation: none	Air Temperature: 35°
Water Level Measurement: Serial No.: B-1632		
Well Labeled (Yes/No): Y	Elev. Ref. for Water Level: 4209.45 MSL	
Comments:		
Odor: none observed		
Water Level Measurement Method: Oil/water interface probe		
Depth to Product 1st: NA	Depth to Interface/Water: NA 5.65'	Product Thickness: NA
Purge Volume Computation Data: $16.63 - 5.65 = 10.98' \times 0.163 = 1.8 \text{ gallons / casing volume}$		
Inside Casing Diameter(d.): 2"	Borehole Diameter (dH): 10.25	
Outside Casing Diameter(d.): 2.089	Total Well Depth (TD): 16.63	
Depth to Water from GS: 5.65 / 5.65	Depth to Seal Base(s): 2.0 ft.	
Calculated Well Volume: 1.8 gallons		
Required Purge Volume: $1.8 \times 5 = 9.00 \text{ gallons}$		
Actual Purge Volume: 9.5 gallons		
Purge Method: bailing -		
Serial No's. Cond. CSI 9009	ph CSI 9009	Temp. CSI 9009
Cond.	ph	Temp.
Initial	1440	7.7
Purged cycle	1529	7.7
	1527	7.7
Sample	1589	7.8
Redox mv		
		192
		174
		171
		189
Sample Type: 2-40ml vials for 8010/8020, 2-950ml for SVOCs 1-500ml polypropylene for Metals		
Turbid (Yes/No): light brown - cloudy		
Sample Filtered: metals sampled with pressure bailer and filter		
Reviewed by: Robert W Graves		
Form Complete (Yes/No)	Decon. Complete (Yes/No):	

Monitoring Well Development Forms

1995

Background Drum # 110

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: BG MWZ		Project No.: 724617	
Sample Start Date: 8-22-95		Time:		Well No./Field Sample No.: BG MWZ			
Installation: UPLAND		Log Book Ref. No.:		Page No.:			
Contractor: Parsons ES		Sampler(s)					
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval			
Weather-wind: mph		Precipitation		Air Temperature: ° F			
Water Level Measurement:		Serial No.:		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC): 17.17		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)			
Type:				Drum Number			
Purge Method Bailing				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft)				No. Purge volumes:			
METER TYPE							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	0900	-	9.73	65.3	NA	NA	7500
Development/ Purge Cycle	0935	5	11.23	NA	NA	NA	7500
	1008	13.5	11.61	NA	NA	NA	7500
	1033	21.00	9.65	65.1	1274	7.05	7200
	1042	25.00	10.87	60.3	1078	7.03	7700
	11:05	29.00	11.18	60.2	1044	7.03	750
Sample							
Sample ID:		Sample Equipment Decontamination Date/Time:					
Comments:							
Prepared by: [Signature] Date: 8-22-95							
Reviewed By:				Date:			

Drum # 111

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: 51MW2		Project No.: 724017	
Sample Start Date: 8-22-95		Time:		Well No./Field Sample No.: 51MW2			
Installation: WANE		Log Book Ref. No.:		Page No.:			
Contractor: Parsons ES		Sampler (s)					
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		Outside Casing Diameter		Inches			
Well Secure (Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		Comments:					
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval			
Weather-wind: 10 mph		Precipitation		Air Temperature: 85 °F			
Water Level Measurement:		Serial No.:		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water 6.02		Product Thickness			
Depth to Water (BTOC): 6.07		Depth of Well (BTOC): 13.95		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer)		Purged water (drummed/labeled) yes #111					
Type:		Drum Number 111					
Purge Method		Are parameters 20% of purge value? <input checked="" type="checkbox"/> (N)					
Purge Volume (Column height x gals/ft) 7.88x		No. Purge volumes:					
METER TYPE							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (°F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1315	0	6.07	69.6	2330	8.14	71500
Development/ Purge Cycle	1333	5	8.78	64.7	2400	8.24	> 1000
	1344	10	8.79	64.5	2560	8.20	7560
	1354	14.5	8.52	62.7	2760	8.15	7500
	1403	20	8.15	61.4	2560	8.21	< 200
Sample							
Sample ID:		Sample Equipment Decontamination Date/Time:					
Comments:							
Prepared by: RWJ TANKS Date: 8-22-95							
Reviewed By:				Date:			

Drum # 112

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: 52 MW2		Project No.: 724017	
Sample Start Date: 8-22-95		Time:		Well No./Field Sample No.: MW2			
Installation: LANE		Log Book Ref. No.:		Page No.:			
Contractor: Parsons ES		Sampler (s)					
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval			
Weather-wind: 10⁴ mph		Precipitation NA		Air Temperature: 90° F			
Water Level Measurement:		Serial No.:		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC): 4.96		Depth of Well (BTOC): 14.58		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) Bailer				Purged water (drummed/labeled) yes			
Type: Teflon				Drum Number 112			
Purge Method Bailer		Are parameters 20% of purge value? (Y/N)					
Purge Volume (Column height x gals/ft)				No. Purge volumes:			
METER TYPE							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1500	0.2	4.96	63.3	950	7.54	
Development/ Purge Cycle	1512	5.0	7.93	61.5	850	8.05	
	1519	10	6.05	61.4	820	8.04	
	1526	15	5.95	60.9	1010	7.83	
	1537	20	8.45	59.8	1100	7.75	
	1546	25	8.71	60.2	1140	7.93	
	Sample						
Sample ID:		Sample Equipment Decontamination Date/Time:					
Comments:							
Prepared by: <i>[Signature]</i>		Date: 8-22-95		Reviewed By:		Date:	

Drum # 104

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: 36 MW4		Project No.: 724017	
Sample Start Date:		Time:		Well No./Field Sample No.: MW4			
Installation: UANG				Log Book Ref. No.:		Page No.:	
Contractor: Parsons ES				Sampler (s)			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval			
Weather-wind: Hot		mph 10		Precipitation		Air Temperature: ° F	
Water Level Measurement:		Serial No.:		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness 1/4			
Depth to Water (BTOC): 4' 9"		Depth of Well (BTOC): 19.5'		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) Bailer				Purged water (drummed/labeled)			
Type:				Drum Number			
Purge Method				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) 7.7 x .163 = 1.25 gallons				No. Purge volumes: 5 = 6.25 gals.			
METER TYPE							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1540	18	6' 7"	11A	NA	NA	7500
Development/ Purge Cycle							
Sample							
Sample ID:							
Sample Equipment Decontamination Date/Time:							
Comments:							
Prepared by: R. J. Jones				Date: 8-21-98		Reviewed By:	
						Date:	

Draw # 105

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>SL MWS</u>		Project No.: <u>722/677</u>	
Sample Start Date: <u>8-21-95</u>		Time: <u>1758</u>		Well No./Field Sample No.: <u>MWS</u>			
Installation: <u>UANG</u>				Log Book Ref. No.:		Page No.:	
Contractor: <u>Parsons Engineering Sci</u>				Sampler (s)			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval			
Weather-wind: mph		Precipitation		Air Temperature: ° F			
Water Level Measurement:		Serial No.:		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC): <u>7.02</u>		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)			
Type:				Drum Number			
Purge Method				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>6.24.163: 1.01</u>				<u>X 9 = 9.155</u>		No. Purge volumes: <u>5</u>	
METER TYPE							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1820	0.25	7.02	6.82	4210	8.06	
Development/ Purge Cycle	1835	5.0	8.62	65.1	4274	8.22	
	1845	10.0	8.35	632	4400	8.23	
	1851	15.0	8.30	62.9	4420	8.25	
	1903	19.5	8.65	61.5	4120	7.47	
Sample							
Sample ID:				Sample Equipment Decontamination Date/Time:			
Comments:							
Prepared by: <u>R. J. J. J.</u>				Date: <u>8-22-95</u>		Reviewed By:	
						Date:	

Groundwater Sampling Forms

1995

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: BG		Project No.:	
Sample Start Date: 8/28/95		Time: 10:30		Well No./Field Sample No.: WW01			
Installation: YANG		Log Book Ref. No.:		Page No.:			
Contractor: Parsons		Sampler (s)					
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter: 2 inches		Borehole Diameter 8.25 inches					
Well Labeled (Yes/No)		Outside Casing Diameter — inches					
Well Secure (Yes/No)		Comments:					
PID Serial No.: PA930524		Reading 0.0 ppm 0		Background 0.0 ppm			
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval			
Weather-wind: PC 10-15 mph		Precipitation none		Air Temperature: 80 ° F			
Water Level Measurement: Solinst		Serial No.: 13327		Odor:			
Depth to Product (BTOC): —		Depth to Interface/Water —		Product Thickness —			
Depth to Water (BTOC): 7.03		Depth of Well (BTOC): 16.25		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) Bailer				Purged water (drummed/labeled) <input checked="" type="checkbox"/>			
Type:				Drum Number			
Purge Method Bailer				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) 9.22 x 1.32 = 12.2 gals				No. Purge volumes: 3X = 36.5 gals			
METER TYPE HVDC							
SERIAL NUMBERS-Conductivity: 9304		pH: 9304		Temperature: 9304		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1053	5	7.58	68.0	1990	7.68	
Development/ Purge Cycle	1120	22	8.25	67.9	1980	7.96	
	1135	35	9.54	64.2	1960	7.82	
Sample	1600		7.06	68.1	2190	7.48	
Sample ID: YANG-BG-WW01-GW2				Sample Equipment Decontamination Date/Time: 8/28/95			
Comments:							
Prepared by: [Signature]		Date: 8/28/95		Reviewed By:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>BG</u>		Project No.:	
Sample Start Date: <u>8-25-95</u>		Time: <u>1250</u>		Well No./Field Sample No.: <u>56 MW2</u>			
Installation: <u>UANG</u>				Log Book Ref. No.: <u>3</u>		Page No.:	
Contractor: <u>Parsons ES</u>				Sampler(s) <u>P. Koste R. GRAVES</u>			
Top of Filter Pack (BGS): <u> </u>		feet		Bottom of Filter Pack (BGS): <u> </u>		feet	
Top of Screen (BGS): <u> </u>		feet		Bottom of Screen (BGS): <u> </u>		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter: <u>8.25</u>		Inches	
Well Labeled (Yes/No) <u>(No)</u>				Outside Casing Diameter: <u> </u> Inches			
Well Secure (Yes/No) <u>(No)</u>				Comments:			
PID Serial No.: <u>PA930254</u>		Reading <u>0.0</u> ppm		Background <u>0.0</u>		ppm	
Original SWL (BTOC): <u>9.83</u>		Final SWL (BTOC): <u> </u>		Screened Interval: <u> </u>			
Weather-wind: <u>PC 10-20 mph</u>		Precipitation: <u>None</u>		Air Temperature: <u>90</u> ° F			
Water Level Measurement:		Serial No.: <u> </u>		Odor: <u> </u>			
Depth to Product (BTOC): <u> </u>		Depth to Interface/Water: <u> </u>		Product Thickness: <u> </u>			
Depth to Water (BTOC): <u>1.83</u>		Depth of Well (BTOC): <u>17.13</u>		Depth BTOC of Pump: <u> </u>			
Sampling Method (Pump or Bailer) <u>Bailer</u>				Purged water (drummed/labeled) <u>yes</u>			
Type: <u> </u>				Drum Number: <u>115</u>			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? <u>(Y/N)</u>			
Purge Volume (Column height x gals/ft) <u>7.3 x 1.32 = 9.64</u>				No. Purge volumes: <u>13 28.9</u>			
METER TYPE <u>HYDAC</u>		" <u> </u> "		" <u> </u> "			
SERIAL NUMBERS-Conductivity: <u>9304</u>		pH: <u>9304</u>		Temperature: <u>9304</u>		Turbidity: <u> </u>	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1255</u>	<u>10</u>	<u>12.34</u>	<u>59.1</u>	<u>720,000</u>	<u>7.08</u>	<u> </u>
Development/ Purge Cycle	<u>1345</u>	<u>28</u>	<u>11.58</u>	<u>59.5</u>	<u>720,000</u>	<u>7.16</u>	<u> </u>
<u>Dry</u>							
Sample	<u>1442</u>		<u>9.85</u>	<u>60.1</u>	<u>720,000</u>	<u>7.03</u>	
Sample ID: <u>UANG BG 92 - MW02 - GW</u>				Sample Equipment Decontamination Date/Time: <u>8/25/95 1500</u>			
Comments:							
Prepared by: <u>[Signature]</u>		Date: <u>8/25/95</u>		Reviewed By:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>S1</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>8/25/95</u>		Time: <u>1530</u>		Well No./Field Sample No.: 44111 <u>MW01</u>			
Installation: <u>U2N6</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s)			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		<u>2</u> inches		Borehole Diameter		<u>8.25</u> inches	
Well Labeled (Yes/No) <u>(No)</u>				Outside Casing Diameter <u>—</u> inches			
Well Secure (Yes/No) <u>(No)</u>				Comments:			
PID Serial No.: <u>PA 930524</u>		Reading <u>0.0</u> ppm		Background		<u>0.0</u> ppm	
Original SWL (BTOC): 5.71		Final SWL (BTOC):		Screened Interval			
Weather-wind: <u>PE 5-10</u> mph		Precipitation <u>None</u>		Air Temperature: <u>—</u> °F			
Water Level Measurement:		Serial No.:		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC): 5.71		Depth of Well (BTOC): 16.9		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>Bailer</u>				Purged water (drummed/labeled) <input checked="" type="checkbox"/>			
Type: <u>Teflon</u>				Drum Number <u>RES 115</u>			
Purge Method				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>10.08 x 1.32</u>				<u>> 13.30</u>			
				No. Purge volumes: <u>3 = 39.91</u>			
METER TYPE							
SERIAL NUMBERS-Conductivity:			pH:		Temperature:		Turbidity:
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (°F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1553	5.0	6.39	64.5	1930	9.03	
Development/ Purge Cycle	1640	40.0	6.85	65.5	10940 ⁷⁴ 1940	8.88	
Sample	1740		5.81	67.7	1960	8.85	
Sample ID: <u>U2N6-S1-MW01-GW2</u>				Sample Equipment Decontamination Date/Time: <u>8/25/95 1800</u>			
Comments:							
Prepared by: <u>Paul H. [Signature]</u>				Date: <u>8/25/95</u>		Reviewed By: _____	
						Date: _____	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>S1</u>		Project No.:	
Sample Start Date: <u>8/25/95</u> Time: <u>1515</u>				Well No./Field Sample No.: <u>MWD2</u>			
Installation: <u>HAUG</u>				Log Book Ref. No.: <u>3</u>		Page No.:	
Contractor: <u>Parsons ES</u>				Sampler (s) <u>P. Foster R. GRAVES</u>			
Top of Filter Pack (BGS): <u> </u> feet				Bottom of Filter Pack (BGS): <u> </u> feet			
Top of Screen (BGS): <u> </u> feet				Bottom of Screen (BGS): <u> </u> feet			
Inside Casing Diameter: <u>2</u> inches				Borehole Diameter <u>8.25</u> Inches			
Well Labeled (Yes/No) <u>(No)</u>				Outside Casing Diameter <u> </u> Inches			
Well Secure (Yes/No) <u>(No)</u>				Comments:			
PID Serial No.: <u>PA930524</u>		Reading <u>7.3</u> ppm		Background <u>0.0</u> ppm			
Original SWL (BTOC): <u>6.18</u>				Final SWL (BTOC):		Screened Interval	
Weather-wind: <u>PC 5-15</u> mph				Precipitation <u>None</u>		Air Temperature: <u>89</u> °F	
Water Level Measurement: <u>Solinst</u>				Serial No.: <u>13327</u>		Odor:	
Depth to Product (BTOC): <u> </u>				Depth to Interface/Water <u> </u>		Product Thickness <u> </u>	
Depth to Water (BTOC): <u>6.18</u>				Depth of Well (BTOC): <u>13.85</u>		Depth BTOC of Pump:	
Sampling Method (Pump or Bailer) <u>Bailer</u>				Purged water (drummed/labeled) <u>✓</u>			
Type:				Drum Number <u>AES 111</u>			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N) <u>Y</u>			
Purge Volume (Column height x gals/ft) <u>7.67' x 1.32</u>				<u>10.1</u>		No. Purge volumes: <u>3x = 30.4</u>	
METER TYPE							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (°F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1550</u>	<u>5.0</u>	<u>7.15</u>	<u>62.2</u>	<u>3080</u>	<u>8.11</u>	
Development/ Purge Cycle	<u>1615</u>	<u>30.0</u>	<u>7.00</u>	<u>62.2</u>	<u>2250</u>	<u>8.03</u>	
Sample	<u>1715</u>	<u>—</u>	<u>7.05</u>	<u>64.0</u>	<u>2310</u>	<u>7.99</u>	
Sample ID: <u>HAUG-S1-MWD1-GW2</u> Sample Equipment Decontamination Date/Time: <u>8/25/95 1730</u>							
Comments:							
Prepared by: <u>[Signature]</u> Date: <u>8/25/95</u> Reviewed By: Date:							

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>52</u>		Project No.: <u>724617</u>	
Sample Start Date: <u>8/28/95</u>		Time: <u>0940</u>		Well No./Field Sample No.: <u>MW01</u>			
Installation: <u>UAG</u>		Log Book Ref. No.:		Page No.:			
Contractor: <u>Parsons</u>		Sampler (s)					
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter: <u>2</u> inches		Borehole Diameter <u>8.25</u> Inches					
Well Labeled (Yes/No) <u>Yes</u>		Outside Casing Diameter		Inches			
Well Secure (Yes/No) <u>Yes</u>		Comments:					
PID Serial No.: <u>PA930524</u>		Reading <u>31.2</u> ppm		Background <u>0.0</u> ppm			
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval			
Weather-wind: <u>PC 5-15 mph</u>		Precipitation <u>None</u>		Air Temperature: <u>80</u> °F			
Water Level Measurement: <u>Spinst</u>		Serial No.: <u>13327</u>		Odor: <u>—</u>			
Depth to Product (BTOC): <u>—</u>		Depth to Interface/Water <u>—</u>		Product Thickness			
Depth to Water (BTOC): <u>4.82</u>		Depth of Well (BTOC): <u>16.70</u>		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>Bailer</u>		Purged water (drummed/labeled) <u>✓</u>					
Type:		Drum Number <u>PE5 116</u>					
Purge Method <u>Bailer</u>		Are parameters 20% of purge value? <u>(Y/N)</u>					
Purge Volume (Column height x gals/ft) <u>11.88</u>		<u>x 1.32 = 15.7</u>		No. Purge volumes: <u>3 X = 47.5 gal</u>			
METER TYPE <u>Hydac</u>		Conductivity: <u>9304</u>		pH: <u>9.304</u>		Temperature: <u>9304</u>	
SERIAL NUMBERS		Conductivity: <u>9304</u>		pH: <u>9.304</u>		Turbidity: <u>—</u>	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (°F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1000	5	8.60	69.5	9050	8.37	
Development/ Purge Cycle	1010	10	12.85	59.9	4620	8.59	
		<u>Bailed Dry</u>					
Sample	1420		4.83	69.4	2720	8.71	
Sample ID: <u>UAG-52-MW01-GW2</u>				Sample Equipment Decontamination Date/Time:			
Comments: <u>UAG-52-MW01-GW2 (MS/MSD)</u>							
Prepared by: <u>[Signature]</u>		Date: <u>8/28/98</u>		Reviewed By:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: S2		Project No.: 724017		
Sample Start Date: 8/28/95		Time:		Well No./Field Sample No.: MW02				
Installation: UFG		Log Book Ref. No.: 3		Page No.:				
Contractor: Parsons		Sampler (s)						
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet		
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet		
Inside Casing Diameter:		2 inches		Borehole Diameter		8.25 Inches		
Well Labeled (Yes/No)				Outside Casing Diameter		Inches		
Well Secure (Yes/No)				Comments:				
PID Serial No.: PA930254		Reading 30.8 ppm		Background 0.0 ppm				
Original SWL (BTOC):		Final SWL (BTOC):		Screened Interval				
Weather-wind: PC 0-5 mph		Precipitation None		Air Temperature: 78 °F				
Water Level Measurement: Solinst		Serial No.: 13327		Odor:				
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness				
Depth to Water (BTOC): 4.57		Depth of Well (BTOC): 14.37		Depth BTOC of Pump:				
Sampling Method (Pump or Bailer) Bailer				Purged water (drummed/labeled) <input checked="" type="checkbox"/>				
Type:				Drum Number PES #4				
Purge Method Bailer				Are parameters 20% of purge value? (Y/N)				
Purge Volume (Column height x gals/ft) 9.8 x 1.32 = 12.9				No. Purge volumes: 3 x = 39				
METER TYPE								
SERIAL NUMBERS-Conductivity:			pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (°F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)	
Initial	0910	5	5.65	63.0	9110	7.31		
Development/ Purge Cycle	0925	15	13.37	62.5	10,110	7.47		
	Bailed Dry							
Sample	1320		4.66	62.5	10,050	7.52		
Sample ID: WANA-S2-MW02-GW2				Sample Equipment Decontamination Date/Time: 8/28/95 1400				
Comments: Dup # WANA-S2-MW03-GW2								
Prepared by: [Signature]		Date:		Reviewed By:		Date:		

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: 53		Project No.: 724017	
Sample Start Date: 8/25/95		Time:		Well No./Field Sample No.: MW01			
Installation: UANG		Log Book Ref. No.: 3		Page No.:			
Contractor: Parsons ES		Sampler(s): P. Foster R. Graves					
Top of Filter Pack (BGS): — feet		Bottom of Filter Pack (BGS): — feet					
Top of Screen (BGS): — feet		Bottom of Screen (BGS): — feet					
Inside Casing Diameter: 2 inches		Borehole Diameter: 8.25 inches					
Well Labeled (Yes/No) (Yes)		Outside Casing Diameter: — inches					
Well Secure (Yes/No) (Yes)		Comments:					
PID Serial No.: PA930254		Reading: 1.5 ppm		Background: 0.5 ppm			
Original SWL (BTOC): 7.25		Final SWL (BTOC):		Screened Interval			
Weather-wind: PC 10-20 mph		Precipitation: None		Air Temperature: 76° F			
Water Level Measurement: Solinst		Serial No.: 13327		Odor: —			
Depth to Product (BTOC): —		Depth to Interface/Water: —		Product Thickness: —			
Depth to Water (BTOC): 7.25		Depth of Well (BTOC): 19.15		Depth BTOC of Pump: —			
Sampling Method (Pump or Bailer) Bailer		Purged water (drummed/labeled)		Drum Number			
Type:		Purge Method: Bailer		Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) 11.9' x 1.32 = 15.7		No. Purge volumes: 3 x = 48 gal					
METER TYPE: Hydac		Conductivity: 9304		pH: 9.304		Temperature: 9304	
SERIAL NUMBERS-Conductivity: 9304		pH: 9.304		Temperature: 9304		Turbidity: —	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	0915	7.0	7.35	62.6	6830	6.71	—
Development/	0940	22.0	7.35	61.8	12,219	6.90	
Purge Cycle	1010	50.0	7.15	60.8	720,000	7.32	
Sample	1115		7.32	60.8	5530	7.37	
Sample ID: UANG-53-MW01-GWL Sample Equipment Decontamination Date/Time: 8/25/95 1145							
Comments:							
Prepared by: <i>[Signature]</i>		Date: 8/25/95		Reviewed By:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>53</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>8/25/95</u>		Time:		Well No./Field Sample No.: <u>MW02</u>			
Installation: <u>UANG</u>		Log Book Ref. No.: <u>3</u>		Page No.:			
Contractor: <u>Parsons ES</u>		Sampler(s) <u>P. Foote R. Graves</u>					
Top of Filter Pack (BGS): <u>—</u> feet		Bottom of Filter Pack (BGS): <u>—</u> feet					
Top of Screen (BGS): <u>—</u> feet		Bottom of Screen (BGS): <u>—</u> feet					
Inside Casing Diameter: <u>2</u> inches		Borehole Diameter <u>8.25</u> Inches					
Well Labeled (Yes/No) <u>(Yes)</u>		Outside Casing Diameter <u>—</u> Inches					
Well Secure (Yes/No) <u>(Yes)</u>		Comments:					
PID Serial No.: <u>PA930524</u>		Reading <u>0.0</u> ppm		Background <u>0.0</u> ppm			
Original SWL (BTOC): <u>10.61</u>		Final SWL (BTOC):		Screened Interval			
Weather-wind: <u>PC 5-10 mph</u>		Precipitation <u>None</u>		Air Temperature: <u>80° F</u>			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC): <u>10.61</u>		Depth of Well (BTOC): <u>2292</u>		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>Bailer</u>				Purged water (drummed/labeled)			
Type:				Drum Number			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>12.31 x 1.32 = 16.25</u>				No. Purge volumes: <u>3 = 48.75</u>			
METER TYPE <u>HYDAC</u>		pH: <u>9304</u>		Temperature: <u>9304</u>		Turbidity: <u>—</u>	
SERIAL NUMBERS-Conductivity: <u>9304</u>		pH: <u>9304</u>		Temperature: <u>9304</u>		Turbidity: <u>—</u>	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1010	5	11.04	62.9	10,040	7.07	
Development/	1035	20	10.65	60.1	11,040	7.29	
Purge Cycle	1105	50	10.65	60.1	11,460	7.23	
Sample	1200		10.62	64.4	9840	7.24	
Sample ID: <u>UANG-53-MW02-GW2</u>				Sample Equipment Decontamination Date/Time: <u>8/25/95 1235</u>			
Comments:							
Prepared by: <u>[Signature]</u>				Date:		Reviewed By: <u>[Signature]</u>	
				Date:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>54</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>8/21/95</u>		Time: <u>1625</u>		Well No./Field Sample No.: <u>MW1</u>			
Installation: <u>Utah ANG Base</u>				Log Book Ref. No.: <u>3</u>		Page No.: <u>10</u>	
Contractor: <u>Parsons ES</u>				Sampler (s) <u>P. Foster</u>			
Top of Filter Pack (BGS): <u> </u> feet		Bottom of Filter Pack (BGS): <u> </u> feet					
Top of Screen (BGS): <u> </u> feet		Bottom of Screen (BGS): <u> </u> feet					
Inside Casing Diameter: <u>2</u> inches		Borehole Diameter <u>8.25</u> Inches					
Well Labeled (Yes/No) <u>(No)</u>		Outside Casing Diameter <u> </u> Inches					
Well Secure (Yes/No) <u>(No)</u>		Comments: <u>Marker is Covered by Asphalt (No Rock)</u>					
PID Serial No.: <u>PA930254</u>		Reading <u>6.4</u> ppm		Background <u>0.0</u> ppm			
Original SWL (BTOC): <u>5.75'</u>		Final SWL (BTOC): <u> </u>		Screened Interval <u> </u>			
Weather-wind: <u>W 5-10 mph</u>		Precipitation <u>None</u>		Air Temperature: <u>92</u> °F			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor: <u>None</u>			
Depth to Product (BTOC): <u> </u>		Depth to Interface/Water <u> </u>		Product Thickness <u> </u>			
Depth to Water (BTOC): <u>5.75'</u>		Depth of Well (BTOC): <u>16.72</u>		Depth BTOC of Pump: <u> </u>			
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)			
Type: <u> </u>				Drum Number <u>108</u>			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>11.0 x 0.163 = 1.8 gal</u>				No. Purge volumes: <u>3 = 6.9 gal</u>			
METER TYPE							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (°F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1640</u>		<u>5.75</u>	<u>69.0</u>	<u>516</u>	<u>7.70</u>	<u>—</u>
Development/	<u>1645</u>	<u>3</u>	<u>6.71</u>	<u>69.0</u>	<u>529</u>	<u>7.70</u>	
Purge Cycle	<u>1654</u>	<u>6</u>	<u>10.90</u>	<u>65.4</u>	<u>743</u>	<u>7.70</u>	<u>—</u>
<u>8-22-95</u>							
Sample	<u>1720</u>		<u>5.64</u>	<u>65.8</u>	<u>738</u>	<u>7.70</u>	
Sample ID: <u>UAG-54-MW1-GW2</u>				Sample Equipment Decontamination Date/Time: <u>8/22/95 1245</u>			
Comments:							
Prepared by: <u>[Signature]</u>				Date: <u>9/27/95</u>		Reviewed By: <u> </u>	
				Date:			

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>SS</u>		Project No.: <u>724017</u>		
Sample Start Date: <u>8/21/95</u>		Time: <u>1725</u>		Well No./Field Sample No.: <u>MWD1</u>				
Installation: <u>Utah ANG Base</u>				Log Book Ref. No.: <u>31</u>		Page No.: <u>10</u>		
Contractor: <u>Parsons ES</u>				Sampler (s): <u>P. Foote</u>				
Top of Filter Pack (BGS): <u> </u> feet		Bottom of Filter Pack (BGS): <u> </u> feet		Top of Screen (BGS): <u> </u> feet		Bottom of Screen (BGS): <u> </u> feet		
Inside Casing Diameter: <u>2</u> inches		Borehole Diameter: <u>8.25</u> Inches		Well Labeled (Yes/No) <u>(Yes)</u>		Outside Casing Diameter: <u> </u> Inches		
Well Secure (Yes/No) <u>(No)</u>				Comments:				
PID Serial No.: <u>PA 930254</u>		Reading <u>0.0</u> ppm		Background <u>0.0</u> ppm				
Original SWL (BTOC): <u>8.58</u>		Final SWL (BTOC): <u> </u>		Screened Interval: <u> </u>				
Weather-wind: <u>MC 5.15mph</u>		Precipitation: <u>None</u>		Air Temperature: <u>89</u> °F				
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor: <u>None</u>				
Depth to Product (BTOC): <u> </u>		Depth to Interface/Water: <u> </u>		Product Thickness: <u> </u>				
Depth to Water (BTOC): <u>8.58</u>		Depth of Well (BTOC): <u>19.28</u>		Depth BTOC of Pump: <u> </u>				
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)				
Type:				Drum Number <u>109</u>				
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)				
Purge Volume (Column height x gals/ft) <u>11.0 x 0.163 = 1.8 gal</u>				No. Purge volumes: <u>3 X = 6.0 gal</u>				
METER TYPE								
SERIAL NUMBERS-Conductivity:			pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)	
Initial	1730		8.58	65.9	8,250	7.23		
Development/ Purge Cycle	1735	3	8.60	58.5	9,600	7.38		
	1745	6	8.74	58.7	9,660	7.23		
Sample	1330		8.44	59.2	9,640	7.23		
Sample ID: <u>UANG-SS-MWD1-GWT</u>				Sample Equipment Decontamination Date/Time: <u>8/22/95 1355</u>				
Comments: <u>DUP UANG-SS-MWD2-GWT (1430)</u>								
Prepared by: <u>Paul A. [Signature]</u>				Date:		Reviewed By:		Date:

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: SL		Project No.: 724017	
Sample Start Date: 8/24/95		Time:		Well No./Field Sample No.: MW01			
Installation: Utah ANG Base		Log Book Ref. No.: 3		Page No.:			
Contractor: Parsons ES		Sampler(s) P. Foote					
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		2 inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secure (Yes/No)				Comments:			
PID Serial No.: PA930254		Reading 10.8 ppm		Background 0.0 ppm			
Original SWL (BTOC): 8.15		Final SWL (BTOC):		Screened Interval			
Weather-wind: MC 5-15 mph		Precipitation None		Air Temperature: 77° F			
Water Level Measurement: Solinst		Serial No.: 13377		Odor: Mild H₂S odor			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC): 8.15		Depth of Well (BTOC): 15.79		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) Bailer		Purged water (drummed/labeled)		Drum Number			
Type:							
Purge Method Bailer		Are parameters 20% of purge value? (Y/N)					
Purge Volume (Column height x gals/ft) 7.64 x 0.163 = 1.24 gal		No. Purge volumes: 3		5 gal			
METER TYPE HYDAC		pH: 9.304		Temperature: 9.304		Turbidity: —	
SERIAL NUMBERS-Conductivity: 9304		pH: 9.304		Temperature: 9.304		Turbidity: —	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1010	5	9.25	68.4	16,840	8.08	—
Development/ Purge Cycle	1017	10		67.5	16,610	8.09	
	1027	17	8.05	68.0	720K	8.11	
	1044	30	6.85	67.5	16,350	8.06	
	1105	30	6.85	67.5	16,350	8.06	
Sample							
Sample ID: UANG-SL-MW01-GW1				Sample Equipment Decontamination Date/Time: 8/24/95 11:35			
Comments: WAS/MSD							
Prepared by: Jane A. [Signature]				Reviewed By: _____			
Date: 8/24/95				Date: _____			

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>SL</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>8/24/95</u>		Time:		Well No./Field Sample No.: <u>MW#2</u>		Page No.:	
Installation: <u>Utah Aug Base</u>				Log Book Ref. No.:		Page No.:	
Contractor: <u>Parsons ES</u>				Sampler(s) <u>P. Foote</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		<u>2</u> inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter			
Well Secure (Yes/No)				Comments:			
PID Serial No.: <u>PA930254</u>		Reading <u>0.0</u> ppm		Background		<u>0.0</u> ppm	
Original SWL (BTOC): <u>7.62</u>		Final SWL (BTOC):		Screened Interval			
Weather-wind: <u>WC 515</u> mph		Precipitation <u>None</u>		Air Temperature: <u>78°</u> F			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC): <u>7.62</u>		Depth of Well (BTOC): <u>16.69</u>		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)			
Type:				Drum Number			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>8.07 x 1.32 = 12 gal</u>				No. Purge volumes: <u>3 = 36</u>			
METER TYPE <u>HYDAC</u>		pH: <u>9304</u>		Temperature: <u>9304</u>		Turbidity:	
SERIAL NUMBERS-Conductivity: <u>9304</u>		pH: <u>9304</u>		Temperature: <u>9304</u>		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1320</u>	<u>10</u>	<u>13.35</u>	<u>64.3</u>	<u>13450</u>	<u>8.61</u>	<u>—</u>
Development/ Purge Cycle							
Sample	<u>1347</u>	<u>10</u>	<u>8.65</u>	<u>68.2</u>	<u>13460</u>	<u>8.94</u>	
Sample ID: <u>UAGB-SL-MW#2-GW2</u> Sample Equipment Decontamination Date/Time: <u>8/24/95 1430</u>							
Comments:							
Prepared by: <u>P. Foote</u> Date: <u>8/24/95</u> Reviewed By: Date:							

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>S-6</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>8/24/95</u>		Time: <u>1435</u>		Well No./Field Sample No.: <u>MW#3</u>			
Installation: <u>Utah Air Base</u>				Log Book Ref. No.: <u>3</u>		Page No.:	
Contractor: <u>Parsons ES</u>				Sampler (s) <u>D. Foote</u>			
Top of Filter Pack (BGS): <u> </u> feet		Bottom of Filter Pack (BGS): <u> </u> feet					
Top of Screen (BGS): <u> </u> feet		Bottom of Screen (BGS): <u> </u> feet					
Inside Casing Diameter: <u>2</u> inches		Borehole Diameter <u>8.25</u> Inches					
Well Labeled (Yes/No) <u>Yes</u>		Outside Casing Diameter <u> </u> Inches					
Well Secure (Yes/No) <u>Yes</u>		Comments:					
PID Serial No.: <u>PA930254</u>		Reading <u>0.0</u> ppm		Background <u>0.0</u> ppm			
Original SWL (BTOC): <u>11.09</u>		Final SWL (BTOC): <u> </u>		Screened Interval			
Weather-wind: <u>PC 10-20mph</u>		Precipitation <u>None</u>		Air Temperature: <u>92° F</u>			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor: <u> </u>			
Depth to Product (BTOC): <u> </u>		Depth to Interface/Water <u> </u>		Product Thickness <u> </u>			
Depth to Water (BTOC): <u>11.09</u>		Depth of Well (BTOC): <u>19.65</u>		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>Bailer</u>				Purged water (drummed/labeled)			
Type:				Drum Number			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>8.56' x 1.32 = 11.3</u>				No. Purge volumes: <u>3 x = 34 gal</u>			
METER TYPE <u>HYDAX</u>		<u>"</u>		<u>1'</u>			
SERIAL NUMBERS-Conductivity: <u>9304</u>		pH: <u>9304</u>		Temperature: <u>9304</u>		Turbidity: <u> </u>	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1430</u>	<u>5</u>	<u>11.09</u>	<u>58.6</u>	<u>4650</u>	<u>7.89</u>	<u> </u>
Development/ Purge Cycle	<u>1505</u>	<u>12</u>	<u>16.05</u>	<u>63.8</u>	<u>6170</u>	<u>7.56</u>	<u> </u>
	<u>1517</u>	<u>15</u>	<u>16.58</u>	<u>63.4</u>	<u>6050</u>	<u>7.56</u>	<u> </u>
Sample	<u>1640</u>	<u>15</u>	<u>11.11</u>	<u>63.4</u>	<u>6050</u>	<u>7.56</u>	<u> </u>
Sample ID: <u>UANG-SL-MW#3-60K</u>				Sample Equipment Decontamination Date/Time: <u>8/24/95</u>			
Comments:							
Prepared by: <u>D. Foote</u>		Date: <u>8/24/95</u>		Reviewed By:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>SL</u>		Project No.:		
Sample Start Date: <u>8/24/95</u>		Time:		Well No./Field Sample No.: <u>MW 04</u>				
Installation:				Log Book Ref. No.:		Page No.:		
Contractor:				Sampler (s)				
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet		
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet		
Inside Casing Diameter:		<u>2</u> inches		Borehole Diameter		<u>8.25</u> inches		
Well Labeled (Yes/No) <u>(No)</u>				Outside Casing Diameter		Inches		
Well Secure (Yes/No) <u>(No)</u>				Comments:				
PID Serial No.: <u>PA930254</u>		Reading <u>0.0</u> ppm		Background		<u>0.0</u> ppm		
Original SWL (BTOC): <u>5.97</u>		Final SWL (BTOC):		Screened Interval				
Weather-wind: <u>PC 5-10</u> mph		Precipitation <u>None</u>		Air Temperature: <u>88°</u> F				
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor:				
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness				
Depth to Water (BTOC): <u>5.97</u>		Depth of Well (BTOC): <u>14.58</u>		Depth BTOC of Pump:				
Sampling Method (Pump or Bailer) <u>Bailer</u>				Purged water (drummed/labeled)				
Type: <u>Pressure</u>				Drum Number				
Purge Method <u>bailer</u>				Are parameters 20% of purge value? (Y/N)				
Purge Volume (Column height x gals/ft) <u>8.61 x 1.32 = 11.4</u>				No. Purge volumes: <u>3 = 34</u>				
METER TYPE								
SERIAL NUMBERS-Conductivity:			pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)	
Initial								
Development/ Purge Cycle	<u>1820</u>	<u>5.0</u>	<u>12.86</u>	<u>62.4</u>	<u>14,470</u>	<u>8.30</u>		
	<u>1300</u>	<u>dry</u>						
Sample	<u>1836</u>	<u>5.2</u>	<u>7.78</u>	<u>64.6</u>	<u>14,590</u>	<u>8.29</u>		
Sample ID: <u>UANG-S6-MW04-GW2</u>				Sample Equipment Decontamination Date/Time: <u>8/24/95 1905</u>				
Comments:								
Prepared by: <u>Paul Smith</u> Date: <u>8/24/95</u> Reviewed By: Date:								

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>56</u>		Project No.:	
Sample Start Date: <u>8/24/95</u>		Time: <u>1715</u>		Well No./Field Sample No.: <u>MW05</u>			
Installation:				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s)			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading <u>5.4</u> ppm		Background <u>0.0</u> ppm			
Original SWL (BTOC): <u>7.04</u>		Final SWL (BTOC):		Screened Interval			
Weather-wind: <u>PL 5-15 mph</u>		Precipitation <u>None</u>		Air Temperature: <u>90° F</u>			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor: <u> </u>			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC): <u>7.04</u>		Depth of Well (BTOC): <u>13.92</u>		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>Bailer</u>				Purged water (drummed/labeled)			
Type: <u>Pressure</u>				Drum Number			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>6.52 x 1.32 = 8.6</u>				No. Purge volumes: <u>3 x 24 gal</u>			
METER TYPE <u>Hudac</u>							
SERIAL NUMBERS-Conductivity: <u>9304</u>		pH: <u>8.04</u>		Temperature: <u>9304</u>		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial							
Development/							
Purge Cycle	<u>1728</u>	<u>2.50</u>	<u>9.25</u>	<u>62.3</u>	<u>9430</u>	<u>8.25</u>	
	<u>1755</u>	<u>24.0</u>	<u>9.82</u>	<u>62.8</u>	<u>9620</u>	<u>8.15</u>	
Sample	<u>1918</u>	<u>24.0</u>	<u>7.02</u>	<u>62.5</u>	<u>9570</u>	<u>8.15</u>	
Sample ID: <u>UAG-56-MW05-GW2</u>				Sample Equipment Decontamination Date/Time: <u>8/24/95 1930</u>			
Comments:							
Prepared by: <u>[Signature]</u> Date:				Reviewed By: Date:			

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>57</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>8/21/95</u>		Time: <u>1530</u>		Well No./Field Sample No.: <u>MW1</u>			
Installation: <u>Utah ANG Base</u>				Log Book Ref. No.: <u>3</u>		Page No.:	
Contractor: <u>Parsons ES</u>				Sampler (s) <u>P. Foote</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter:		<u>2</u> inches		Borehole Diameter		<u>8.5</u> Inches	
Well Labeled (Yes/No) <u>(Yes)</u>				Outside Casing Diameter <u>—</u> Inches			
Well Secure (Yes/No) <u>(Yes)</u>				Comments:			
PID Serial No.: <u>PA930254</u>		Reading <u>3.8</u> ppm		Background <u>0.0</u> ppm			
Original SWL (BTOC): <u>6.35</u>		Final SWL (BTOC):		Screened Interval			
Weather-wind: <u>PC 5-15</u> mph		Precipitation <u>None</u>		Air Temperature: <u>92°</u> F			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor: <u>—</u>			
Depth to Product (BTOC): <u>—</u>		Depth to Interface/Water <u>—</u>		Product Thickness <u>—</u>			
Depth to Water (BTOC): <u>6.35</u>		Depth of Well (BTOC): <u>16.68</u>		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)			
Type:				Drum Number <u>107</u>			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>10.33' X 0.163</u>				<u>2.60</u>		No. Purge volumes: <u>3 = 5 gallons</u>	
METER TYPE <u>Hvdae</u>		SERIAL NUMBERS-Conductivity: <u>9304</u>		pH: <u>9304</u>		Temperature: <u>9304</u>	
Turbidity: <u>—</u>							
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1545</u>	<u>1</u>	<u>6.35</u>	<u>64.7</u>	<u>1,770</u>	<u>7.69</u>	
Development/ Purge Cycle	<u>1550</u>	<u>3</u>	<u>11.40</u>	<u>64.8</u>	<u>1,870</u>	<u>7.69</u>	
	<u>1557</u>	<u>5</u>	<u>11.25</u>	<u>63.4</u>	<u>1,790</u>	<u>7.82</u>	
<u>8/22/95</u> Sample	<u>1120</u>		<u>6.22</u>	<u>63.6</u>	<u>1,780</u>	<u>7.80</u>	
Sample ID: <u>Utah 57 MW01 GW2</u>				Sample Equipment Decontamination Date/Time: <u>8/22/95 11:40</u>			
Comments:							
Prepared by: <u>PAF</u>		Date: <u>8/21/95</u>		Reviewed By:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>S7</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>8/21/95</u> Time: <u>1400</u>				Well No./Field Sample No.: <u>MW2</u>			
Installation: <u>Utah ANG Base</u>				Log Book Ref. No.: <u>3</u>		Page No.:	
Contractor: <u>Parsons ES</u>				Sampler(s) <u>P. FOOTE</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS):		feet		Bottom of Screen (BGS):		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter <u>8.5</u>		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter <u> </u> Inches			
Well Secure (Yes/No)				Comments:			
PID Serial No.: <u>PA 930254</u>		Reading <u>4.7</u> ppm		Background <u>0.0</u>		ppm	
Original SWL (BTOC): <u>6.89</u>		Final SWL (BTOC): <u>6.67</u>		Screened Interval <u> </u>			
Weather-wind: <u>PC 5-10 mph</u>		Precipitation <u>None</u>		Air Temperature: <u>88</u> ° F			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor: <u> </u>			
Depth to Product (BTOC): <u> </u>		Depth to Interface/Water <u> </u>		Product Thickness <u> </u>			
Depth to Water (BTOC): <u>6.89'</u>		Depth of Well (BTOC): <u>16.45'</u>		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)			
Type:				Drum Number <u>106</u>			
Purge Method <u>Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>9.6' x 0.69 = 5 gallons</u>				No. Purge volumes: <u>3</u>			
METER TYPE <u>H/DAC</u>							
SERIAL NUMBERS-Conductivity: <u>9304</u>		pH: <u>9304</u>		Temperature: <u>9304</u>		Turbidity: <u> </u>	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1435</u>	<u>1</u>	<u>6.89</u>	<u>72.0</u>	<u>3,030</u>	<u>7.75</u>	
Development/ Purge Cycle	<u>1450</u>	<u>14</u>	<u>6.90</u>	<u>68.8</u>	<u>2,600</u>	<u>7.65</u>	
	<u>1455</u>	<u>15</u>	<u>6.90</u>	<u>69.0</u>	<u>2650</u>	<u>7.95</u>	
8/22/95 Sample	<u>0915</u>		<u>6.67</u>	<u>69.0</u>	<u>2670</u>	<u>7.85</u>	
Sample ID: <u>Utah-S7-MW02-W2</u>				Sample Equipment Decontamination Date/Time: <u>8/22/95 10:30</u>			
Comments:							
Prepared by: <u>Paul H. [Signature]</u> Date: <u>8/22/95</u>				Reviewed By: <u> </u> Date: <u> </u>			

Groundwater Sampling Forms

1995 Resampling

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Site 1</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>11/6/95</u>		Time: <u>1245</u>		Well No./Field Sample No.: <u>MW1</u>			
Installation: <u>WANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s) <u>TM Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>5.35</u>		feet		Bottom of Screen (BGS): <u>15.35</u>		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter			
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
Original SWL (BTOC): <u>6.78</u>		Final SWL (BTOC): <u>6.89</u>		Screened Interval			
Weather-wind: mph		Precipitation <u>none, threatening</u>		Air Temperature: <u>52 °F</u>			
Water Level Measurement: <u>Solinst</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or <u>Bailer</u>)				Purged water (drummed/labeled)			
Type: <u>Taflon 1.5 liter</u>				Drum Number <u>115</u>			
Purge Method <u>bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>15-6.78 x .163 = 1.34 gal</u>				No. Purge volumes: <u>3 to 5</u>			
METER TYPE <u>Hydac 910</u>							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1300</u>	<u>—</u>	<u>6.78</u>	<u>63</u>	<u>3,020</u>	<u>9.29</u>	
Development/ Purge Cycle		<u>5 gal</u>		<u>64.5</u>	<u>2,920</u>	<u>9.40</u>	
		<u>"</u>		<u>64.4</u>	<u>2,940</u>	<u>9.40</u>	
		<u>"</u>		<u>64.4</u>	<u>2,940</u>	<u>9.40</u>	
Sample	<u>1320</u>		<u>6.89</u>				
Sample ID: <u>WANG-S1-MW1-6W2</u> Sample Equipment Decontamination Date/Time:							
Comments: <u>sediment free, amber color, more clear after purging</u>							
<u>re-sampled for VOCs only</u>							
Prepared by: <u>TM Jensen</u>		Date: <u>Nov 6, 1995</u>		Reviewed By:		Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>SLK1</u>		Project No.:	
Sample Start Date: <u>11/6/95</u>		Time: <u>1400</u>		Well No./Field Sample No.: <u>MW2</u>			
Installation: <u>WANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s) <u>TM Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>4</u>		feet		Bottom of Screen (BGS): <u>14</u>		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter			
Well Secure (Yes/No) <u>(No)</u>				Comments: <u>Casing well not secure</u>			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC): <u>6.95</u>		Final SWL (BTOC): <u>7.07</u>		Screened Interval			
Weather-wind: mph		Precipitation <u>none, overcast</u>		Air Temperature: <u>50</u> ° F			
Water Level Measurement: <u>5.125</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>(Pump)</u>				Purged water (drummed/labeled)			
Type: <u>To Flow</u>				Drum Number <u>111</u>			
Purge Method <u>SAT</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>14 - 6.95 x .163 = 1.15</u>				No. Purge volumes: <u>345</u>			
METER TYPE <u>Hydra 910</u>		pH:		Temperature:		Turbidity:	
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1400	—	6.95	60.4	3,510	8.46	
Development/ Purge Cycle		5 gal	—	61.5	3,600	8.45	
				61.9	3,480	8.48	
				3,480 TMS	8.48		
				62.0	3,540	8.48	
Sample	1410	—	7.07	—	—	—	
Sample ID: <u>WANG-S1-MW2-GW2</u>				Sample Equipment Decontamination Date/Time:			
Comments: <u>water amber, but relatively free of sediment. clearer after purging</u> <u>re-sampled for VOCs only</u>							
Prepared by: <u>TM Jensen</u> Date: <u>Nov 6, 1995</u> Reviewed By: Date:							

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Site 2</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>1800 6 Nov 95</u> Time: <u>1800</u>				Well No./Field Sample No.: <u>MW1</u>			
Installation: <u>UANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler(s) <u>T.M. Jansen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>4</u>		feet		Bottom of Screen (BGS): <u>14</u>		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter			
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC): <u>6.15</u>		Final SWL (BTOC): <u>5.85</u>		Screened Interval			
Weather-wind: <u>calm</u> mph		Precipitation <u>none</u>		Air Temperature: <u>50</u> ° F			
Water Level Measurement: <u>Selfist</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer)				Purged water (drummed/labeled)			
Type: <u>T-tube</u>				Drum Number <u>116</u>			
Purge Method <u>SA</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>15 - 6.15 X .163 = 1.44</u>				No. Purge volumes: <u>365</u>			
METER TYPE <u>Hobac 910</u>							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1605</u>		<u>6.15</u>	<u>59.4</u>	<u>10,810</u>	<u>8.51</u>	
Development/ Purge Cycle							
<p><i>Did not take 3 successive measurements to avoid contact w/ water that may be contaminated with chlorinated solvents purged 5 gal</i></p>							
Sample	<u>1630</u>		<u>5.85</u>				
Sample ID: <u>UANG-S2-MW1-GW2</u>				Sample Equipment Decontamination Date/Time:			
Comments: <u>Well is contaminated based on Aug 95 sampling resampled for VOCs only</u>							
Prepared by: <u>T.M. Jansen</u> Date: <u>6 Nov 1995</u> Reviewed By: Date:							

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Srk 2</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>1500 Nov 6, 1995</u> Time: <u>1500</u>				Well No./Field Sample No.: <u>MW2</u>			
Installation: <u>UANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s) <u>T.M. Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>4</u>		feet		Bottom of Screen (BGS): <u>14</u>		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter			
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC): <u>6.68</u>		Final SWL (BTOC): <u>6.80</u>		Screened Interval			
Weather-wind: <u>calm</u> mph		Precipitation <u>none</u>		Air Temperature: <u>50</u> °F			
Water Level Measurement: <u>solinst</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or <u>Bailer</u>)				Purged water (drummed/labeled)			
Type: <u>Teflon</u>				Drum Number <u>112</u>			
Purge Method <u>S4A</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>14 - 6.68 x .163 = 1.19</u>				No. Purge volumes: <u>3.45</u>			
METER TYPE <u>Hudac 910</u>							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (°F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1512	—	6.68	57.4	1,351	8.0	
Development/ Purge Cycle		5 gal		58.4	1,160	8.05	
			58.7	1,157	8.01		
Sample	1530		6.80				
Sample ID: <u>UANG-S2-MW2-GW2</u>				Sample Equipment Decontamination Date/Time:			
Comments: <u>collected duplicate UANG-S2-MW2-GW2 for VOCs only</u>							
<u>water cloudy, not much sediment</u>							
Prepared by: <u>T.M. Jensen</u>				Date: <u>Nov 6, 1995</u>		Reviewed By:	
						Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Site 3</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>7 Nov 95</u>		Time: <u>1000</u>		Well No./Field Sample No.: <u>MW1</u>			
Installation: <u>UANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler(s) <u>TM Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>4</u>		feet		Bottom of Screen (BGS): <u>14</u>		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secured (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC): <u>7.78</u>		Final SWL (BTOC): <u>7.77</u>		Screened Interval			
Weather-wind: mph		Precipitation <u>none</u>		Air Temperature: <u>48</u> ° F			
Water Level Measurement: <u>Static</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>pressure bailer w/ filter MW</u>				Purged water (drummed/labeled)			
Type: <u>700 cm² Norwell filter MW T-flu bailer</u>				Drum Number <u>113</u>			
Purge Method <u>T-flu Bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>17.13 x 7.78 x .163 = 152 gal</u>				No. Purge volumes: <u>3 @ 5</u>			
METER TYPE <u>Hydax 910</u>							
SERIAL NUMBER		Conductivity:		pH:		Temperature:	
Turbidity:							
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1010		7.78	59.7	7,960	7.32	
Development/ Purge Cycle		5 gal		61.0	12,300	7.5	
			61.5	14,500	7.53		
Sample	1045		7.77	61.4	12,350	7.61	
Sample ID: <u>UANG-S3-MW1-GW2</u> Sample Equipment Decontamination Date/Time:							
Comments: <u>water darker colored gray, bubbly in 5 gal bucket</u>							
<u>re sampled for VOCs only</u>							
Prepared by: <u>TM Jensen</u> Date: <u>11/7/95</u> Reviewed By: Date:							

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Site 6</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>11/8/95</u>		Time: <u>0900</u>		Well No./Field Sample No.: <u>MW1</u>			
Installation: <u>KANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s) <u>TM Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>5.24</u>		feet		Bottom of Screen (BGS): <u>15.24</u>		feet	
Inside Casing Diameter: <u>7</u>		inches		Borehole Diameter: <u>10 1/4</u>		Inches	
Well Labeled (<input checked="" type="checkbox"/> Yes/ <input type="checkbox"/> No)				Outside Casing Diameter: _____ Inches			
Well Secure (<input checked="" type="checkbox"/> Yes/ <input type="checkbox"/> No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
ppm		ppm		ppm		ppm	
Original SWL (BTOC): <u>6.52</u>		Final SWL (BTOC): <u>6.57</u>		Screened Interval			
Weather-wind: <u>calm</u> mph		Precipitation: <u>none</u>		Air Temperature: <u>50</u> °F			
Water Level Measurement: <u>solinst</u>		Serial No.: <u>13327</u>		Odor: <u>sulfur smell</u>			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>pressure bailer w/ filter</u>				Purged water (drummed/labeled)			
Type: <u>700 cm² filter, vacuum pump</u>				Drum Number			
Purge Method <u>Teflon bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>15 - 6.52 x .163 = 1.42</u>				No. Purge volumes: <u>365</u>			
METER TYPE <u>Hydax 910</u>		Conductivity:		pH:		Temperature:	
SERIAL NUMBERS		Conductivity:		pH:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	ORP (mV) Turbidity (NTU)
Initial	<u>0945</u>		<u>6.52</u>	<u>65.4</u>	<u>< 20,000</u>	<u>7.84</u>	
Development/ Purge Cycle		<u>5 gal</u>		<u>67.4</u>	<u>17,960</u>	<u>8.29</u>	
			<u>68.1</u>	<u>19,990</u>	<u>8.30</u>		
Sample	<u>1015</u>			<u>68.1</u>	<u>19,980</u>	<u>8.30</u>	<u>- 220</u>
Sample ID: <u>KANG-56-MW1-602</u>				Sample Equipment Decontamination Date/Time:			
Comments: <u>water has sulfur smell and is cloudy, dk. gray</u>							
<u>Sampled for arsenic only (filtered)</u>							
Prepared by: <u>TM Jensen</u>				Date: <u>8 Nov 1995</u>		Reviewed By: _____ Date: _____	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Site 6</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>11/8/95</u>				Time: <u>1300</u>		Well No./Field Sample No.: <u>MW2</u>	
Installation: <u>UANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s) <u>TM Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>5.26</u>		feet		Bottom of Screen (BGS): <u>15.26</u>		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter <u>10 1/4</u>		Inches	
Well Labeled <input checked="" type="checkbox"/> (Yes/No)				Outside Casing Diameter			
Well Secure <input checked="" type="checkbox"/> (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC): <u>8.10</u>		Final SWL (BTOC): <u>8.15</u>		Screened Interval			
Weather-wind: <u>SW</u>		mph <u>5</u>		Precipitation <u>none</u>		Air Temperature: <u>60</u> ° F	
Water Level Measurement: <u>solinst</u>		Serial No.: <u>13327</u>		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>pressure bailer w/ filter</u>				Purged water (drummed/labeled)			
Type: <u>700 cm² Norwell filter</u>				Drum Number			
Purge Method <u>Teflon bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>15.26 - 8.10 x 1.163 = 1.17</u>				No. Purge volumes: <u>365</u>			
METER TYPE <u>Hydax 910</u>		pH:		Temperature:		Turbidity:	
SERIAL NUMBERS-Conductivity:							
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	1300		8.10	66.0	187170	8.68	
Development/ <u>Purge Cycle</u>		5 gal		66.0	14,520	8.69	
			59.8	14,100	8.67		
Sample	1345		8.15	66.0	14,400	8.68	
Sample ID:							
Sample Equipment Decontamination Date/Time:							
Comments: <u>resample for arsenic (filtered)</u>							
<u>water color brown free of sediment</u>							
Prepared by: <u>TM Jensen</u>				Date: <u>8 Nov. 1995</u>		Reviewed By:	
						Date:	

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Site 4</u>		Project No.: <u>724017</u>	
Sample Start Date: <u>11/8/95</u>		Time: <u>1400</u>		Well No./Field Sample No.: <u>MW3</u>			
Installation: <u>UANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s) <u>TM Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>4.75</u>		feet		Bottom of Screen (BGS): <u>14.75</u>		feet	
Inside Casing Diameter: <u>2</u>		inches		Borehole Diameter <u>10 1/4</u>		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter			
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC): <u>11.38</u>		Final SWL (BTOC): <u>11.39</u>		Screened Interval			
Weather-wind: <u>calm</u>		mph		Precipitation <u>none, clear</u>		Air Temperature: <u>60</u> ° F	
Water Level Measurement: <u>solinst</u>		Serial No.: <u>13327</u>		Odor: <u>none</u>			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or Bailer) <u>pressure bailer w/ filter</u>				Purged water (drummed/labeled)			
Type: <u>700 cm² Howell filter</u>				Drum Number			
Purge Method <u>feet/bailer</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>12.15 - 11.38 x .163 = 0.94</u>				No. Purge volumes: <u>365</u>			
METER TYPE <u>Hydra</u>		pH: <u>9.10</u>					
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial		<u>1400</u>	<u>11.38</u>	<u>64.7</u>	<u>6,200</u>	<u>7.53</u>	
Development/ Purge Cycle		<u>5 gal</u>		<u>63.4</u>	<u>6,230</u>	<u>7.60</u>	
			<u>62.9</u>	<u>6,270</u>	<u>7.44</u>		
Sample		<u>1445</u>	<u>11.39</u>	<u>62.7</u>	<u>6,300</u>	<u>7.42</u>	
Sample ID: <u>UANG-56-MW3-GW2</u> Sample Equipment Decontamination Date/Time:							
Comments: <u>Resample for arsenic (filtered)</u>							
<u>water brown</u>							
Prepared by: <u>TM Jensen</u> Date: <u>8 Nov 1995</u> Reviewed By: Date:							

PARSONS ENGINEERING SCIENCE, INC.

GW PURGING/SAMPLING/DEVELOPMENT FORM				Sample Site I.D.: <u>Site 6</u>		Project No.:	
Sample Start Date: <u>11/8/95</u>		Time: <u>1040</u>		Well No./Field Sample No.: <u>MW4</u>			
Installation: <u>UANG</u>				Log Book Ref. No.:		Page No.:	
Contractor:				Sampler (s) <u>T.M. Jensen</u>			
Top of Filter Pack (BGS):		feet		Bottom of Filter Pack (BGS):		feet	
Top of Screen (BGS): <u>4</u>		feet		Bottom of Screen (BGS): <u>14</u>		feet	
Inside Casing Diameter:		inches		Borehole Diameter		Inches	
Well Labeled (Yes/No)				Outside Casing Diameter		Inches	
Well Secure (Yes/No)				Comments:			
PID Serial No.:		Reading		ppm		Background	
						ppm	
Original SWL (BTOC): <u>6.20</u>		Final SWL (BTOC): <u>6.30</u>		Screened Interval			
Weather-wind: mph		Precipitation <u>none</u>		Air Temperature: <u>58</u> ° F			
Water Level Measurement: <u>calm</u>		Serial No.:		Odor:			
Depth to Product (BTOC):		Depth to Interface/Water		Product Thickness			
Depth to Water (BTOC):		Depth of Well (BTOC):		Depth BTOC of Pump:			
Sampling Method (Pump or <u>Railer</u>) <u>pressure w/ filter</u>				Purged water (drummed/labeled)			
Type: <u>700 cm² filter - Norwell</u>				Drum Number			
Purge Method <u>fellon bucket</u>				Are parameters 20% of purge value? (Y/N)			
Purge Volume (Column height x gals/ft) <u>14 - 6.20 x .163 = 1.27</u>				No. Purge volumes: <u>3 to 5</u>			
METER TYPE <u>Hydra 910</u>							
SERIAL NUMBERS-Conductivity:		pH:		Temperature:		Turbidity:	
Description	Time	Volume Purged (Gallons)	Water Level (ft. BTOC)	Temp (° F)	Conductivity umhos/cm	pH (s.u.)	Turbidity (NTU)
Initial	<u>1040</u>		<u>6.20</u>	<u>61.7</u>	<u>17,150</u>	<u>8.52</u>	
Development/ <u>Purge Cycle</u>		<u>5 gal</u>		<u>61.4</u>	<u>16,220</u>	<u>8.48</u>	
				<u>61.0</u>	<u>13,500</u>	<u>8.39</u>	
Sample	<u>1115</u>			<u>60.9</u>	<u>13,680</u>	<u>8.41</u>	
Sample ID: <u>UANG-S6-MW4-GW2</u>		Sample Equipment Decontamination Date/Time:					
Comments: <u>resample for arsenic only, water fairly free of sediment</u> <u>filtered</u>							
Prepared by: <u>T.M. Jensen</u>		Date: <u>8 Nov 1995</u>		Reviewed By:		Date:	

APPENDIX D
CHAIN-OF-CUSTODY FORMS

APPENDIX D

TABLE OF CONTENTS

Chain-of-Custody Forms - 1992, 1993 and 1994 D-1

Chain-of Custody Forms - 1995 D-47

Chain-of-Custody Forms

1992, 1993 and 1994

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		STATION LOCATION		NO. OF CONTAINERS	PARAMETER	REMARKS
STA. NO.	DATE	TIME	COMB	GRAB				
UT04		Utah Air National Guard		F. H. Graves				
SAMPLERS: (Signature)		James M. Jones		F. H. Graves				
Sample 1	10/27	1600		X	UANG-PI5 (0-2)	1-3" ring	X	
Sample 2	10/27	1600	X		UANG-PI5 (0-2)	1-500ml	X	
Sample 1	10/27	1600	X		UANG-PI5 (0-2)	1-500ml	X	
Sample 1	10/27	1600	X		UANG-PI5 (0-2)	1-500ml	X	
Sample 2	10/27	1620		X	UANG-PI5 (6-8)	1-3" ring	X	
Sample 2	10/27	1620	X		UANG-PI5 (6-8)	1-500ml	X	
Sample 2	10/27	1625	X		UANG-PI5 (6-8)	1-500ml	X	
Sample 2	10/27	1627	X		UANG-PI5 (6-8)	1-500ml	X	
→ UANG-PI5 (6-8)								
MS/MSD FOR VOCs, SVOCs, TPH, PCB/PEST, METS								
Relinquished by: (Signature)						Relinquished by: (Signature)		Date / Time
F. H. Graves						F. H. Graves		10-27-92 17:45
Relinquished by: (Signature)						Relinquished by: (Signature)		Date / Time
F. H. Graves						F. H. Graves		
Relinquished by: (Signature)						Relinquished by: (Signature)		Date / Time
F. H. Graves						F. H. Graves		10-27-92 17:45
Remarks Temp - 6°C						Remarks		

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CON-TAINERS		PARAMETER		REMARKS
STA. NO.	DATE	TIME	STATION LOCATION	COMP	GRAB	850/8020 820/8080 TPH/PPM		
CS	2-12-93	1030	UANG- C51	X		X	X	All samples are - sediment and are preserved with Ice.
CS	2-12-93	1057	UANG- C52	X		X	X	
CS	2-12-93	1126	UANG- C53	X		X	X	
CS	2-12-93	1155	UANG- C54	X		X	X	
CS	2-12-93	1415	UANG- C55	X		X	X	
CS	2-12-93	1415	UANG- C55-MS	X		X	X	
CS	2-12-93	1415	UANG- C55-MSD	X		X	X	
CS	2-12-93	1501	UANG- C56	X		X	X	
CS	2-12-93	1523	UANG- C57	X		X	X	
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks

Fed Ex # 6288611700

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CON-TAINERS		PARAMETER		REMARKS
SAMPLERS: (Signature)		STATION LOCATION						
STA. NO.	DATE	TIME	COMP	GRAB				
11-08	2-11-93	1728		X	UANG- CW1	3	X	All samples presented with HCl
11-08	2-11-93	1735		X	UANG- CW2	3	X	
11-08	2-11-93	1428		X	UANG- CW3	3	X	
11-08	2-11-93	1428		X	UANG- CW3 MS	3	X	
11-08	2-11-93	1428		X	UANG- CW3 MSD	3	X	
11-08	2-11-93	1610		X	UANG- CW3 EDR	3	X	
11-08	2-11-93	1115		X	UANG- CW4	3	X	
11-08	2-11-93	1532		X	UANG- FB8	3	X	
11-08	2-11-93	0932		X	UANG- TR22	2	X	
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks

Fed Ex # 6288611711

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CONTAINERS		PARAMETER		REMARKS	
STA. NO.	DATE	TIME	COMP.	GRAB.	STATION LOCATION	NO. OF CONTAINERS	PARAMETER	REMARKS	
51	12/1/92	1005		X	UANG-51-5B1(0-2)	1-8oz	Ice	please send results to Gene A. Wright	
51	12/1/92	1015		X	UANG-51-5B1(4-6.5)	1-8oz	Ice	Project Manager.	
51	12/1/92	1110		X	UANG-51-5B3(2-4)	1-8oz	Ice		
51	12/1/92	1120		X	UANG-51-5B3(4-6.5)	1-8oz	Ice		
51	12/1/92	1115		X	UANG-51-5B3(6.5-8.5)	1-8oz	Ice		
51	12/1/92	1030		X	UANG-FB1	7	H ₂ SO ₄ , HCl, HNO ₃ , Ice		
51	12/1/92	0930		X	UANG-TB8 - (BROKEN)	11-10A	HCl/Ice		
51	12/1/92	1300		X	UANG-RB6-51	2-10	Ice		
51	12/1/92	1800		X	UANG-RB7-56	7	H ₂ SO ₄ , HCl, HNO ₃ , Ice		
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Relinquished by: (Signature)		Date / Time	
Daren Bost		12/1/92 18:15							
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Relinquished by: (Signature)		Date / Time	
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Relinquished by: (Signature)		Date / Time	

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CON-TAINERS		PARAMETER		REMARKS	
72401740205		UANG							
SAMPLERS: (Signature)		STATION LOCATION							
Amie E. ...		Salt Lake							
STA. NO.	DATE	TIME	COMP.	GRAB.					
Site 1	10/26	1031		X	UANG-S1-SB4 (7.5-9.5)	1			Soil Matrix, kept at $< 4^{\circ}C$
	10/26	1323		X	UANG-S1-SB4 (3.5-5.5)	1			
	11/26	1125		X	UANG-S1-SB5 (1-3)	1			
	10/26	1143		X	UANG-S1-SB5 (5-7)	1			
	10/26	1311		X	UANG-S1-SB6 (1-3)	1			
	10/26	1323		X	UANG-S1-SB6 (3-5)	1			
	10/26	1331		X	UANG-S1-SB6 (5-7)	1			
	10/26	1407		X	UANG-S1-SB7 (1-3)	1			
	10/26	1427		X	UANG-S1-SB7 (5-7)	1			
	10/26	1524		X	UANG-S1-SB8 (1-3)	1			
	10/26	1524		X	UANG-S1-SB8 MS	1			
	10/26	1524		X	UANG-S1-SB8 MSD	1			
	10/26	1530		X	UANG-S1-SB8 (7-9)	1			
	10/26	1540		X	UANG-S1-SB8 (5-7)	1			
	10/26	1632		X	UANG-S1-SB9 (3-5)	1			
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)	
Amie E. ...									
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)	
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks	

Distribution Original Accompanies Shipment. Copy returned with Report.

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

[illegible]

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

Chain-of Custody Record

[illegible]

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of-Custody Record

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CONTAINERS		PARAMETER		REMARKS
STA. NO.	DATE	TIME	GRAB	COMP	STATION LOCATION	TPM (PM-46)	TPH (E918.1)	
UTD14-1408		UANG - Site 2						
SAMPLERS: (Signature) Robert W. Gravel								
S-2	12-3-92	1130	X		UANG-52-SB3 2.5-4.5	X	X	Ice All samples are soil unless otherwise noted.
S-2	12-3-92	1200	X		UANG-52-SB3 4.5-6.5	X	X	Ice
S-2	12-3-92	1245	X		UANG-52-SB3 6.5-8.5	X	X	Ice
S-2	12-2-92	1630	X		UANG-52-SB2 2.5-4.5	X	X	Ice Please Send Results to
S-2	12-2-92	1630	X		UANG-52-SB2 2.5-4.5	X	X	Ice Gene A. Wright
S-2	12-2-92	1700	X		UANG-52-SB2 4.5-6.5	X	X	Ice Salt Lake City, Ut.
S-2	12-2-92	1700	X		UANG-52-SB2 4.5-6.5	X	X	Ice
S-2	12-2-92	1532	X		UANG-52-SB1 5.0-7.5	X	X	Ice
S-2	12-2-92	1532	X		UANG-52-SB1 5.0-7.5	X	X	Ice
S-2	12-2-92	1445	X		UANG-52-SB1 5.5-2.5	X	X	Ice
S-2	12-2-92	1445	X		UANG-52-SB1 5.5-2.5	X	X	Ice
TR-2	12-2-92	0800	X		UANG TBZ	X	X	Ice (water sample) Ice + MEL
Relinquished by: (Signature) [Signature] Date / Time 12-3-92 1837 Received by: (Signature) [Signature] Date / Time []								
Relinquished by: (Signature) [Signature] Date / Time [] Received by: (Signature) [Signature] Date / Time []								
Relinquished by: (Signature) [Signature] Date / Time [] Received for Laboratory by: (Signature) [Signature] Date / Time []								
Remarks Fed Ex Bill # 9258743944								

Distribution Original Accompanies Shipment. Copy returned with Report.

Q

Chain-of Custody Record

D-19

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

PROJECT NAME/LOCATION

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CONTAINERS	PARAMETER				REMARKS		
STA. NO.	DATE	TIME	COMP		GRAB	STATION LOCATION	WGL (GND/10.2)	TPH (E-WLR) (PPM/10.2)		TPH (E-WLR) (PPM/10.2)	
UT01414.03				UAVG side 2, side 3, side 7							
SAMPLERS: (Signature) Darin Brast											
S7	12/17	14:00		X	UAVG S7-SB3 (4.5-6.5)	X	X	X	Ice All samples are sealed unless otherwise noted.		
S2	12/17	16:15		X	UAVG S3-SB2 (4.5-6.5)	X	X	X			
S3	12/17	16:15		X	UAVG S2-SB3 (4.5-6.5) MS	X	X	X			
S3	12/17	16:15		X	UAVG S3-SB2 (4.5-6.5) MS	X	X	X			
S3	12/17	17:00		X	UAVG S2-SB3 (4.5-6.5)	X	X	X	Please send Results to Gene A. Wright		
S3	12/17	17:10		X	UAVG S3-SB3 (4.5-6.5)	X	X	X	Salt Lake City, UT.		
S3	12/17	15:15		X	UAVG S3-SB1 (4.5-6.5)	X	X	X			
S3	12/17	15:30		X	UAVG S3-SB1 (4.5-6.5)	X	X	X			
S3	12/17	11:35		X	UAVG S2-SB4 (4.5-6.5)	X	X	X			
S3	12/17	17:45		X	UAVG TP-12	X	X	X	Ice-Hcl (water sample)		
Relinquished by: (Signature) Darin Brast				Received by: (Signature)		Date / Time 12/18/19:00		Relinquished by: (Signature)		Received by: (Signature)	
Relinquished by: (Signature)				Received by: (Signature)		Date / Time		Relinquished by: (Signature)		Received by: (Signature)	
Relinquished by: (Signature)				Received for Laboratory by: (Signature)		Date / Time		Relinquished by: (Signature)		Received by: (Signature)	

File Ex # 9250743085

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of-Custody Record

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CON-TAINERS		PARAMETER		REMARKS
DATE	TIME	DATE	TIME	DATE	TIME	DATE	TIME	
11/14/14 03		UANG - Site 2, 3, 4, 7						
SAMPLERS: (Signature) <i>James F. Bernard</i>								
STATION LOCATION								
STA. NO.	DATE	TIME	GRAB	COMP	STATION LOCATION	PARAMETER	REMARKS	
S-4	12/24/12	1400	X		UANG-54-SB8 (0.5-2.5)	X X X X	Ice All samples are soil	
S-4	12/24/12	1430	X		UANG-54-SB8 (4.5-6.5)	X X X X	Ice unless otherwise noted	
S-4	12/24/12	1527	X		UANG-54-SB9 (2.5-4.5)	X X X X	Ice	
S-4	12/24/12	1530	X		UANG-54-TB 14	X X X X	thicken) Please send Analytical	
S-4	12/24/12	1545	X		UANG-54-SB9 (4.5-6.5)	X X X X	Results To:	
S-4	12/24/12	1135	X		UANG-57-SB9 (2.5-4.5)	X X X X	Gene A. Wright	
S-4	12/24/12	1205	X		UANG-57-SB9 (8.5-9.5)	X X X X	Salt Lake City, UT.	
S-4	12/24/12	1140	X		UANG-57-SB9 (4.5-6.5)	X X X X	Ice	
S-4	12/24/12	1140	X		UANG-57-SB9 (4.5-6.5) MS	X X X X	Ice	
S-4	12/24/12	1140	X		UANG-57-SB9 (4.5-6.5) MS	X X X X	Ice	
S-4	12/24/12	1650	X		UANG-57-SB10 (4.5-6.5)	X X X X	Ice	
S-4	12/24/12	1630	X		UANG-57-SB10 (4.5-6.5)	X X X X	Ice (water)	
S-2	12/24/12	1525	X		UANG-52-SB5-6.5-8.5	X X X X	Ice	
S-2	12/24/12	1615	X		UANG-52-SB6-6.5-8.5	X X X X	Ice	
S-3	12/24/12	1420	X		UANG-53-SB5 4.0-6.0	X X X X	Ice	
Relinquished by: (Signature) <i>James F. Bernard</i>		Date / Time 12/30/12 1815		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks Fed Ex Bill # 925 874 3863

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CON-TAINERS		PARAMETER		REMARKS	
1004.14.03		UANG - Site 6 / Site 1/ Site 3				E 418.1 510 8240 510 8270 510 8080			
SAMPLERS: (Signature) Dawn Brost									
STA. NO.	DATE	TIME	COMP	GR SB	STATION LOCATION				
56	12/14/92	1410		X	UANG-56-SB9(0-2)	X	X	X	Ice
56	12/14/92	1440		X	UANG-56-SB9(6-8.5)	X	X	X	Ice
56	12/14/92	1507		X	UANG-56-SB10(0-2)	X	X	X	Ice please send results to Gene A. Wright
56	12/14/92	1545		X	UANG-56-SB10(6-8.5)	X	X	X	Ice Project Manager
56	12/14/92	1445		X	UANG-56-SB9(8.5-11)	X	X	X	Ice 2-8oz jars
53	12/14/92	1410		X	UANG-53-S54(North Sample)	X	X	X	Ice 2-8oz jars
53	12/14/92	1420		X	UANG-53-S55(South Sample)	X	X	X	Ice 2-8oz jars
53	12/14/92	1415		X	UANG-53-S56(West Sample)	X	X	X	Ice 2-8oz jars
53	12/14/92	1030		X	UANG-53-S53(Sample 3)	X	X	X	Ice
56	12/14/92	1545		X	UANG-SB-10(6-8.5)MS	X	X	X	Ice * All samples consist
56	12/14/92	1545		X	UANG-SB-10(6-8.5)MSD	X	X	X	Ice 1-8oz jar of 1 stainless capped
51	12/14/92	1036		X	UANG-SB-2(0-2)				Ice 1-8oz jar for VOA and 1-8oz jar
51	12/14/92	1055		X	UANG-SB-2(4-6.5)				Ice 1-8oz jar for SIDA + TPH unless
51	12/14/92	1055		X	UANG-SB-2(4-6.5)MS				Ice 1-8oz jar otherwise stated.
51	12/14/92	1055		X	UANG-SB-2(4-6.5)MSD				
Relinquished by: (Signature) Dawn Brost		Date / Time 12/11/92 18:15		Received by: (Signature)		Relinquished by: (Signature)		Date / Time Received by: (Signature)	
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Relinquished by: (Signature)		Date / Time Received by: (Signature)	
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks Fed Ex # 9258743911	

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CONTAINERS		PARAMETER		REMARKS	
STATION NO.		STATION LOCATION		DATE		TIME		TIME	
DATE		TIME		COMPL.		GRAB		TIME	
56	12/10/92	1670							
53	12/10/92	1945							
56	12/10/92	2000							
<p>UNANG site 6, site 3</p> <p>SAMPLERS: (Signature) <i>Darin Best</i></p>									
Relinquished by: (Signature)		Received by: (Signature)		Date / Time		Relinquished by: (Signature)		Received by: (Signature)	
<i>Darin Best</i>				12/10/92 18:00					
Relinquished by: (Signature)		Received by: (Signature)		Date / Time		Relinquished by: (Signature)		Received by: (Signature)	
Relinquished by: (Signature)		Received for Laboratory by: (Signature)		Date / Time		Remarks		Date / Time	
						FED EX AIR BILL # 9250743030			

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

PROJ. NO.		PROJECT NAME/LOCATION		PARAMETER		NO. OF CONTAINERS	STATION LOCATION	REMARKS
UTOM	WANG	DATE	TIME	GRAB	COMP.			
SAMPLERS: (Signature) Damen Boat								
56	12/14/01	1115		X		2	WANG 56-583 (6.5-9.0)	
56	12/14/01	1450		X		2	WANG 56-584 (6.0-8.5)	
56	12/14/01	1455		X		2	WANG 56-584 (8.5-11.0)	
56	12/14/01	1455		X		2	WANG 56-582 (6.0-8.5)	
56	12/14/01	1410		X		2	WANG 56-584 (8.0-7)	
56	12/14/01	1432		X		2	WANG 56-584 (7.0-11.5)	
56	12/14/01	1104		X		2	WANG 56-583 (8.5-11.5)	
56	12/14/01	0950		X		2	WANG 56-582 (2-4)	
Relinquished by: (Signature) Damen Boat				Received by: (Signature)			Date / Time 12-9-98 19:00	
Relinquished by: (Signature)				Received by: (Signature)			Date / Time	
Relinquished by: (Signature)				Received for Laboratory by: (Signature)			Date / Time	
Remarks				Date / Time		Remarks		
						Fed Ex Bill #9250743826		

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

[illegible]

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		STATION LOCATION		NO. OF CON-TAINERS		PARAMETER		REMARKS	
DATE		TIME		GRAB		COM		DATE / Time		RECEIVED BY: (Signature)	
2/4/93		1534		X		X		X		D All Vials are preserved with HCl	
2/4/93		1549		X		X		X		② PPM is preserved with HNO ₃	
2/4/93		1610		X		X		X		③ All B270 and P270 bottles are preserved with Ice.	
2/4/93		1203		X		X		X		* - one bottle is one this C.O.C and in this order the other	
2/4/93		1115		X		X		X		90ml Amber bottle is on the other C.O.C and in the other cooler.	
2/4/93		1515		X		X		X		Please send Results to:	
2/4/93		0915		X		X		X		Gene A. Wright	
										Engineering - Science, Inc.	
										Salt Lake City, UT.	
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Relinquished by: (Signature)		Date / Time	
2/4/93 1730		2/4/93 1730									
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time		Relinquished by: (Signature)		Date / Time	
2/4/93 1730		2/4/93 1730									
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks		Fed Ex # 6288611630	

Distribution Original Accompanies Shipment. Copy returned with Report.

Q

Chain-of Custody Record

Distribution Original Accompanies Shipment. Copy returned with Report.

Fed Ex # 6288611630

570-915-AM

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

ENGINEERING-SCIENCE

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.		PROJECT NAME/LOCATION		NO. OF CONTAINERS		PARAMETER		REMARKS
STA. NO.	DATE	TIME	STATION LOCATION	COMPR	GRAB	BOD/BOD ₅	WDD	
UT04.14.08		UANGS - Utah Air National Guard						
SAMPLERS: (Signature) <i>[Signature]</i>								
S7	2/3/93	1600	UANGS 57 MW1-11		X	X		① B270 was analyzed
S7	2/5/93	1745	UANGS 57 MW1-EQR-13		X	X		② TPA - Filtered + preserved with HAN ₂
S4	2/6/93	1200	UANGS 54 MW1-9		X	X		
FB6	2/6/93	1525	UANGS FB6-15		X	X		③ B210/B220 analyzed with HCl
S7	2/6/93	1753	UANGS-57-MW2-EQR-14		X	X	X	④ All samples are water and are shipped on ice.
S7	2/3/93	1720	UANGS-57-MW2-12		X	X	X	
FB	2/3/93	1104	UANGS-FB-18-GW		X	X		
Please send Results to: Gene A. Wright Engineering-Science, Inc. Salt Lake City								
Relinquished by: (Signature) <i>[Signature]</i>		Date / Time 2/3/93 1925		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature) <i>[Signature]</i>		Date / Time		Received by: (Signature)		Date / Time		Received by: (Signature)
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks Fed Ex # 6288611733

1935 Vine Street - Suite 240, Salt Lake City, Utah 84121 • 801-272-5999 • 801-272-6069 (Fax)

[illegible]

	Distribution Original Accompanies Shipment. Copy returned with Report.
--	--

THIS SET DIES:	TIME	DEADLINE	STARTED
Preparation:			
Analysis:			

[illegible][illegible]

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

Chain-of Custody Record

[illegible]

ENGINEERING-SCIENCE

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

Chain-of Custody Record

PROJ. NO.	PROJECT NAME/LOCATION			NO. OF CONTAINERS	PARAMETER	REMARKS
724017	Utah Air National Guard-FDL					
SAMPLERS: (Signature) <i>Robert Graves</i>						
STA. NO.	DATE	TIME	COMP	GRAB	STATION LOCATION	
S10	5/26	0730	X	X	UANG-S10-SB2	2-40m 10A5-6120 <i>200g</i>
S10	5/26	0940	X	X	UANG-S10-SB2	1318
S10	5/26	0954	X	X	UANG-S10-SB2	1319
S10	5/26	1049	X	X	UANG-S10-SB3	1320
S10	5/26	1102	X	X	UANG-S10-SB3	1321
S10	5/26	1334	X	X	UANG-S10-SB4	1322
S10	5/26	1353	X	X	UANG-S10-SB4	1323
Relinquished by: (Signature) <i>Robert Graves</i> Date / Time 5-26-94 1722 Received by: (Signature) <i>Mark Henderson</i> Date / Time						
Relinquished by: (Signature) <i>Robert Graves</i> Date / Time Received by: (Signature) Date / Time						
Relinquished by: (Signature) Date / Time Received for Laboratory by: (Signature) <i>Julie Wootton</i> Date / Time 5-26-94 5:22pm Remarks						

Distribution Original Accompanies Shipment. Copy returned with Report.

Chain-of-Custody Forms

1995

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

Chain-of Custody Record

PROJ. NO.	PROJECT NAME/LOCATION
-----------	-----------------------

24017 UAG / site 4

SAMPLERS: (Signature)

A. Fort

STA. NO.	DATE	TIME	COMP.	GRAB.
197-254				

✓	5/16/50	8/22/50	9027
---	---------	---------	------

5028	8/20/95	1120	✓
------	---------	------	---

✓	02/15/2018	✓
✓	02/15/2018	✓

7050	8/22/99	13300	✓
7051	8/22/99	13300	✓

9036	8/28/8	1450	✓
------	--------	------	---

9033	8/20/95	14/30	✓
------	---------	-------	---

--	--	--	--	--	--

--	--	--	--	--	--

[illegible][illegible]

--	--	--	--	--

--	--	--	--	--

[illegible]

10/10/10

Flottniquished by: (Signature)

Redeem by: (Signature)

—

Distribution Original Accompanies Shipment. Copy returned with Report.

D-48

ENGINEERING-SCIENCE

462 W. 520 Jordan Pkwy Suite 300
1935 Vine Street - Suite 240, Salt Lake City, Utah 84124 • 801-272-5999 • 801-272-6069 (Fax)
94095

Chain-of Custody Record

[illegible]

406 W. So. Jordan Pkwy, Suite 500
935 Vine Street - Suite 240, Salt Lake City, Utah 84119 • 801-272-5999 • 801-272-6069 (Fax)
84025

Chain-of Custody Record

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

402 W. S. Jordan Ave. Ste 300 84095
1935 Vine Street Suite 240, Salt Lake City, Utah 84144 • 801-272-5999 • 801-272-6069 (Fax)

Chain-of Custody Record

PROJ. NO.	PROJECT NAME/LOCATION						
724017	Utah MIA Base						
SAMPLERS: (Signature)							
P. Foote							
STA. NO.	DATE	TIME	COMP	GRAB	STATION LOCATION	NO. OF CON-TAINERS	PARAMETER
							JOC SWC TRPH Metals Residues
11	1250			✓	UAG-RB03-GWZ	10	✓
11	1320			✓	UAG-S2-MWD2-GWZ	7	✓
11	1320			✓	UAG-S2-MWD3-GWZ	7	✓
11	1420			✓	UAG-S2-MWD1-GWZ	7	✓
11	1420			✓	UAG-S2-MWD1-GWZ	7	✓
11	1600			✓	UAG-BG-MWD1-GWZ	10	✓
11	1720			✓	UAG-FB03-GWZ	10	✓
11	0930			✓	UAG-TB05-GWZ	2	✓
							MIS/MISD
							Note: Returned
							5 Cases of
							1st Amber Glass
							PAGE
Relinquished by: (Signature) _____							
Date / Time		Received by: (Signature)		Relinquished by: (Signature)		Date / Time	
8-28-95 1755		Mary Jo McElwee					
Relinquished by: (Signature) _____							
Date / Time		Received by: (Signature)		Relinquished by: (Signature)		Date / Time	
Relinquished by: (Signature) _____							
Date / Time		Received for Laboratory by: (Signature)		Date / Time		Remarks	

Distribution Original Accompanies Shipment. Copy returned with Report.

ENGINEERING-SCIENCE

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

Chain-of Custody Record

[illegible]

406 West South Jordan Parkway, Suite 300 • South Jordan, Utah 84095 • (801) 572-5999 • (801) 572-9069 (Fax)

Chain-of Custody Record

[illegible]

Distribution Original Accompanies Shipment. Copy returned with Report.

APPENDIX E
TABLE OF CONTENTS

QA/QC Report No. 1	E1-1
Data Validation Summary 1992, 1993, and 1994	
QA/QC Report No. 2	E2-1
Data Validation Summary 1995	

QA/QC Report No. 1
Data Validation Summary
1992, 1993, and 1994

QA/QC REPORT NO. 1

TABLE OF CONTENTS

LIST OF TABLES.....	iv
LIST OF ACRONYMS	v
E.1 INTRODUCTION	E1-1
E.1.1 Criteria Used to Assess Laboratory Data Quality	E1-2
E.1.2 Data Validation Qualifiers	E1-2
E.1.3 Holding Time Compliance.....	E1-2
E.2 QUALITY CONTROL ASSESSMENT	E1-49
E.2.1 Metals Analysis Using EPA Methods SW6010, SW7060, SW7421, SW7470/71, SW7740, and SW7841	E1-49
E.2.1.1 Introduction.....	E1-49
E.2.1.2 Technical Holding Times.....	E1-49
E.2.1.3 Initial and Continuing Calibration Verification.....	E1-49
E.2.1.4 Blanks	E1-49
E.2.1.5 Matrix Spike/Matrix Spike Duplicates	E1-50
E.2.1.6 Interference Check Sample	E1-50
E.2.1.7 Laboratory Control Samples	E1-50
E.2.1.8 Duplicate Sample Analysis	E1-51
E.2.1.9 ICP Serial Dilution.....	E1-51
E.2.1.10 Furnace Atomic Absorption.....	E1-51
E.2.1.11 Furnace Atomic Absorption QC	E1-51
E.2.2 Volatile Organics Analysis using EPA Method SW8240.....	E1-52
E.2.2.1 Introduction.....	E1-52
E.2.2.2 Technical Holding Times.....	E1-52
E.2.2.3 GC/MS Instrument Performance Check	E1-52
E.2.2.4 Initial Calibration	E1-52
E.2.2.5 Continuing Calibration	E1-53
E.2.2.6 Blanks	E1-53
E.2.2.7 System Monitoring Compounds (Surrogates)	E1-54
E.2.2.8 Matrix Spike/Matrix Spike Duplicates	E1-54
E.2.2.9 Laboratory Control Spikes/Laboratory Control Spike Duplicates	E1-54
E.2.2.10 Field Duplicates	E1-55
E.2.3 Purgable Halogenated Volatile Organic & Purgable Aromatic Volatile	

Organic Analyses by GC Using Methods SW8010 & SW8020.....	E1-55
E.2.3.1 Introduction.....	E1-55
E.2.3.2 Technical Holding Times.....	E1-55
E.2.3.3 Initial Calibration.....	E1-55
E.2.3.4 Continuing Calibration	E1-56
E.2.3.5 Blanks	E1-56
E.2.3.6 Surrogate Spikes	E1-56
E.2.3.7 Matrix Spike/Matrix Spike Duplicates	E1-57
E.2.3.8 Laboratory Control Sample.....	E1-58
E.2.3.9 Field Duplicates	E1-58
E.2.3.10 Additional Comments	E1-58
E.2.4 Semivolatile Organic Analysis by GC/MS Using EPA Method SW8270.....	E1-58
E.2.4.1 Introduction.....	E1-58
E.2.4.2 Holding Times	E1-58
E.2.4.3 GC/MS Instrument Performance Check	E1-59
E.2.4.4 Initial Calibration.....	E1-59
E.2.4.5 Continuing Calibration	E1-59
E.2.4.6 Blanks	E1-60
E.2.4.7 Surrogate Spike Compounds.....	E1-60
E.2.4.8 Matrix Spikes/Matrix Spike Duplicates.....	E1-63
E.2.4.9 Laboratory Control Spikes/Laboratory Control Spike Duplicates	E1-64
E.2.4.10 Internal Standards	E1-64
E.2.4.11 Field Duplicates	E1-64
E.2.5 Pesticides and PCB Analysis Using EPA Method SW 8080.....	E1-64
E.2.5.1 Introduction.....	E1-64
E.2.5.2 Technical Holding Times.....	E1-64
E.2.5.3 Initial Calibration.....	E1-65
E.2.5.4 Continuing Calibration	E1-65
E.2.5.5 Blanks	E1-65
E.2.5.6 Surrogate Spike Compounds.....	E1-66
E.2.5.7 Laboratory Control Spikes/Laboratory Control Spike Duplicates	E1-66
E.2.5.8 Matrix Spikes/Matrix Spike Duplicates.....	E1-67
E.2.5.9 Coded Field Duplicates.....	E1-68
E.2.6 Total Recoverable Petroleum Hydrocarbons Using EPA Method 418.1	E1-68
E.2.6.1 Introduction.....	E1-68
E.2.6.2 Technical Holding Time	E1-68
E.2.6.3 Initial Calibration.....	E1-69
E.2.6.4 Continuing Calibration Verification	E1-69
E.2.6.5 Blanks	E1-69

E.2.6.6	Matrix Spike/Matrix Spike Duplicates	E1-69
E.2.6.7	Laboratory Control Sample.....	E1-69
E.2.6.8	Field Duplicates	E1-70
E.2.7	Total Petroleum Hydrocarbon Using EPA Method SW8015M (Diesel And Gasoline).....	E1-70
E.2.7.1	Introduction.....	E1-70
E.2.7.2	Technical Holding Time	E1-70
E.2.7.3	Initial Calibration.....	E1-70
E.2.7.4	Continuing Calibration	E1-70
E.2.7.5	Blanks	E1-70
E.2.7.6	Surrogate Spikes	E1-71
E.2.7.7	Matrix Spike/Matrix Spike Duplicates	E1-71
E.2.7.8	Laboratory Control Sample.....	E1-71
E.2.7.9	Field Duplicates	E1-71
E.2.8	Discussion of Field QA Procedures and Results	E1-71
E.2.8.1	Introduction.....	E1-71
E.2.8.2	Trip Blanks.....	E1-71
E.2.8.3	Equipment Rinseate Blanks	E1-72
E.2.8.4	Field Blanks	E1-84
E.2.8.5	Coded Field Duplicates.....	E1-84
E.3	DATA QUALITY ASSESSMENT	E1-94
E.3.1	Precision.....	E1-94
E.3.2	Accuracy	E1-94
E.3.3	Representativeness	E1-96
E.3.4	Completeness	E1-96
E.4	CONCLUSION.....	E1-97

QA/QC REPORT NO. 1

LIST OF TABLES

No.	Title	Page
E.1	Table of Estimated Data Analytical Data Summary	E1-3
E.2	Table of Unusable Data Analytical Data Summary	E1-37
E.3	EPA Qualifiers Assigned to Analytical Results.....	E1-41
E.4	Summary of Holding Times for Environmental and QA Samples	E1-42
E.5	GC/MS Instrument Performance Check	E1-52
E.6	System Monitoring Compound Criteria	E1-54
E.7	MS/MSD Criteria for Volatile Analysis	E1-54
E.8	Pace Laboratory MS/MSD Criteria	E1-57
E.9	DataChem Laboratory MS/MSD Criteria	E1-57
E.10	Performance Check Using Decafluorotriphenylphosphine.....	E1-59
E.11	Base/Neutral/Acid Surrogate Compounds with Associated Target Analytes	E1-61
E.12	Surrogate Recovery Limits	E1-63
E.13	Semivolatile Organic MS/MSD Criteria.....	E1-63
E.14	LCS/LCSD Requirements for Pesticide Analysis.....	E1-66
E.15	Berkeley (Pace) Laboratory LCS/LCSD QC Limits	E1-66
E.16	DataChem Laboratory LCS QC Limits	E1-67
E.17	Pace Laboratory MS/MSD Requirements for Pesticide Analysis	E1-67
E.18	DataChem Laboratory MS/MSD Requirements for Pesticide Analysis.....	E1-68
E.19	QA/QC Blank Field Associations Table.....	E1-73
E.20	Trip Blanks Analytes Detected	E1-80
E.21	Split-Spoon Sampler, Bailer, and Auger Rinseate Blanks Analytes Detected.....	E1-81
E.22	Field Blanks Analytes Detected.....	E1-85
E.23	Field Duplicates	E1-87
E.24	Percent of Acceptable Accuracy and Precision Results.....	E1-95
E.25	Summary of Percent Completeness	E1-97

QA/QC REPORT NO. 1

ACRONYMS

%C	Percent Complete
%D	Percent Difference
%R	Percent Recovery
%RSD	Percent Relative Standard Deviation
ANGRC	Air National Guard Readiness Center
ASTM	American Society for Testing and Materials
BFB	Bromofluorobenzene
BNA	Base/Neutral/Acid Equivalent to Semivolatile Organic Compounds
BP	2-Fluorobiphenyl
BRCLM	Bromochloromethane
CCAL	Continuing Instrument Calibration for Organics Analysis
CCB	Continuing Calibration Blank
CCV	Continuing Calibration Verifications (for metals analysis)
CLFLB	Chlorofluorobenzene
CLP	Contract Laboratory Program
CRDL	Contract Required Detection Limit
CRQL	Contract Required Quantitation Limit
CVAA	Cold-Vapor Flameless Atomic Absorption Spectrometer
DCB	Decachlorobiphenyl or 1,2-Dichlorobenzene-d ₄
DCE	1,2-dichloroethane-d ₄
DOE/HWP	Department of Energy Hazardous Waste Plan
oC	Degrees Celsius
DFTPP	Decafluorotriphenylphosphine
ECD	Electron Capture Detection
EPA	Environmental Protection Agency
EQR	Equipment Rinseate Blank
FB	Field Blank
FBP	2-Fluorobiphenyl
GC	Gas Chromatograph

GC/MS	Gas Chromatography/Mass Spectrometry
GFAA	Graphite Furnace Atomic Absorption
HAZWRAP	Hazardous Waste Remedial Action Program
ICAL	Initial Instrument Calibration for Organics Analysis
ICB	Initial Calibration Blank
ICP	Inductively Coupled Plasma
ICS	Interference Check Sample
ICV	Initial Calibration Verification (for metals analysis)
IDL	Instrument Detection Limit
IR	Infrared
IS	Internal Standards
ISM-A	Individual Standard Mixture A
ISM-B	Individual Standard Mixture B
LCS/LCSD	Laboratory Control Sample/Laboratory Control Sample Duplicate
m/z	Mass to Charge Ratio
MDL	Method Detection Limit
Metals	13 Priority Pollutant Metals
mg/Kg	Milligrams Per Kilogram
MSA	Method of Standard Addition
MS/MSD	Matrix Spike/Matrix Spike Duplicate
NA	Not Applicable
NBZ	Nitrobenzene-d ₅
ND	Non-Detect
PB	Preparation Blank
PCBs	Polychlorinated Biphenyls
PEM	Performance Evaluation Mixture
PESTs	Pesticides
PHL	Phenol-d ₅
PQL	Practical Quantitation Limit
PRDL	Project-required Detection Limit
PRQL	Project Required Quantitation Limit

QA	Quality Assurance
QA/QC	Quality Assurance/Quality Control
QC	Quality Control
r	Linear Regression Correlation Coefficient
RB	Rinseate Blank
RCRA	Resource Conservation and Recovery Act
RPD	Relative Percent Difference
RRF	Relative Response Factor
RT	Retention Time
SAP	Sampling and Analysis Plan (1992b)
SDG	Sample Delivery Group
SI	Site Investigation
SVOCs	Semi Volatile Organic Compounds
TB	Trip Blank
TBP	2,4,6-Tribromophenol
TCLP	Toxicity Characteristic Leachate Procedure
TCX	Tetrachloro-m-xylene
TOL	Toluene-d ₈
TPH	Total Petroleum Hydrocarbons or Terphenyl-d ₁₄
TRIFL	Toluene-trifluorotoluene
TRPH	Total Recoverable Petroleum Hydrocarbons
2CP	2-Chlorophenol-d ₄
2FP	2-Fluorophenol
UANG	Utah Air National Guard
ug/g	Micrograms per Gram
ug/L	Micrograms per Liter
ug/Kg	Micrograms per Kilogram
USEPA	United States Environmental Protection Agency
VOCs	Volatile Organic Compounds

This page intentionally left blank.

QA/QC REPORT NO. 1

DATA VALIDATION SUMMARY

E.1 INTRODUCTION

Soil and groundwater samples were collected to determine the presence and/or absence and the extent of contamination present at Sites 1-7, at the Utah Air National Guard (UANG) Base and sediment, and surface water samples from the City Drain Canal which drains surface and groundwater from the Base and industrial facilities located to the south. The samples were collected following the Site Investigation (SI) Sample and Analysis Plan (SAP, 1992b). A total of 208 field samples including 127 soil, 10 sediment, and 71 aqueous samples were collected between October 22, 1992, and February 12, 1993.

Soil and water samples were collected for priority pollutant metals (PPM), volatile organic compounds (VOCs), purgable halogenated and aromatic volatile organic compounds, total recoverable petroleum hydrocarbons (TRPH), and pesticides (PESTs) and polychlorinated biphenyls (PCBs) analysis. Samples were shipped via overnight courier to Engineering-Science, Inc.-Berkeley Laboratory (now Pace Laboratory) for analysis. All samples were packed in the field and shipped on ice to maintain sample temperatures between four and six degrees centigrade (°C).

Additionally, a second sampling event was requested by HAZWRAP, and the Air National Guard Readiness Center (ANGRC) during May of 1994. One water and nine soil samples were collected from Site 10 for SW846 methods 8010/8020 and 8015 Modified (diesel and gasoline TPH). One soil sample was analyzed for 8080, 8270 and 8240 only. During October of 1994, 16 soils and three water samples were collected from Site 1, for analysis by EPA SW846 methods 8010 and 8080. On 9 December 1994 two soil samples, composited from 9 drums at Sites 1 and 10, were collected for Toxicity Characteristic Leachate Procedure (TCLP) analysis. These samples were analyzed by DataChem Laboratories of Salt Lake City, Utah.

The laboratories analyzed the samples using the following methods;

- 13 PPM by methods SW6010 and the appropriate SW7000 series,
- VOCs by method SW8240,
- Purgable halogenated volatile organics by method SW8010,
- Purgable aromatic volatile organics by method SW8020,
- Semivolatile organic compounds (SVOCs) [Base/Neutral/Acids (BNAs)] by method SW8270,
- PESTs/PCBs by method SW8080,
- TRPH by method E418.1,
- Total Petroleum Hydrocarbons (TPH), both gasoline and diesel fractions by method SW8015 Modified, and
- TCLP by extraction method 1311 and analyses methods 8240, 8270, and 3015 for 8 RCRA Metals.

The analysis methods used are specified in USEPA, 1986a, *Test Methods for Evaluating Solid Wastes*, SW846, 3rd Edition ("SW" Methods); and *Methods for Chemical Analysis of Water and Wastes*, EPA 600/4-79-0202 ("E" methods).

Level C data review and validation were performed using guidelines specified in Section 6.2 of DOE/HWP-65/R1. Specific criteria used for data assessment were based on the EPA CLP *National Functional Guidelines for Organic Data Review*; documents OLM01.0 and OLC01.0 dated December 1990; and *Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analysis*, dated July 1988.

E.1.1 Criteria Used to Assess Laboratory Data Quality

The Quality Control (QC) criteria used to assess data quality included technical holding times, initial instrument calibration (ICAL), initial and continuing calibration verification (ICV and CCV), preparation blanks (PB), initial and continuing calibration blank (ICBs and CCBs), matrix spike/matrix spike duplicates (MS/MSDs), inductively coupled plasma analysis (ICP), interference check samples (ICSs), laboratory control samples (LCSs), laboratory duplicate sample analysis, ICP serial dilution, graphite furnace atomic absorption (GFAA), and post digestion spike results.

E.1.2 Data Validation Qualifiers

Specific sample analytes traceable to QC violations were qualified as estimated ("J"), undetected ("U"), estimated as undetected ("UJ"), or unusable ("R"). Estimated and estimated as undetected field sample data are shown in Table E.1. Unusable field sample data are shown in Table E.2. The EPA qualifiers assigned to analytical results are shown in Table E.3.

E.1.3 Holding Time Compliance

For all of the analyses conducted, specific holding times applied. Table E.4 presents A Summary of Holding Times for Environmental and QA Samples. Metals are not shown because of the 180-day holding times allowed.

TABLE E. 1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Antimony	D,I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Arsenic	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Beryllium	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Cadmium	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Chromium	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Copper	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Lead	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Nickel	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Selenium	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Silver	C
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Thallium	I
UJ	Metals	CLP 12075	UANG-BG-MW1-1	Zinc	I
UJ	SVOCs	CLP 12075	UANG-BG-MW1-1	4-Nitroaniline	C
UJ	Metals	4737.01	UANG-BG-SB1 (S1)	Antimony	D
J	Metals	4737.01	UANG-BG-SB1 (S1)	Arsenic	D
J	Metals	4737.01	UANG-BG-SB1 (S1)	Beryllium	A
J	Metals	4737.01	UANG-BG-SB1 (S1)	Cadmium	A
J	Metals	4737.01	UANG-BG-SB1 (S1)	Chromium	G
J	Metals	4737.01	UANG-BG-SB1 (S1)	Lead	D
UJ	Metals	4737.01	UANG-BG-SB1 (S1)	Mercury	E
UJ	Metals	4737.01	UANG-BG-SB1 (S1)	Thallium	D,H
J	Metals	4737.01	UANG-BG-SB1 (S1)	Zinc	G
UJ	SVOCs	4737.01	UANG-BG-SB1 (S1)	4-Chloroaniline	C
UJ	SVOCs	4737.01	UANG-BG-SB1 (S1)	4-Nitroaniline	C
UJ	VOCs	4737.01	UANG-BG-SB1 (S1)	Dibromomethane	C
UJ	VOCs	4737.01	UANG-BG-SB1 (S1)	Dichlorodifluoromethane	B
UJ	Metals	4737.02	UANG-BG-SB1 (S2)	Antimony	E,D,A
J	Metals	4737.02	UANG-BG-SB1 (S2)	Arsenic	D
J	Metals	4737.02	UANG-BG-SB1 (S2)	Beryllium	A
J	Metals	4737.02	UANG-BG-SB1 (S2)	Cadmium	A
J	Metals	4737.02	UANG-BG-SB1 (S2)	Chromium	G
J	Metals	4737.02	UANG-BG-SB1 (S2)	Lead	D
UJ	Metals	4737.02	UANG-BG-SB1 (S2)	Mercury	E
J	Metals	4737.02	UANG-BG-SB1 (S2)	Zinc	G
UJ	SVOCs	4737.02	UANG-BG-SB1 (S2)	Hexachlorocyclopentadiene	C
UJ	VOCs	4737.02	UANG-BG-SB1 (S2)	Dibromomethane	C
UJ	VOCs	4737.02	UANG-BG-SB1 (S2)	Dichlorodifluoromethane	B
UJ	Metals	4806.01	UANG-CS1	Antimony	D
J	Metals	4806.01	UANG-CS1	Beryllium	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Metals	4483.01	UANG-PI-5 (0-2)	Antimony	D
J	Metals	4483.01	UANG-PI-5 (0-2)	Arsenic	D
J	Metals	4483.01	UANG-PI-5 (0-2)	Beryllium	A
UJ	Metals	4483.01	UANG-PI-5 (0-2)	Cadmium	D
J	Metals	4483.01	UANG-PI-5 (0-2)	Chromium	D
J	Metals	4483.01	UANG-PI-5 (0-2)	Copper	D,E
UJ	Metals	4483.01	UANG-PI-5 (0-2)	Mercury	E
J	Metals	4483.01	UANG-PI-5 (0-2)	Nickel	D
UJ	Metals	4483.01	UANG-PI-5 (0-2)	Selenium	D,H
UJ	Metals	4483.01	UANG-PI-5 (0-2)	Silver	D
J	Metals	4483.01	UANG-PI-5 (0-2)	Zinc	D,G
UJ	SVOCs	4483.01	UANG-PI-5 (0-2)	Benzyl Alcohol	C
UJ	SVOCs	4483.01	UANG-PI-5 (0-2)	Hexachlorocyclopentadiene	B
UJ	SVOCs	4483.01	UANG-PI-5 (0-2)	4-Chlorophenyl-phenylether	B
UJ	SVOCs	4483.01	UANG-PI-5 (0-2)	Di-n-Butylphthalate	B,C
UJ	SVOCs	4483.01	UANG-PI-5 (0-2)	3, 3'-Dichlorobenzidine	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Aldrin	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Alpha-BHC	B,C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Delta-BHC	B,C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Gamma-BHC	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	4, 4'-DDD	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	4, 4'-DDT	B,C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Dieldrin	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Endosulfan I	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Endosulfan Sulfate	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Endrin Aldehyde	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Heptachlor	C
UJ	Pesticides	4483.01	UANG-PI-5 (0-2)	Methoxychlor	B,C
UJ	Metals	4483.02	UANG-PI-5 (6-8)	Antimony	D
J	Metals	4483.02	UANG-PI-5 (6-8)	Arsenic	D
J	Metals	4483.02	UANG-PI-5 (6-8)	Beryllium	A
UJ	Metals	4483.02	UANG-PI-5 (6-8)	Cadmium	D
J	Metals	4483.02	UANG-PI-5 (6-8)	Chromium	D
J	Metals	4483.02	UANG-PI-5 (6-8)	Copper	D,G
UJ	Metals	4483.02	UANG-PI-5 (6-8)	Mercury	E
J	Metals	4483.02	UANG-PI-5 (6-8)	Nickel	D
UJ	Metals	4483.02	UANG-PI-5 (6-8)	Selenium	D,H
UJ	Metals	4483.02	UANG-PI-5 (6-8)	Silver	D
J	Metals	4483.02	UANG-PI-5 (6-8)	Zinc	D,G
UJ	SVOCs	4483.02	UANG-PI-5 (6-8)	Benzyl Alcohol	C
UJ	SVOCs	4483.02	UANG-PI-5 (6-8)	Hexachlorocyclopentadiene	B
UJ	SVOCs	4483.02	UANG-PI-5 (6-8)	4-Chlorophenyl-phenylether	B
UJ	SVOCs	4483.02	UANG-PI-5 (6-8)	Di-n-Butylphthalate	B,C
UJ	SVOCs	4483.02	UANG-PI-5 (6-8)	3, 3'-Dichlorobenzidine	C
UJ	SVOCs	4483.02	UANG-PI-5 (6-8)	bis (2-Ethylhexyl) Phthalate	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Aldrin	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Alpha-BHC	B,C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Delta-BHC	B,C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Gamma-BHC	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	4, 4'-DDD	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	4, 4'-DDT	B,C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Dieldrin	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Endosulfan I	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Endosulfan Sulfate	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Endrin Aldehyde	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Heptachlor	C
UJ	Pesticides	4483.02	UANG-PI-5 (6-8)	Methoxychlor	B,C
J	Metals	4806.01	UANG-CS1	Chromium	G
J	Metals	4806.01	UANG-CS1	Lead	F
J	Metals	4806.01	UANG-CS1	Mercury	E,A
UJ	Metals	4806.01	UANG-CS1	Selenium	D,H
UJ	Metals	4806.01	UANG-CS1	Thallium	D,H
J	Metals	4806.01	UANG-CS1	Zinc	G
J	TRPH	4806.01	UANG-CS1	TRPH	D
UJ	SVOCs	4806.01	UANG-CS1	4-Chloroaniline	C
UJ	SVOCs	4806.01	UANG-CS1	3-Nitroaniline	B,C
J	SVOCs	4806.01	UANG-CS1	Phenanthrene	A
J	SVOCs	4806.01	UANG-CS1	bis (2-Ethylhexyl) Phthalate	C
UJ	SVOCs	4806.01	UANG-CS1	Di-n-octylphthalate	C
J	SVOCs	4806.01	UANG-CS1	Benzo (k) Fluoranthene	A
UJ	Pesticides	4806.01	UANG-CS1	Aldrin	C
UJ	Pesticides	4806.01	UANG-CS1	Endrin	C
UJ	Metals	4806.02	UANG-CS2	Antimony	D
UJ	Metals	4806.02	UANG-CS2	Cadmium	E,A
J	Metals	4806.02	UANG-CS2	Chromium	G
J	Metals	4806.02	UANG-CS2	Lead	F
UJ	Metals	4806.02	UANG-CS2	Mercury	E
UJ	Metals	4806.02	UANG-CS2	Selenium	D,H
UJ	Metals	4806.02	UANG-CS2	Thallium	D,H
J	Metals	4806.02	UANG-CS2	Zinc	G
UJ	SVOCs	4806.02	UANG-CS2	3-Nitroaniline	B
UJ	Pesticides	4806.02	UANG-CS2	Aldrin	C
UJ	Pesticides	4806.02	UANG-CS2	Endrin	C
J	TRPH	4806.02	UANG-CS2	TRPH	D
UJ	Metals	4806.03	UANG-CS3	Antimony	D
J	Metals	4806.03	UANG-CS3	Beryllium	A
J	Metals	4806.03	UANG-CS3	Chromium	G
J	Metals	4806.03	UANG-CS3	Lead	F,H
UJ	Metals	4806.03	UANG-CS3	Mercury	E
UJ	Metals	4806.03	UANG-CS3	Selenium	D,H
UJ	Metals	4806.03	UANG-CS3	Thallium	D,H

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	Metals	4806.03	UANG-CS3	Zinc	G
UJ	SVOCs	4806.03	UANG-CS3	4-Chloroaniline	C
UJ	SVOCs	4806.03	UANG-CS3	3-Nitroaniline	B,C
J	SVOCs	4806.03	UANG-CS3	Pyrene	A
J	SVOCs	4806.03	UANG-CS3	Chrysene	A
J	SVOCs	4806.03	UANG-CS3	bis (2-Ethylhexyl) Phthalate	C
UJ	SVOCs	4806.03	UANG-CS3	Di-n-octylphthalate	C
UJ	Pesticides	4806.03	UANG-CS3	Aldrin	C
UJ	Pesticides	4806.03	UANG-CS3	Endrin	C
J	TRPH	4806.03	UANG-CS3	TRPH	D
UJ	Metals	4806.04	UANG-CS4	Antimony	D
J	Metals	4806.04	UANG-CS4	Beryllium	A
UJ	Metals	4806.04	UANG-CS4	Cadmium	E,A
J	Metals	4806.04	UANG-CS4	Chromium	G
J	Metals	4806.04	UANG-CS4	Lead	F
UJ	Metals	4806.04	UANG-CS4	Mercury	E
UJ	Metals	4806.04	UANG-CS4	Selenium	D,H
UJ	Metals	4806.04	UANG-CS4	Thallium	D,H
J	Metals	4806.04	UANG-CS4	Zinc	G
UJ	SVOCs	4806.04	UANG-CS4	4-Chloroaniline	C
UJ	SVOCs	4806.04	UANG-CS4	3-Nitroaniline	B,C
UJ	SVOCs	4806.04	UANG-CS4	bis (2-Ethylhexyl) Phthalate	C
UJ	SVOCs	4806.04	UANG-CS4	Di-n-octylphthalate	C
UJ	Pesticides	4806.04	UANG-CS4	Aldrin	C
UJ	Pesticides	4806.04	UANG-CS4	Endrin	C
J	TRPH	4806.04	UANG-CS4	TRPH	D
UJ	Metals	4806.05	UANG-CS5	Antimony	D
J	Metals	4806.05	UANG-CS5	Beryllium	A
J	Metals	4806.05	UANG-CS5	Chromium	G
J	Metals	4806.05	UANG-CS5	Lead	F
UJ	Metals	4806.05	UANG-CS5	Mercury	E
J	Metals	4806.05	UANG-CS5	Selenium	D,H,A
UJ	Metals	4806.05	UANG-CS5	Thallium	D,H
J	Metals	4806.05	UANG-CS5	Zinc	G
J	SVOCs	4806.05	UANG-CS5	2-Methylnaphthalene	A
J	SVOCs	4806.05	UANG-CS5	bis (2-Ethylhexyl) Phthalate	A
UJ	Metals	4806.06	UANG-CS6	Antimony	D
J	Metals	4806.06	UANG-CS6	Beryllium	A
J	Metals	4806.06	UANG-CS6	Chromium	G
J	Metals	4806.06	UANG-CS6	Lead	F
J	Metals	4806.06	UANG-CS6	Mercury	E
J	Metals	4806.06	UANG-CS6	Selenium	D,H
UJ	Metals	4806.06	UANG-CS6	Thallium	D,H
J	Metals	4806.06	UANG-CS6	Zinc	G
J	SVOCs	4806.06	UANG-CS6	Pyrene	A
J	SVOCs	4806.06	UANG-CS6	bis (2-Ethylhexyl) Phthalate	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Pesticides	4806.06	UANG-CS6	Endrin	C
J	TRPH	4806.06	UANG-CS6	TRPH	D
J	Metals	4806.07	UANG-CS7	Antimony	D,A
J	Metals	4806.07	UANG-CS7	Beryllium	A
J	Metals	4806.07	UANG-CS7	Chromium	G
J	Metals	4806.07	UANG-CS7	Lead	F
J	Metals	4806.07	UANG-CS7	Mercury	E
J	Metals	4806.07	UANG-CS7	Selenium	D,H,A
UJ	Metals	4806.07	UANG-CS7	Thallium	D,H
J	Metals	4806.07	UANG-CS7	Zinc	G
UJ	SVOCs	4806.07	UANG-CS7	3-Nitroaniline	B
J	SVOCs	4806.07	UANG-CS7	Pyrene	A
J	SVOCs	4806.07	UANG-CS7	bis (2-Ethylhexyl) Phthalate	A
UJ	Pesticides	4806.07	UANG-CS7	Endrin	C
J	TRPH	4806.07	UANG-CS7	TRPH	D
UJ	Pesticides	4806-10	UANG-CS-FB10	Heptachlor Epoxide	B
UJ	Metals	4806-10	UANG-CS-FB10	Antimony	E
UJ	Metals	4806-10	UANG-CS-FB10	Arsenic	D,F
UJ	Metals	4806-10	UANG-CS-FB10	Copper	E,A
UJ	Metals	4806-10	UANG-CS-FB10	Lead	D
UJ	Metals	4806-10	UANG-CS-FB10	Mercury	E
UJ	Metals	4806-10	UANG-CS-FB10	Nickel	E
UJ	Metals	4806-10	UANG-CS-FB10	Selenium	D
UJ	Metals	4806-10	UANG-CS-FB10	Thallium	D
UJ	Metals	4806-10	UANG-CS-FB10	Zinc	E,A
UJ	Pesticides	4806.09	UANG-CS-EQR	Heptachlor Epoxide	B
UJ	Metals	4806.09	UANG-CS-EQR	Antimony	E
UJ	Metals	4806.09	UANG-CS-EQR	Arsenic	D,F
J	Metals	4806.09	UANG-CS-EQR	Copper	E,A
UJ	Metals	4806.09	UANG-CS-EQR	Lead	D,H
UJ	Metals	4806.09	UANG-CS-EQR	Mercury	E
UJ	Metals	4806.09	UANG-CS-EQR	Nickel	E
UJ	Metals	4806.09	UANG-CS-EQR	Selenium	D
UJ	Metals	4806.09	UANG-CS-EQR	Thallium	D
UJ	Metals	4806.09	UANG-CS-EQR	Zinc	E,A
J	Metals	4804.01	UANG-CW1	Antimony	E,A
J	Metals	4804.01	UANG-CW1	Arsenic	D,F
J	Metals	4804.01	UANG-CW1	Cadmium	A
UJ	Metals	4804.01	UANG-CW1	Chromium	E,A
J	Metals	4804.01	UANG-CW1	Copper	A
UJ	Metals	4804.01	UANG-CW1	Lead	E,D
UJ	Metals	4804.01	UANG-CW1	Mercury	E
J	Metals	4804.01	UANG-CW1	Nickel	E,A
J	Metals	4804.01	UANG-CW1	Selenium	D,A
UJ	Metals	4804.01	UANG-CW1	Thallium	D,H
UJ	Metals	4804.01	UANG-CW1	Zinc	E,A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	VOCs	4804.01	UANG-CW1	Benzyl Chloride	C
UJ	VOCs	4804.01	UANG-CW1	Bromoform	B,C
UJ	VOCs	4804.01	UANG-CW1	Dibromochloromethane	C
UJ	VOCs	4804.01	UANG-CW1	Dichlorodifluoromethane	C
UJ	VOCs	4804.01	UANG-CW1	1,3-Dichloropropene	C
J	SVOCs	4804.01	UANG-CW1	Phenol	A
J	SVOCs	4804.01	UANG-CW1	2-Methylnaphthalene	A
UJ	SVOCs	4804.01	UANG-CW1	Hexachlorocyclopentadiene	C
J	SVOCs	4804.01	UANG-CW1	4-Nitrophenol	A
UJ	SVOCs	4804.01	UANG-CW1	Hexachlorobenzene	C
UJ	SVOCs	4804.01	UANG-CW1	3,3'-Dichlorobenzidine	C
J	SVOCs	4804.01	UANG-CW1	bis (2-Ethylhexyl) Phthalate	E,A
UJ	Pesticides	4804.01	UANG-CW1	Aldrin	J
UJ	Pesticides	4804.01	UANG-CW1	Alpha-BHC	J
UJ	Pesticides	4804.01	UANG-CW1	Beta-BHC	J
UJ	Pesticides	4804.01	UANG-CW1	Delta-BHC	J
UJ	Pesticides	4804.01	UANG-CW1	Gamma-BHC	J
UJ	Pesticides	4804.01	UANG-CW1	Chlordane	J
UJ	Pesticides	4804.01	UANG-CW1	4,4'-DDD	J
UJ	Pesticides	4804.01	UANG-CW1	4,4-DDE	J
UJ	Pesticides	4804.01	UANG-CW1	4,4-DDT	J
UJ	Pesticides	4804.01	UANG-CW1	Dieldrin	J
UJ	Pesticides	4804.01	UANG-CW1	Endosulfan I	J
UJ	Pesticides	4804.01	UANG-CW1	Endosulfan II	J
UJ	Pesticides	4804.01	UANG-CW1	Endosulfan Sulfate	J
UJ	Pesticides	4804.01	UANG-CW1	Endrin	J
UJ	Pesticides	4804.01	UANG-CW1	Heptachlor	J
UJ	Pesticides	4804.01	UANG-CW1	Heptachlor Epoxide	J
UJ	Pesticides	4804.01	UANG-CW1	Endrin aldehyde	J
UJ	Pesticides	4804.01	UANG-CW1	Methoxychlor	J
UJ	Pesticides	4804.01	UANG-CW1	Toxaphene	J
UJ	PCBs	4804.01	UANG-CW1	PCB_1016	J
UJ	PCBs	4804.01	UANG-CW1	PCB_1221	J
UJ	PCBs	4804.01	UANG-CW1	PCB_1232	J
UJ	PCBs	4804.01	UANG-CW1	PCB_1242	J
UJ	PCBs	4804.01	UANG-CW1	PCB_1248	J
UJ	PCBs	4804.01	UANG-CW1	PCB_1254	J
UJ	PCBs	4804.01	UANG-CW1	PCB_1260	J
UJ	Metals	4804.02	UANG-CW2	Antimony	E
J	Metals	4804.02	UANG-CW2	Arsenic	D,F
UJ	Metals	4804.02	UANG-CW2	Chromium	E,A
J	Metals	4804.02	UANG-CW2	Copper	A
J	Metals	4804.02	UANG-CW2	Lead	D
UJ	Metals	4804.02	UANG-CW2	Mercury	E
UJ	Metals	4804.02	UANG-CW2	Nickel	E
UJ	Metals	4804.02	UANG-CW2	Selenium	D,H

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Metals	4804.02	UANG-CW2	Thallium	D,H
UJ	Metals	4804.02	UANG-CW2	Zinc	E,A
UJ	VOCs	4804.02	UANG-CW2	Benzyl Chloride	C
UJ	VOCs	4804.02	UANG-CW2	Bromoform	C,B
UJ	VOCs	4804.02	UANG-CW2	Dibromochloromethane	C
UJ	VOCs	4804.02	UANG-CW2	Dichlorodifluoromethane	C
UJ	VOCs	4804.02	UANG-CW2	1,3-Dichloropropene	C
J	SVOCs	4804.02	UANG-CW2	2-Methylnaphthalene	A
UJ	SVOCs	4804.02	UANG-CW2	3-Nitroaniline	C
UJ	SVOCs	4804.02	UANG-CW2	3,3'-Dichlorobenzidine	C
J	Metals	4804.03	UANG-CW3	Antimony	E,A
J	Metals	4804.03	UANG-CW3	Arsenic	D,F
UJ	Metals	4804.03	UANG-CW3	Cadmium	A
UJ	Metals	4804.03	UANG-CW3	Chromium	E,A
UJ	Metals	4804.03	UANG-CW3	Copper	E,A
UJ	Metals	4804.03	UANG-CW3	Lead	E,D,A
UJ	Metals	4804.03	UANG-CW3	Mercury	E
UJ	Metals	4804.03	UANG-CW3	Nickel	E
J	Metals	4804.03	UANG-CW3	Selenium	D,H,A
UJ	Metals	4804.03	UANG-CW3	Thallium	D,H
UJ	Metals	4804.03	UANG-CW3	Zinc	E,A
UJ	VOCs	4804.03	UANG-CW3	Benzyl Chloride	C
UJ	VOCs	4804.03	UANG-CW3	Bromoform	B,C
UJ	VOCs	4804.03	UANG-CW3	Dibromochloromethane	C
UJ	VOCs	4804.03	UANG-CW3	Dichlorodifluoromethane	C
UJ	VOCs	4804.03	UANG-CW3	1,3-Dichloropropene	C
J	SVOCs	4804.03	UANG-CW3	Phenol	A
J	SVOCs	4804.03	UANG-CW3	1,3-Dichlorobenzene	A
J	SVOCs	4804.03	UANG-CW3	Napthalene	A
J	SVOCs	4804.03	UANG-CW3	4-Methylnaphthalene	A
UJ	SVOCs	4804.03	UANG-CW3	Hexachlorocyclopentadiene	C
UJ	SVOCs	4804.03	UANG-CW3	Hexachlorobenzene	C
UJ	SVOCs	4804.03	UANG-CW3	3,3'-Dichlorobenzidine	C
J	SVOCs	4804.03	UANG-CW3	bis (2-Ethylhexyl) Phthalate	E,A
UJ	Pesticides	4804.03	UANG-CW3	Beta-BHC	C
UJ	Pesticides	4804.03	UANG-CW3	Gamma-BHC	C
UJ	Pesticides	4804.03	UANG-CW3	Chlordane	C
UJ	Pesticides	4804.03	UANG-CW3	4,4-DDE	C
UJ	Pesticides	4804.03	UANG-CW3	4,4-DDT	C
J	Pesticides	4804.03	UANG-CW3	Dieldrin	C
UJ	Pesticides	4804.03	UANG-CW3	Endosulfan I	C
UJ	Pesticides	4804.03	UANG-CW3	Endrin	C
UJ	Pesticides	4804.03	UANG-CW3	Heptachlor Epoxide	C
UJ	Pesticides	4804.03	UANG-CW3	Methoxychlor	C
UJ	Metals	4804.05	UANG-CW3-EQR	Antimony	E
UJ	Metals	4804.05	UANG-CW3-EQR	Arsenic	D,F

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	Metals	4804.05	UANG-CW3-EQR	Cadmium	E,A
UJ	Metals	4804.05	UANG-CW3-EQR	Copper	E,D,A
UJ	Metals	4804.05	UANG-CW3-EQR	Lead	E
UJ	Metals	4804.05	UANG-CW3-EQR	Mercury	E
UJ	Metals	4804.05	UANG-CW3-EQR	Nickel	D
UJ	Metals	4804.05	UANG-CW3-EQR	Selenium	D
UJ	Metals	4804.05	UANG-CW3-EQR	Thallium	A
UJ	Metals	4804.05	UANG-CW3-EQR	Zinc	B
UJ	Pesticides	4804.05	UANG-CW3-EQR	Heptachlor Epoxide	C
UJ	VOCs	4804.05	UANG-CW3-EQR	Benzyl Chloride	B,C
UJ	VOCs	4804.05	UANG-CW3-EQR	Bromoform	C
UJ	VOCs	4804.05	UANG-CW3-EQR	Dibromochloromethane	C
UJ	VOCs	4804.05	UANG-CW3-EQR	Dichlorodifluoromethane	C
UJ	VOCs	4804.05	UANG-CW3-EQR	1,3-Dichloropropene	C
UJ	SVOCs	4804.05	UANG-CW3-EQR	Hexachlorocyclopentadiene	C
UJ	SVOCs	4804.05	UANG-CW3-EQR	Hexachlorobenzene	C
UJ	SVOCs	4804.05	UANG-CW3-EQR	3,3'-Dichlorobenzidine	C
J	Metals	4804.06	UANG-CW4	Antimony	E,A
J	Metals	4804.06	UANG-CW4	Arsenic	D,F
UJ	Metals	4804.06	UANG-CW4	Chromium	E,A
J	Metals	4804.06	UANG-CW4	Copper	A
UJ	Metals	4804.06	UANG-CW4	Lead	E,D
UJ	Metals	4804.06	UANG-CW4	Mercury	E
UJ	Metals	4804.06	UANG-CW4	Nickel	E
J	Metals	4804.06	UANG-CW4	Selenium	D,A
UJ	Metals	4804.06	UANG-CW4	Thallium	D,H
UJ	Metals	4804.06	UANG-CW4	Zinc	E,A
UJ	VOCs	4804.06	UANG-CW4	Benzyl Chloride	C
UJ	VOCs	4804.06	UANG-CW4	Bromoform	B,C
UJ	VOCs	4804.06	UANG-CW4	Dibromochloromethane	C
UJ	VOCs	4804.06	UANG-CW4	Dichlorodifluoromethane	C
UJ	VOCs	4804.06	UANG-CW4	1,3-Dichloropropene	C
J	SVOCs	4804.06	UANG-CW4	Phenol	A
J	SVOCs	4804.06	UANG-CW4	1,3-Dichlorobenzene	A
J	SVOCs	4804.06	UANG-CW4	Napthalene	A
J	SVOCs	4804.06	UANG-CW4	2-Methylnapthalene	A
UJ	SVOCs	4804.06	UANG-CW4	Hexachlorocyclopentadiene	C
UJ	SVOCs	4804.06	UANG-CW4	Hexachlorobenzene	C
UJ	SVOCs	4804.06	UANG-CW4	3,3'-Dichlorobenzidine	C
J	Pesticides	4804.06	UANG-CW4	Aldrin	J
UJ	Pesticides	4804.06	UANG-CW4	Alpha-BHC	J
UJ	Pesticides	4804.06	UANG-CW4	Beta-BHC	J
UJ	Pesticides	4804.06	UANG-CW4	Delta-BHC	J
UJ	Pesticides	4804.06	UANG-CW4	Gamma-BHC	J
UJ	Pesticides	4804.06	UANG-CW4	Chlordane	J
UJ	Pesticides	4804.06	UANG-CW4	4,4'-DDD	J

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Pesticides	4804.06	UANG-CW4	4,4-DDE	J
UJ	Pesticides	4804.06	UANG-CW4	4,4-DDT	J
J	Pesticides	4804.06	UANG-CW4	Dieldrin	J
UJ	Pesticides	4804.06	UANG-CW4	Endosulfan I	J
UJ	Pesticides	4804.06	UANG-CW4	Endosulfan II	J
UJ	Pesticides	4804.06	UANG-CW4	Endosulfan Sulfate	J
UJ	Pesticides	4804.06	UANG-CW4	Endrin	J
UJ	Pesticides	4804.06	UANG-CW4	Heptachlor	J
UJ	Pesticides	4804.06	UANG-CW4	Heptachlor Epoxide	J
UJ	Pesticides	4804.06	UANG-CW4	Endrin aldehyde	J
UJ	Pesticides	4804.06	UANG-CW4	Methoxychlor	J
UJ	Pesticides	4804.06	UANG-CW4	Toxaphene	J
UJ	PCBs	4804.06	UANG-CW4	PCB_1016	J
UJ	PCBs	4804.06	UANG-CW4	PCB_1221	J
UJ	PCBs	4804.06	UANG-CW4	PCB_1232	J
UJ	PCBs	4804.06	UANG-CW4	PCB_1242	J
UJ	PCBs	4804.06	UANG-CW4	PCB_1248	J
UJ	PCBs	4804.06	UANG-CW4	PCB_1254	J
UJ	PCBs	4804.06	UANG-CW4	PCB_1260	J
J	Metals	4779.08	UANG-S2-MW1	Arsenic	D
UJ	Metals	4779.08	UANG-S2-MW1	Cadmium	E,A
UJ	Metals	4779.08	UANG-S2-MW1	Chromium	E,A
J	Metals	4779.08	UANG-S2-MW1	Copper	A
UJ	Metals	4779.08	UANG-S2-MW1	Mercury	E
UJ	Metals	4779.08	UANG-S2-MW1	Nickel	E
J	Metals	4779.08	UANG-S2-MW1	Selenium	D,H,A
UJ	Metals	4779.08	UANG-S2-MW1	Thallium	H,A
UJ	Metals	4779.08	UANG-S2-MW1	Zinc	E,A
UJ	VOCs	4779.08	UANG-S2-MW1	Chloromethane	C
UJ	VOCs	4779.08	UANG-S2-MW1	Dichlorodifluoromethane	C
J	VOCs	4779.08	UANG-S2-MW1	1,1-Dichloroethane	A
UJ	VOCs	4779.08	UANG-S2-MW1	1,2-Dichloropropane	C
J	Metals	4595.07	UANG-S2-SB1 (0.5-2.5)	Arsenic	F
UJ	Metals	4595.07	UANG-S2-SB1 (0.5-2.5)	Cadmium	D
J	Metals	4595.07	UANG-S2-SB1 (0.5-2.5)	Chromium	G
UJ	Metals	4595.07	UANG-S2-SB1 (0.5-2.5)	Mercury	E
UJ	Metals	4595.07	UANG-S2-SB1 (0.5-2.5)	Selenium	D,H
J	Metals	4595.07	UANG-S2-SB1 (0.5-2.5)	Zinc	G
J	SVOCs	4595.07	UANG-S2-SB1 (0.5-2.5)	bis (2-Ethylhexyl) Phthalate	A
J	Metals	4595.06	UANG-S2-SB1 (5-7.5)	Arsenic	F
UJ	Metals	4595.06	UANG-S2-SB1 (5-7.5)	Cadmium	D
J	Metals	4595.06	UANG-S2-SB1 (5-7.5)	Chromium	G
UJ	Metals	4595.06	UANG-S2-SB1 (5-7.5)	Mercury	E
UJ	Metals	4595.06	UANG-S2-SB1 (5-7.5)	Selenium	D,H
J	Metals	4595.06	UANG-S2-SB1 (5-7.5)	Thallium	H,A,D
J	Metals	4595.06	UANG-S2-SB1 (5-7.5)	Zinc	G

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	4-Nitroaniline	C
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	Pyrene	C
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	bis (2-Chloroisopropyl) Ether	C
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	bis-(2-Chloroethoxy) methane	C
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	2-Nitroaniline	C
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	3-Nitroaniline	C
UJ	SVOCs	4595.06	UANG-S2-SB1 (5-7.5)	4-Nitrophenol	C
J	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Arsenic	F
J	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Beryllium	A
UJ	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Cadmium	D
J	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Chromium	G
UJ	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Mercury	E
UJ	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Selenium	D,H
J	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Thallium	D,H,A
J	Metals	4595.04	UANG-S2-SB2 (2.5-4.5)	Zinc	G
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Bromomethane	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Chloroethane	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Trichlorofluoromethane	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	1,1-Dichloroethane	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	1,2-Dichloroethene (Total)	C
J	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Chloroform	A
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	1,1,1-Trichloroethane	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Carbon Tetrachloride	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Bromodichloromethane	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Bromoform	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	1,3-Dichlorobenzene	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	1,4-Dichlorobenzene	C
UJ	VOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	1,2-Dichlorobenzene	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	bis (2-Chloroisopropyl) Ether	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	bis-(2-Chloroethoxy) methane	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	2-Nitroaniline	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	3-Nitroaniline	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	4-Nitrophenol	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	4-Nitroaniline	C
UJ	SVOCs	4595.04	UANG-S2-SB2 (2.5-4.5)	Pyrene	C
J	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Arsenic	F
J	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Beryllium	A
UJ	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Cadmium	D
J	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Chromium	G
J	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Lead	H
UJ	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Mercury	E
UJ	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Selenium	D,H
J	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Thallium	D,H,A
J	Metals	4595.05	UANG-S2-SB2 (4.5-6.5)	Zinc	G

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	VOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	1,2-Dichloroethene (Total)	A
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	N-Nitroso-Di-n-Propylamine	C
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	bis-(2-Chloroethoxy) methane	C
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	2-Nitroaniline	C
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	3-Nitroaniline	C
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	4-Nitrophenol	C
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	Pyrene	C
UJ	SVOCs	4595.05	UANG-S2-SB2 (4.5-6.5)	3,3'-Dichlorobenzidine	C
J	Metals	4595.01	UANG-S2-SB3 (2.5-4.5)	Arsenic	F
UJ	Metals	4595.01	UANG-S2-SB3 (2.5-4.5)	Cadmium	D
J	Metals	4595.01	UANG-S2-SB3 (2.5-4.5)	Chromium	G
UJ	Metals	4595.01	UANG-S2-SB3 (2.5-4.5)	Mercury	E
UJ	Metals	4595.01	UANG-S2-SB3 (2.5-4.5)	Selenium	D,H
J	Metals	4595.01	UANG-S2-SB3 (2.5-4.5)	Zinc	G
UJ	VOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Bromomethane	C
UJ	VOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Acetone	C
UJ	VOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	1,1-Dichloroethane	C
J	VOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Toluene	A
UJ	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Benzyl Alcohol	C
UJ	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Benzoic Acid	B,C
UJ	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	3-Nitroaniline	C
UJ	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	4-Nitroaniline	C
J	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Phenanthrene	A
J	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Fluoranthene	A
J	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	Pyrene	A
UJ	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	3,3'-Dichlorobenzidine	C
UJ	SVOCs	4595.01	UANG-S2-SB3 (2.5-4.5)	bis (2-Ethylhexyl) Phthalate	C
J	Metals	4595.02	UANG-S2-SB3 (4.5-6.5)	Arsenic	F,A
UJ	Metals	4595.02	UANG-S2-SB3 (4.5-6.5)	Cadmium	D
J	Metals	4595.02	UANG-S2-SB3 (4.5-6.5)	Chromium	G
UJ	Metals	4595.02	UANG-S2-SB3 (4.5-6.5)	Mercury	E
UJ	Metals	4595.02	UANG-S2-SB3 (4.5-6.5)	Selenium	D,H
J	Metals	4595.02	UANG-S2-SB3 (4.5-6.5)	Thallium	D,H,A
J	Metals	4595.02	UANG-S2-SB3 (4.5-6.5)	Zinc	G
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Bromomethane	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Chloroethane	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Trichlorofluoromethane	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	1,2-Dichloroethene (Total)	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	1,2-Dichloroethane	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	1,1,1-Trichloroethane	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Carbon Tetrachloride	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Bromodichloromethane	C
J	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Benzene	A
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Bromoform	C
J	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Toluene	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Ethylbenzene	J
J	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Total Xylenes	J
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	1,3-Dichlorobenzene	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	1,4-Dichlorobenzene	C
UJ	VOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	1,2-Dichlorobenzene	C
UJ	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	bis-(2-Chloroethoxy) methane	C
UJ	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	2-Nitroaniline	C
UJ	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	3-Nitroaniline	C
UJ	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	4-Nitrophenol	C
UJ	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	4-Nitroaniline	C
J	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Phenanthrene	A
UJ	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	Pyrene	C
J	SVOCs	4595.02	UANG-S2-SB3 (4.5-6.5)	bis (2-Ethylhexyl) Phthalate	A
J	Metals	4595.03	UANG-S2-SB3 (6.5-8.5)	Arsenic	F
J	Metals	4595.03	UANG-S2-SB3 (6.5-8.5)	Beryllium	A
UJ	Metals	4595.03	UANG-S2-SB3 (6.5-8.5)	Cadmium	D
J	Metals	4595.03	UANG-S2-SB3 (6.5-8.5)	Chromium	G
UJ	Metals	4595.03	UANG-S2-SB3 (6.5-8.5)	Mercury	E
UJ	Metals	4595.03	UANG-S2-SB3 (6.5-8.5)	Selenium	D,H
J	Metals	4595.03	UANG-S2-SB3 (6.5-8.5)	Zinc	G
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Bromomethane	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Chloroethane	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Trichlorofluoromethane	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	1,1-Dichloroethane	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	1,2-Dichloroethene (Total)	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	1,1,1-Trichloroethane	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Carbon Tetrachloride	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Bromodichloromethane	C
J	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Benzene	A
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Bromoform	C
J	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Toluene	A
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	1,3-Dichlorobenzene	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	1,4-Dichlorobenzene	C
UJ	VOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	1,2-Dichlorobenzene	C
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	N-Nitroso-Di-n-Propylamine	C
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	bis-(2-Chloroethoxy) methane	C
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	2-Nitroaniline	C
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	3-Nitroaniline	C
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	4-Nitrophenol	C
J	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Fluorene	A
J	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Phenanthrene	A
J	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Fluoranthene	A
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Pyrene	C
UJ	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	3-3'-Dichlorobenzidine	C

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	Chrysene	A
J	SVOCs	4595.03	UANG-S2-SB3 (6.5-8.5)	bis (2-Ethylhexyl) Phthalate	A
UJ	SVOCs	4683.1	UANG-S2-SB4 (4.5-6.5)	Hexachlorocyclopentadiene	C
UJ	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Antimony	D
J	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Arsenic	D
J	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Cadmium	A
J	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Chromium	G
J	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Lead	D
UJ	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Mercury	E
UJ	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Thallium	D,H
J	Metals	4705.09	UANG-S2-SB5 (6.5-8.5)	Zinc	G
UJ	SVOCs	4705.09	UANG-S2-SB5 (6.5-8.5)	Phenol	C
UJ	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Antimony	E,D,A
J	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Arsenic	D
J	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Beryllium	A
J	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Chromium	G
J	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Lead	D,H
UJ	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Mercury	E
UJ	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Thallium	D,H
J	Metals	4705.10	UANG-S2-SB6 (6.5-8.5)	Zinc	G
UJ	SVOCs	4705.10	UANG-S2-SB6 (6.5-8.5)	Phenol	C
J	VOCs	4779.10	UANG-S3-MW1	Toluene	A
J	VOCs	4779.10	UANG-S3-MW1	1,3-Dichlorobenzene	A
J	SVOCs	4779.10	UANG-S3-MW1	1,4-Dichlorobenzene	A
J	SVOCs	4779.10	UANG-S3-MW1	1,2-Dichlorobenzene	A
J	VOCs	4779.10	UANG-S3-MW1	1,3-Dichlorobenzene	A
UJ	VOCs	4779.10	UANG-S3-MW1	Dichlorodifluoromethane	C
J	SVOCs	4779.11	UANG-S3-MW2	1,4-Dichlorobenzene	A
J	SVOCs	4779.11	UANG-S3-MW2	1,2-Dichlorobenzene	A
J	VOCs	4779.11	UANG-S3-MW2	Ethylbenzene	A
J	VOCs	4779.11	UANG-S3-MW2	Toluene	A
J	VOCs	4779.11	UANG-S3-MW2	Chlorobenzene	A
J	VOCs	4779.11	UANG-S3-MW2	1,2-Dichlorobenzene	A
J	VOCs	4779.11	UANG-S3-MW2	1,4-Dichlorobenzene	A
UJ	VOCs	4779.11	UANG-S3-MW2	Dichlorodifluoromethane	C
J	VOCs	4779.09	UANG-S3-MW3	Toluene	A
J	VOCs	4779.09	UANG-S3-MW3	1,3-Dichlorobenzene	A
J	SVOCs	4779.09	UANG-S3-MW3	Phenol	A
J	SVOCs	4779.09	UANG-S3-MW3	4-Methylphenol	A
J	VOCs	4779.09	UANG-S3-MW3	1,3-Dichlorobenzene	A
UJ	VOCs	4779.09	UANG-S3-MW3	Dichlorodifluoromethane	C
UJ	SVOCs	4633.09	UANG-S3-SS1	Benzyl Alcohol	B
UJ	SVOCs	4633.09	UANG-S3-SS1	3-Nitroaniline	B
J	SVOCs	4633.10	UANG-S3-SS2	Pyrene	A
J	SVOCs	4633.10	UANG-S3-SS2	Chrysene	A
J	SVOCs	4633.10	UANG-S3-SS2	bis(2-ethylhexyl) Phthalate	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4633.10	UANG-S3-SS2	Benzyl Alcohol	B
J	SVOCs	4683.08	UANG-S3-SB1 (4-6)	N-Nirosodiphenylamine	A
UJ	SVOCs	4683.08	UANG-S3-SB1 (4-6)	Hexachlorocyclopentadiene	B
UJ	SVOCs	4683.09	UANG-S3-SB1 (6-8)	Hexachlorocyclopentadiene	B
J	SVOCs	4683.07	UANG-S3-SB3 (6-8)	bis(2-ethylhexyl) Phthalate	A
UJ	SVOCs	4683.07	UANG-S3-SB3 (6-8)	Hexachlorocyclopentadiene	B
UJ	SVOCs	4705.11	UANG-S3-SB5 (4-6)	Phenol	C
UJ	Metals	4705.11	UANG-S3-SB5 (4-6)	Antimony	E,D,A
J	Metals	4705.11	UANG-S3-SB5 (4-6)	Arsenic	D
J	Metals	4705.11	UANG-S3-SB5 (4-6)	Beryllium	A
J	Metals	4705.11	UANG-S3-SB5 (4-6)	Chromium	G
J	Metals	4705.11	UANG-S3-SB5 (4-6)	Lead	D,H
UJ	Metals	4705.11	UANG-S3-SB5 (4-6)	Mercury	E
UJ	Metals	4705.11	UANG-S3-SB5 (4-6)	Thallium	D,H
J	Metals	4705.11	UANG-S3-SB5 (4-6)	Zinc	G
J	SVOCs	4642.06	UANG-S3-SS4	Pyrene	A
J	SVOCs	4642.06	UANG-S3-SS4	Chrysene	A
J	SVOCs	4642.06	UANG-S3-SS4	bis(2-ethylhexyl) Phthalate	A
UJ	SVOCs	4642.06	UANG-S3-SS4	Hexachlorocyclopentadiene	B
UJ	SVOCs	4642.07	UANG-S3-SS5	4-Nitroaniline	B
J	SVOCs	4642.07	UANG-S3-SS5	bis(2-ethylhexyl) Phthalate	A
UJ	SVOCs	4642.07	UANG-S3-SS5	3-Nitroaniline	B
UJ	SVOCs	4642.07	UANG-S3-SS5	2,4-Dinitrophenol	B
J	SVOCs	4642.08	UANG-S3-SS6	Diethylphthalate	A
J	SVOCs	4642.08	UANG-S3-SS6	Pyrene	A
J	SVOCs	4642.08	UANG-S3-SS6	Chrysene	A
UJ	SVOCs	4642.08	UANG-S3-SS6	3-Nitroaniline	B
UJ	VOCs	4781.03	UANG-S4-MW1	Chloromethane	C
UJ	VOCs	4781.03	UANG-S4-MW1	Dichlorodifluoromethane	C
UJ	VOCs	4781.03	UANG-S4-MW1	1,2-Dichloropropane	C
J	Metals	4781.03	UANG-S4-MW1	Arsenic	D
UJ	Metals	4781.03	UANG-S4-MW1	Chromium	E,A
UJ	Metals	4781.03	UANG-S4-MW1	Copper	E,A
UJ	Metals	4781.03	UANG-S4-MW1	Lead	E,A
UJ	Metals	4781.03	UANG-S4-MW1	Mercury	E
UJ	Metals	4781.03	UANG-S4-MW1	Nickel	E
UJ	Metals	4781.03	UANG-S4-MW1	Selenium	D,H
UJ	Metals	4781.03	UANG-S4-MW1	Zinc	E,A
J	VOCs	4781.03	UANG-S4-MW1	Toluene	A
J	Metals	4601-08	UANG-S4-SB1 (2.5-4.5)	Arsenic	F
J	Metals	4601-08	UANG-S4-SB1 (2.5-4.5)	Beryllium	A
UJ	Metals	4601-08	UANG-S4-SB1 (2.5-4.5)	Cadmium	D
J	Metals	4601-08	UANG-S4-SB1 (2.5-4.5)	Chromium	G
UJ	Metals	4601-08	UANG-S4-SB1 (2.5-4.5)	Mercury	E
UJ	Metals	4601-08	UANG-S4-SB1 (2.5-4.5)	Selenium	D,H
J	Metals	4601-08	UANG-S4-SB1 (2.5-4.5)	Zinc	G

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	bis (2-Chloroisopropyl) Ether	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	N-Nitroso-Di-n-Propylamine	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	bis-(2-Chloroethoxy) methane	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	2-Nitroaniline	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	3-Nitroaniline	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	4-Nitrophenol	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	4-Nitroaniline	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	Pyrene	C
UJ	SVOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	3,3'-Dichlorobenzidine	C
UJ	VOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	Chloromethane	C
J	VOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	Methylene Chloride	A
J	VOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	Toluene	A
J	VOCs	4601-08	UANG-S4-SB1 (2.5-4.5)	Total Xylenes	A
J	Metals	4601.09	UANG-S4-SB1 (6.5-9)	Arsenic	F
UJ	Metals	4601.09	UANG-S4-SB1 (6.5-9)	Cadmium	D
J	Metals	4601.09	UANG-S4-SB1 (6.5-9)	Chromium	G
UJ	Metals	4601.09	UANG-S4-SB1 (6.5-9)	Mercury	E
UJ	Metals	4601.09	UANG-S4-SB1 (6.5-9)	Selenium	D,H
J	Metals	4601.09	UANG-S4-SB1 (6.5-9)	Zinc	G
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	bis (2-Chloroisopropyl) Ether	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	N-Nitroso-Di-n-Propylamine	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	bis-(2-Chloroethoxy) methane	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	2-Nitroaniline	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	3-Nitroaniline	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	4-Nitrophenol	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	4-Nitroaniline	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	Pyrene	C
UJ	SVOCs	4601.09	UANG-S4-SB1 (6.5-9)	3,3'-Dichlorobenzidine	C
UJ	Metals	4608.03	UANG-S4-SB2 (2.5-4.5)	Antimony	D
J	Metals	4608.03	UANG-S4-SB2 (2.5-4.5)	Arsenic	D
J	Metals	4608.03	UANG-S4-SB2 (2.5-4.5)	Cadmium	D
J	Metals	4608.03	UANG-S4-SB2 (2.5-4.5)	Mercury	E,A
UJ	Metals	4608.03	UANG-S4-SB2 (2.5-4.5)	Selenium	D,H
UJ	Metals	4608.03	UANG-S4-SB2 (2.5-4.5)	Thallium	D,H
J	Metals	4608.03	UANG-S4-SB2 (2.5-4.5)	Zinc	G
UJ	VOCs	4608.03	UANG-S4-SB2 (2.5-4.5)	Chloromethane	C
J	VOCs	4608.03	UANG-S4-SB2 (2.5-4.5)	Methylene Chloride	A
J	VOCs	4608.03	UANG-S4-SB2 (2.5-4.5)	2-Butanone	A
J	VOCs	4608.03	UANG-S4-SB2 (2.5-4.5)	Toluene	A
J	VOCs	4608.03	UANG-S4-SB2 (2.5-4.5)	Ethylbenzene	J
J	VOCs	4608.03	UANG-S4-SB2 (2.5-4.5)	Total Xylenes	J
J	SVOCs	4608.03	UANG-S4-SB2 (2.5-4.5)	2,4-Dimethylphenol	A
UJ	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Antimony	D

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Arsenic	D,A
J	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Beryllium	A
UJ	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Cadmium	D
UJ	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Mercury	E
UJ	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Selenium	D,H
UJ	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Thallium	D,H
J	Metals	4608.04	UANG-S4-SB2 (6.5-9)	Zinc	G
UJ	VOCs	4608.04	UANG-S4-SB2 (6.5-9)	Chloromethane	C
J	VOCs	4608.04	UANG-S4-SB2 (6.5-9)	Toluene	A
UJ	SVOCs	4608.04	UANG-S4-SB2 (6.5-9)	Indeno (1,2,3-cd) Pyrene	B
UJ	SVOCs	4608.04	UANG-S4-SB2 (6.5-9)	Dibenz (a,h) Anthracene	B
UJ	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Antimony	D
J	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Arsenic	D
J	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Beryllium	A
UJ	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Cadmium	D
UJ	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Mercury	E
UJ	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Selenium	D,H
UJ	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Thallium	D,H
J	Metals	4608.05	UANG-S4-SB3 (2.5-4.5)	Zinc	G
UJ	VOCs	4608.05	UANG-S4-SB3 (2.5-4.5)	Chloromethane	C
J	VOCs	4608.05	UANG-S4-SB3 (2.5-4.5)	Toluene	A
J	SVOCs	4608.05	UANG-S4-SB3 (2.5-4.5)	Di-n-Butylphthalate	A
UJ	SVOCs	4608.05	UANG-S4-SB3 (2.5-4.5)	Indeno (1,2,3-cd) Pyrene	B
UJ	SVOCs	4608.05	UANG-S4-SB3 (2.5-4.5)	Dibenz (a,h) Anthracene	B
UJ	Metals	4608.06	UANG-S4-SB3 (6.5-9)	Antimony	D
J	Metals	4608.06	UANG-S4-SB3 (6.5-9)	Arsenic	D
UJ	Metals	4608.06	UANG-S4-SB3 (6.5-9)	Cadmium	D
UJ	Metals	4608.06	UANG-S4-SB3 (6.5-9)	Mercury	E
UJ	Metals	4608.06	UANG-S4-SB3 (6.5-9)	Selenium	D,H
UJ	Metals	4608.06	UANG-S4-SB3 (6.5-9)	Thallium	D,H
J	Metals	4608.06	UANG-S4-SB3 (6.5-9)	Zinc	G
UJ	VOCs	4608.06	UANG-S4-SB3 (6.5-9)	Chloromethane	C
J	VOCs	4608.06	UANG-S4-SB3 (6.5-9)	Toluene	A
UJ	SVOCs	4608.06	UANG-S4-SB3 (6.5-9)	Indeno (1,2,3-cd) Pyrene	B
UJ	SVOCs	4608.06	UANG-S4-SB3 (6.5-9)	Dibenz (a,h) Anthracene	B
UJ	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Antimony	D
J	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Arsenic	D
J	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Beryllium	A
J	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Cadmium	D,A
UJ	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Mercury	E
UJ	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Selenium	D,H
J	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Thallium	D,H,A
J	Metals	4608.07	UANG-S4-SB4 (2.5-4.5)	Zinc	G
UJ	VOCs	4608.07	UANG-S4-SB4 (2.5-4.5)	Chloromethane	C
J	SVOCs	4608.07	UANG-S4-SB4 (2.5-4.5)	Di-n-Butylphthalate	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4608.07	UANG-S4-SB4 (2.5-4.5)	Indeno (1,2,3-cd) Pyrene	B
UJ	SVOCs	4608.07	UANG-S4-SB4 (2.5-4.5)	Dibenz (a,h) Anthracene	B
UJ	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Antimony	D
J	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Arsenic	D
J	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Beryllium	A
UJ	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Cadmium	D
UJ	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Mercury	E
UJ	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Selenium	D,H
UJ	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Thallium	D,H
J	Metals	4608.08	UANG-S4-SB4 (6.5-9)	Zinc	G
UJ	VOCs	4608.08	UANG-S4-SB4 (6.5-9)	Chloromethane	C
J	VOCs	4608.08	UANG-S4-SB4 (6.5-9)	2-Butanone	A
J	VOCs	4608.08	UANG-S4-SB4 (6.5-9)	Toluene	A
UJ	SVOCs	4608.08	UANG-S4-SB4 (6.5-9)	Indeno (1,2,3-cd) Pyrene	B
UJ	SVOCs	4608.08	UANG-S4-SB4 (6.5-9)	Dibenz (a,h) Anthracene	B
UJ	Metals	4608.09	UANG-S4-SB4 (9-11)	Antimony	D
J	Metals	4608.09	UANG-S4-SB4 (9-11)	Arsenic	D,A
J	Metals	4608.09	UANG-S4-SB4 (9-11)	Beryllium	A
UJ	Metals	4608.09	UANG-S4-SB4 (9-11)	Cadmium	D
UJ	Metals	4608.09	UANG-S4-SB4 (9-11)	Mercury	E
UJ	Metals	4608.09	UANG-S4-SB4 (9-11)	Selenium	D,H
UJ	Metals	4608.09	UANG-S4-SB4 (9-11)	Thallium	D
J	Metals	4608.09	UANG-S4-SB4 (9-11)	Zinc	G
UJ	VOCs	4608.09	UANG-S4-SB4 (9-11)	Chloromethane	C
J	VOCs	4608.09	UANG-S4-SB4 (9-11)	Methylene Chloride	A
J	VOCs	4608.09	UANG-S4-SB4 (9-11)	Carbon Disulfide	A
J	VOCs	4608.09	UANG-S4-SB4 (9-11)	Toluene	A
UJ	SVOCs	4608.09	UANG-S4-SB4 (9-11)	Indeno (1,2,3-cd) Pyrene	B
UJ	SVOCs	4608.09	UANG-S4-SB4 (9-11)	Dibenz (a,h) Anthracene	B
UJ	Metals	4662.01	UANG-S4-SB5 (5-7)	Antimony	D
J	Metals	4662.01	UANG-S4-SB5 (5-7)	Arsenic	D
J	Metals	4662.01	UANG-S4-SB5 (5-7)	Beryllium	A
UJ	Metals	4662.01	UANG-S4-SB5 (5-7)	Cadmium	D
UJ	Metals	4662.01	UANG-S4-SB5 (5-7)	Mercury	E
UJ	Metals	4662.01	UANG-S4-SB5 (5-7)	Selenium	D,H
UJ	Metals	4662.01	UANG-S4-SB5 (5-7)	Thallium	D,H
J	Metals	4662.01	UANG-S4-SB5 (5-7)	Zinc	G
UJ	SVOCs	4662.01	UANG-S4-SB5 (5-7)	N-Nitroso-Dimethylamine	C
J	Metals	4662.02	UANG-S4-SB5 (7-9)	Antimony	D,A
J	Metals	4662.02	UANG-S4-SB5 (7-9)	Arsenic	D
J	Metals	4662.02	UANG-S4-SB5 (7-9)	Beryllium	A
UJ	Metals	4662.02	UANG-S4-SB5 (7-9)	Cadmium	D
UJ	Metals	4662.02	UANG-S4-SB5 (7-9)	Mercury	E
UJ	Metals	4662.02	UANG-S4-SB5 (7-9)	Selenium	D,H
UJ	Metals	4662.02	UANG-S4-SB5 (7-9)	Thallium	D,H

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	Metals	4662.02	UANG-S4-SB5 (7-9)	Zinc	G
UJ	SVOCs	4662.02	UANG-S4-SB5 (7-9)	N-Nitroso-Dimethylamine	C
UJ	Metals	4662.04	UANG-S4-SB5 (2.5-4.5)	Antimony	D
J	Metals	4662.04	UANG-S4-SB5 (2.5-4.5)	Arsenic	D
UJ	Metals	4662.04	UANG-S4-SB5 (2.5-4.5)	Cadmium	D
UJ	Metals	4662.04	UANG-S4-SB5 (2.5-4.5)	Mercury	E
UJ	Metals	4662.04	UANG-S4-SB5 (2.5-4.5)	Selenium	D,H
UJ	Metals	4662.04	UANG-S4-SB5 (2.5-4.5)	Thallium	D,H
J	Metals	4662.04	UANG-S4-SB5 (2.5-4.5)	Zinc	G
UJ	SVOCs	4662.04	UANG-S4-SB5 (2.5-4.5)	N-Nitroso-Dimethylamine	C
UJ	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Antimony	D
J	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Arsenic	D
J	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Beryllium	A
UJ	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Cadmium	D
UJ	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Mercury	E
UJ	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Selenium	D,H
UJ	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Thallium	D,H
J	Metals	4662.05	UANG-S4-SB5 (6.5-8.5)	Zinc	G
UJ	SVOCs	4662.05	UANG-S4-SB5 (2.5-4.5)	N-Nitroso-Dimethylamine	C
UJ	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Antimony	D
J	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Arsenic	D
J	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Beryllium	A
UJ	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Cadmium	D
UJ	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Mercury	E
UJ	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Selenium	D,H
UJ	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Thallium	D,H
J	Metals	4662.03	UANG-S4-SB7 (4.5-6.5)	Zinc	G
UJ	SVOCs	4662.03	UANG-S4-SB7 (4.5-6.5)	N-Nitroso-Dimethylamine	C
J	Metals	4705.01	UANG-S4-SB8 (0.5-2.5)	Antimony	D,A
J	Metals	4705.01	UANG-S4-SB8 (0.5-2.5)	Arsenic	D
J	Metals	4705.01	UANG-S4-SB8 (0.5-2.5)	Chromium	G
J	Metals	4705.01	UANG-S4-SB8 (0.5-2.5)	Lead	D,H
UJ	Metals	4705.01	UANG-S4-SB8 (0.5-2.5)	Mercury	E
UJ	Metals	4705.01	UANG-S4-SB8 (0.5-2.5)	Thallium	D
J	Metals	4705.01	UANG-S4-SB8 (0.5-2.5)	Zinc	G
UJ	SVOCs	4705.01	UANG-S4-SB8 (0.5-2.5)	Hexachlorocyclopentadiene	B
UJ	SVOCs	4705.01	UANG-S4-SB8 (0.5-2.5)	2,4-Dinitrophenol	C
UJ	SVOCs	4705.01	UANG-S4-SB8 (0.5-2.5)	Fluoranthene	C
UJ	SVOCs	4705.01	UANG-S4-SB8 (0.5-2.5)	Pyrene	C
UJ	SVOCs	4705.01	UANG-S4-SB8 (0.5-2.5)	3,3'-Dichlorobenzidine	C
UJ	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Antimony	E,D
J	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Arsenic	D
J	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Beryllium	A
J	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Cadmium	A
J	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Chromium	G

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Lead	D
UJ	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Mercury	E
UJ	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Thallium	D
J	Metals	4705.02	UANG-S4-SB8 (4.5-6.5)	Zinc	G
UJ	SVOCs	4705.02	UANG-S4-SB8 (4.5-6.5)	Hexachlorocyclopentadiene	B,C
UJ	SVOCs	4705.02	UANG-S4-SB8 (4.5-6.5)	2,4-Dinitrophenol	C
UJ	SVOCs	4705.02	UANG-S4-SB8 (4.5-6.5)	Fluoranthene	C
UJ	SVOCs	4705.02	UANG-S4-SB8 (4.5-6.5)	Pyrene	C
UJ	SVOCs	4705.02	UANG-S4-SB8 (4.5-6.5)	3,3'-Dichlorobenzidine	C
UJ	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Antimony	D,A
J	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Arsenic	D
J	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Beryllium	A
J	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Cadmium	A
J	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Chromium	G
J	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Lead	D
UJ	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Mercury	E
UJ	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Thallium	D,H
J	Metals	4705.03	UANG-S4-SB9 (2.5-4.5)	Zinc	G
UJ	SVOCs	4705.03	UANG-S4-SB9 (2.5-4.5)	Hexachlorocyclopentadiene	B,C
UJ	SVOCs	4705.03	UANG-S4-SB9 (2.5-4.5)	2,4-Dinitrophenol	C
UJ	SVOCs	4705.03	UANG-S4-SB9 (2.5-4.5)	Fluoranthene	C
UJ	SVOCs	4705.03	UANG-S4-SB9 (2.5-4.5)	Pyrene	C
UJ	SVOCs	4705.03	UANG-S4-SB9 (2.5-4.5)	3,3'-Dichlorobenzidine	C
UJ	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Antimony	E,D,A
J	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Arsenic	D
J	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Beryllium	A
J	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Cadmium	A
J	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Chromium	G
J	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Lead	H,D
UJ	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Mercury	E
UJ	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Thallium	D,H
J	Metals	4705.04	UANG-S4-SB9 (4.5-6.5)	Zinc	G
UJ	SVOCs	4705.04	UANG-S4-SB9 (4.5-6.5)	Phenol	C
UJ	VOCs	4608.10	UANG-S5-SB1 (0-2)	Chloromethane	C
J	VOCs	4608.10	UANG-S5-SB1 (0-2)	Methylene Chloride	A
UJ	SVOCs	4608.10	UANG-S5-SB1 (0-2)	bis(2-ethylhexyl) Phthalate	C
	SVOCs	4608.10	UANG-S5-SB1 (0-2)	Pyrene	C
	VOCs	4608.10	UANG-S5-SB1 (0-2)	Total Xylenes	A
UJ	VOCs	4608.11	UANG-S5-SB1 (6-8.5)	Chloromethane	C
J	VOCs	4608.11	UANG-S5-SB1 (6-8.5)	Methylene Chloride	A
UJ	SVOCs	4608.11	UANG-S5-SB1 (6-8.5)	Ideno(1,2,3-cd) Pyrene	B
UJ	SVOCs	4608.11	UANG-S5-SB1 (6-8.5)	Dibenz (a,h) Anthracene	B
J	VOCs	4624.09	UANG-S5-SB2 (2-4)	Carbon Disulfide	A
J	VOCs	4624.09	UANG-S5-SB2 (2-4)	2-Butanone	A
J	VOCs	4624.09	UANG-S5-SB2 (2-4)	4-Methyl-2-pentanone	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	VOCs	4624.09	UANG-S5-SB2 (2-4)	Total Xylenes	A
UJ	SVOCs	4624.09	UANG-S5-SB2 (2-4)	Benzyl Alcohol	C
UJ	SVOCs	4624.09	UANG-S5-SB2 (2-4)	Hexachlorobutadiene	C
UJ	SVOCs	4624.09	UANG-S5-SB2 (2-4)	3-Nitroaniline	C
UJ	SVOCs	4624.09	UANG-S5-SB2 (2-4)	4-Nitroaniline	C
UJ	SVOCs	4624.09	UANG-S5-SB2 (2-4)	Hexachlorobenzene	C
J	VOCs	4624.01	UANG-S5-SB2 (6-8.5)	Acetone	A
UJ	SVOCs	4624.01	UANG-S5-SB2 (6-8.5)	Benzyl Alcohol	C
UJ	SVOCs	4624.01	UANG-S5-SB2 (6-8.5)	3-Nitroaniline	B
UJ	SVOCs	4624.01	UANG-S5-SB2 (6-8.5)	Hexachlorobenzene	C
UJ	SVOCs	4624.01	UANG-S5-SB2 (6-8.5)	Pyrene	C
UJ	SVOCs	4624.01	UANG-S5-SB2 (6-8.5)	Di-n-octylphthalate	C
J	VOCs	4624.08	UANG-S5-SB3 (2-4)	Acetone	A
UJ	SVOCs	4624.08	UANG-S5-SB3 (2-4)	3-Nitroaniline	B
J	SVOCs	4624.08	UANG-S5-SB3 (2-4)	Phenanthrene	A
J	SVOCs	4624.08	UANG-S5-SB3 (2-4)	Fluoranthene	A
J	SVOCs	4624.08	UANG-S5-SB3 (2-4)	Pyrene	A
J	SVOCs	4624.08	UANG-S5-SB3 (2-4)	Chrysene	A
J	SVOCs	4624.08	UANG-S5-SB3 (2-4)	bis(2-ethylhexyl) Phthalate	A
J	SVOCs	4624.08	UANG-S5-SB3 (2-4)	Benzo (b) Fluoranthene	A
J	SVOCs	4624.08	UANG-S5-SB3 (2-4)	Benzo (k) Fluoranthene	A
J	VOCs	4624.02	UANG-S5-SB3 (6-8.5)	Acetone	A
J	VOCs	4624.02	UANG-S5-SB3 (6-8.5)	Toluene	A
UJ	SVOCs	4624.02	UANG-S5-SB3 (6-8.5)	Benzyl Alcohol	C
UJ	SVOCs	4624.02	UANG-S5-SB3 (6-8.5)	Hexachlorobutadiene	C
UJ	SVOCs	4624.02	UANG-S5-SB3 (6-8.5)	3-Nitroaniline	C
UJ	SVOCs	4624.02	UANG-S5-SB3 (6-8.5)	4-Nitroaniline	C
UJ	SVOCs	4624.02	UANG-S5-SB3 (6-8.5)	Hexachlorobenzene	C
J	VOCs	4624.03	UANG-S5-SB3 (8.5-11)	Acetone	A
J	VOCs	4624.03	UANG-S5-SB3 (8.5-11)	Toluene	A
UJ	SVOCs	4624.03	UANG-S5-SB3 (8.5-11)	Benzyl Alcohol	C
UJ	SVOCs	4624.03	UANG-S5-SB3 (8.5-11)	Hexachlorobutadiene	C
UJ	SVOCs	4624.03	UANG-S5-SB3 (8.5-11)	3-Nitroaniline	C
UJ	SVOCs	4624.03	UANG-S5-SB3 (8.5-11)	4-Nitroaniline	C
UJ	SVOCs	4624.03	UANG-S5-SB3 (8.5-11)	Hexachlorobenzene	C
J	SVOCs	4624.03	UANG-S5-SB3 (8.5-11)	bis(2-ethylhexyl) Phthalate	A
J	VOCs	4624.06	UANG-S5-SB4 (2-4)	Acetone	A
J	VOCs	4624.06	UANG-S5-SB4 (2-4)	Toluene	A
J	SVOCs	4624.06	UANG-S5-SB4 (2-4)	Phenanthrene	A
J	SVOCs	4624.06	UANG-S5-SB4 (2-4)	Fluoranthene	A
J	SVOCs	4624.06	UANG-S5-SB4 (2-4)	Pyrene	A
J	VOCs	4624.04	UANG-S5-SB4 (6-8.5)	Methylene Chloride	A
J	VOCs	4624.04	UANG-S5-SB4 (6-8.5)	Acetone	A
J	VOCs	4624.04	UANG-S5-SB4 (6-8.5)	Toluene	A
J	VOCs	4624.04	UANG-S5-SB4 (6-8.5)	Total Xylenes	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4624.04	UANG-S5-SB4 (6-8.5)	Benzyl Alcohol	C
UJ	SVOCs	4624.04	UANG-S5-SB4 (6-8.5)	3-Nitroaniline	B
UJ	SVOCs	4624.04	UANG-S5-SB4 (6-8.5)	Hexachlorobenzene	C
UJ	SVOCs	4624.04	UANG-S5-SB4 (6-8.5)	Pyrene	C
UJ	SVOCs	4624.04	UANG-S5-SB4 (6-8.5)	Di-n-octylphthalate	C
UJ	SVOCs	4797.07	UANG-S5-SB5 (1-3)	Pentachlorophenol	C
UJ	SVOCs	4797.08	UANG-S5-SB5 (5-7)	3-Nitroaniline	C
UJ	SVOCs	4797.08	UANG-S5-SB5 (5-7)	4-Nitroaniline	C
J	SVOCs	4797.08	UANG-S5-SB5 (5-7)	Di-n-Butylphthalate	A
UJ	SVOCs	4797.01	UANG-S5-SB6 (1-3)	Pentachlorophenol	C
UJ	SVOCs	4797.02	UANG-S5-SB6 (5-7)	Pentachlorophenol	C
J	SVOCs	4797.02	UANG-S5-SB6 (5-7)	Di-n-Butylphthalate	A
UJ	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Pentachlorophenol	C
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Phenanthrene	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Di-n-Butylphthalate	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Fluoranthene	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Pyrene	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Chrysene	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Benzo (b) Fluoranthene	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Benzo(a) Pyrene	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Ideno (1,2,3-cd) Pyrene	A
J	SVOCs	4797.05	UANG-S5-SB7 (1-3)	Benzo (g,h,i) Perylene	A
UJ	SVOCs	4797.06	UANG-S5-SB7 (5-7)	3-Nitroaniline	B,C
UJ	SVOCs	4797.06	UANG-S5-SB7 (5-7)	4-Nitroaniline	C
UJ	VOCs	4788.05	UANG-S5-MW1	Bromoform	B
UJ	SVOCs	4788.05	UANG-S5-MW1	4-Chloroaniline	C
UJ	SVOCs	4788.05	UANG-S5-MW1	3-Nitroaniline	C
UJ	SVOCs	4788.05	UANG-S5-MW1	4-Nitroaniline	C
UJ	SVOCs	4788.05	UANG-S5-MW1	3,3'-Dichlorobenzidene	C
UJ	SVOCs	4788.04	UANG-S6-MW1	4-Nitroaniline	C
UJ	SVOCs	4788.04	UANG-S6-MW1	3,3'-Dichlorobenzidine	C
UJ	SVOCs	4788.04	UANG-S6-MW1	4-Chloroaniline	C
UJ	SVOCs	4788.04	UANG-S6-MW1	3-Nitroaniline	C
UJ	SVOCs	4788.06	UANG-S6-MW2	Benzoic Acid	C
UJ	SVOCs	4788.06	UANG-S6-MW2	3-Nitroaniline	C
UJ	SVOCs	4788.06	UANG-S6-MW3	4-Nitroaniline	C
UJ	SVOCs	4788.06	UANG-S6-MW3	3,3'-Dichlorobenzidine	C
UJ	SVOCs	4788.03	UANG-S6-MW3	4-Chloroaniline	C
UJ	SVOCs	4788.03	UANG-S6-MW3	3-Nitroaniline	C
UJ	SVOCs	4624.07	UANG-S6-SB1 (2.5-4.5)	4-Nitroaniline	C
UJ	SVOCs	4624.07	UANG-S6-SB1 (2.5-4.5)	Hexachlorobenzene	C
UJ	SVOCs	4624.07	UANG-S6-SB1 (2.5-4.5)	Benzyl Alcohol	C
UJ	SVOCs	4624.07	UANG-S6-SB1 (2.5-4.5)	Hexachlorobutadiene	C
UJ	SVOCs	4624.07	UANG-S6-SB1 (2.5-4.5)	3-Nitroaniline	B,C
J	SVOCs	4624.05	UANG-S6-SB1 (6.5-9)	Diethylphthalate	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4624.05	UANG-S6-SB1 (6.5-9)	Hexachlorobenzene	C
UJ	SVOCs	4624.05	UANG-S6-SB1 (6.5-9)	Pyrene	C
UJ	SVOCs	4624.05	UANG-S6-SB1 (6.5-9)	Di-n-octylphthalate	C
UJ	SVOCs	4624.05	UANG-S6-SB1 (6.5-9)	Benzyl Alcohol	C
UJ	SVOCs	4624.05	UANG-S6-SB1 (6.5-9)	3-Nitroaniline	B
UJ	SVOCs	4627.07	UANG-S6-SB2 (2-4)	Benzyl Alcohol	C
UJ	SVOCs	4627.07	UANG-S6-SB2 (2-4)	3-Nitroaniline	B
UJ	SVOCs	4627.07	UANG-S6-SB2 (2-4)	Hexachlorobenzene	C
UJ	SVOCs	4627.07	UANG-S6-SB2 (2-4)	Di-n-octylphthalate	C
UJ	VOCs	4627.04	UANG-S6-SB2 (6-8.5)	1,2-Dichloroethane	C
UJ	SVOCs	4627.04	UANG-S6-SB2 (6-8.5)	Benzyl Alcohol	C
UJ	SVOCs	4627.04	UANG-S6-SB2 (6-8.5)	3-Nitroaniline	B
UJ	SVOCs	4627.04	UANG-S6-SB2 (6-8.5)	Hexachlorobenzene	C
J	SVOCs	4627.04	UANG-S6-SB2 (6-8.5)	bis(2-ethylhexyl) Phthalate	A
UJ	SVOCs	4627.04	UANG-S6-SB2 (6-8.5)	Di-n-octylphthalate	C
UJ	VOCs	4627.06	UANG-S6-SB3 (0.5-2.5)	1,2-Dichloroethane	C
UJ	SVOCs	4627.06	UANG-S6-SB3 (0.5-2.5)	Benzyl Alcohol	C
UJ	SVOCs	4627.06	UANG-S6-SB3 (0.5-2.5)	3-Nitroaniline	B
UJ	SVOCs	4627.06	UANG-S6-SB3 (0.5-2.5)	Hexachlorobenzene	C
UJ	SVOCs	4627.06	UANG-S6-SB3 (0.5-2.5)	Di-n-octylphthalate	C
UJ	SVOCs	4627.01	UANG-S6-SB3 (6.5-9)	N-Nitroso-Dimethylamine	C
UJ	VOCs	4627.05	UANG-S6-SB4 (0-2)	1,2-Dichloroethane	C
UJ	SVOCs	4627.05	UANG-S6-SB4 (0-2)	Benzyl Alcohol	C
UJ	SVOCs	4627.05	UANG-S6-SB4 (0-2)	3-Nitroaniline	B
UJ	SVOCs	4627.05	UANG-S6-SB4 (0-2)	Hexachlorobenzene	C
UJ	SVOCs	4627.05	UANG-S6-SB4 (0-2)	Di-n-octylphthalate	C
UJ	SVOCs	4627.02	UANG-S6-SB4 (6-8.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4627.03	UANG-S6-SB4 (8.5-11)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4633.14	UANG-S6-SB5 (0-2)	Benzyl Alcohol	B
UJ	SVOCs	4633.04	UANG-S6-SB5 (6-8.5)	Benzyl Alcohol	B
UJ	SVOCs	4633.11	UANG-S6-SB6 (2-4)	Benzyl Alcohol	B
UJ	SVOCs	4633.08	UANG-S6-SB6 (6-8.5)	Benzyl Alcohol	B
J	SVOCs	4633.08	UANG-S6-SB6 (6-8.5)	bis(2-ethylhexyl) Phthalate	A
UJ	SVOCs	4633.07	UANG-S6-SB6 (8.5-11)	Benzyl Alcohol	B
UJ	SVOCs	4633.12	UANG-S6-SB7 (2-4)	Benzyl Alcohol	B
UJ	SVOCs	4633.06	UANG-S6-SB7 (6-8.5)	Benzyl Alcohol	B
UJ	SVOCs	4633.13	UANG-S6-SB8 (2.5-4.5)	Benzyl Alcohol	B
UJ	SVOCs	4633.05	UANG-S6-SB8 (6.5-9)	Benzyl Alcohol	B
J	SVOCs	4642.01	UANG-S6-SB9 (0-2)	Benzyl Alcohol	B
UJ	SVOCs	4642.01	UANG-S6-SB9 (0-2)	3-Nitroaniline	B
UJ	SVOCs	4642.01	UANG-S6-SB9 (0-2)	Pyrene	C
UJ	SVOCs	4642.02	UANG-S6-SB9 (6-8.5)	Benzyl Alcohol	B
UJ	SVOCs	4642.02	UANG-S6-SB9 (6-8.5)	3-Nitroaniline	B,C
UJ	SVOCs	4642.03	UANG-S6-SB10 (0-2)	3-Nitroaniline	B,C
UJ	SVOCs	4642.03	UANG-S6-SB10 (0-2)	2,4-Dinitrophenol	B

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4642.03	UANG-S6-SB10 (0-2)	4-Nitroaniline	B
UJ	SVOCs	4642.04	UANG-S6-SB10 (6-8.5)	3-Nitroaniline	C
J	Metals	4781.01	UANG-S7-MW1	Arsenic	D
UJ	Metals	4781.01	UANG-S7-MW1	Copper	A
UJ	Metals	4781.01	UANG-S7-MW1	Mercury	E
UJ	Metals	4781.01	UANG-S7-MW1	Nickel	E
UJ	Metals	4781.01	UANG-S7-MW1	Selenium	D
UJ	Metals	4781.01	UANG-S7-MW1	Zinc	E,A
J	VOCs	4781.01	UANG-S7-MW1	Ethylbenzene	A
J	VOCs	4781.01	UANG-S7-MW1	Toluene	A
UJ	VOCs	4781.01	UANG-S7-MW1	Chloromethane	C
UJ	VOCs	4781.01	UANG-S7-MW1	Dichlorodifluoromethane	C
UJ	VOCs	4781.01	UANG-S7-MW1	1,2-Dichloropropane	C
J	Metals	4781.06	UANG-S7-MW2	Arsenic	D
UJ	Metals	4781.06	UANG-S7-MW2	Chromium	E,A
UJ	Metals	4781.06	UANG-S7-MW2	Copper	E,A
UJ	Metals	4781.06	UANG-S7-MW2	Mercury	E
UJ	Metals	4781.06	UANG-S7-MW2	Nickel	E
J	Metals	4781.06	UANG-S7-MW2	Selenium	A
UJ	Metals	4781.06	UANG-S7-MW2	Zinc	A
J	VOCs	4781.06	UANG-S7-MW2	Toluene	A
UJ	SVOCs	4781.06	UANG-S7-MW2	4-Nitroaniline	C
UJ	SVOCs	4781.06	UANG-S7-MW2	3,3-Dichlorobenzidine	C
UJ	SVOCs	4781.06	UANG-S7-MW2	4-Chloroaniline	C
UJ	SVOCs	4781.06	UANG-S7-MW2	3-Nitroaniline	C
UJ	VOCs	4781.06	UANG-S7-MW2	Chloromethane	C
UJ	VOCs	4781.06	UANG-S7-MW2	Dichlorodifluoromethane	C
UJ	VOCs	4781.06	UANG-S7-MW2	1,2-Dichloropropane	C
J	Metals	4595.08	UANG-S7-SB1 (2.5-4.5)	Arsenic	F
UJ	Metals	4595.08	UANG-S7-SB1 (2.5-4.5)	Cadmium	D
J	Metals	4595.08	UANG-S7-SB1 (2.5-4.5)	Chromium	G
UJ	Metals	4595.08	UANG-S7-SB1 (2.5-4.5)	Mercury	E
UJ	Metals	4595.08	UANG-S7-SB1 (2.5-4.5)	Selenium	D,H
J	Metals	4595.08	UANG-S7-SB1 (2.5-4.5)	Zinc	G
UJ	VOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	Acetone	B
UJ	VOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	1,1-Dichloroethane	C
UJ	VOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	2-Hexanone	C
UJ	SVOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	Benzyl Alcohol	C
UJ	SVOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	Benzoic Acid	B,C
UJ	SVOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	3-Nitroaniline	C
UJ	SVOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	4-Nitroaniline	C
UJ	SVOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	3,3'-Dichlorobenzidine	C
UJ	SVOCs	4595.08	UANG-S7-SB1 (2.5-4.5)	bis(2-ethylhexyl) Phthalate	C
J	Metals	4595.09	UANG-S7-SB1 (7-9)	Arsenic	F
J	Metals	4595.09	UANG-S7-SB1 (7-9)	Beryllium	A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Metals	4595.09	UANG-S7-SB1 (7-9)	Cadmium	D
J	Metals	4595.09	UANG-S7-SB1 (7-9)	Chromium	G
UJ	Metals	4595.09	UANG-S7-SB1 (7-9)	Mercury	E
UJ	Metals	4595.09	UANG-S7-SB1 (7-9)	Selenium	D,H
J	Metals	4595.09	UANG-S7-SB1 (7-9)	Zinc	G
UJ	SVOCs	4595.09	UANG-S7-SB1 (7-9)	Benzyl Alcohol	C
UJ	SVOCs	4595.09	UANG-S7-SB1 (7-9)	Benzoic Acid	C
UJ	SVOCs	4595.09	UANG-S7-SB1 (7-9)	3-Nitroaniline	C
UJ	SVOCs	4595.09	UANG-S7-SB1 (7-9)	4-Nitroaniline	C
UJ	SVOCs	4595.09	UANG-S7-SB1 (7-9)	3-3'-Dichlorobenzidine	C
UJ	SVOCs	4595.09	UANG-S7-SB1 (7-9)	bis(2-ethylhexyl) Phthalate	C
J	Metals	4601.03	UANG-S7-SB2 (2.5-4.5)	Arsenic	F
UJ	Metals	4601.03	UANG-S7-SB2 (2.5-4.5)	Cadmium	D
J	Metals	4601.03	UANG-S7-SB2 (2.5-4.5)	Chromium	G
UJ	Metals	4601.03	UANG-S7-SB2 (2.5-4.5)	Mercury	E
UJ	Metals	4601.03	UANG-S7-SB2 (2.5-4.5)	Selenium	D,H
J	Metals	4601.03	UANG-S7-SB2 (2.5-4.5)	Zinc	G
J	VOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Benzene	A
UJ	VOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	2-Chloroethylvinylether	B
J	VOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Toluene	A
J	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Napthalene	A
UJ	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Hexachlorocyclopentadiene	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	3-Nitroaniline	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	2,4-Dinitrophenol	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	4-Nitrophenol	C
J	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Fluorene	A
UJ	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	4,6-Dinitro-2-Methylphenol	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Pentachlorophenol	C
J	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Phenanthrene	A
J	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Fluoranthene	A
UJ	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	Butylbenzylphthalate	C
J	SVOCs	4601.03	UANG-S7-SB2 (2.5-4.5)	bis(2-ethylhexyl) Phthalate	C
J	Metals	4601.03	UANG-S7-SB2 (6.5-9)	Arsenic	F
UJ	Metals	4601.03	UANG-S7-SB2 (6.5-9)	Cadmium	D
J	Metals	4601.03	UANG-S7-SB2 (6.5-9)	Chromium	G
UJ	Metals	4601.03	UANG-S7-SB2 (6.5-9)	Mercury	E
UJ	Metals	4601.03	UANG-S7-SB2 (6.5-9)	Selenium	D,H
J	Metals	4601.03	UANG-S7-SB2 (6.5-9)	Zinc	G
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	bis (2-chloroisopropyl) Ether	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	N-Nitroso-Di-n-Propylamine	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	bis (2-Chloroethoxy) methane	C
J	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	Napthalene	A
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	2-Nitroaniline	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	3-Nitroaniline	C

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	4-Nitrophenol	C
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	4-Nitroaniline	C
J	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	Phenanthrene	A
J	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	Fluoranthene	A
J	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	Pyrene	A,C
UJ	SVOCs	4601.03	UANG-S7-SB2 (6.5-9)	3-3'-Dichlorobenzidine	C
UJ	VOCs	4601.03	UANG-S7-SB2 (6.5-9)	Chloromethane	C
J	Metals	4601.05	UANG-S7-SB3 (2.5-4.5)	Arsenic	F
UJ	Metals	4601.05	UANG-S7-SB3 (2.5-4.5)	Cadmium	D
J	Metals	4601.05	UANG-S7-SB3 (2.5-4.5)	Chromium	G
UJ	Metals	4601.05	UANG-S7-SB3 (2.5-4.5)	Mercury	E
UJ	Metals	4601.05	UANG-S7-SB3 (2.5-4.5)	Selenium	D,H
J	Metals	4601.05	UANG-S7-SB3 (2.5-4.5)	Zinc	G
UJ	VOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	2-Chloroethylvinylether	B
J	VOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	Toulene	A
J	VOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	Ethylbenzene	A
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	bis (2-chloroisopropyl) Ether	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	N-Nitroso-Di-n-Propylamine	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	bis (2-Chloroethoxy) methane	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	2-Nitroaniline	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	3-Nitroaniline	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	4-Nitrophenol	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	4-Nitroaniline	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	Pyrene	C
UJ	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	3-3'-Dichlorobenzidine	C
J	SVOCs	4601.05	UANG-S7-SB3 (2.5-4.5)	bis(2-ethylhexyl) Phthalate	A
J	Metals	4601.06	UANG-S7-SB3 (6.5-9)	Arsenic	F
UJ	Metals	4601.06	UANG-S7-SB3 (6.5-9)	Cadmium	D
J	Metals	4601.06	UANG-S7-SB3 (6.5-9)	Chromium	G
UJ	Metals	4601.06	UANG-S7-SB3 (6.5-9)	Mercury	E
UJ	Metals	4601.06	UANG-S7-SB3 (6.5-9)	Selenium	D,H
J	Metals	4601.06	UANG-S7-SB3 (6.5-9)	Zinc	G
UJ	VOCs	4601.06	UANG-S7-SB3 (6.5-9)	Chloromethane	C
J	VOCs	4601.06	UANG-S7-SB3 (6.5-9)	Methylene Chloride	A
J	VOCs	4601.06	UANG-S7-SB3 (6.5-9)	Total Xylenes	A
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	N-Nitroso-Dimethylamine	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	bis (2-chloroisopropyl) Ether	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	N-Nitroso-Di-n-Propylamine	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	bis (2-Chloroethoxy) methane	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	2-Nitroaniline	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	3-Nitroaniline	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	4-Nitrophenol	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	4-Nitroaniline	C
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	Pyrene	C

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	3-3'-Dichlorobenzidine	C
J	SVOCs	4601.06	UANG-S7-SB3 (6.5-9)	bis(2-ethylhexyl) Phthalate	A
UJ	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Antimony	D
J	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Arsenic	D
J	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Beryllium	A
UJ	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Cadmium	D
UJ	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Mercury	E
UJ	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Selenium	D,H
UJ	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Thallium	D,H
J	Metals	4654.02	UANG-S7-SB4 (4.5-6.5)	Zinc	G
UJ	SVOCs	4654.02	UANG-S7-SB4 (4.5-6.5)	Benzyl Alcohol	B
UJ	SVOCs	4654.02	UANG-S7-SB4 (4.5-6.5)	3-Nitroaniline	B
UJ	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Antimony	D
J	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Arsenic	D,A
J	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Beryllium	A
UJ	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Cadmium	D
J	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Lead	H
UJ	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Mercury	E
UJ	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Selenium	D,H
UJ	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Thallium	D,H
J	Metals	4654.03	UANG-S7-SB5 (4.5-6.5)	Zinc	G
UJ	SVOCs	4654.03	UANG-S7-SB5 (4.5-6.5)	3-Nitroaniline	B,C
UJ	SVOCs	4654.03	UANG-S7-SB5 (4.5-6.5)	2,4-Dinitrophenol	B
UJ	SVOCs	4654.03	UANG-S7-SB5 (4.5-6.5)	4-Nitroaniline	B
UJ	Metals	4654.04	UANG-S7-SB5 (6.5-9)	Antimony	D
J	Metals	4654.04	UANG-S7-SB5 (6.5-9)	Arsenic	D
UJ	Metals	4654.04	UANG-S7-SB5 (6.5-9)	Cadmium	D
UJ	Metals	4654.04	UANG-S7-SB5 (6.5-9)	Mercury	E
UJ	Metals	4654.04	UANG-S7-SB5 (6.5-9)	Selenium	D,H
UJ	Metals	4654.04	UANG-S7-SB5 (6.5-9)	Thallium	D,H
J	Metals	4654.04	UANG-S7-SB5 (6.5-9)	Zinc	G
UJ	SVOCs	4654.04	UANG-S7-SB5 (6.5-9)	Benzyl Alcohol	B
UJ	SVOCs	4654.04	UANG-S7-SB5 (6.5-9)	3-Nitroaniline	B,C
UJ	Metals	4654.05	UANG-S7-SB6 (4-6)	Antimony	D
J	Metals	4654.05	UANG-S7-SB6 (4-6)	Arsenic	D
J	Metals	4654.05	UANG-S7-SB6 (4-6)	Beryllium	A
UJ	Metals	4654.05	UANG-S7-SB6 (4-6)	Cadmium	D
J	Metals	4654.05	UANG-S7-SB6 (4-6)	Mercury	E
UJ	Metals	4654.05	UANG-S7-SB6 (4-6)	Nickel	A
UJ	Metals	4654.05	UANG-S7-SB6 (4-6)	Selenium	D,H
UJ	Metals	4654.05	UANG-S7-SB6 (4-6)	Thallium	D,H
J	Metals	4654.05	UANG-S7-SB6 (4-6)	Zinc	G
UJ	SVOCs	4654.05	UANG-S7-SB6 (4-6)	Benzyl Alcohol	B
UJ	SVOCs	4654.05	UANG-S7-SB6 (4-6)	3-Nitroaniline	B,C
UJ	SVOCs	4683.14	UANG-S7-SB7 (1-3)	Pentachlorophenol	C

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Metals	4683.14	UANG-S7-SB7 (1-3)	Antimony	D
UJ	Metals	4683.14	UANG-S7-SB7 (1-3)	Cadmium	E,A
J	Metals	4683.14	UANG-S7-SB7 (1-3)	Chromium	G
J	Metals	4683.14	UANG-S7-SB7 (1-3)	Lead	F
UJ	Metals	4683.14	UANG-S7-SB7 (1-3)	Mercury	E
UJ	Metals	4683.14	UANG-S7-SB7 (1-3)	Selenium	D,H
UJ	Metals	4683.14	UANG-S7-SB7 (1-3)	Thallium	D,H
J	Metals	4683.14	UANG-S7-SB7 (1-3)	Zinc	G
UJ	SVOCs	4797.04	UANG-S7-SB7 (5-7)	3-Nitroaniline	B,C
UJ	SVOCs	4797.04	UANG-S7-SB7 (5-7)	4-Nitroaniline	C
UJ	Metals	4797.04	UANG-S7-SB7 (5-7)	Antimony	D
J	Metals	4797.04	UANG-S7-SB7 (5-7)	Arsenic	A
UJ	Metals	4797.04	UANG-S7-SB7 (5-7)	Cadmium	E,A
J	Metals	4797.04	UANG-S7-SB7 (5-7)	Chromium	G
J	Metals	4797.04	UANG-S7-SB7 (5-7)	Lead	F
UJ	Metals	4797.04	UANG-S7-SB7 (5-7)	Mercury	E
UJ	Metals	4797.04	UANG-S7-SB7 (5-7)	Selenium	D,H
UJ	Metals	4797.04	UANG-S7-SB7 (5-7)	Thallium	D,H
J	Metals	4797.04	UANG-S7-SB7 (5-7)	Zinc	G
J	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Antimony	D,A
J	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Arsenic	D,A
J	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Beryllium	A
UJ	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Cadmium	D
UJ	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Mercury	E
UJ	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Selenium	D,H
UJ	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Thallium	D,H
J	Metals	4683.04	UANG-S7-SB8 (4.5-6.5)	Zinc	G
UJ	SVOCs	4683.04	UANG-S7-SB8 (4.5-6.5)	3-Nitroaniline	B
UJ	SVOCs	4683.04	UANG-S7-SB8 (4.5-6.5)	2,4-Dinitrophenol	B
UJ	SVOCs	4683.04	UANG-S7-SB8 (4.5-6.5)	4-Nitroaniline	B
UJ	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Antimony	E,D,A
J	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Arsenic	D
J	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Beryllium	A
J	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Cadmium	A
J	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Chromium	G
J	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Lead	D,H
UJ	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Mercury	E
UJ	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Thallium	D,H
J	Metals	4705.05	UANG-S7-SB9 (2.5-4.5)	Zinc	G
UJ	SVOCs	4705.05	UANG-S7-SB9 (2.5-4.5)	Phenol	C
UJ	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Antimony	E,D,A
J	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Arsenic	D
J	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Beryllium	A
J	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Cadmium	A
J	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Chromium	G

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Lead	D,H
UJ	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Mercury	E
UJ	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Thallium	D,H
J	Metals	4705.07	UANG-S7-SB9 (4.5-6.5)	Zinc	G
UJ	SVOCs	4705.07	UANG-S7-SB9 (4.5-6.5)	Phenol	C
UJ	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Antimony	E,D,A
J	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Arsenic	D
J	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Beryllium	A
J	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Cadmium	A
J	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Chromium	G
J	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Lead	D,H
UJ	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Mercury	E
UJ	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Thallium	D,H
J	Metals	4705.06	UANG-S7-SB9 (8.5-9.5)	Zinc	G
UJ	SVOCs	4705.06	UANG-S7-SB9 (8.5-9.5)	Phenol	C
UJ	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Antimony	E,D,A
J	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Arsenic	D
J	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Beryllium	A
J	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Cadmium	A
J	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Chromium	G
J	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Lead	D,H
UJ	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Mercury	E
UJ	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Thallium	D,H
J	Metals	4705.08	ANG-S7-SB10 (4.5-6.5)	Zinc	G
UJ	SVOCs	4705.08	ANG-S7-SB10 (4.5-6.5)	Phenol	C
UJ	VOCs	EN 1324	UANG-S10-SB1 (2-4)	Chloromethane	C
UJ	VOCs	EN 1324	UANG-S10-SB1 (2-4)	Bromoform	C
UJ	VOCs	EN 1324	UANG-S10-SB1 (2-4)	1,1,2,2-Tetrachloroethane	C
UJ	VOCs	EN 1324	UANG-S10-SB1 (2-4)	1,1,1-Trichloroethane	C
J	VOCs	EN 1324	UANG-S10-SB1 (2-4)	Xylene	C
UJ	VOCs	EN 1325	UANG-S10-SB1 (6-8)	Chloromethane	C
UJ	VOCs	EN 1325	UANG-S10-SB1 (6-8)	Bromoform	C
UJ	VOCs	EN 1325	UANG-S10-SB1 (6-8)	1,1,2,2-Tetrachloroethane	C
UJ	VOCs	EN 1325	UANG-S10-SB1 (6-8)	1,1,1-Trichloroethane	C
J	VOCs	EN 1325	UANG-S10-SB1 (6-8)	Xylene	C
J	TPH	EN 1325	UANG-S10-SB1 (6-8)	Gasoline	J
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	Acetone	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	Acrylonitrile	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	2-Butanone	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	Vinylacetate	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	2-Chloroethylvinylether	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	4-Methyl-2-pentanone	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	1,2,3-Trichloropropane	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	2-Hexanone	C
UJ	VOCs	EN1311	UANG-S10-SB1 (8-10)	Ethyl Methacrylate	C

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
J	VOCs	EN1311	UANG-S10-SB1 (8-10)	Benzene	C
UJ	VOCs	EN1318	UANG-S10-SB2 (2-4)	Chloromethane	C
UJ	VOCs	EN1319	UANG-S10-SB2 (4-6)	Chloromethane	C
J	VOCs	EN1319	UANG-S10-SB2 (4-6)	Xylenes	C
UJ	VOCs	EN1320	UANG-S10-SB3 (1-3)	Chloromethane	C
UJ	VOCs	EN1321	UANG-S10-SB3 (3-5)	Chloromethane	C
UJ	VOCs	EN1322	UANG-S10-SB4 (2-4)	Chloromethane	C
UJ	VOCs	EN1323	UANG-S10-SB4 (4-6)	Chloromethane	C
UJ	VOCs	4737.03	UANG-TB2	Chloroform	C
UJ	VOCs	4737.03	UANG-TB2	Dibromomethane	B,C
UJ	VOCs	4737.03	UANG-TB2	Trichlorofluoromethane	C
UJ	VOCs	4595-10	UANG-TB2	Chloromethane	C
UJ	VOCs	4595-10	UANG-TB2	Acetone	B
UJ	VOCs	4595-10	UANG-TB2	1,1-Dichloroethane	C
UJ	VOCs	4601.02	UANG-TB3	Acetone	B,C
UJ	VOCs	4601.02	UANG-TB3	1,1-Dichloroethane	C
UJ	VOCs	4601.02	UANG-TB3	2-Hexanone	C
UJ	VOCs	4608.02	UANG-TB4	Chloroethene	C
UJ	VOCs	4608.02	UANG-TB4	Acetone	B
UJ	VOCs	4608.02	UANG-TB4	1,1-Dichloroethane	C
UJ	VOCs	4608.02	UANG-TB4	2-Hexanone	C
UJ	VOCs	4624.11	UANG-TB5	Chloroethane	B
UJ	VOCs	4624.11	UANG-TB5	Acetone	B
UJ	VOCs	4627.09	UANG-TB6	Chloroethane	B
UJ	VOCs	4627.09	UANG-TB6	Acetone	B
UJ	VOCs	4627.09	UANG-TB6	1,2-Dichloroethene (Total)	C
UJ	VOCs	4779.12	UANG-TB17	Dichlorodifluoromethane	C
UJ	VOCs	4718.07	UANG-TB18	Chloromethane	C
UJ	VOCs	4718.07	UANG-TB18	Dichlorodifluoromethane	C
UJ	VOCs	4718.07	UANG-TB18	1,2-Dichloropropane	C
UJ	VOCs	4788.07	UANG-TB-19	Bromoform	B
UJ	VOCs	4801.02	UANG-TB21	Benzyl Chloride	C
UJ	VOCs	4801.02	UANG-TB21	Bromoform	B,C
UJ	VOCs	4801.02	UANG-TB21	Dibromochloromethane	C
UJ	VOCs	4801.02	UANG-TB21	Dichlorodifluoromethane	C
UJ	VOCs	4801.02	UANG-TB21	1,2-Dichloropropene	C
UJ	VOCs	4804.09	UANG-TB22	Benzyl Chloride	C
UJ	VOCs	4804.09	UANG-TB22	Bromoform	B,C
UJ	VOCs	4804.09	UANG-TB22	Dibromochloromethane	C
UJ	VOCs	4804.09	UANG-TB22	Dichlorodifluoromethane	C
UJ	VOCs	4804.09	UANG-TB22	1,2-Dichloropropene	C
UJ	VOCs	4601.01	UANG-RB1	Hexachlorocyclopentadiene	C
UJ	VOCs	4601.01	UANG-RB1	2,4-Dinitrophenol	C
UJ	VOCs	4601.01	UANG-RB1	Acetone	B,C
UJ	VOCs	4601.01	UANG-RB1	1,1-Dichloroethane	C

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	VOCs	4601.01	UANG-RB1	2-Hexanone	C
UJ	Metals	4601.01	UANG-RB1	Lead	E,K,A
UJ	Metals	4601.01	UANG-RB1	Mercury	E
J	Metals	4601.01	UANG-RB1	Zinc	A
UJ	VOCs	4608.01	UANG-RB2	Chloroethane	B
UJ	VOCs	4608.01	UANG-RB2	Acetone	B
UJ	SVOCs	4608.01	UANG-RB2	Benzoic Acid	B
UJ	SVOCs	4608.01	UANG-RB2	Hexachlorocyclopentadiene	C
UJ	SVOCs	4608.01	UANG-RB2	2,4-Dinitrophenol	C
UJ	Metals	4608.01	UANG-RB2	Cadmium	E,A
UJ	Metals	4608.01	UANG-RB2	Lead	E,A
UJ	Metals	4608.01	UANG-RB2	Mercury	A
UJ	VOCs	4624.10	UANG-RB3	Chloroethane	B
UJ	VOCs	4624.10	UANG-RB3	Acetone	B
UJ	SVOCs	4624.10	UANG-RB3	Benzoic Acid	B
UJ	SVOCs	4624.10	UANG-RB3	Hexachlorocyclopentadiene	C
UJ	SVOCs	4624.10	UANG-RB3	2,4-Dinitrophenol	C
UJ	SVOCs	4627.08	UANG-S6-ERB4	Benzoic Acid	B
UJ	SVOCs	4627.08	UANG-S6-ERB4	Hexachlorocyclopentadiene	C
UJ	SVOCs	4627.08	UANG-S6-ERB4	2,4-Dinitrophenol	C
UJ	VOCs	4627.08	UANG-S6-ERB4	Chloroethane	B,C
UJ	VOCs	4627.08	UANG-S6-ERB4	Acetone	B,C
UJ	VOCs	4627.08	UANG-S6-ERB4	1,2-Dichloroethene (Total)	C
UJ	SVOCs	4633.01	UANG-S6-RB5	Benzoic Acid	B
J	VOCs	4779.07	UANG-S3-RB6	Toluene	A
UJ	VOCs	4779.07	UANG-S3-RB6	Dichlorodifluoromethane	C
UJ	SVOCs	4683.01	UANG-S3-RB9	Benzoic Acid	B
UJ	SVOCs	4683.01	UANG-S3-RB9	3,3'-Dichlorobenzidine	C
UJ	Metals	4781.02	UANG-S7-ER13	Arsenic	E,D
UJ	Metals	4781.02	UANG-S7-ER13	Chromium	E,A
UJ	Metals	4781.02	UANG-S7-ER13	Copper	E,A
UJ	Metals	4781.02	UANG-S7-ER13	Mercury	E
UJ	Metals	4781.02	UANG-S7-ER13	Nickel	E
UJ	Metals	4781.02	UANG-S7-ER13	Selenium	D,H
UJ	Metals	4781.02	UANG-S7-ER13	Zinc	E,A
J	VOCs	4781.05	UANG-S7-ER14	Toluene	A
UJ	Metals	4781.05	UANG-S7-ER14	Arsenic	E,D
UJ	Metals	4781.05	UANG-S7-ER14	Chromium	E,A
UJ	Metals	4781.05	UANG-S7-ER14	Copper	E,A
UJ	Metals	4781.05	UANG-S7-ER14	Mercury	E
UJ	Metals	4781.05	UANG-S7-ER14	Nickel	E
UJ	Metals	4781.05	UANG-S7-ER14	Selenium	D
UJ	Metals	4781.05	UANG-S7-ER14	Zinc	E,A
J	VOCs	4781.05	UANG-S7-ER14	Carbon Tetrachloride	C
UJ	VOCs	4781.05	UANG-S7-ER14	Chloromethane	C

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	VOCs	4781.05	UANG-S7-ER14	Dichlorodifluoromethane	C
UJ	VOCs	4781.05	UANG-S7-ER14	1,2-Dichloropropane	C
UJ	SVOCs	4788.02	UANG-S6-ER20	4-Chloroaniline	C
UJ	SVOCs	4788.02	UANG-S6-ER20	3-Nitroaniline	C
J	SVOCs	4788.02	UANG-S6-ER20	Diethyphthalate	A
UJ	SVOCs	4788.02	UANG-S6-ER20	4-Nitroaniline	C
UJ	SVOCs	4788.02	UANG-S6-ER20	3,3'-Dichlorobenzidine	C
UJ	VOCs	4779.06	UANG-FB5-8	Dichlorodifluoromethane	C
UJ	VOCs	4779.07	UANG-S3-RB6	Dichlorodifluoromethane	C
UJ	SVOCs	4654.01	UANG-S7-RB8	Benzoic Acid	C
UJ	SVOCs	4654.01	UANG-S7-RB8	3-Nitroaniline	C
UJ	SVOCs	4654.01	UANG-S7-RB8	2,4-Dinitrophenol	C
UJ	SVOCs	4654.01	UANG-S7-RB8	4-Nitrophenol	C
UJ	SVOCs	4654.01	UANG-S7-RB8	4-Nitroaniline	C
UJ	SVOCs	4654.01	UANG-S7-RB8	4,6-Dinitro-2-Methylphenol	C
UJ	SVOCs	4654.01	UANG-S7-RB8	Pyrene	C
UJ	SVOCs	4654.01	UANG-S7-RB8	Butylbenzylphthalate	C
UJ	SVOCs	4654.01	UANG-S7-RB8	bis (2-Ethylhexyl) Phthalate	C
UJ	Metals	4654.01	UANG-S7-RB8	Cadmium	E,A
J	Metals	4654.01	UANG-S7-RB8	Chromium	A
UJ	Metals	4654.01	UANG-S7-RB8	Mercury	E
J	Metals	4642.17	UANG-FB1	Copper	A
UJ	Metals	4642.17	UANG-FB1	Lead	E,K,H
UJ	Metals	4642.17	UANG-FB1	Mercury	E
UJ	Metals	4642.17	UANG-FB1	Thallium	H
J	Metals	4642.17	UANG-FB1	Zinc	A
UJ	SVOCs	4779.01	UANG-FB4	3-Nitroaniline	B,C
J	VOCs	4779.06	UANG-FB5-8	Ethylbenzene	A
J	VOCs	4779.06	UANG-FB5-8	Chlorobenzene	A
	VOCs	4779.06	UANG-FB5-8	Dichlorodifluoromethane	C
UJ	Metals	4779.06	UANG-FB5-8	Arsenic	E,D
UJ	Metals	4779.06	UANG-FB5-8	Chromium	E,A
UJ	Metals	4779.06	UANG-FB5-8	Copper	E,A
UJ	Metals	4779.06	UANG-FB5-8	Mercury	E
UJ	Metals	4779.06	UANG-FB5-8	Nickel	E
UJ	Metals	4779.06	UANG-FB5-8	Selenium	D,H
UJ	Metals	4779.06	UANG-FB5-8	Zinc	E,A
UJ	VOCs	4781.04	UANG-FB6-15	Chloromethane	C
UJ	VOCs	4781.04	UANG-FB6-15	Dichlorodifluoromethane	C
UJ	VOCs	4781.04	UANG-FB6-15	1,2-Dichloropropane	C
UJ	Metals	4781.04	UANG-FB6-15	Arsenic	E,D,H
UJ	Metals	4781.04	UANG-FB6-15	Chromium	E,A
UJ	Metals	4781.04	UANG-FB6-15	Lead	H
UJ	Metals	4781.04	UANG-FB6-15	Mercury	E
UJ	Metals	4781.04	UANG-FB6-15	Nickel	E

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	Metals	4781.04	UANG-FB6-15	Selenium	D
J	Metals	4781.04	UANG-FB6-15	Zinc	A
UJ	VOCs	4788.01	UANG-FB7-19	Bromoform	B
UJ	SVOCs	4788.01	UANG-FB7-19	4-Chloroaniline	C
UJ	SVOCs	4788.01	UANG-FB7-19	3-Nitroaniline	C
UJ	SVOCs	4788.01	UANG-FB7-19	4-Nitroaniline	C
UJ	SVOCs	4788.01	UANG-FB7-19	3,3'-Dichlorobenzidine	C
UJ	Metals	4788.01	UANG-FB7-19	Arsenic	E,D
UJ	Metals	4788.01	UANG-FB7-19	Cadmium	E,A
UJ	Metals	4788.01	UANG-FB7-19	Chromium	E,A
UJ	Metals	4788.01	UANG-FB7-19	Copper	E,A
UJ	Metals	4788.01	UANG-FB7-19	Mercury	E
UJ	Metals	4788.01	UANG-FB7-19	Nickel	E
UJ	Metals	4788.01	UANG-FB7-19	Selenium	D
UJ	Metals	4788.01	UANG-FB7-19	Zinc	E,A
UJ	VOCs	4804.08	UANG-FB8	Benzyl Chloride	C
UJ	VOCs	4804.08	UANG-FB8	Bromoform	B,C
UJ	VOCs	4804.08	UANG-FB8	Dibromochloromethane	C
UJ	VOCs	4804.08	UANG-FB8	Dichlorodifluoromethane	C
UJ	VOCs	4804.08	UANG-FB8	1,2-Dichloropropane	C
J	SVOCs	4804.08	UANG-FB8	1,3-Dichlorobenzene	A
UJ	SVOCs	4804.08	UANG-FB8	Hexachlorocyclopentadiene	C
UJ	SVOCs	4804.08	UANG-FB8	Hexachlorobenzene	C
UJ	SVOCs	4804.08	UANG-FB8	3,3'-Dichlorobenzidine	C
UJ	Pesticides	4804.08	UANG-FB8	Heptachlor Epoxide	B
UJ	Metals	4804.08	UANG-FB8	Antimony	E
UJ	Metals	4804.08	UANG-FB8	Arsenic	D,F
UJ	Metals	4804.08	UANG-FB8	Copper	E,A
UJ	Metals	4804.08	UANG-FB8	Lead	D,H
UJ	Metals	4804.08	UANG-FB8	Mercury	E
UJ	Metals	4804.08	UANG-FB8	Nickel	E
UJ	Metals	4804.08	UANG-FB8	Selenium	D
UJ	Metals	4804.08	UANG-FB8	Thallium	D
UJ	Metals	4804.08	UANG-FB8	Zinc	E,A
UJ	Pesticides	4806.08	UANG-FB9	Heptachlor Epoxide	B
UJ	Metals	4806.08	UANG-FB9	Antimony	E
UJ	Metals	4806.08	UANG-FB9	Arsenic	,D,F,A
UJ	Metals	4806.08	UANG-FB9	Chromium	E,A
UJ	Metals	4806.08	UANG-FB9	Copper	E,A
UJ	Metals	4806.08	UANG-FB9	Lead	E,D,A
UJ	Metals	4806.08	UANG-FB9	Mercury	E
UJ	Metals	4806.08	UANG-FB9	Nickel	E
UJ	Metals	4806.08	UANG-FB9	Selenium	D
UJ	Metals	4806.08	UANG-FB9	Thallium	D,H
UJ	Metals	4806.08	UANG-FB9	Zinc	E,A

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
UJ	SVOCs	4806.10	UANG-CS-FB10	3-Nitroaniline	C
UJ	SVOCs	4806.09	UANG-CS-EQR	3-Nitroaniline	C
UJ	VOCs	4788.02	UANG-S6-ER20	Bromoform	B
J	VOCs	4781.05	UANG-S7-ER14	Carbon Tetrachloride	A
UJ	VOCs	4781.05	UANG-S7-ER14	Chloromethane	C
UJ	VOCs	4781.05	UANG-S7-ER14	Dichlorodifluoromethane	C
UJ	VOCs	4781.05	UANG-S7-ER14	1,2-Dichloropropane	C
J	VOCs	4781.02	UANG-S7-ER13	Carbon Tetrachloride	A
UJ	VOCs	4781.02	UANG-S7-ER13	Chloromethane	C
UJ	VOCs	4781.02	UANG-S7-ER13	Dichlorodifluoromethane	C
UJ	VOCs	4781.02	UANG-S7-ER13	1,2-Dichloropropane	C

METHOD BLANK QUALIFICATIONS

U	Metals	4781.02	UANG-S7-EQR13	Lead	E
U	Metals	4788.01	UANG-FB7-19	Lead	E
5U	VOCs	EN1311	UANG-S10-SB1 (8-10)	Dichloromethane	E
40U	VOCs	4595.04	UANG-S2-SB2	Acetone	E
20U	VOCs	4595.05	UANG-S2-SB2	Acetone	E
40U	VOCs	4595.02	UANG-S2-SB3	Acetone	E
40U	VOCs	4595.03	UANG-S2-SB3	Acetone	E
20U	VOCs	4595.06	UANG-S2-SB1	Acetone	E
10U	VOCs	4601.09	UANG-S4-SB1	Acetone	E
16U	VOCs	4608.03	UANG-S4-SB2	Acetone	E
13U	VOCs	4608.04	UANG-S4-SB2	Acetone	E
12U	VOCs	4608.05	UANG-S4-SB3	Acetone	E
13U	VOCs	4608.06	UANG-S4-SB3	Acetone	E
19U	VOCs	4608.07	UANG-S4-SB4	Acetone	E
12U	VOCs	4608.08	UANG-S4-SB4	Acetone	E
15U	VOCs	4608.09	UANG-S4-SB4	Acetone	E
11U	VOCs	4608.10	UANG-S5-SB1	Acetone	E
13U	VOCs	4608.11	UANG-S5-SB1	Acetone	E
12U	VOCs	4627.04	UANG-S6-SB2	Acetone	E
13U	VOCs	4627.01	UANG-S6-SB3	Acetone	E
12U	VOCs	4627.06	UANG-S6-SB3	Acetone	E
14U	VOCs	4627.02	UANG-S6-SB4	Acetone	E
14U	VOCs	4627.03	UANG-S6-SB4	Acetone	E
12U	VOCs	4627.05	UANG-S6-SB4	Acetone	E
500U	VOCs	4595.09	UANG-S7-SB1	Acetone	E
50U	VOCs	4601.04	UANG-S7-SB2	Acetone	E
410U	SVOCs	4601.04	UANG-S7-SB2	Di-n-butylphthalate	E
30U	VOCs	4601.06	UANG-S7-SB3	Acetone	E
100U	VOCs	4601.05	UANG-S7-SB3	Acetone	E
10U	SVOCs	4781.02	UANG-S7-EQR13	bis (2-Ethylhexyl) Phthalate	E
10U	SVOCs	4806.09	UANG-CS-EQR	bis (2-Ethylhexyl) Phthalate	E

TABLE E. 1 Continued

Qualifier	Fraction	Lab I.D.	Field ID	Analyte	Cause
10U	SVOCs	4804.01	UANG-CW1	bis (2-Ethylhexyl) Phthalate	E
10U	SVOCs	4804.03	UANG-CW3	bis (2-Ethylhexyl) Phthalate	E

Qualifiers (Cause Codes)

A- Reported value is between the CRQL and the MDL or the CRDL and the IDL.

B- Initial calibration is out of control.

C- Continuing calibration is out of control.

D- Matrix spike recovery is outside of QC limit.

E- The sample concentration was estimated due to contribution by the laboratory blank .

F- Laboratory duplicate was out of control.

G- Serial dilution %D was out of control.

H- Post spike recovery was outside of the QC limit.

I- Sample preservation method unclear.

J- Surrogate recovery is outside of QC limits.

K- Laboratory Control Sample was out of control.

TABLE E.2
TABLE OF UNUSABLE DATA
ANALYTICAL DATA SUMMARY
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Fraction	Field ID	Lab ID	Analyte	Cause
Metals	UANG-S2-SB1 (0.5-2.5)	4595-07	Antimony	MS %R
Metals	UANG-S2-SB1 (5-7.5)	4595-06	Antimony	MS %R
Metals	UANG-S2-SB2 (2.5-4.5)	4595-04	Antimony	MS %R
Metals	UANG-S2-SB2 (4.5-6.5)	4595-05	Antimony	MS %R
Metals	UANG-S2-SB3 (2.5-4.5)	4595-01	Antimony	MS %R
Metals	UANG-S2-SB3 (4.5-6.5)	4595-02	Antimony	MS %R
Metals	UANG-S2-SB3 (6.5-8.5)	4595-03	Antimony	MS %R
Metals	UANG-S7-SB1 (2.5-4.5)	4595-08	Antimony	MS %R
Metals	UANG-S7-SB1 (7-9)	4595-09	Antimony	MS %R
Metals	UANG-S7-SB2 (2.5-4.5)	4601-03	Antimony	MS %R
Metals	UANG-S7-SB2 (6.5-9)	4601-04	Antimony	MS %R
Metals	UANG-S7-SB3 (2.5-4.5)	4601-05	Antimony	MS %R
Metals	UANG-S7-SB3 (6.5-9)	4601-06	Antimony	MS %R
Metals	UANG-S4-SB1 (6.5-9)	4601-09	Antimony	MS %R
Metals	UANG-S4-SB1 (2.5-4.5)	4601-08	Antimony	MS %R
Metals	UANG-S4-SB8 (0.5-2.5)	4705-01	Selenium	MS %R
Metals	UANG-S4-SB8 (4.5-6.5)	4705-02	Selenium	MS %R
Metals	UANG-S4-SB9 (2.5-4.5)	4705-03	Selenium	MS %R
Metals	UANG-S4-SB9 (4.5-6.5)	4705-04	Selenium	MS %R
Metals	UANG-S7-SB9 (2.5-4.5)	4705-05	Selenium	MS %R
Metals	UANG-S7-SB9 (8.5-9.5)	4705-06	Selenium	MS %R
Metals	UANG-S7-SB9 (4.5-6.5)	4705-07	Selenium	MS %R
Metals	UANG-S7-SB10 (4.5-6.5)	4705-08	Selenium	MS %R
Metals	UANG-S2-SB5 (6.5-8.5)	4705-09	Selenium	MS %R
Metals	UANG-S2-SB6 (6.5-8.5)	4705-10	Selenium	MS %R
Metals	UANG-S3-SB5 (2.5-4.5)	4705.11	Selenium	MS %R
Metals	UANG-BG-MW1 (0-2)	4737-01	Selenium	MS %R
Metals	UANG-BG-MW1 (4-6)	4737-02	Selenium	MS %R
Metals	UANG-PI5 (0-2)	4483-01	Thallium	MS %R
Metals	UANG-PI5 (6-8)	4483-02	Thallium	MS %R
Metals	UANG-BG-MW1 (4-6)	4737-02	Thallium	MS %R
Metals	UANG-FB5-8	4779-06	Thallium	MS %R
Metals	UANG-S7-MW1-11	4781-01	Thallium	MS %R
Metals	UANG-S7-EQR-13	4781-02	Thallium	MS %R
Metals	UANG-S4-MW1-9	4781-03	Thallium	MS %R
Metals	UANG-FB6-15	4781-04	Thallium	MS %R
Metals	UANG-S7-MW2-EQR-14	4781-05	Thallium	MS %R
Metals	UANG-S7-MW2-12	4781-06	Thallium	MS %R
Metals	UANG-S7-SB2 (2.5-4.5)	4601-03	Thallium	MS %R
Metals	UANG-S7-SB2 (6.5-9)	4601-04	Thallium	MS %R

TABLE E.2 Continued

Fraction	Field ID	Lab ID	Analyte	Cause
Metals	UANG-S7-SB3 (2.5-4.5)	4601-05	Thallium	MS %R
Metals	UANG-S7-SB3 (6.5-9)	4601-06	Thallium	MS %R
Metals	UANG-S4-SB1 (6.5-9)	4601-09	Thallium	MS %R
Metals	UANG-S4-SB1 (2.5-4.5)	4601-08	Thallium	MS %R
Metals	UANG-S2-SB1 (0.5-2.5)	4595-07	Thallium	MS %R
Metals	UANG-S2-SB3 (2.5-4.5)	4595-01	Thallium	MS %R
Metals	UANG-S2-SB3 (6.5-8.5)	4595-03	Thallium	MS %R
Metals	UANG-S6-FB7-19	4788-01	Thallium	MS %R
Metals	UANG-S2-MW1	4801-01	Thallium	MS %R
SVOCs	UANG-BG-MW1 (0-2)	4737-01	3-Nitroaniline	CCAL
SVOCs	UANG-FB5-8	4779-06	3-Nitroaniline	CCAL
SVOCs	UANG-S3-RB6	4779-07	3-Nitroaniline	CCAL
SVOCs	UANG-S2-MW1-4	4779-08	3-Nitroaniline	CCAL
SVOCs	UANG-S3-MW3-5	4779-09	3-Nitroaniline	CCAL
SVOCs	UANG-S3-MW1-6	4779-10	3-Nitroaniline	CCAL
SVOCs	UANG-S3-MW2-7	4779-11	3-Nitroaniline	CCAL
SVOCs	UANG-S7-SB7 (2.5-4.5)	4797-03	3-Nitroaniline	CCAL (%D & RRF)
SVOCs	UANG-FB6-15	4781-04	2-Chlorophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2-Methylphenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2-Nitrophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2,4-Dichlorophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2,4-Dimethylphenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2,4-Dinitrophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2,4,5-Trichlorophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2,4,6-Trichlorophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	2-Chlorophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	4-Chloro-3-methylphenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	4-Nitrophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	4,6-Dinitro-2-methylphenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	Pentachlorophenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	Phenol	Surrogate
SVOCs	UANG-FB6-15	4781-04	4-Methylphenol	Surrogate
SVOCs	UANG-S5-SB6 (1-3)	4797-01	3-Nitroaniline	CCAL
SVOCs	UANG-S5-SB6 (5-7)	4797-02	3-Nitroaniline	CCAL
SVOCs	UANG-S5-SB7 (1-3)	4797-05	3-Nitroaniline	CCAL
SVOCs	UANG-S5-SB5 (1-3)	4797-07	3-Nitroaniline	CCAL
SVOCs	UANG-CS5	4806-05	3-Nitroaniline	CCAL
SVOCs	UANG-CS6	4806-06	3-Nitroaniline	CCAL
SVOCs	UANG-FB9	4806-08	2-Chlorophenol	Surrogate
SVOCs	UANG-FB9	4806-08	2-Methylphenol	Surrogate
SVOCs	UANG-FB9	4806-08	2-Nitrophenol	Surrogate
SVOCs	UANG-FB9	4806-08	2,4-Dichlorophenol	Surrogate
SVOCs	UANG-FB9	4806-08	2,4-Dimethylphenol	Surrogate
SVOCs	UANG-FB9	4806-08	2,4-Dinitrophenol	Surrogate
SVOCs	UANG-FB9	4806-08	2,4,5-Trichlorophenol	Surrogate
SVOCs	UANG-FB9	4806-08	2,4,6-Trichlorophenol	Surrogate
SVOCs	UANG-FB9	4806-08	2-Chlorophenol	Surrogate

TABLE E.2 Continued

Fraction	Field ID	Lab ID	Analyte	Cause
SVOCs	UANG-FB9	4806-08	3-Nitroaniline	CCAL
SVOCs	UANG-FB9	4806-08	4-Chloro-3-methylphenol	Surrogate
SVOCs	UANG-FB9	4806-08	4-Nitrophenol	Surrogate
SVOCs	UANG-FB9	4806-08	4-Methylphenol	Surrogate
SVOCs	UANG-FB9	4806-08	4,6-Dinitro-2-methylphenol	Surrogate
SVOCs	UANG-FB9	4806-08	Pentachlorophenol	Surrogate
SVOCs	UANG-FB9	4806-08	Phenol	Surrogate
TRPH	UANG-CS5	4806-05	TRPH	MS/MSD
VOCs	UANG-S7-SB1 (2.5-4.5)	4595-08	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-S7-SB1 (2.5-4.5)	4595-08	2-Butanone	CCAL (%D & RRF)
VOCs	UANG-S7-SB1 (2.5-4.5)	4595-08	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-S7-SB1 (7-9)	4595-09	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S7-SB2 (6.5-9)	4601-04	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S7-SB3 (6.5-9)	4601-06	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S6-SB1 (2.5-4.5)	4624-07	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S6-SB1 (6.5-9)	4624-05	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S6-SB2 (2.5-4.5)	4627-07	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S6-SB2 (6.5-9)	4627-04	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S6-SB3 (2.5-4.5)	4627-06	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S6-SB3 (6.5-9)	4627-01	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S6-SB4 (2.5-4.5)	4627-05	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S6-SB4 (8.5-11)	4627-03	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S6-SB4 (6.5-8.5)	4627-02	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S5-SB1-(6-8.5)	4608-11	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-S5-SB1 (0-2)	4608-10	2-Chloroethylvinylether	CCAL (%D & RRF)
VOCs	UANG-S5-SB2 (6-8.5)	4624-01	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S5-SB2 (2-4)	4624-09	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S5-SB3 (6-8.5)	4624-02	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S5-SB3 (8.5-11)	4624-03	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S5-SB3 (2-4)	4624-08	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S5-SB4 (6-8.5)	4624-04	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S5-SB4 (2-4)	4624-06	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB1 (2.5-4.5)	4601-08	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB2 (2.5-4.5)	4608-03	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB2 (6.5-9)	4608-04	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB1 (6.5-9)	4601-09	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB3 (2.5-4.5)	4608-05	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB3 (6.5-9)	4608-06	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB4 (2.5-4.5)	4608-07	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-S4-SB4 (6.5-9)	4608-08	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S4-SB4 (9-11)	4608-09	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S2-SB1 (0.5-2.5)	4595-07	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S2-SB1 (5-7.5)	4595-06	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S2-SB2 (4.5-6.5)	4595-05	2-Chloroethylvinylether	ICAL (RSD&RRF)
VOCs	UANG-S2-SB2 (2.5-4.5)	4595-04	2-Chloroethylvinylether	ICAL (none rptd.)
VOCs	UANG-S2-SB3 (6.5-8.5)	4595-03	2-Chloroethylvinylether	ICAL (none rptd.)
VOCs	UANG-S2-SB3 (4.5-6.5)	4595-02	2-Chloroethylvinylether	ICAL (none rptd.)

TABLE E.2 Continued

Fraction	Field ID	Lab ID	Analyte	Cause
VOCs	UANG-S2-SB3 (2.5-4.5)	4595-01	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-S2-SB3 (2.5-4.5)	4595-01	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-EQR-456	4627-08	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-EQR-456	4627-08	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-TB6	4627-09	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-TB6	4627-09	Trichlorofluoromethane	CCAL (RRF)
VOCs	UANG-TB2	4595-10	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-TB2	4595-10	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-RB1	4601-01	2-Chloroethylvinylether	CCAL (RRF)
VOCs	UANG-RB1	4601-01	2-Butanone	CCAL (RSD & RRF)
VOCs	UANG-RB1	4601-01	Trichlorofluoromethane	CCAL (%D & RRF)
VOCs	UANG-TB3	4601-02	Trichlorofluoromethane	CCAL (%D)
VOCs	UANG-TB3	4601-02	2-Butanone	CCAL (RSD & RRF)
VOCs	UANG-TB3	4601-02	2-Chloroethylvinylether	CCAL (none rptd.)
VOCs	UANG-RB3	4624-10	2-Chloroethylvinylether	ICAL (RRF)
VOCs	UANG-RB3	4624-10	2-Butanone	CCAL (%D & RRF)
VOCs	UANG-RB3	4624-10	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-TB5	4624-11	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-TB5	4624-11	2-Butanone	CCAL (%D & RRF)
VOCs	UANG-TB5	4624-11	2-Chloroethylvinylether	ICAL (RRF)
VOCs	UANG-RB2	4608-01	2-Chloroethylvinylether	ICAL (RRF)
VOCs	UANG-RB2	4608-01	2-Butanone	CCAL (%D & RRF)
VOCs	UANG-RB2	4608-01	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-TB4	4608-02	Trichlorofluoromethane	ICAL (RSD&RRF)
VOCs	UANG-TB4	4608-02	2-Chloroethylvinylether	ICAL (RRF)
VOCs	UANG-TB4	4608-02	2-Butanone	CCAL (%D & RRF)

TABLE E.3
EPA QUALIFIERS ASSIGNED TO ANALYTICAL RESULTS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Organic Data Validation Qualifiers	
U	The analyte is not present above the level of the associated value. The associated numerical value indicates the approximate concentration necessary to detect the analyte in this sample (e.g., the reporting limit).
J	The analyte is positively identified, but the associated numerical value may not reflect the amount actually present in the environmental sample. The data can be used for many purposes. This data should be seriously considered for decision-making.
R	The data are unusable for all purposes. The presence or absence of the analyte has not been verified. Resampling and re-analysis are necessary to confirm or deny its presence.
UJ	Combines the "U" and "J" qualifiers. The analyte was not present above the level of the associated value. The associated numerical value may not accurately or precisely represent the concentration in the sample.
N	The analysis indicates that an analyte is present. There are strong indications that the identity is correct.
NJ	Combines the "N" and "J" qualifiers. The analysis indicates that the analyte is "tentatively identified". The associated numerical value may not reflect the amount actually present in the environmental sample.
Inorganic Data Validation Qualifiers	
U	The material was not detected above the level of the associated value. The associated value is the project reporting level (e.g., <i>the non-detect level</i>).
J	The associated value is an estimated quantity [e.g., <i>the value falls between the method detection limit (MDL) and the practical quantitation limit (PQL)</i>].
R	The data are unusable. (Note: <i>Analyte may or may not be present.</i>)
UJ	The material was not detected. The associated value is an estimate and may be inaccurate or imprecise.

TABLE E.4
SUMMARY OF HOLDING TIMES FOR ENVIRONMENTAL AND QA SAMPLES
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Sample Identification	Date Sample Collected	DATE ANALYZED-Holding Time in Days												TPH - diesel 8015 Mod.	PH - Gasoline 8015 Mod.		
		Total Rec. Petroleum Hydrocarbons E418.1	Volatile Organics	Semivolatile Organics		Mercury	Pesticides and PCBs		Extracted 14 days(2)	Analyzed 40 days	Extracted 14 days(1)	Analyzed 40 days					
				Extracted 7/14 days(1)	Analyzed 40 days		Extracted 7/14 days(1)	Analyzed 40 days									
UANG-P15 (0-2)	10/22/92	11/3/92	12	11/2/92	13	11/3/92	12	11/6/92	3	11/17/92	26	11/4/92	13	11/23/92	19	--	--
UANG-P15 (6-8)	10/22/92	11/3/92	12	11/3/92	14	11/3/92	14	11/7/92	4	11/17/92	26	11/4/92	13	11/23/92	19	--	--
UANG-S2-SB3 (2.5-4)	12/3/92	12/29/92	26	12/15/92	12	12/14/92	11	12/28/92	14	12/23/92	20	--	--	--	--	--	--
UANG-S2-SB3 (4.5-6)	12/3/92	12/29/92	26	12/8/92	5	12/14/92	11	12/23/92	9	12/23/92	20	--	--	--	--	--	--
UANG-S2-SB3 (6.5-8)	12/3/92	12/29/92	26	12/8/92	5	12/14/92	11	12/24/92	10	12/23/92	20	--	--	--	--	--	--
UANG-S2-SB2 (2.5-4)	12/3/92	12/29/92	26	12/8/92	5	12/14/92	11	12/23/92	9	12/23/92	20	--	--	--	--	--	--
UANG-S2-SB2 (4.5-6)	12/3/92	12/29/92	26	12/12/92	9	12/14/92	11	12/24/92	10	12/23/92	20	--	--	--	--	--	--
UANG-S2-SB1 (5-7.5)	12/3/92	12/29/92	26	12/12/92	9	12/14/92	11	12/23/92	9	12/23/92	20	--	--	--	--	--	--
UANG-S2-SB1 (0.5-2)	12/3/92	12/29/92	26	12/12/92	9	12/14/92	11	12/23/92	9	12/23/92	20	--	--	--	--	--	--
UANG-S7-SB1 (2.5-4)	12/3/92	12/29/92	26	12/16/92	13	12/14/92	11	12/28/92	14	12/23/92	20	--	--	--	--	--	--
UANG-S7-SB1 (7-9)	12/3/92	12/29/92	26	12/12/92	9	12/14/92	11	12/28/92	14	12/23/92	20	--	--	--	--	--	--
UANG-S7-SB2 (2.5-4)	12/4/92	12/29/92	25	12/12/92	8	12/14/92	10	12/24/92	10	12/23/92	19	--	--	--	--	--	--
UANG-S7-SB2 (6.5-9)	12/4/92	12/29/92	25	12/14/92	10	12/14/92	10	12/24/92	10	12/23/92	19	--	--	--	--	--	--
UANG-S7-SB3 (2.5-4)	12/4/92	12/29/92	25	12/12/92	8	12/14/92	10	12/24/92	10	12/23/92	19	--	--	--	--	--	--
UANG-S7-SB3 (6.5-9)	12/4/92	12/29/92	25	12/14/92	10	12/14/92	10	12/24/92	10	12/23/92	19	--	--	--	--	--	--
UANG-S7-SB3 (9-11)	12/4/92	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
UANG-S4-SB1 (2.5-4)	12/4/92	12/29/92	25	12/14/92	10	12/14/92	10	12/24/92	10	12/23/92	19	--	--	--	--	--	--
UANG-S4-SB1 (6.5-9)	12/4/92	12/29/92	25	12/14/92	10	12/14/92	10	12/24/92	10	12/23/92	19	--	--	--	--	--	--
UANG-S4-SB2 (2.5-4)	12/7/92	1/4/93	28	12/14/92	7	12/18/92	11	12/30/92	12	12/23/92	16	--	--	--	--	--	--
UANG-S4-SB2 (6.5-9)	12/7/92	1/4/93	28	12/14/92	7	12/18/92	11	12/28/92	10	12/23/92	16	--	--	--	--	--	--
UANG-S4-SB3 (2.5-4)	12/7/92	1/4/93	28	12/14/92	7	12/18/92	11	12/28/92	10	12/23/92	16	--	--	--	--	--	--
UANG-S4-SB3 (6.5-9)	12/7/92	1/4/93	28	12/14/92	7	12/18/92	11	12/28/92	10	12/23/92	16	--	--	--	--	--	--
UANG-S4-SB4 (2.5-4)	12/7/92	1/4/93	28	12/14/92	7	12/18/92	11	12/28/92	10	12/23/92	16	--	--	--	--	--	--
UANG-S4-SB4 (6.5-9)	12/7/92	1/4/93	28	12/14/92	7	12/18/92	11	12/28/92	10	12/23/92	16	--	--	--	--	--	--
UANG-S4-SB4 (9-11)	12/7/92	1/4/93	28	12/14/92	7	12/18/92	11	12/28/92	10	12/23/92	16	--	--	--	--	--	--
UANG-S5-SB1 (0-2)	12/7/92	1/4/93	28	12/15/92	8	12/18/92	11	12/29/92	11	--	--	--	--	--	--	--	--
UANG-S5-SB1 (6-8)	12/7/92	1/4/93	28	12/15/92	8	12/18/92	11	12/28/92	10	--	--	--	--	--	--	--	--
UANG-S5-SB2 (6-8.5)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/11/93	20	--	--	--	--	--	--	--	--

TABLE E.4 Continued

Sample Identification	Date Sample Collected	DATE ANALYZED-Holding Time in Days														Gasoline 8015 Mod. Analyzed 14 days
		Total Petroleum Hydrocarbons E418.1 28 days	Volatile Organics 14 days	Semivolatile Organics 40 days		Mercury 28 days	Pesticides and PCBs 7/14 days(1) 40 days		Diesel 8015 Mod. 14 days(2) 40 days							
				Extracted 7/14 days(1)	Analyzed 40 days		Extracted 7/14 days(1)	Analyzed 40 days	Extracted 14 days(2)	Analyzed 40 days						
UANG-S5-SB3 (6-8.5)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/12/93	21	--	--	--	--	--	--	
UANG-S5-SB3 (8.5-11)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/12/93	21	--	--	--	--	--	--	
UANG-S5-SB4 (6-8.5)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/11/93	20	--	--	--	--	--	--	
UANG-S6-SB1 (7-9)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/11/93	20	--	--	--	--	--	--	
UANG-S5-SB4 (2-4)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/9/93	18	--	--	--	--	--	--	
UANG-S6-SB1 (2.5-4)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/12/93	21	--	--	--	--	--	--	
UANG-S5-SB3 (0-2)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/12/93	21	--	--	--	--	--	--	
UANG-S5-SB2 (2-4)	12/8/92	1/5/93	28	12/17/92	9	12/22/92	14	1/9/93	18	--	--	--	--	--	--	
UANG-S6-SB3 (6.5-9)	12/9/92	1/6/93	28	12/20/92	11	12/22/92	13	1/8/93	17	--	--	--	--	--	--	
UANG-S6-SB4 (6-8.5)	12/9/92	1/6/93	28	12/20/92	11	12/22/92	13	1/8/93	17	--	--	--	--	--	--	
UANG-S6-SB4 (8.5-11)	12/9/92	1/6/93	28	12/20/92	11	12/22/92	13	1/8/93	17	--	--	--	--	--	--	
UANG-S6-SB2 (6-8.5)	12/9/92	1/6/93	28	12/21/92	12	12/22/92	13	1/11/93	20	--	--	--	--	--	--	
UANG-S6-SB4 (0-2)	12/9/92	1/6/93	28	12/21/92	12	12/22/92	13	1/11/93	20	--	--	--	--	--	--	
UANG-S6-SB3 (0.5-2)	12/9/92	1/6/93	28	12/21/92	12	12/22/92	13	1/11/93	20	--	--	--	--	--	--	
UANG-S6-SB2 (2-4)	12/9/92	1/6/93	28	12/20/92	11	12/23/92	14	1/11/93	19	--	--	--	--	--	--	
UANG-S6-SB5 (6-8.5)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB8 (6.5-9)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB7 (6-8.5)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB6 (8.5-11)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB6 (6.5-8)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S3-SS1	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/14/93	22	--	--	--	--	--	--	
UANG-S3-SS2	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB6 (2-4)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB7 (2-4)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB8 (2.5-4)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB5 (0-2)	12/10/92	1/7/93	28	12/21/92	11	12/23/92	13	1/13/93	21	--	--	--	--	--	--	
UANG-S6-SB9 (0-2)	12/11/92	1/8/93	28	12/21/92	10	12/23/92	12	1/14/93	22	--	--	--	--	--	--	
UANG-S6-SB9 (6-8.5)	12/11/92	1/8/93	28	12/21/92	10	12/23/92	12	1/14/93	22	--	--	--	--	--	--	
UANG-S6-SB10 (0-2)	12/11/92	1/8/93	28	12/21/92	10	12/23/92	12	1/16/93	24	--	--	--	--	--	--	
UANG-S6-SB10 (6.0-8	12/11/92	1/8/93	28	12/21/92	10	12/23/92	12	1/14/93	22	--	--	--	--	--	--	
UANG-S6-SB9 (8.5-11	12/11/92	1/8/93	28	12/21/92	10	12/23/92	12	1/14/93	22	--	--	--	--	--	--	
UANG-S3-SS4 (North)	12/11/92	1/8/93	28	12/21/92	10	12/23/92	12	1/18/93	26	--	--	--	--	--	--	
UANG-S3-SS5 (South)	12/11/92	1/8/93	28	12/21/92	10	12/23/92	12	1/16/93	24	--	--	--	--	--	--	
UANG-S3-SS6 (West)	12/11/92	1/8/93	28	12/21/92	10	12/24/92	13	1/16/93	23	--	--	--	--	--	--	

TABLE E.4 Continued

Sample Identification	Date Sample Collected	DATE ANALYZED-Holding Time in Days																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		Total Petroleum Hydrocarbons E418.1		Volatile Organics		Semivolatile Organics		Mercury		Pesticides and PCBs		Diesel		Gasoline																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
		28 days	14 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days

TABLE E.4 Continued

Sample Identification	Date Sample Collected	DATE ANALYZED-Holding Time in Days																Diesel		Gasoline																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
		Total Petroleum Hydrocarbons E418.1	Volatile Organics	Semivolatile Organics		Mercury	Pesticides and PCBs		Diesel		Gasoline																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
				Extracted	Analyzed		Extracted	Analyzed	Extracted	Analyzed	Extracted	Analyzed																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
		28 days	14 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1)	40 days	28 days	7/14 days(1

TABLE E.4 Continued

Sample Identification	Date Sample Collected	DATE ANALYZED-Holding Time in Days														Diesel 8015 Mod.	Gasoline 8015 Mod.
		Total Petroleum Hydrocarbons E418.1	Volatile Organics 14 days	Semivolatile Organics		Mercury 28 days	Pesticides and PCBs		Extracted 14 days(2)	Analyzed 40 days	Extracted 40 days	Analyzed 14 days					
				Extracted 7/14 days(1)	Analyzed 40 days		Extracted 7/14 days(1)	Analyzed 40 days									
UANG-CS3	2/12/93	2/19/93	7	2/26/93	14	2/17/93	5	2/23/93	6	3/2/93	18	2/18/93	6	3/5/93	15	--	--
UANG-CS4	2/12/93	2/19/93	7	2/26/93	14	2/17/93	5	2/23/93	6	3/2/93	18	2/18/93	6	3/5/93	15	--	--
UANG-CS5	2/12/93	2/19/93	7	2/26/93	14	2/17/93	5	2/23/93	6	3/2/93	18	2/18/93	6	3/4/93	14	--	--
UANG-CS6	2/12/93	2/19/93	7	2/26/93	14	2/18/93	6	2/23/93	5	3/2/93	18	2/18/93	6	3/5/93	15	--	--
UANG-CS7	2/12/93	2/19/93	7	2/26/93	14	2/17/93	5	2/24/93	7	3/2/93	18	2/18/93	6	3/5/93	15	--	--
UANG-S10-SB1 (2-4)	5/25/94	6/08/94	12	6/06/94	10	--	--	--	--	--	--	--	--	--	--	--	--
UANG-S10-SB1 (6-8)	5/25/94	6/08/94	12	6/06/94	10	5/28/94	3	5/30/94	5	--	6/29/94	35	6/30/94	1	6/8/94	14	6/11/94
UANG-S10-SB1 (8-10)	5/25/94	--	--	5/26/94	1	--	--	--	--	--	--	--	--	--	--	--	--
UANG-S10-SB2 (2-4)	5/26/94	6/07/94	10	6/08/94	11	--	--	--	--	--	--	--	--	--	6/8/94	13	6/11/94
UANG-S10-SB2 (4-6)	5/26/94	6/08/94	11	6/08/94	11	--	--	--	--	--	--	--	--	--	6/8/94	13	6/11/94
UANG-S10-SB3 (1-3)	5/26/94	6/08/94	11	6/06/94	9	--	--	--	--	--	--	--	--	--	6/8/94	13	6/11/94
UANG-S10-SB3 (3-5)	5/26/94	6/07/94	10	6/06/94	9	--	--	--	--	--	--	--	--	--	6/8/94	13	6/11/94
UANG-S10-SB4 (2-4)	5/26/94	6/07/94	10	6/06/94	9	--	--	--	--	--	--	--	--	--	6/8/94	13	6/11/94
UANG-S10-SB4 (4-6)	5/26/94	6/08/94	11	6/06/94	9	--	--	--	--	--	--	--	--	--	6/8/94	13	6/11/94
UANG-S1-SB4 (3.5-5.10/26/94	10/26/94	--	--	11/09/94	14	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB4 (7.5-9.10/26/94	10/26/94	--	--	11/09/94	14	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB5 (1-3)10/26/94	10/26/94	--	--	11/09/94	14	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB5 (5-7)10/26/94	10/26/94	--	--	11/09/94	14	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB6 (1-3)10/26/94	10/26/94	--	--	11/09/94	14	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB6 (3-5)10/26/94	10/26/94	--	--	11/09/94	14	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB6 (5-7)10/26/94	10/26/94	--	--	11/09/94	14	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB7 (1-3)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB7 (5-7)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/23/94	26	--	--
UANG-S1-SB8 (1-3)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/24/94	27	--	--
UANG-S1-SB8 (5-7)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/24/94	27	--	--
UANG-S1-SB8 (7-9)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/24/94	27	--	--
UANG-S1-SB9 (3-5)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/24/94	27	--	--
UANG-S1-SB9 (5-7)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/24/94	27	--	--
UANG-S1-SB10 (1-3)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/24/94	27	--	--
UANG-S1-SB10 (3-5)10/26/94	10/26/94	--	--	11/10/94	15	--	--	--	--	--	--	10/28/94	2	11/24/94	27	--	--
UANG-TB2	12/2/92	--	--	12/15/92	13	--	--	--	--	--	--	--	--	--	--	--	--
UANG-TB3	12/4/92	--	--	12/16/92	12	--	--	--	--	--	--	--	--	--	--	--	--
UANG-TB4	12/7/92	--	--	12/16/92	9	--	--	--	--	--	--	--	--	--	--	--	--
UANG-TB5	12/8/92	--	--	12/17/92	9	--	--	--	--	--	--	--	--	--	--	--	--

TABLE E.4 Continued

Sample Identification	Date Sample Collected	DATE ANALYZED-Holding Time in Days											Diesel		Gasoline	
		Total Petroleum Hydrocarbons E418.1 28 days	Volatile Organics 14 days	Semivolatile Organics		Mercury 28 days	Pesticides and PCBs		8015 Mod.		8015 Mod.					
				Extracted 7/14 days(1)	Analyzed 40 days		Extracted 7/14 days(1)	Analyzed 40 days	Extracted 14 days(2)	Analyzed 40 days	Extracted 14 days	Analyzed 14 days				
UANG-TB6	12/9/92	--	12/20/92 11	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB7	12/10/92	--	12/24/92 14	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB8	12/10/92	--	12/24/92 14	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB9	12/14/92	--	12/24/92 10	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB10	12/15/92	--	12/24/92 9	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB2 (16)	1/13/93	--	1/20/93 7	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB-BG-1	1/29/93	--	2/3/93 5	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB11	12/16/92	--	12/30/92 14	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB12	12/17/92	--	12/31/92 14	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB14	12/29/92	--	1/5/93 7	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB15	12/30/92	--	1/5/93 6	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB17	2/1/93	--	2/11/93 10	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB18-GW	2/3/93	--	2/12/93 9	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB19	2/4/93	--	2/17/93 13	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB20	2/9/93	--	2/22/93 13	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB21	2/10/93	--	2/24/93 14	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-TB22	2/11/93	--	2/24/93 13	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-FB1	12/11/92	1/6/93	12/24/92 13	12/16/93 5	12/22/93 6	12/27/93 16	--	--	2/4/93 3	2/20/93 16	--	--	--	--	--	
UANG-FB2	2/1/93	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
UANG-FB4	1/29/93	--	--	2/3/93 5	2/9/93 6	--	--	2/4/93 6	2/19/93 15	--	--	--	--	--	--	
UANG-FB5-8	2/2/93	--	2/11/93 9	2/3/93 1	2/10/93 7	2/18/93 16	2/4/93 2	2/20/93 16	--	--	--	--	--	--	--	
UANG-FB6-15	2/3/93	--	2/12/93 9	2/5/93 2	2/10/93 5	2/18/93 15	--	--	--	--	--	--	--	--	--	
UANG-FB7-19	2/4/93	--	2/17/93 13	2/5/93 1	2/12/93 7	2/18/93 14	2/8/93 4	2/19/93 11	--	--	--	--	--	--	--	
UANG-FB8	2/11/93	2/16/93	5 2/24/93 13	2/12/93 1	2/17/93 5	3/1/93 18	2/17/93 6	2/25/93 8	--	--	--	--	--	--	--	
UANG-FB9	2/12/93	2/19/93	7 2/25/93 13	2/16/93 4	2-18-93 2	3/1/93 17	2/17/93 5	2/25/93 8	--	--	--	--	--	--	--	
UANG-CS-FB-10	2/12/93	2/19/93	7 2/25/93 13	2/16/93 4	2/18/93 2	3/1/93 17	2/17/93 5	2/25/93 8	--	--	--	--	--	--	--	
UANG-RB1	12/4/92	12/30/92	26 12/16/92 12	12/9/92 5	12/19/92 10	12/27/92 23	--	--	--	--	--	--	--	--	--	
UANG-RB2-S4	12/7/92	12/30/92	23 12/17/92 10	12/10/92 3	12/19/92 9	12/27/92 20	--	--	--	--	--	--	--	--	--	
UANG-RB3-55	12/8/92	1/5/93	28 12/17/92 9	12/12/92 4	12/19/92 7	--	--	--	--	--	--	--	--	--	--	
UANG-RB4-S6	12/9/92	1/5/93	27 12/20/92 11	12/12/92 3	12/19/92 7	--	--	--	--	--	--	--	--	--	--	
UANG-RB5-S6	12/10/92	1/6/93	27 12/24/92 14	12/15/92 5	12/19/92 4	--	--	--	--	--	--	--	--	--	--	
UANG-RB6-S1	12/11/92	--	--	--	--	--	--	2/16/93 5	12/30/92 14	--	--	--	--	--	--	
UANG-RB7-S6	12/11/92	1/6/93	26 12/24/92 13	12/16/92 5	12/22/92 6	--	--	--	--	--	--	--	--	--	--	
UANG-RB8-S7	12/14/93	1/6/93	23 12/24/92 10	--	2 12/23/92 7	--	--	--	--	--	--	--	--	--	--	

TABLE E.4 Continued

Sample Identification	Date Sample Collected	DATE ANALYZED-Holding Time in Days														Diesel 8015 Mod.	Gasoline 8015 Mod.
		Total Petroleum Hydrocarbons E418.1		Volatile Organics		Semivolatile Organics		Mercury	Pesticides and PCBs		Extracted 14 days(2)	Analyzed 40 days					
		28 days	14 days	7/14 days(1)	Extracted	Analyzed 40 days	28 days		7/14 days(1)	Extracted							
UANG-RB9-S3	12/14/92	1/13/93	26	1/1/93	14	12/16/92	4	12/30/92	8	--	--	--	--	--	--	--	
UANG-BGRB-1	1/29/93	--	--	2/3/93	5	--	--	--	--	--	--	--	--	--	--	--	
UANG-RB5-S1	2/1/93	--	--	--	--	--	--	--	--	2/4/92	3	2/20/93	16	--	--	--	
UANG-RB6-S3	2/2/93	--	--	2/11/93	9	2/3/93	1	2/10/93	7	12/27/92	13	--	--	--	--	--	
UANG-S7MW1-EQR1	2/3/93	--	--	2/12/93	9	2/5/93	2	2/10/93	5	2/18/93	15	--	--	--	--	--	
UANG-S7MW2-EQR1	2/3/93	--	--	2/12/93	9	2/5/93	2	2/10/93	5	2/18/93	15	--	--	--	--	--	
UANG-MW3-EQR20	2/4/93	--	--	2/17/93	13	2/5/93	1	2/12/93	7	--	--	--	--	--	--	--	
UANG-CW3-EQR	2/11/93	2/16/93	5	2/24/93	13	2/12/93	1	2/17/93	5	3/1/93	18	2/17/93	6	2/25/93	8	--	
UANG-CS-EQR	2/12/93	2/16/93	7	2/25/93	13	2/16/93	4	2/18/93	2	3/1/93	18	2/17/93	5	2/25/93	8	--	
UANG-S1-FB3	10/26/94	--	--	--	--	--	--	--	--	--	--	11/1/94	6	11/18/94	17	--	
UANG-S1-RB3	10/26/94	--	--	--	--	--	--	--	--	--	--	11/1/94	6	11/18/94	17	--	
UANG-S1-FB4	10/26/94	--	--	--	--	--	--	--	--	--	--	11/1/94	6	11/18/94	17	--	
UANG-S10-TBI	5/25/94	--	--	6/6/94	9	--	--	--	--	--	--	--	--	--	--	--	

(1) Seven day extraction after collection for water, 14 day extraction after collection for soil.

E.2 QUALITY CONTROL ASSESSMENT

E.2.1 METALS ANALYSIS USING EPA METHODS SW6010, SW7060, SW7421, SW7470/71, SW7740, and SW7841

E.2.1.1 Introduction

Three types of instrumentation were used to analyze 94 field samples for the 13 priority pollutant metals included in the analytical program. The samples included 29 aqueous and 65 soil/sediment samples. ICP analysis was performed for all metal analytes (SW6010) except arsenic (As), lead (Pb), selenium (Se), thallium (Tl), and mercury (Hg). The aqueous sample from UANG-BG-MW1, due to a miscommunication between ES Berkeley Laboratory and DataChem Laboratory resulted in all analysis being performed by ICP. The GFAA method was employed to analyze As (SW7060), Pb (SW7421), Se (SW7740), and Tl (SW7841) in selected samples because the instrument detection limit (IDL) of the GFAA accommodates low-concentration levels for these elements. A cold-vapor technique, using a flameless atomic absorption (CVAA) spectrophotometer, was used to analyze Hg (SW7470/71).

E.2.1.2 Technical Holding Times

Holding times were measured from the date of collection to the date of analysis. Chain-of-custody forms were used to verify technical holding times. The specified holding times for preserved aqueous and soil/sediment samples for metals are 28 days for mercury and 180 days for all other analytes. All samples met technical holding times.

E.2.1.3 Initial and Continuing Calibration Verification

The ICAL for ICP must include one blank and two standards per curve. The GFAA ICAL requires a blank and three standards, one of which represents the contract required detection limit (CRDL). The ICAL curve for CVAA calibration requires one blank and four standards per curve. The curves generated by the ICALs must produce a linear least squares correlation coefficient (r) greater than or equal to 0.995 for the GFAA analyses.

To verify the accuracy of the ICAL, an ICV standard (prepared from a standard source other than the source used to prepare the ICAL standards) is analyzed. A CCV standard, of a known concentration, must be analyzed at a 10% frequency for all analytes and after the last analytical sample in each run. The accuracy of the ICV and the CCV is based on the percent recoveries (%R). The %R range criterion is 80-120% for Hg and 90-110% for all other metals. All ICV and CCV results met control criterion except for one sample which was qualified as "UJ" due to the %R of the As results falling outside of QC limits.

E.2.1.4 Blanks

One laboratory blank must be analyzed for every ten samples and after each CCV for GFAA analysis. Qualification of analytes in field samples is required if identifiable quantities of target compounds are found in the laboratory blanks and the analytical results are less than five times the absolute value of the blank results.

Small concentrations of contaminants (greater than the MDL but less than the CRDL) were reported in several of the laboratory blanks. This resulted in the qualification of 71 samples as "J", "U", or "UJ". In some cases, when contaminants were detected, no qualifications were required since the sample analytes had concentrations greater than five times the blank contaminant concentration.

Field QC blanks were analyzed to verify that no contamination occurred during sampling. These field QC blanks (analyzed for this fraction) were equipment rinseate blanks and field blanks. All field blanks showed some of the following analytes: cadmium (Cd), chromium (Cr), copper (Cu), Pb, and zinc (Zn). Ten sample results were qualified as "U" because most samples had relatively high concentrations of these analytes.

E.2.1.5 Matrix Spike/Matrix Spike Duplicates

An MS or MSD must be included for every ten samples (one MS/MSD pair per 20 samples), for each matrix analyzed. Spiked-sample analysis provides information about the effect of each sample matrix on digestion and measurement methodologies. Samples identified as field blanks cannot be used for spiked-sample analysis. The %R values for all elements must be within the limits of 75-125%. If the measured %R value falls outside of this range, all associated samples must be qualified as estimated. If the analytical results for an analyte still fall below 30%, these results must be rejected in all associated samples.

As part of the inorganic metals analysis, three aqueous and five soil/sediment MS/MSDs were analyzed. The 10% frequency requirement for both matrices was met. The %R fell outside of QC criteria for several MS/MSDs requiring the qualification of 68 sample values as "J", "U", or "UJ" due to possible matrix interference. The %R of the MS/MSDs were less than 30% warranting rejection of specific analytes in several MS/MSDs. Rejected "R" flags were applied to 21 associated samples for possible matrix effects on Tl, 15 associated antimony (Sb) results, and 13 associated Se results. The "R" qualification of these analytes affected a total of 49 samples.

E.2.1.6 Interference Check Sample

The ICS verifies the laboratory's ICP inter-element and background correction factors. The ICS solution A and ICS solution AB must be analyzed at the beginning and end of each analysis run. The ICS solution AB recovery results must fall within the control range of 80-120%. The concentrations of aluminum, calcium, iron, and magnesium in the samples must be less than 2/3 of their respective concentrations in the ICS solutions. All ICS results met the required criteria.

E.2.1.7 Laboratory Control Samples

An LCS is a laboratory reagent blank spiked with known concentrations of target analytes and is processed with samples through sample preparation procedures. LCS spike recovery indicate accuracy relevant to all samples and matrices within an analytical batch lot and are strictly a measure of analytical accuracy conditions independent of samples and matrices. A successful result requires that the %Rs for all analytes fall within the control limits of 80-120%. Three sample results for lead were qualified as "J" or "UJ" for the LCS exceeding the %R criteria.

E.2.1.8 Duplicate Sample Analysis

One laboratory duplicate sample is analyzed for every 10 samples and for each matrix in the sample delivery group (SDG). The resulting relative percent difference (RPD) should be less than or equal to 20% for aqueous samples and less than or equal to 35% for soil and sediment samples, where measured analyte results are greater than five times the CRDL. Therefore, samples that are identified as field blanks are not used. Duplicate analyses are indicators of overall precision based on each sample matrix. For duplicate analyte concentrations less than five times the CRDL, the difference between the two reported results should be less than the CRDL for aqueous samples and two times the CRDL for soil/sediment samples.

A total of 33 samples did not meet the above criteria and were qualified as either "J" or "UJ". Twenty-four samples were qualified due to the As percent difference between the primary and duplicate samples exceeding QC limits. Nine samples were qualified due to Pb exceeding QC limits.

Field duplicates are analyzed to determine the representativeness of sampling procedures. One member of the duplicate pair is given a coded (false) identifier so that the sample analysis is not biased. Six sets of field duplicates were analyzed for metals and 12 of the 13 metals were detected. Five individual analyte comparisons between the primary and duplicate samples exceeded QC limits for percent difference. Analytical results are not qualified because of duplicate results.

E.2.1.9 ICP Serial Dilution

One serial dilution is performed for every ten samples and for each matrix. A serial dilution is performed for metals analyzed by ICP to determine if any physical or chemical interference's exist in the sample matrix. If the concentration in the original sample is greater than 50 times the IDL, a five-fold dilution must agree within $\pm 10\%$ of the difference between the dilution and the original result. Fifty seven samples were qualified as "J" or "UJ" because Cr and/or Zn values did not meet serial dilution criteria.

E.2.1.10 Furnace Atomic Absorption

GFAA duplicate injections percent relative standard deviation (%RSD) must be less than 20% with post digestion spike %R between 85-115%. If the sample's analyte recovery is less than 40% the sample should be diluted once and re-analyzed. For the method of standard addition (MSA), the r value must be greater than or equal to 0.995. A total of 72 samples were qualified as either "J" or "UJ" because analytical spike recoveries fell outside QC limits.

E.2.1.11 Furnace Atomic Absorption QC

The analytical results detected a significant number of heavy metals, particularly As, Cd, Cr, Cu, Pb, and Zn.

E.2.2 VOLATILE ORGANICS ANALYSIS USING EPA METHOD SW8240

E.2.2.1 Introduction

Thirty-nine target analytes were analyzed by gas chromatography/mass spectrometry (GC/MS). Sixty-one field samples composed of 52 soil samples and 9 aqueous samples were evaluated based on technical holding time results, GC/MS instrument performance checks, ICALs, CCALs, blanks, system monitoring compounds (surrogates), MS/MSDs, and LCS/LCSDs.

E.2.2.2 Technical Holding Times

The maximum allowable holding time for preserved water samples and soil samples is 14 days from the date of collection to VOC analysis. All samples met holding time criteria.

E.2.2.3 GC/MS Instrument Performance Check

The instrument performance checks (also called tunings) are performed to ensure mass resolution, compound identification, and, to some degree, instrument sensitivity. Using bromofluorobenzene (BFB) as the check solution. All samples met ion abundance criteria. A check was performed every 12 hours, as required.

TABLE E.5
GC/MS INSTRUMENT PERFORMANCE CHECK
USING BROMOFLUOROBENZENE
ION ABUNDANCE CRITERIA

Bromofluorobenzene	m/z	ion abundance criteria
50		15-40.0% of m/z 95
75		30.0-60.0% of m/z 95
95		Base peak, 100% relative abundance
96		5.0-9.0% of m/z 95
173		Less than 2.0% of m/z 174
174		>50.0% of m/z 95
175		5.0-9.0% of m/z 174
176		95.0-101.0% of m/z 174
177		5.0-9.0% of m/z 176

E.2.2.4 Initial Calibration

The ICAL is based on a 5-point standard calibration curve at concentrations of 10, 20, 50, 100, and 200µg/L, using standards containing both target compounds, internal

standards, and system monitoring compounds. Sample results are quantified using the relative response factor (RRF) of the ICAL, for samples analyzed within the ICAL sequence preceding analysis of a CCAL. Sample results are quantified using the RRF of the CCAL for samples analyzed within the CCAL 12-hour sequence. A mean RRF of greater than 0.05 must be maintained. The RRF %RSD result must be less than or equal to 30 for all compounds to meet data validation criteria. Sample results were qualified for minimum RRF results based on the CCAL from which the values were quantified. If the %RSD for a compound was greater than or equal to 30%, positive results were qualified as estimated, "J". Non-detected volatile target compounds were qualified as estimated non-detects, "UJ". For any ICAL mean RRF less than 0.05, positive results were qualified as estimated, "J". Non-detected analytes were qualified as unusable, "R". Twelve samples were qualified as estimated, "J" or "UJ" due to acetone and/or chloroethane exceeding QC limits. In almost every sample, 2-chloroethylvinylether did not meet the minimum RRF criteria and was qualified as unusable, "R". Thirty-seven other analytes were qualified as "R" twenty-nine as 2-Chloroethylvinylether and eight as Trichlorofluoromethane.

E.2.2.5 Continuing Calibration

A CCAL must be analyzed at the beginning of each 12-hour analysis period after the instrument performance check and before the analysis of any blanks or samples. The relative response factor for each target analyte must be >0.05 . The percent difference (%D) between the mean ICAL RRF and the CCAL RRF for each compound must be within $\pm 25\%$. A total of 42 samples were qualified as "J" or "UJ" due to acetone and several other target analytes exceeding quality control limits.

E.2.2.6 Blanks

Samples associated with blanks (laboratory and field) containing target analytes with concentrations less than 10 times the blank concentration for common laboratory contaminants (methylene chloride, acetone, 2-butanone, and toluene) and 5 times the blank concentration for other contaminants are qualified as undetected, "U".

Laboratory blanks were analyzed for possible laboratory sample contamination. A total of 25 samples were qualified as "U" due to acetone contamination in laboratory blanks. The presence of methylene chloride in the laboratory blank qualified one sample as non-detected "U".

Field QC blanks analyzed for this fraction included equipment rinseate blanks, field blanks, and trip blanks. Field QC blanks were analyzed to verify that no contamination of the samples occurred during sampling and shipping. Chloroform was detected in four equipment rinseate blanks; however, results were not qualified as all the related field samples showed no presence of chloroform.

The trip blank (TB1) collected and associated with sample S10-SB1-8-10, was not delivered to the laboratory at the same time the sample was delivered. The analysis of sample S10-SB1-8-10 indicated a low level of benzene in addition to methylene chloride. The trip blank TB1 contained a low level of methylene chloride. Benzene is believed to be representative of the sample site.

E.2.2.7 System Monitoring Compounds (Surrogates)

Laboratory performance on individual samples is established by means of spiking activities. All samples are spiked with system monitoring compounds prior to sample purging. The surrogates used were toluene-d₈ (TOL), BFB, and 1,2-dichloroethane-d₄ (DCE). Two samples exceeded the %R criteria resulting in "J" qualifications. Table E.6 below, indicates the surrogate recovery ranges.

TABLE E.6
SYSTEM MONITORING COMPOUND CRITERIA

System Monitoring Compounds	Water %R	Soil %R
Toluene-d ₈ (TOL)	88-110	87-138
Bromofluorobenzene (BFB)	86-115	82-113
1,2-Dichloroethane-d ₄ (DCE)	76-114	79-121

E.2.2.8 Matrix Spike/Matrix Spike Duplicates

Data from MS/MSDs are generated to determine the long-term precision and accuracy of the analytical method for various matrices and to demonstrate acceptable compound recovery by the laboratory at the time of sample analysis. These data alone are not used to evaluate the precision and accuracy of other samples. Four soil MS/MSDs were analyzed for this fraction. The %R and RPD criteria for 1,1-dichloroethene, trichloroethene, benzene, toluene, and chlorobenzene were met for the applicable MS/MSD results.

TABLE E.7
MS/MSD CRITERIA FOR VOLATILE ANALYSIS

	Water		Soil	
	%R	RPD	%R	RPD
1,1-Dichloroethene	61-145	14	59-172	22
Trichloroethene	71-120	14	62-137	24
Benzene	76-127	11	66-142	21
Toluene	76-125	13	59-139	21
Chlorobenzene	75-130	13	60-133	21

E.2.2.9 Laboratory Control Spikes/Laboratory Control Spike Duplicates

LCS/LCSDs are to be performed for every 10 samples analyzed to check the proficiency of the analysis. Control criteria for the LCS/LCSD are the same as for the

MS/MSD are listed in Table E.7 above. This data can determine if the MS/MSD is out of control, whether the cause is a system problem or a matrix effect. The LCS/LCSD was not analyzed for every 10 samples because it is not required by SW846, except in the cases where the MS/MSD is out of control limits. All LCS/LCSDs met control criteria.

E.2.2.10 Field Duplicates

Field duplicates are analyzed to determine the representativeness of sampling procedures. Of each duplicate pair, one is given a coded (false) identifier so that the laboratory results will not be biased. A total of four field duplicate pairs were analyzed for this fraction. Eight analytes were detected and all but one analyte comparison for RPD (%) or difference was within QC limits. Samples are not qualified due to duplicate results.

E.2.3 PURGABLE HALOGENATED VOLATILE ORGANIC AND PURGABLE AROMATIC VOLATILE ORGANIC ANALYSES BY GC USING METHODS SW8010 AND SW8020

E.2.3.1 Introduction

The EPA methods SW8010 and SW8020 require analysis by gas chromatograph (GC). The laboratory analyzed 138 field samples: 51 aqueous and 87 soil/sediment samples for 36 target analytes (using method SW8010) and eight target analytes (using method SW8020). The laboratory QC data were reviewed for technical holding times, ICALs, CCALs, blank concentration, surrogate spikes, MS/MSDs, and LCSs.

E.2.3.2 Technical Holding Times

The required holding times for both analytical methods is 14 days. All samples analyzed by the SW8010/SW8020 methods met holding times except the field samples from the second sampling event at Site 1, which were all analyzed within 10-25 hours past the 14 day limit. Samples include: UANG-SB7(1-3), UANG-SB7(5-7), UANG-SB8(5-7), UANG-SB8(7-9), UANG-SB9(3-5), UANG-SB9(5-7), UANG-SB10(1-3), UANG-SB10(3-5), UANG-SB8(1-3), UANG-SB8(1-3)MS, and UANG-SB8(1-3)MSD. These samples were qualified as estimated, "J" or "UJ", because they exceeded the specified holding time. UANG-S3-RB9 (Laboratory I.D. 4683-01), exceeded the 12-hour limit by 17 minutes. Since the time limit was only slightly exceeded and no analytes were detected, the results were not qualified.

E.2.3.3 Initial Calibration

A five-point ICAL is performed for each compound at concentrations of 5, 10, 15, 20, and 40 µg/L, that establishes the daily retention time (RT) window. The resulting RRF %RSDs must be less than or equal to 20%, or the linear regression r value must be less than or equal to 0.995. All ICAL determinations met these criteria with the exception of chloromethane which had an r value less than the specified limit. This resulted in the qualification of 24 soil samples and three water samples as estimated, "J" or "UJ", for chloromethane.

E.2.3.4 Continuing Calibration

A mid-range CCAL standard containing all the target compounds must be analyzed at the beginning of each 12-hour analysis period or one per ten samples, whichever is more frequent. The CCAL was analyzed following the analysis of the instrument performance check and prior to the analysis of any blanks or samples. The %D between the mean ICAL RRF and the CCAL RRF for each compound must be within $\pm 15\%$, with the peak midpoint within the daily RT window established by the ICAL. Twenty samples were qualified as "J" or "UJ" due to CCAL analytes exceeding the %D in the SW8010/SW8020 methods.

For samples collected during the second sampling event at Site 1, a %D limit of $\pm 15\%$ was used as a criterion for continuing calibration. Ten compounds exceeded this criterion resulting in the qualification of two samples as estimated, "J" or "UJ".

E.2.3.5 Blanks

One laboratory method blank must be analyzed for every 10 samples and for each matrix type in every SDG. If a blank is contaminated with target compounds and the associated samples contain less than 10 times the blank concentration of compounds considered to be common laboratory contaminants, or less than five times the blank concentration for other target compounds, the analyte is qualified as undetected. All method blanks were free of target analytes.

Blanks provide a measure of contamination that may have been introduced into a sample set during the field work, while samples were being collected or transported to the laboratory, or in the laboratory during sample preparation and analysis. Each blank is discussed in more detail in Section E.2.7. QC blanks analyzed for this fraction included equipment rinseate blanks, field blanks, and trip blanks. The association of these blanks with their respective samples is given in Table E.19.

There were no trip blanks, rinseate blanks, or field blanks analyzed with the samples collected from the second sampling event at Site 1. Only one out of the 16 samples had a target detect. Data quality is not believed to have been compromised. The trichloroethene in sample SB9(5-7) is indicative of site contamination because this compound is not considered a common laboratory contaminant. The introduction of trichloroethene through field contamination would most likely have affected more than one sample.

E.2.3.6 Surrogate Spikes

Bromochloromethane (BRCLM), Chlorofluorobenzene (CLFLB) and H-2,6-Dichlorotoluene were used as surrogates for method SW8010 with a,a,a-Trifluorotoluene (TRIFL Toluene) used as the surrogate for method SW8020. An acceptance range of 50-150% was used as the surrogate spike recovery criterion for both methods. Surrogate spike recoveries were within control criteria exception for one sample, UANG-SB7(1-7), which had a surrogate recovery of 42.7%. Re-analysis of this sample yielded a similar result. This sample was qualified as estimated, "J" or "UJ".

E.2.3.7 Matrix Spike/Matrix Spike Duplicates

For every 10 samples analyzed, an MS or MSD must be analyzed (one MS/MSD pair per 20 samples). The MS/MSD measures the precision and accuracy of the laboratory and the potential presence of matrix interference's. Qualification of the field samples is not based on the results of the MS/MSD alone.

The MS/MSD criteria for both methods is presented in the following Tables E.8 and E.9 and was met in all cases for all analytes. Three water and five soil MS/MSDs were analyzed meeting the criteria of one MS/MSD per 20 samples.

TABLE E.8**PACE LABORATORY MS/MSD CRITERIA**

Compound	Soil/Sediment		Aqueous	
	RPD	%R	RPD	%R
SW8010 Analysis				
1,1-Dichloroethene	47	28-167	47	28-167
Trichloroethene	30	35-146	30	35-146
Chlorobenzene	35	38-150	35	38-150
SW8020 Analysis				
Benzene	29	39-150	29	39-150
Toluene	28	46-148	28	46-148
Chlorobenzene	25	55-135	25	55-135

TABLE E.9**DATACHEM LABORATORY MS/MSD CRITERIA**

Compound	Soil/Sediment		Aqueous	
	RPD	%R	RPD	%R
SW8010 Analysis				
Chloroform	50	39-150	50	39-150
Tetachloroethene	50	39-150	50	39-150
Trichloroethene	50	39-150	50	39-150
trans-1,2-Dichloroethene	50	39-150	50	39-150

E.2.3.8 Laboratory Control Sample

An LCS was required for every 10 samples or for each SDG, whichever was more frequent. The LCS recovery criterion for methods SW8010/SW8020 is the same as for the MS/MSD. Data are only qualified as a result of the LCS if the MS/MSD percentage recovery is out of control. The LCS requirements met required criteria in all cases and no results were qualified due to the combined results of the MS/MSD and the LCS.

E.2.3.9 Field Duplicates

Field duplicates are analyzed to determine the representativeness of sampling procedures. Out of each duplicate pair, one is given a coded (false) identifier so that the laboratory results will not be biased. Eight field duplicates were analyzed for this fraction. Nine analytes were detected. All but two individual analyte percent comparisons between the primary and the duplicate were within QC limits. Two field duplicates were collected during the sampling event. No analytes were detected in any of the duplicate pairs. Samples are not qualified due to duplicate results.

E.2.3.10 Additional Comments

Based on the case narrative for SDG S94-0681-ED, the request for SW8010 analysis was made six days after sample receipt by the laboratory. Sample volume from the PESTs/PCBs sample containers was used for the SW8010 analysis. The sample containers had been opened and a quantity extracted previously for Pesticides/PCBs analysis. Therefore, the sample containers contained headspace. Due to the headspace, all samples in this SDG were qualified as estimated, "J" or "UJ".

E.2.4 SEMIVOLATILE ORGANIC ANALYSIS BY GC/MS USING EPA METHOD SW8270

E.2.4.1 Introduction

The SVOCs, also called BNAs, are assessed by QC criteria similar to those used for the volatile fraction. The EPA method for SVOCs requires analysis by GC/MS. A total of 171 samples including 128 soil/sediment and 43 aqueous samples were analyzed for 65 target compounds. Laboratory QC data were reviewed for technical holding time, GC/MS instrument performance check, ICAL and CCAL, blanks, surrogate spike compounds, and MS/MSDs.

E.2.4.2 Holding Times

The technical holding times are seven days for aqueous samples and 14 days for soil/sediment samples from the date of sample collection to extraction. Sample extracts must be analyzed 40 days from the date of extraction. Chemical preservation is not required for either soil/sediment or water samples. The technical holding times were met for all samples.

E.2.4.3 GC/MS Instrument Performance Check

Decafluorotriphenylphosphine (DFTPP) is used as the tuning standard for BNA analysis. A performance check is to be performed every 12 hours. In all cases, the DFTPP performance check was performed and met the following criteria indicated here on Table E.10.

TABLE E.10
PERFORMANCE CHECK USING
DECAFLUOROTRIPHENYLPHOSPHINE

m/z	Ion Abundance Criteria
51	30.0 - 60.0% of m/z 198
68	Less than 2.0% of m/z 69
69	Present
70	Less than 2.0% of m/z 69
127	40.0 - 60.0% of m/z 198
197	Less than 1.0% of m/z 198
198	Base peak, 100% relative abundance
199	5.0 - 9.0% of m/z 198
275	10.0 - 30.0% of m/z 198
365	Greater than 1.0% of m/z 198
441	Present, but less than m/z 443
442	Greater than 40.0% of m/z 198
443	17.0 - 23.0% of m/z 442

E.2.4.4 Initial Calibration

The ICAL is based on a 5-point standard calibration curve, using standards of 10, 25, 40, 60, and 80 µg/L containing both target compounds, internal standards, and system monitoring compounds. The instrument must demonstrate an RRF of < 0.05 for each compound and a %RSD result <30%. Seventy-eight samples were qualified as "J" or "UJ" due to %RSD values > 30%.

E.2.4.5 Continuing Calibration

A CCAL must be analyzed at the beginning of each 12-hour analysis period after the analysis of the instrument performance check and before to the analysis of any blanks or

samples using a midrange standard. The RRF for each target analyte must be 0.05. The %D between the mean ICAL RRF and the CCAL RRF for each compound must be within $\pm 25\%$. Ninety-five samples were qualified because the %D criterion was exceeded. In 15 samples the 3-nitroaniline RRF was < 0.05 , requiring an "R" qualification.

E.2.4.6 Blanks

If concentrations of analytes in field samples are less than five times the contaminant concentration in the associated laboratory blanks (10 times for common laboratory contaminants), the results are qualified as "U". Four samples were qualified for contamination by bis(2-ethylhexyl)phthalate and one sample for di-n-butylphthalate contamination (two common laboratory contaminants).

Field QC blanks are analyzed to verify that no contamination occurred during sampling. Field QC blanks analyzed for this fraction are equipment rinseate blanks and field blanks. Data were qualified using the same criteria as laboratory blanks. While some field blanks had detectable analyte concentrations, no results were qualified.

E.2.4.7 Surrogate Spike Compounds

Eight surrogate spike compounds are used to calculate %R for BNA analytes. Qualification is only applied to samples if two surrogates in the same fraction exceed control limits or if a single surrogate has a recovery of less than 10%. Sample re-analysis is to be performed if surrogate %R results are outside of recovery criteria. Surrogate spike recoveries required qualification of the acid fractions as "R" for field samples UANG-FB6-15 (4781-04) and UANG-FB9 (4806-08). The following two Tables (E.11 and E.12) give the BNA Surrogate Compounds with Associated Target Analytes, and Surrogate Recovery Limits.

TABLE E.11
BASE/NEUTRAL/ACID SURROGATE COMPOUNDS
WITH ASSOCIATED TARGET ANALYTES

Base/Neutral (B/N) Fraction Surrogates:

Nitrobenzene-d ₅ (NBZ)	2-Fluorobiphenyl (FBP)
Terphenyl-d ₁₄ (TPH)	1,2-Dichlorobenzene-d ₄ (DCB)

Base/Neutral (B/N) Fraction Target Compounds:

Dibenzofuran	Indeno(1,2,3-cd)pyrene
2,4-Dinitrotoluene	Dibenz(a,h)anthracene
Diethylphthalate	Benzo(g,h,i)perylene
4-Chlorophenyl-phenylether	bis(2-Chloroethyl)ether
Fluorene	1,3-Dichlorobenzene
4-Nitroaniline	1,4-Dichlorobenzene
N-Nitrosodiphenylamine	1,2-Dichlorobenzene
4-Bromophenyl-phenylether	2,2'-oxybis(1-Chloropropane)
Hexachlorobenzene	N-Nitroso-di-n-propylamine
Phenanthrene	Hexachloroethane
Anthracene	Nitrobenzene
Carbazole	Isophorone
Di-n-butylphthalate	bis(2-Chloroethoxy)methane
Fluoranthene	1,2,4-Trichlorobenzene
Pyrene	Naphthalene
Butylbenzylphthalate	4-Chloroaniline
3,3'-Dichlorobenzidine	Hexachlorocyclopentadiene
Benzo(a)anthracene	2-Chloronaphthalene
Chrysene	2-Nitroaniline
bis(2-Ethylhexyl)phthalate	Dimethylphthalate
Di-n-octylphthalate	Acenaphthylene
Benzo(b)fluoranthene	2,6-Dinitrotoluene
Benzo(k)fluoranthene	3-Nitroaniline
Benzo(a)pyrene	Acenaphthene
Hexachlorobutadiene	2-Methylnaphthalene

TABLE E.11 CONTINUED
BASE/NEUTRAL/ACID SURROGATE COMPOUNDS
WITH ASSOCIATED TARGET ANALYTES (CONTINUED)

Acid (A) Fraction Surrogates:

Phenol-d ₅ (PHL)	2-Fluorophenol (2FP)
2-Chlorophenol-d ₄ (2CP)	

Acid (A) Fraction Target Compounds:

2,4-Dinitrophenol	4-Methylphenol
4-Nitrophenol	2-Nitrophenol
4,6-Dinitro-2-methylphenol	2,4-Dimethylphenol
Pentachlorophenol	2,4-Dichlorophenol
Phenol	4-Chloro-3-methylphenol
2-Chlorophenol	2,4,6-Trichlorophenol
2-Methylphenol	2,4,5-Trichlorophenol

TABLE E.12
SURROGATE RECOVERY LIMITS

	Water %R	Soil/Sediment %R
NBZ (Nitrobenzene-d5)	35-114	23-120
BP (2-Fluorobiphenyl)	43-116	30-115
TPH (Terphenyl-d14)	33-141	18-137
PHL (Phenol-d5)	10-94	24-113
2FP (2-Fluorophenol)	21-110	25-121
TBP (2,4,6-Tribromophenol)	10-123	19-122
DCB (1,2-Dichlorobenzene-d4)	16-110	20-130 (advisory)
2CP (2-Chlorophenol-d4)	33-110	20-130 (advisory)

E.2.4.8 Matrix Spikes/Matrix Spike Duplicates

A MS or MSD is to be analyzed for every 10 samples (one MS/MSD pair per 20 samples) and should be analyzed for all matrices present in every SDG. Eight soil/sediment samples and two aqueous samples were spiked with the standard MS/MSD solution to meet the frequency criteria. In some cases the MS/MSD did not meet control criteria listed below in Table E.13. However, samples were not qualified because data is not qualified by the MS/MSD results alone.

TABLE E.13
SEMIVOLATILE ORGANIC MS/MSD CRITERIA

Compound	Water		Soil/Sediment	
	%R	RPD	%R	RPD
Phenol	12-110	42	26-90	35
2-Chlorophenol	27-123	40	25-102	50
1,4-Dichlorobenzene	36-97	28	28-104	27
N-Nitroso-Di-n-propylamine	41-116	38	41-126	38
1,2,4-Trichlorobenzene	39-98	28	38-107	23
4-Chloro-3-methylphenol	23-97	42	26-103	33
Acenaphthene	46-118	31	31-137	19
4-Nitrophenol	10-80	50	11-114	50
2-4-Dinitrotoluene	24-96	38	28-89	47
Pentachlorophenol	9-103	50	17-109	47
Pyrene	26-127	31	35-142	36

E.2.4.9 Laboratory Control Spikes/Laboratory Control Spike Duplicates

LCS/LCSDs are performed for every 10 samples analyzed to check the proficiency of the analysis. Control criteria for the LCS/LCSD is the same as for the MS/MSD and is listed above in Table E.13. This data can determine if the MS/MSD is out of control, related to the system, or is a matrix effect. In some cases, the LCS/LCSD results were slightly out of control criteria; samples were not qualified because the LCS/LCSD is not considered alone.

E.2.4.10 Internal Standards

Six internal standard (IS) compounds are used in SVOC analysis; each is associated with a group of analytes. The IS performance criteria ensures that GC/MS sensitivity and responses are stable during each analysis. The IS area counts must not vary more than a factor of two (-50% to +100%) for the associated standard. The relative retention time of the IS must not vary more than +/- 30 seconds from the relative retention time of the associated calibration standard. The laboratory case narrative states that QC criteria were not met; however, the data package did not include the IS summary form. The validators did not consider IS criteria during the validation process.

E.2.4.11 Field Duplicates

Field duplicates are analyzed to determine the representativeness of sampling procedures. Out of each duplicate pair, one is given a coded (false) identifier so that the laboratory results will not be biased. A total of 12 duplicate pairs were analyzed for semivolatiles. Concentrations of 13 analytes were detected in eight of the 12 pairs with none of the individual analyte percent difference comparisons between the primary and the duplicate exceeding QC limits. Samples are not qualified due to duplicate results.

E.2.5 PESTICIDES AND PCB ANALYSIS USING EPA METHOD SW 8080

E.2.5.1 Introduction

This EPA method analyzes PESTs and PCBs using a gas chromatograph (GC) with an electron capture-detector (ECD). A total of 66 field samples, including 25 aqueous and 41 soil/sediment samples, were analyzed for 20 PESTs. Three of the 25 aqueous and 16 of the 41 soil/sediment samples were from the second sampling event at Site 1. Detected PESTs must be confirmed by analyzing the sample extracts on a second GC column. QC assessment for pesticides included evaluation of technical holding times, ICALs, CCALs, blanks, surrogate spike compounds, LCS/LCSDs, and MS/MSDs. Instrument performance checks and pesticide clean-up check QC are not required deliverables for SW846 and were not received.

E.2.5.2 Technical Holding Times

Technical holding times for PESTs/PCB analyses are 7 days from sample collection to extraction for water samples and 14 days from collection to extraction for

soils/sediment samples. The maximum holding time between extraction and analysis is 40 days for both matrices. All samples met holding times.

E.2.5.3 Initial Calibration

Gas chromatograph (GC) calibration is established by injecting individual standard mixtures: A (ISM-A) and B (ISM-B) into the injection port of the GC. These mixtures contain all of the single-component PESTs and surrogates, (using standards of 10, 25, 40, 60, and 80 µg/L) for each GC column used for analysis. The %RSD of the calibration factors for each of the single-component pesticides and surrogates in the initial calibration must be 20% on both columns for ISM-A and ISM-B. For both surrogates the %RSD must be 30%. A single concentration calibration standard must be analyzed for each multi-component target compound. Six samples were qualified as estimated, "J" or "UJ", because the %RSD criterion was not met.

For samples collected during the second sampling event at Site 1, a criterion of greater than or equal to 0.990 was used for the r^2 value of the initial calibration curve. This criterion was met during initial calibration.

E.2.5.4 Continuing Calibration

An instrument blank and a midpoint concentration of the ISM-A and ISM-B are to bracket the front end of a 12-hour period during which samples are analyzed. A second instrument blank and a calibration sample using the mid-level concentration of ISM-A and ISM-B are to be analyzed after each 10 samples or at the end of the 12-hour period. The %D between the calculated amount and the true amount for each of the pesticides and surrogates in the mid-level concentration of the ISM-A and ISM-B should not exceed 15%. The continuing calibration sequence described applies to each individual column. Twenty-seven samples were qualified as "J" or "UJ" due to calibration results not meeting QC limits.

For samples collected during the sampling event at Site 1, a frequency of 10% and a %D limit of +/-15% were used as criteria for continuing calibration. Fourteen pesticide compounds had %Ds above the upper limit of the QC limits; however, since there were no detects, qualification was not required. One pesticide compound had a %R below the lower limit of the QC limits. This resulted in the qualification of eight soil samples as estimated, "J" or "UJ".

E.2.5.5 Blanks

A method blank analysis must be performed for every 10 samples for each matrix type in every SDG. If concentrations of analytes in field samples are less than 5 times the contaminant concentration in the associated laboratory blanks (10 times for common laboratory contaminants), the results are qualified as "U". Contamination was not detected in any of the laboratory blanks for any analytes.

Field QC blanks are analyzed to verify that no contamination occurred during sampling. Field QC blanks analyzed for this fraction are equipment rinse blanks and field blanks and qualify data using the same criteria as laboratory blanks. No analytes were detected in the blanks.

E.2.5.6 Surrogate Spike Compounds

Three surrogate spikes, tetrachloro-m-xylene (TCX), decachlorobiphenyl (DCB) and dibutylchloroendate are added to all samples (ISMs, Performance Evaluation Mixture (PEMs), blanks, and MSs) to measure their recovery in sample and blank matrices. The Pace Laboratory advisory limits for %R of the surrogates TCX and DCB are 50-150% for both aqueous and soil/sediment matrices. Five samples were qualified as "J" or "UJ" due to surrogate spike %R being outside of QC limits. DataChem Laboratories advisory limits for %R of the surrogates TCX and DCB are 10-115% for both aqueous and soil matrices. About half of the 16 soil samples from the second sampling event at Site 1 had PESTs and/or PCB surrogate recoveries within 10% (115-126%) above the required QC limit. Since none of the samples demonstrated any target detects, qualification was unnecessary as per EPA guidelines.

E.2.5.7 Laboratory Control Spikes/Laboratory Control Spike Duplicates

The LCS/LCSDs are used in conjunction with information on other deficiencies to evaluate precision and accuracy. One LCS must be prepared and analyzed for each matrix type, for each 10 samples, or for each SDG, whichever is more frequent. All LCS/LCSD samples within the control criteria listed below in Tables (E.14, E.15, and E.16).

TABLE E.14
LCS/LCSD REQUIREMENTS FOR PESTICIDE ANALYSIS

LCS Concentrations in the Sample	Aqueous ($\mu\text{g/L}$)	Soil/Sediment ($\mu\text{g/kg}$)
Lindane	0.5	16.67
Heptachlor	0.5	16.67
Aldrin	0.5	16.67
Dieldrin	1.0	33.33
Endrin	1.0	33.33
4,4'-DDT	1.0	33.33

TABLE E.15
Berkeley (Pace) Laboratory LCS/LCSD QC Limits

Compound	%Recovery RPD		%Recovery RPD	
	Water		Soil/Sediment	
Lindane	56-123	15	46-127	50
Heptachlor	40-131	20	35-130	31
Aldrin	40-120	22	34-132	43
Dieldrin	52-126	18	31-134	38
Endrin	56-121	21	42-139	45
4,4'-DDT	38-127	27	23-134	50

TABLE E.16
DataChem Laboratory LCS QC Limits

Compound	%Recovery	%Recovery
	Water	Soil/Sediment
Lindane	32-127	32-127
Heptachlor	34-111	34-111
Aldrin	42-122	42-122
Dieldrin	36-146	36-146
Endrin	30-147	30-147
4,4'-DDT	25-160	25-160

E.2.5.8 Matrix Spikes/Matrix Spike Duplicates

The MS/MSDs are used in conjunction with information on other deficiencies to evaluate precision and accuracy. At least one MS was run for each 10 samples (one MS/MSD pair per 20 samples). A total of three soil/sediment and two aqueous MS/MSDs were analyzed and all met control criteria listed below in Table E.17 and E.18, with the exception of one MSD (4448-01). One soil and one aqueous MS/MSD pair were analyzed with the samples from the second sampling event at Site 1. All MS/MSD recoveries were within the specified QC limits except Endrin which was recovered at 150% and 148%. Samples were not qualified because data is not qualified by the MS/MSD results for this method.

TABLE E.17
PACE LABORATORY
MS/MSD REQUIREMENTS FOR PESTICIDE ANALYSIS

Compound	%Recovery RPD		%Recovery RPD	
	Water		Soil	
gamma-BHC (Lindane)	56-123	15	46-127	50
Heptachlor	40-131	20	35-130	31
Aldrin	40-120	22	34-132	43
Dieldrin	52-126	18	31-134	38
Endrin	56-121	21	42-139	45
4,4'-DDT	38-127	27	23-134	50
Endrin	30-147	50	30-147	50
Lindane	32-127	50	32-127	50

TABLE E.18
DATA CHEM LABORATORY MS/MSD REQUIREMENTS FOR
PESTICIDE ANALYSIS

Compound	%Recovery	RPD	%Recovery	RPD
	Water	Water	Soil	Soil
4,4'-DDT	25-160	50	25-160	50
Heptachlor	34-111	50	34-111	50
Aldrin	42-122	50	42-122	50
Dieldrin	36-146	50	36-146	50

E.2.5.9 Coded Field Duplicates

Field duplicates are analyzed to determine the representativeness of sampling procedures. One of each duplicate pair is given a coded (false) identifier so that the laboratory will not bias the analytical results. Four field duplicates were analyzed with this fraction and no analytes were detected. Two field duplicates were collected during the second sampling event at Site 1. No analytes were detected in any of the duplicate pairs. Samples are not qualified.

E.2.6 TOTAL RECOVERABLE PETROLEUM HYDROCARBONS USING EPA METHOD 418.1

E.2.6.1 Introduction

The total recoverable petroleum hydrocarbons (TRPH) are analyzed using infrared (IR) spectroscopy. The concentrations are determined by direct comparison with standards. One hundred fifty-one field samples, including 129 soil and 22 aqueous, were analyzed by this method. The QC assessment includes technical holding times, ICALs, CCALs, blanks, MS/MSDs, and LCSs.

E.2.6.2 Technical Holding Time

The technical holding time for TRPH analysis is measured from the time of collection to the time of analysis. Analysis of the samples must occur within 28 days of collection. In no instances were holding times exceeded.

E.2.6.3 Initial Calibration

Instrument performance criteria are established to ensure that correct IR detection limits and wavelengths are set on the spectrophotometer. One calibration must be performed on the instrument every 24 hours or each time the instrument is set up. An ICAL curve is established using a series of five calibration standards of 5, 10, 20, 40, and 80 mg/L. The resulting ICAL curve must have an r value greater than or equal to 0.995. All ICAL results met these requirements.

E.2.6.4 Continuing Calibration Verification

CCAL verification is performed after the ICAL at a frequency of one for every 10 samples. The CCAL %R must fall within the range of 85-115%. CCAL %Rs were within these limits for all samples.

E.2.6.5 Blanks

One laboratory method blank must be analyzed with every 20 samples or at least one per day. Instrument blanks must be analyzed at a frequency of one for every 10 sample analyses after the last CCAL. Target analyte concentrations should not be found in any blank above the project-required detection limit (PRDL). No target analyte was detected in any of the laboratory blanks.

Field QC blanks are analyzed to verify that no contamination occurred during sampling. Equipment rinseate blanks and field blanks were analyzed for this fraction and none was detected.

E.2.6.6 Matrix Spike/Matrix Spike Duplicates

One MS or MSD must be included for every 10 samples (one MS/MSD pair per 20 samples) for each matrix analyzed. The MS %R results should fall in the range 62-114% for aqueous samples and 82-110% for soil samples for this fraction. The MSD RPD results should be below 16% for aqueous samples and below 9% for soil samples. Nine MS/MSD soil samples and two aqueous samples were associated with these samples. Six samples were qualified as estimated J and one sample was qualified as unusable "R" because of the poor performance of the MS/MSD pair identified as UANG-CS5.

E.2.6.7 Laboratory Control Sample

No LCS (or blank spike) samples were analyzed since they are not required by the method. Qualifications of data are not made due to blank spike %R results alone. However, in conjunction with MS/MSD results, blank spikes are used to assess reproducibility and are used to qualify results only when the MS/MSD results are out of control limits. One MS/MSD pair performed poorly, making it difficult to determine if the poor performance was due to matrix effects or if the instrument was out of control limits; since no LCS sample was performed for this method.

E.2.6.8 Field Duplicates

Field duplicates are analyzed to determine the representativeness of sampling procedures. One of each duplicate pair is given a coded (false) identifier so that the laboratory will not bias the analytical results. A total of 11 field duplicates were analyzed, with three pairs having this fraction detected. One comparison for RPD (%) or difference was outside of QC limits. Samples are not qualified due to duplicate results.

E.2.7 TOTAL PETROLEUM HYDROCARBON USING EPA METHOD SW8015M (DIESEL AND GASOLINE)**E.2.7.1 Introduction**

Eight soil samples were collected and analyzed for method SW 8015M (diesel and gasoline). The QC assessment includes; technical holding times, ICALs, CCALs, blanks, MS/MSDs, and LCSs and surrogates.

E.2.7.2 Technical Holding Time

The technical holding time for diesel is 14 days from sample collection to extraction and 40 days from sample extraction to analysis. The holding time for gasoline is 14 days from sample collection to analysis. All samples for diesel and gasoline analyses met holding time criteria.

E.2.7.3 Initial Calibration

A five-point ICAL is performed for both diesel and gasoline. The resulting correlation coefficient square of the calibration curve must be ≥ 0.990 . All initial calibration results were within control limits.

E.2.7.4 Continuing Calibration

A continuing calibration standard is analyzed at the beginning of each 12-hour analysis period, before the analysis of any samples, and once every 10 samples. The %D must be $\leq \pm 15\%$. All continuing calibration results were in control.

E.2.7.5 Blanks

One laboratory method blank is analyzed for each matrix type; diesel and gasoline samples. If a blank contains detected target compounds, the associated samples containing less than 5 times the blank concentration are qualified as non-detected, "U". All method blanks were found to be free of target analytes.

Blank samples provide a measure of contamination that may have been introduced into a sample set during the field work while samples were being collected, or during transport to the laboratory. Each blank is discussed in more detail in Section E.2.8. There were no field blanks collected for this analysis.

E.2.7.6 Surrogate Spikes

BFB, cumene, and TRIFL were used as surrogates for gasoline. All detects in three samples were qualified as estimated, "J", due to surrogate results. No surrogate was used in the diesel analysis.

E.2.7.7 Matrix Spike/Matrix Spike Duplicates

For every 20 samples, one MS/MSD must be analyzed. The MS/MSD measures the precision and accuracy of the matrix and the potential presence of matrix interference's. The MS/MSD criteria for diesel and gasoline are 50-125% and 39-150%, respectively. All MS/MSD results were within control limits.

E.2.7.8 Laboratory Control Sample

One LCS is required for every 10 samples or for each SDG, whichever was more frequent. The LCS measures the the percent difference between two samples with the same concentrations. The LCS recovery criteria for diesel and gasoline are the same as their respective MS/MSD. All LCS data were within control limits.

E.2.7.9 Field Duplicates

Field duplicates are analyzed to determine the representativeness of sampling procedures. One of each duplicate pair is given a coded (false) identifier so that the laboratory will not bias the analytical results. No field duplicates were analyzed for this method.

E.2.8 DISCUSSION OF FIELD QA PROCEDURES AND RESULTS**E.2.8.1 Introduction**

Field QC blanks are analytical samples analyzed in the same manner as site samples. Blank samples provide a measure of contamination that may have been introduced into a sample set during sample collection, transport or while in the laboratory during sample preparation and analysis. As a check of field sampling QA/QC procedures, trip blanks, equipment rinseate blanks, field blanks, and field duplicates were collected and sent to the laboratory at frequencies specified in the SAP (1992b). The purpose of each type of blank, the frequency with which each blank was sampled, and the analytical results are discussed below. A complete list of field QC blank associations are listed in Table E.19.

E.2.8.2 Trip Blanks

Trip blanks are used to indicate potential contamination of volatile organic samples during sample shipping and handling. Trip blanks originate at the laboratory, are transported to the site with the empty sample containers, are handled like samples but are not opened, and are returned to the laboratory for analysis with the sample containers.

One trip blank is sent with every container of VOC samples submitted to the laboratory and is analyzed for VOCs only. Out of 204 samples analyzed for VOCs (by SW8240 and SW8010/SW8020), 53 (including 16 samples from the second sampling event at Site 1) were not accompanied by trip blanks when shipped to the laboratory for analysis. However, this does not appear to affect data integrity; in the cases where trip blanks were sent with samples, all trip blanks, except three, were free of contamination. In most cases, the trip blank accompanied samples in the field during sampling and, for validation purposes, is associated with these samples, as well as the samples with which it was shipped.

Three trip blanks, TB1, TB18, and TB19, contained detectable VOCs as shown in Table E.20. Methylene chloride was detected in TB1 at a concentration of 3.0 µg/l. This compound was not detected in any of the associated samples. Dichloromethane was detected in TB18 at the estimated concentration of 1.6 µg/L, but was not detected in any of the associated samples. 1,1-Dichloroethane was detected at a concentration of 1.0 µg/L in TB19. This compound also was detected in an associated groundwater sample at the same concentration. No other organic compounds were detected in the trip blanks.

E.2.8.3 Equipment Rinseate Blanks

Equipment rinseate blanks (RB) are used to indicate possible contamination due to improperly cleaned sampling equipment. Equipment rinseate blanks consist of analyte-free, (American Standards Testing Material (ASTM) Type II or High Performance Liquid Chromatography (HPLC)-grade water) poured into or through the sampling device following decontamination. The rinseate from the sampling device is collected in a sample container. One RB was collected for every 10 samples assembled per matrix and for each piece of sampling equipment used. The RB samples were analyzed for the same parameters as the associated samples. A total of 18 RBs (including one from the re-sampling event) were analyzed to meet the requirement of one blank for every 10 field samples acquired.

Rinseate blanks that were analyzed for volatile organics contained chloroform, except (RB9-S3), as shown in Table E.21. The concentrations of chloroform range from 11 µg/L to 27 µg/L. Chloroform was detected in an associated groundwater sample from Site 7. It is suspected that the chloroform may have been introduced by the HPLC grade water used for sampling equipment decontamination because the compound was detected in field QC samples from this water source. HPLC-grade water often contains trace quantities of chlorinated organic compounds, particularly chloroform. Carbon Tetrachloride was detected in EQR 13 and EQR 14 at an estimated concentration of 0.9 µg/L. This compound was not detected in associated field samples. Toluene was detected in EQR 14 at an estimated concentration of 0.5 µg/L and was also detected in an associated groundwater sample. Xylenes were detected in RB6-S3 at an estimated total concentration of 0.54 µg/L. 1,3 Dichlorobenzene, was detected in CS-EQR at an estimated concentration of 2.0 µg/L. Diethylphthalate was detected in EQR20 at an estimated concentration of 4.0 µg/L. No other organic compounds were detected in the rinseate blanks. The metals Cd, Cr, Cu, and Zn were also detected in the rinseate samples at the concentrations shown in Table E.21.

TABLE E.19
QA/QC BLANK FIELD ASSOCIATIONS TABLE
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

ES	Matrix	ES	Lab. I.D.	atche	Sample	Equipment	Trip Blank	HPLC Water	Potable Water
Field I.D.		Lab. I.D.	Lab. I.D.		Date	Rinseate Blank		Field Blank	Field Blank
UANG-PI5 (0-2)	S	4483.01	--	--	10/22/92	--	--	NC	UANG-FBI
UANG-PI5 (6-8)	S	4483.02	--	--	10/22/92	--	--	NC	UANG-FBI
UANG-PI5 (6-8)	S	4483.02MS	--	--	10/22/92	--	--	NC	UANG-FBI
UANG-PI5 (6-8)	S	4483.02MSD	--	--	10/22/92	--	--	NC	UANG-FBI
UANG-S2-SB3 (2.5-4.5)	S	4595.01	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S2-SB3 (4.5-6.5)	S	4595.02	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S2-SB3 (6.5-8.5)	S	4595.03	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S2-SB2 (2.5-4.5)	S	4595.04	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S2-SB2 (4.5-6.5)	S	4595.05	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S2-SB1 (5-7.5)	S	4595.06	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S2-SB1 (0.5-2.5)	S	4595.07	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S7-SB1 (2.5-4.5)	S	4595.08	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-S7-SB1 (7-9)	S	4595.09	--	--	12/3/92	UANG-RBI	UANG-TB2	NC	UANG-FBI
UANG-TB2	W	4595.1	--	--	12/3/92	--	--	NC	--
UANG-RB1	W	4601.01	--	--	12/4/92	N/A	UANG-TB3	NC	UANG-FBI
UANG-TB3	W	4601.02	--	--	12/4/92	N/A	N/A	NC	N/A
UANG-S7-SB2 (2.5-4.5)	S	4601.03	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S7-SB2 (6.5-9)	S	4601.04	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S7-SB3 (2.5-4.5)	S	4601.05	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S7-SB3 (6.5-9)	S	4601.06	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S7-SB3 (6.5-9)	S	4601.06MS	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S7-SB3 (6.5-9)	S	4601.06MSD	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S7-SB3 (9-11)	S	4601.07	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S4-SB1 (2.5-4.5)	S	4601.08	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-S4-SB1 (6.5-9)	S	4601.09	--	--	12/4/92	UANG-RBI	UANG-TB3	NC	UANG-FBI
UANG-RB2-S4	W	4608.01	--	--	12/7/92	--	UANG-TB4	NC	UANG-FBI
UANG-TB4	W	4608.02	--	--	12/7/92	--	--	NC	--
UANG-S4-SB2 (2.5-4.5)	S	4608.03	--	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S4-SB2 (6.5-9)	S	4608.04	--	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S4-SB3 (2.5-4.5)	S	4608.05	--	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S4-SB3 (6.5-9)	S	4608.06	--	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI

TABLE E.19 Continued

ES Field I.D.	Matrix	ES Lab. I.D.	atache Lab. I.D.	Sample Date	Equipment Rinseate Blank	Trip Blank	HPLC Water Field Blank	Potable Water Field Blank
UANG-S4-SB4 (2.5-4.5)	S	4608.07	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S4-SB4 (6.5-9)	S	4608.08	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S4-SB4 (9-11)	S	4608.09	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S5-SB1 (0-2)	S	4608.1	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S5-SB1 (6-8)	S	4608.11	--	12/7/92	UANG-RB2-S4	UANG-TB4	NC	UANG-FBI
UANG-S5-SB2 (6-8.5)	S	4624.01	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB3 (6-8.5)	S	4624.02	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB3 (8.5-11)	S	4624.03	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB4 (6-8.5)	S	4624.04	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB4 (6-8.5)	S	4624.04MS	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB4 (6-8.5)	S	4624.04MSD	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S6-SB1 (7-9)	S	4624.05	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB4 (2-4)	S	4624.06	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S6-SB1 (2.5-4.5)	S	4624.07	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB3 (0-2)	S	4624.08	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-S5-SB2 (2-4)	S	4624.09	--	12/8/92	UANG-RB3-S5	UANG-TB5	NC	UANG-FBI
UANG-RB3-S5	W	4624.1	--	12/8/92	--	UANG-TB5	NC	UANG-FBI
UANG-TB5	W	4624.11	--	12/8/92	--	--	NC	--
UANG-S6-SB3 (6.5-9)	S	4627.01	--	12/9/92	UANG-RB4-S6	UANG-TB6	NC	UANG-FBI
UANG-S6-SB4 (6-8.5)	S	4627.02	--	12/9/92	UANG-RB4-S6	UANG-TB6	NC	UANG-FBI
UANG-S6-SB4 (8.5-11)	S	4627.03	--	12/9/92	UANG-RB4-S6	UANG-TB6	NC	UANG-FBI
UANG-S6-SB2 (6-8.5)	S	4627.04	--	12/9/92	UANG-RB4-S6	UANG-TB6	NC	UANG-FBI
UANG-S6-SB4 (0-2)	S	4627.05	--	12/9/92	UANG-RB4-S6	UANG-TB6	NC	UANG-FBI
UANG-S6-SB3 (0.5-2.5)	S	4627.06	--	12/9/92	UANG-RB4-S6	UANG-TB6	NC	UANG-FBI
UANG-S6-SB2 (2-4)	S	4627.07	--	12/9/92	UANG-RB4-S6	UANG-TB6	NC	UANG-FBI
UANG-RB4-S6	W	4627.08	--	12/9/92	--	UANG-TB6	NC	UANG-FBI
UANG-TB6	W	4627.09	--	12/9/92	--	--	NC	--
UANG-RB5-S6	W	4633.01	EL5746	12/10/92	--	UANG-TB7/TB8	NC	UANG-FBI
UANG-TB8	W	4633.02	EL5747	12/10/92	--	N/A	NC	--
UANG-TB7	W	4633.03	EL5748	12/10/92	--	N/A	NC	--
UANG-S6-SB5 (6-8.5)	S	4633.04	EL5749	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB8 (6.5-9)	S	4633.05	EL5750	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB7 (6-8.5)	S	4633.06	EL5751	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB6 (8.5-11)	S	4633.07	EL5752	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB6 (6-8.5)	S	4633.08	EL5753	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S3-SS1	S	4633.09	EL5754	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S3-SS2	S	4633.1	EL5755	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB6 (2-4)	S	4633.11	EL5756	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB7 (2-4)	S	4633.12	EL5757	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI

TABLE E.19 Continued

ES Field I.D.	Matrix	ES Lab. I.D.	atache Lab. I.D.	Sample Date	Equipment Rinseate Blank	Trip Blank	HPLC Water Field Blank	Potable Water Field Blank
UANG-S6-SB8 (2.5-4.5)	S	4633.13	EL5758	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB5 (0-2)	S	4633.14	EL5759	12/10/92	UANG-RB5-S6	UANG-TB7	NC	UANG-FBI
UANG-S6-SB9 (0-2)	S	4642.01	EL5760	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S6-SB9 (6-8.5)	S	4642.02	EL5761	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S6-SB10 (0-2)	S	4642.03	EL5762	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S6-SB10 (6-8.5)	S	4642.04	EL5763	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S6-SB10 (6-8.5)	S	4642.04MS	EL5763	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S6-SB10 (6-8.5)	S	4642.04MSD	EL5763	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S6-SB9 (8.5-11)	S	4642.05	EL5764	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S3-SS4 (NORTH)	S	4642.06	EL5765	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S3-SS5 (SOUTH)	S	4642.07	EL5766	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S3-SS6 (WEST)	S	4642.08	EL5767	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S3-SS3 (SMP.3)	S	4642.09	EL5768	12/11/92	UANG-RB7-S6	B	NC	UANG-FBI
UANG-S1-SB2 (0-2)	S	4642.1	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-S1-SB2 (4-6.5)	S	4642.11	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-SB2 (4-6.5)	S	4642.11MS	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-SB2 (4-6.5)	S	4642.11MSD	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-S1-SB1 (0-2)	S	4642.12	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-S1-SB1 (4-6.5)	S	4642.13	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-S1-SB3 (2-4)	S	4642.14	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-S1-SB3 (4-6.5)	S	4642.15	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-S1-SB3 (6.5-8.5)	S	4642.16	--	12/11/92	UANG-RB6-S1	B	NC	UANG-FBI
UANG-FBI	W	4642.17	EL5769	12/11/92	N/A	B	NC	N/A
UANG-RB6-S1	W	4642.18	--	12/11/92	N/A	B	NC	UANG-FBI
UANG-RB7-S6	W	4642.19	EL5770	12/11/92	N/A	B	NC	UANG-FBI
UANG-RB8-S7	W	4654.01	EL5771	12/14/92	N/A	UANG-TB9	NC	UANG-FBI
UANG-S7-SB4 (4.5-6.5)	S	4654.02	EL5772	12/14/92	UANG-RB8-S7	UANG-TB9	NC	UANG-FBI
UANG-S7-SB5 (4.5-6.5)	S	4654.03	EL5773	12/14/92	UANG-RB8-S7	UANG-TB9	NC	UANG-FBI
UANG-S7-SB5 (6.5-9)	S	4654.04	EL5774	12/14/92	UANG-RB8-S7	UANG-TB9	NC	UANG-FBI
UANG-S7-SB6 (4-6)	S	4654.05	EL5775	12/14/92	UANG-RB8-S7	UANG-TB9	NC	UANG-FBI
UANG-S4-SB5 (5-7)	S	4662.01	EL5776	12/15/92	UANG-RB8-S7	ANG-TB9/TBI	NC	UANG-FBI
UANG-S4-SB5 (7-9)	S	4662.02	EL5777	12/15/92	UANG-RB8-S7	ANG-TB9/TBI	NC	UANG-FBI
UANG-S4-SB7 (4.5-6.5)	S	4662.03	EL5778	12/15/92	UANG-RB8-S7	ANG-TB9/TBI	NC	UANG-FBI
UANG-S4-SB7 (4.5-6.5)	S	4662.03MS	EL5778	12/15/92	UANG-RB8-S7	ANG-TB9/TBI	NC	UANG-FBI
UANG-S4-SB7 (4.5-6.5)	S	4662.03MSD	EL5778	12/15/92	UANG-RB8-S7	ANG-TB9/TBI	NC	UANG-FBI
UANG-S4-SB6 (2.5-4.5)	S	4662.04	EL5779	12/15/92	UANG-RB8-S7	ANG-TB9/TBI	NC	UANG-FBI
UANG-S4-SB6 (6.5-8.5)	S	4662.05	EL5780	12/15/92	UANG-RB8-S7	ANG-TB9/TBI	NC	UANG-FBI
UANG-TB10	W	4662.06	EL5781	12/15/92	N/A	N/A	NC	N/A
UANG-TB9	W	4662.07	EL5782	12/15/92	N/A	N/A	NC	N/A
UANG-RB9-S3	W	4683.01	--	12/18/92	N/A	N/A	NC	UANG-FBI

TABLE E.19 Continued

ES Field I.D.	Matrix	ES Lab. I.D.	atache Lab. I.D.	Sample Date	Equipment Rinseate Blank	Trip Blank	HP/LC Water Field Blank	Potable Water Field Blank
UANG-TB11	W	4683.02	--	12/17/92	N/A	N/A	NC	N/A
UANG-TB12	W	4683.03	--	12/17/92	N/A	N/A	NC	N/A
UANG-S7-SB8 (4.5-6.5)	S	4683.04	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S3-SB2 (4.5-6.5)	S	4683.05	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S3-SB2 (4.5-6.5)	S	4683.05MS	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S3-SB2 (4.5-6.5)	S	4683.05MSD	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S3-SB3 (4-6)	S	4683.06	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S3-SB3 (6-8)	S	4683.07	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S3-SB1 (4-6)	S	4683.08	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S3-SB1 (6-8)	S	4683.09	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S2-SB4 (4.5-6.5)	S	4683.1	--	12/17/92	UANG-RB9-S3	UANG-TB12	NC	UANG-FB1
UANG-S5-SB6 (4-6)	S	4683.11	--	12/17/92	UANG-RB9-S3	UANG-TB11	NC	UANG-FB1
UANG-S5-SB5 (6-8.5)	S	4683.12	--	12/17/92	UANG-RB9-S3	UANG-TB11	NC	UANG-FB1
UANG-S5-SB7 (6-8)	S	4683.13	--	12/17/92	UANG-RB9-S3	UANG-TB11	NC	UANG-FB1
UANG-S7-SB7 (6-8)	S	4683.14	--	12/17/92	UANG-RB9-S3	UANG-TB11	NC	UANG-FB1
UANG-S3-SB4 (6-8)	S	4683.15	--	12/17/92	UANG-RB9-S3	--	NC	UANG-FB1
UANG-S4-SB8 (0.5-2.5)	S	4705.01	--	12/29/92	N/A	UANG-TB14	NC	UANG-FB1
UANG-S4-SB8 (4.5-6.5)	S	4705.02	--	12/29/92	N/A	UANG-TB14	NC	UANG-FB1
UANG-S4-SB9 (2.5-4.5)	S	4705.03	--	12/29/92	N/A	UANG-TB14	NC	UANG-FB1
UANG-S4-SB9 (4.5-6.5)	S	4705.04	--	12/29/92	N/A	UANG-TB14	NC	UANG-FB1
UANG-S7-SB9 (2.5-4.5)	S	4705.05	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S7-SB9 (8.5-9.5)	S	4705.06	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S7-SB9 (4.5-6.5)	S	4705.07	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S7-SB9 (4.5-6.5)	S	4705.07MS	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S7-SB9 (4.5-6.5)	S	4705.07MSD	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S7-SB10 (4.5-6.5)	S	4705.08	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S2-SB5 (6.5-8.5)	S	4705.09	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S2-SB6 (6.5-8.5)	S	4705.1	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-S3-SB5 (4-6)	S	4705.11	--	12/30/92	N/A	UANG-TB15	NC	UANG-FB1
UANG-TB14	W	4705.12	--	12/29/92	N/A	--	NC	--
UANG-TB15	W	4705.13	--	12/30/92	N/A	--	NC	--
UANG-BG-MW1 (0-2)	S	4737.01	--	1/13/93	N/A	UANG-TB2 (16)	N/A	UANG-FB1
UANG-BG-MW1 (4-6)	S	4737.02	--	1/13/93	N/A	UANG-TB2 (16)	N/A	UANG-FB1
UANG-TB2 (16)	W	4737.03	--	1/13/93	N/A	N/A	N/A	N/A
UANG-BG-MW1-1	W	--	CLP072	1/29/93	UANG-BG-RBI	UANG-TB-BG1	UANG-FB2	UANG-FB6-15
UANG-BG-MW1-1	W	--	072MS	1/29/93	UANG-BG-RBI	UANG-TB-BG1	UANG-FB2	UANG-FB6-15
UANG-BG-MW1-1	W	--	072MSD	1/29/93	UANG-BG-RBI	UANG-TB-BG1	UANG-FB2	UANG-FB6-15
UANG-BG-RBI	W	--	CLP073	1/29/93	N/A	UANG-TB-BG1	UANG-FB2	UANG-FB6-15
UANG-TB-BG-1	W	--	CLP074	1/29/93	N/A	N/A	N/A	N/A
UANG-FB4	W	4779.01	--	1/29/93	N/A	N/A	UANG-FB2	N/A

TABLE E.19 Continued

ES Field I.D.	Matrix	ES Lab. I.D.	atache Lab. I.D.	Sample Date	Equipment Rinseate Blank	Trip Blank	HPLC Wafer Field Blank	Potable Water Field Blank
UANG-S1-MW1-3	W	4779.02	--	2/1/93	UANG-RB5-S1	UANG-TB17	UANG-FB2	UANG-FB6-15
UANG-RB5-S1	W	4779.03	--	2/1/93	N/A	N/A	UANG-FB2	UANG-FB6-15
UANG-S1-MW2-2	W	4779.04	--	2/1/93	UANG-RB5-S1	UANG-TB17	UANG-FB2	UANG-FB6-15
UANG-FB2	W	4779.05	--	2/1/93	N/A	N/A	--	UANG-FB6-15
UANG-FB5-8	W	4779.06	--	2/2/93	N/A	N/A	UANG-FB5-8	UANG-FB6-15
UANG-RB6-S3	W	4779.07	--	2/2/93	N/A	N/A	UANG-FB5-8	UANG-FB6-15
UANG-S2-MW1-4	W	4779.08	--	2/2/93	UANG-RB6-S3	UANG-TB17	UANG-FB5-8	UANG-FB6-15
UANG-S3-MW3-5	W	4779.09	--	2/2/93	UANG-RB6-S3	UANG-TB17	UANG-FB5-8	UANG-FB6-15
UANG-S3-MW1-6	W	4779.1	--	2/2/93	UANG-RB6-S3	UANG-TB17	UANG-FB5-8	UANG-FB6-15
UANG-S3-MW2-7	W	4779.11	--	2/2/93	UANG-RB6-S3	UANG-TB17	UANG-FB5-8	UANG-FB6-15
UANG-TB17	W	4779.12	--	2/2/93	N/A	N/A	N/A	N/A
UANG-S7-MW1-11	W	4781.01	--	2/3/93	UANG-EQR13	UANG-TB18	UANG-FB4	UANG-FB6-15
UANG-EQR13	W	4781.02	--	2/3/93	N/A	UANG-TB18	UANG-FB4	UANG-FB6-15
UANG-S4-MW1-9	W	4781.03	--	2/3/93	UANG-EQR13	UANG-TB18	UANG-FB4	UANG-FB6-15
UANG-FB6-15	W	4781.04	--	2/3/93	N/A	N/A	UANG-FB4	UANG-FB6-15
UANG-EQR14	W	4781.05	--	2/3/93	N/A	UANG-TB18	UANG-FB4	UANG-FB6-15
UANG-S7-MW2-12	W	4781.06	--	2/3/93	UANG-EQR14	UANG-TB18	UANG-FB4	UANG-FB6-15
UANG-TB18	W	4781.07	--	2/3/93	N/A	N/A	N/A	N/A
UANG-FB7-19	W	4788.01	--	2/4/93	N/A	UANG-TB19	UANG-FB4	UANG-FB6-15
UANG-EQR20	W	4788.02	--	2/4/93	N/A	UANG-TB19	UANG-FB7-19	UANG-FB6-15
UANG-S6-MW3-18	W	4788.03	--	2/4/93	UANG-EQR20	UANG-TB19	UANG-FB7-19	UANG-FB6-15
UANG-S6-MW1-16	W	4788.04	--	2/4/93	UANG-EQR20	UANG-TB19	UANG-FB7-19	UANG-FB6-15
UANG-S5-MW1-10	W	4788.05	--	2/4/93	UANG-EQR20	UANG-TB19	UANG-FB7-19	UANG-FB6-15
UANG-S6-MW2-17	W	4788.06	--	2/4/93	UANG-EQR20	UANG-TB19	UANG-FB7-19	UANG-FB6-15
UANG-TB19	W	4788.07	--	2/4/93	N/A	--	--	--
UANG-S5-SB6 (1-3)	S	4797.01	--	2/8/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-S5-SB6 (5-7)	S	4797.02	--	2/8/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-S7-SB7 (1-3)	S	4797.03	--	2/8/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-S7-SB7 (5-7)	S	4797.04	--	2/8/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-S5-SB7 (1-3)	S	4797.05	--	2/9/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-S5-SB7 (5-7)	S	4797.06	--	2/9/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-S5-SB5 (1-3)	S	4797.07	--	2/9/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-S5-SB5 (5-7)	S	4797.08	--	2/9/93	N/A	UANG-TB20	UANG-FB8	UANG-FB9
UANG-TB20	W	4797.09	--	2/9/93	N/A	N/A	N/A	N/A
UANG-S2-MW1	W	4801.01	--	2/10/93	UANG-CW3-EQR	UANG-TB21	UANG-FB8	UANG-FB9
UANG-S2-MW1	W	4801.01MS	--	2/10/93	UANG-CW3-EQR	UANG-TB21	UANG-FB8	UANG-FB9
UANG-S2-MW1	W	4801.01MSD	--	2/10/93	UANG-CW3-EQR	UANG-TB21	UANG-FB8	UANG-FB9
UANG-TB21	W	4801.02	--	2/10/93	UANG-CW3-EQR	UANG-TB21	N/A	N/A
UANG-CW1	W	4804.01	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FB1	UANG-FB9
UANG-CW2	W	4804.02	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FB1	UANG-FB9

TABLE E.19 Continued

ES Field I.D.	Matrix	ES Lab. I.D.	atache Lab. I.D.	Sample Date	Equipment Rinseate Blank	Trip Blank	HPLC Water Field Blank	Potable Water Field Blank
UANG-CW3	W	4804.03	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW3	W	4804.03MS	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW1	W	4804.01	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW2	W	4804.02	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW3	W	4804.03	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW3	W	4804.03MS	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW3	W	4804.03MSD	--	2/11/93	N/A	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW3-EQR	W	4804.05	--	2/11/93	N/A	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-CW4	W	4804.06	--	2/11/93	UANG-CW3-EQR	UANG-TB22	ANG-CS-FBI	UANG-FB9
UANG-FB8	W	4804.08	--	2/11/93	N/A	UANG-TB22	N/A	N/A
UANG-TB22	W	4804.09	--	2/11/93	N/A	N/A	N/A	N/A
UANG-CS1	S	4806.01	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS2	S	4806.02	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS3	S	4806.03	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS4	S	4806.04	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS5	S	4806.05	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS5	S	4806.05MS	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS5	S	4806.05MSD	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS6	S	4806.06	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-CS7	S	4806.07	--	2/12/93	UANG-CS-EQR	N/A	ANG-CS-FBI	UANG-FB9
UANG-FB9	W	4806.08	--	2/12/93	N/A	N/A	N/A	N/A
UANG-CS-EQR	W	4806.09	--	2/12/93	N/A	N/A	N/A	N/A
UANG-CS-FB10	W	4806.1	--	2/12/93	N/A	N/A	N/A	N/A
UANG-S10-SB1 (2-4)	S	--	1324	5/25/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB1 (6-8)	S	--	1325	5/25/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB1 (8-10)	S	--	1311	5/25/94	N/A	N/A	N/A	N/A
UANG-S10-SB1 (8-MS)	S	--	1311MS	5/25/94	N/A	N/A	N/A	N/A
UANG-S10-SB1 (8MSD)	S	--	1311MS	5/25/94	N/A	N/A	N/A	N/A
UANG-S10-SB2 (2-4)	S	--	1318	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB2 (4-6)	S	--	1319	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB3 (1-3)	S	--	1320	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB3 (3-5)	S	--	1321	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB3 (3-MS)	S	--	1321MS	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB3 (3MSD)	S	--	1321MS	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB4 (2-4)	S	--	1322	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB4 (4-6)	S	--	1323	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-SB4 (4-6)	S	--	1326	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S10-TBI	W	--	--	5/26/94	N/A	UANG-S10-TBI	N/A	N/A
UANG-S1-SB4 (7.5-9.5)	S	--	2981	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB4 (3.5-5.5)	S	--	2982	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB5 (1-3)	S	--	2983	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3

TABLE E.19 Continued

ES Field I.D.	Matrix	ES Lab. I.D.	atache Lab. I.D.	Sample Date	Equipment Rinseate Blank	Trip Blank	HPLC Water Field Blank	Potable Water Field Blank
UANG-S1-SB5 (3-5)	S	--	2984	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB6 (1-3)	S	--	2985	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB6 (3-5)	S	--	2986	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB6 (5-7)	S	--	2987	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB7 (1-3)	S	--	2988	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB7 (5-7)	S	--	2989	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB8 (1-3)	S	--	2990	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB8 (1MS)	S	--	2990MS	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB8 (1MSD)	S	--	2990MS	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB8 (7-9)	S	--	2991	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB8 (5-7)	S	--	2992	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB9 (3-5)	S	--	2993	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB9 (5-7)	S	--	2994	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB10 (1-3)	S	--	2995	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-SB10 (3-5)	S	--	2996	10/26/94	UANG-S1-RB3	N/A	UANG-S1-FB4	UANG-S1-FB3
UANG-S1-129-2	S	--	4422	12/9/94	N/A	N/A	N/A	N/A
UANG-S1-129-2MS	S	--	4422MS	12/9/94	N/A	N/A	N/A	N/A
UANG-S1-129-2MSD	S	--	4422MS	12/9/94	N/A	N/A	N/A	N/A
UANG-S10-129-1	S	--	4423	12/9/94	N/A	N/A	N/A	N/A

B - Broken

W - Water

S - Soil

N/A - Not applicable

NC - Not collected

TABLE E.20
TRIP BLANKS
ANALYTES DETECTED
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	(units)	TB2*	TB3*	TB4*	TB5*	TB6*	TB7***	TB8***	TB9***	TB10***
-----------	----------	---------	------	------	------	------	------	--------	--------	--------	---------

Volatile Organics (SW8240, 8010/8020) (µg/L)

Dilution Factor 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0

1,1-Dichloroethane

1U

Dichloromethane

1U

Parameter	(method)	(units)	TB-BG-1***	TB11**	TB12**	TB14**	TB15**	TB-2(16)***	TB17**	TB18**	TB19**
-----------	----------	---------	------------	--------	--------	--------	--------	-------------	--------	--------	--------

Volatile Organics (SW8240, 8010/8020) (µg/L)

Dilution Factor 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0

1,1-Dichloroethane

1U

Dichloromethane

1U

Parameter	(method)	(units)	TB20**	TB21**	TB22**	TB1-POL***
-----------	----------	---------	--------	--------	--------	------------

Volatile Organics (SW8240, 8010/8020) (µg/L)

Dilution Factor 1.0 1.0 1.0 1.0

1,1-Dichloroethane

1U

Dichloromethane

1U

U Compound not present above its detection limit, which precedes the flag.

J Concentration of the compound is estimated.

* Method 8240 used for analysis of VOC samples by ES-Berkley Laboratory.

** Method 8010/8020 was used for analysis of VOC samples by ES-Berkley Laboratory.

*** Method 8010/8020 was used for analysis of VOC samples by Datachem Laboratories.

TABLE E.21
SPLIT-SPOON SAMPLER, BAILER, AND AUGER RINSEATE BLANKS
ANALYTES DETECTED
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	(units)	RB1*	RB2-S4*	RB3-S5*	RB4-S6*	RB5-S6***	RB6-S1	RB7-S6***	RB8-S7***	RB9-S3**
Volatile Organics (SW8240, 8010/8020) (µg/L)											
Dilution Factor			1.0	1.0	1.0	1.0	1.0	--	1.0	1.0	1.0
Carbon Tetrachloride			5U	5U	5U	5U	1U	--	1U	1U	1U
Chloroform			19	22	21	27	21	--	11	21	1U
Toluene			5U	5U	5U	5U	1U	--	1U	1U	2U
Xylenes			5U	5U	5U	5U	1U	--	1U	1U	2U
Semivolatile Organics (SW8270) (µg/L)											
Dilution Factor			1.0	1.0	1.0	1.0	1.0	--	1.0	1.0	1.0
1,3 Dichlorobenzene			10U	10U	10U	10U	10U	--	10U	10U	10U
Diethylphthalate			10U	10U	10U	10U	10U	--	10U	10U	10U
Total Petroleum Hydrocarbons (E418.1) (mg/L)											
Results			1U	1U	1U	1U	1U	--	1U	1U	1U
Pesticides/PCBs (SW 8080) (µg/L)											
Dilution Factor			--	--	--	--	--	1.0	--	--	--
All Pesticides/PCBs were below their detection limits.											

TABLE E.21 Continued

Parameter	(method)	(units)	BG-RB1**	RB5-S1	RB6-S3**	EQR13**	EQR14**	EQR20**	CW3-EQR**	CS-EQR**
Volatile Organics (SW8240, 8010/8020) (µg/L)										
Dilution Factor		1.0	--	--	1.0	1.0	1.0	1.0	1.0	1.0
Carbon Tetrachloride		1U	--	--	1U	0.9J	0.9J	1U	1U	1U
Chloroform		20	--	--	19	20	19J	21	25	13
Toluene		1U	--	--	2U	2U	0.5J	2U	2U	2U
Xylenes		1U	--	--	0.54J	2U	2U	2U	2U	2U
Semivolatile Organics (SW8270) (µg/L)										
Dilution Factor		--	--	--	1.0	1.0	1.0	1.0	1.0	1.0
1,3 Dichlorobenzene		--	--	--	10U	10U	10U	10U	10U	2J
Diethylphthalate		--	--	--	10U	10U	10U	4J	10U	10U
Total Petroleum Hydrocarbons (E418.1) (mg/L)										
Results		--	--	--	--	--	--	--	1U	1U
Pesticides/PCBs (SW8080) (µg/L)										
Dilution Factor		--	1.0	--	--	--	--	--	1.0	1.0
All Pesticides/PCBs were below their detection limits.										

TABLE E.21 Continued

Parameter	(method)	(units)	RB1	RB2-S4	RB3-S5	RB4-S6	RB5-S6	RB6-S1	RB7-S6	RB8-S7	RB9-S3
Priority-Pollutant Metals (µg/L)											
Cadmium			2U	2.2UJ	--	--	--	--	--	2.6UJ	--
Chromium			2U	2U	--	--	--	--	--	2.6J	--
Copper			5U	5U	--	--	--	--	--	5U	--
Zinc			5.2J	5U	--	--	--	--	--	5U	--
Parameter	(method)	(units)	BG-RB1	RB5-S1	RB6-S3	EQR13	EQR14	EQR20	CW3-EQR	CS-EQR	
Priority-Pollutant Metals (µg/L)											
Cadmium			--	--	--	1U	1U	--	1.3J	1U	--
Chromium			--	--	--	2.9UJ	3.2UJ	--	2U	2U	--
Copper			--	--	--	3.0B	4.3UJ	--	2.4UJ	3.3J	--
Zinc			--	--	--	5.4UJ	5.4UJ	--	7.7UJ	7.1UJ	--

U Compound not present above its detection limit, which precedes the flag.

UJ Compound not detected, but the detection limit is estimated.

J Concentration of the compound is estimated.

-- Not Analyzed.

* Method 8240 used for analysis of VOC samples by ES-Berkley Laboratory.

** Method 8010/8020 was used for analysis of VOC samples by ES-Berkley Laboratory.

*** Method 8010/8020 was used for analysis of VOC samples by Datachem Laboratories.

E.2.8.4 Field Blanks

Field blanks are samples of potable source water (used for decontamination and steam cleaning) and samples of analyte-free deionized water (used for decontamination). A field blank is defined as water that is poured into a sample container at the site, is handled like a sample, and is transported to the laboratory for analysis. A minimum of one sample of each water source for a given sampling event is collected. Normally two field blanks are sampled per sampling event: a sample of the potable water used for steam cleaning and a sample of the deionized water used for decontamination. These samples determine if contamination occurred during the decontamination process, or also, in the case of the deionized water, if contamination was introduced in the field environment during sampling. Additional field blanks are also analyzed for each lot or water source. The potable water source was Vern and Carol's Diner (the Base Diner) in all cases. The final rinse was an HPLC-grade deionized water. A total of 11 (including two from the re-sampling event) field blanks were sampled and analyzed.

The potable water field blanks FB1, FB6-15, and FB9 contained chloroform, bromodichloromethane (except FB9), and dibromochloromethane at concentrations shown in Table E.22. These compounds are often present in chlorinated water supplies. Chloroform was also detected in the HPLC-water blanks at similar concentrations shown in the table, indicating that chloroform may have been introduced by the hydrochloric acid preservative. Ethylbenzene and chlorobenzene were reported at estimated concentrations of 0.4 µg/L and 0.8 µg/L, respectively, in FB5-8. In FB8 and FB9, 1,3-dichlorobenzene was reported at estimated concentrations of 3.0 µg/L and 2.0 µg/L, respectively.

Two field blanks contained metals as shown in Table E.22. Cu and Zn were detected in FB1 and FB6-15.

E.2.8.5 Coded Field Duplicates

Field duplicates are defined as two or more samples collected at a sampling location during a single act of sampling and are coded with a false identifier indistinguishable from other samples. Field duplicates are examined for precision by calculating the RPD when measured sample values are greater than five times the CRDL or else by calculating the difference. Control limits of $\pm 40\%$ for water and $\pm 70\%$ for soil/sediment are used for evaluating the RPD values. Control limits of ± 2 times the contract required quantitation limit (CRQL) for water and ± 4 times the CRQL for soil are used for evaluating the difference. Field duplicate results are listed by fraction in Table E.23.

TABLE E.22
FIELD BLANKS
ANALYTES DETECTED
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	(units)	FB18*	FB2	FB4	FB5-8**	FB6-15**	FB7-19**	FB8**	FB9**	CS-FB10**	FB3*	FB4*
Volatile Organics (SW8240, 8010/8020) (µg/L)													
Dilution Factor			1.0	--	--	1.0	1.0	1.0	1.0	1.0	1.0	--	--
Chloroform			27	--	--	20	11	21	20	11	15	--	--
Bromodichloromethane			11	--	--	1U	4.5	1U	1U	1U	1U	--	--
Dibromochloromethane			3.7	--	--	1U	2.1	1U	1U	1.9	1U	--	--
Ethylbenzene			1U	--	--	0.4J	2U	2U	2U	2U	2U	--	--
Chlorobenzene			1U	--	--	0.8J	2U	2U	2U	2U	2U	--	--
Semivolatile Organics (SW8270) (µg/L)													
Dilution Factor			1.0	--	1.0	1.0	1.0	1.0	1.0	1.0	1.0	--	--
1,3 Dichlorobenzene			10U	--	10U	10U	10U	10U	3J	2J	10U	--	--
Total Petroleum Hydrocarbons (E418.1) (mg/L)													
Results			1U	--	--	--	--	--	1U	1U	1U	--	--
Pesticides/PCBs (SW 8080) (µg/L)													
Dilution Factor			--	1.0	1.0	1.0	--	1.0	1.0	--	--	1.0	1.0

All Pesticides/PCBs were below their detection limits.

TABLE E.22 Continued
FIELD BLANKS
ANALYTES DETECTED
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	(units)	FB1	FB2	FB4	FB5-8	FB6-15	FB7-19	FB8	FB9	CS-FB10	FB3	FB4
Priority-Pollutant Metals (µg/L)													
Cadmium			1U	--	--	1U	1U	1.2UJ	1U	1U	1U	--	--
Chromium			2U	--	--	3.4UJ	3.6UJ	2.6UJ	2U	2.8UJ	2U	--	--
Copper			5.0J	--	--	4.0UJ	26.2	3.3UJ	2.4UJ	6.5UJ	2.4UJ	--	--
Zinc			10.2J	--	--	4.8UJ	16.8J	2.3UJ	5.8UJ	13.7UJ	4.4UJ	--	--

- E1- 86
- U Compound not present above its detection limit, which precedes the flag.
J Concentration of the compound is estimated.
UJ Compound not detected, but the detection limit is estimated.
-- Not Analyzed.
* Method 8010/8020 was used for analysis of VOC samples by Datachem Laboratories.
** Method 8010/8020 was used for analysis of VOC samples by ES-Berkley Laboratory.

TABLE E.23
FIELD DUPLICATES
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH
(Results by Fraction)

Fraction: Priority Pollutant Metals

UANG City Drain CS6 and UANG City Drain CS7

Analyte	CRQL (mg/kg)	[Sample] (mg/kg)	[Duplicate] (mg/kg)	RPD (%)	Diff. (mg/kg)	Out of Limit
Antimony	12	ND	1.9		1.90	NO
Arsenic	2	29.80	20.00	39		NO
Beryllium	1	0.40	0.39		0.01	NO
Cadmium	1	3.30	3.70		0.40	NO
Chromium	2	52.20	52.60	1		NO
Copper	5	66.60	115.00	53		NO
Lead	0.6	568.00	322.00	55		NO
Mercury	0.1	0.42	0.36		0.06	NO
Nickel	8	16.80	11.90		4.90	NO
Selenium	1	4.80	0.39		4.41	YES
Zinc	4	283.00	383.00	30		NO

UANG City Drain CW3 and UANG City Drain CW4

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
Antimony	60	13.8	19		5.20	NO
Arsenic	10	63.00	86.50	31		YES
Cadmium	5	ND	1.00		1.00	NO
Copper	25	ND	12.60		12.60	NO
Selenium	5	1.90	7.40		5.50	NO

UANG-S2-SB3 (4.5-6.5) and UANG-S2-SB3 (6.5-8.5)

Analyte	CRQL (mg/kg)	[Sample] (mg/kg)	[Duplicate] (mg/kg)	RPD (%)	Diff. (mg/kg)	Out of Limit
Arsenic	2	9.00	4.50		4.50	NO
Beryllium	1	0.77	0.27		0.50	NO
Chromium	2	22.80	5.20		17.60	YES
Copper	5	35.10	11.30		23.80	YES
Lead	0.6	25.80	15.00	53	10.80	NO
Nickel	8	15.20	5.40		9.80	NO
Thallium	2	0.71	ND		0.71	NO
Zinc	4	78.10	29.50	90		YES

TABLE E.23 (Continued)

UANG-S4-SB4 (6.5-9) and UANG-S4-SB4 (9-11)

Analyte	CRQL (mg/kg)	[Sample] (mg/kg)	[Duplicate] (mg/kg)	RPD (%)	Diff. (mg/kg)	Out of Limit
Arsenic	2	17.10	11.40	40	0.03	NO
Beryllium	1	0.46	0.43			NO
Chromium	2	13.10	11.70	11		NO
Copper	5	26.40	41.20	44		NO
Lead	0.6	18.80	18.20	3	1.10	NO
Nickel	8	10.50	9.40			NO
Zinc	4	53.50	53.80	1		NO

UANG-S4-SB5 (5-7) and UANG-S4-SB5 (7-9)

Analyte	CRQL (mg/kg)	[Sample] (mg/kg)	[Duplicate] (mg/kg)	RPD (%)	Diff. (mg/kg)	Out of Limit
Antimony	12	ND	2.60	--	2.60	NO
Arsenic	2	4.70	4.70	0	0.00	NO
Beryllium	1	0.38	0.36	5	0.02	NO
Chromium	2	7.70	6.30	20	1.40	NO
Copper	5	29.40	35.80	20	0.70	NO
Lead	0.6	15.90	14.00	13		NO
Nickel	8	8.10	7.40	9		NO
Zinc	4	42.20	41.10	3		NO

UANG-S7-SB9 (2.5-4.5) and UANG-S7-SB9 (8.5-9.5)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Arsenic	2	11.70	10.20	13.6	0.14	NO
Beryllium	1	0.53	0.39			NO
Cadmium	1	0.33	0.30			NO
Chromium	2	20.00	11.00	58.1	6.40	NO
Copper	5	25.50	19.10			NO
Lead	0.6	7.00	6.00	15.3	5.80	NO
Nickel	8	13.70	7.90			NO
Zinc	4	58.70	41.00	35.5		NO

Fraction: Volatile Organics

UANG-S2-SB3 (4.5-6.5) and UANG-S2-SB3 (6.5-8.5)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Benzene	10	6	3		3	NO
Toluene	10	5	3		2	NO
Ethylbenzene	10	100	48		52	YES
Total Xylenes	10	43	16		27	NO

TABLE E.23 (Continued)

UANG-S4-SB4 (6.5-9) and UANG-S4-SB4 (9-11)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Toluene	10	3	5		2	NO
2-Butanone	10	3	ND		3	NO
Toluene	10	3	5		2	NO
Methylene Chloride	5	ND	2		2	NO
Carbon Disulfide	5	ND	2		2	NO

UANG-S5-SB3 (6-8.5) and UANG-S5-SB3 (8.5-11)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Acetone	10	5	5		0	NO
Toluene	10	3	4		1	NO

UANG-S6-SB4 (6-8.5) and UANG-S6-SB4 (8.5-11) (No analytes detected)

Fraction: Aromatic Compounds

UANG City Drain CS6 and UANG City Drain CS7

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Toluene	10	430	ND		430	YES
Xylenes (total)	10	710	ND		710	YES

UANG City Drain CW3 and UANG City Drain CW4

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
Benzene	10	1.10	ND		1.10	NO
Toluene	10	3.50	2.40		1.10	NO
Xylenes (total)	10	5.10	ND		5.10	NO

UANG-S3-MW1 and UANG-S3-MW3

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
Toluene	10	0.27	0.24		0.03	NO
Chlorobenzene	10	33.00	32.00		1.00	NO
1,2-Dichlorobenzene	10	5.70	5.40		0.30	NO
1,3-Dichlorobenzene	10	1.10	1.20		0.10	NO
1,4-Dichlorobenzene	10	7.60	7.60		0.00	NO

TABLE E.23 (Continued)**Fraction: Halogenated Compounds**

UANG City Drain CW3 and UANG City Drain CW4

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
1,1,1-Trichlorethane	10	2.60	4.00		1.40	NO
Trichloroethene	10	ND	1.40		1.40	NO

UANG-S3-MW1 and UANG-S3-MW3

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
Chlorobenzene	10	36.00	40.00		4.00	NO
1,2-Dichlorobenzene	10	4.80	5.10		0.30	NO
1,3-Dichlorobenzene	10	0.72	0.73		0.01	NO
1,4-Dichlorobenzene	10	7.60	7.90		0.30	NO

UANG City Drain CS6 and UANG City Drain CS7 (No analytes detected)

Fraction: Halogenated/Aromatic Compounds

UANG-S1-SB8 (7-9) and UANG-SB8 (5-7) (No analytes detected)

UANG-S1-SB6 (3-5) and UANG-SB6 (1-3) (No analytes detected)

UANG-S3-SB3 (4-6) and UANG-S3-SB3 (6-8) (No analytes detected)

UANG-S4-SB5 (5-7) and UANG-S4-SB5 (7-9) (No analytes detected)

UANG-S6-SB6 (6-8.5) and UANG-S6-SB6 (8.5-11) (No analytes detected)

UANG-S6-SB9 (6-8.5) and UANG-S6-SB9 (8.5-11) (No analytes detected)

UANG-S7-SB9 (2.5-4.5) and UANG-S7-SB9 (8.5-9.5) (No analytes detected)

Fraction: Semivolatile Organics

UANG City Drain CS6 and UANG City Drain CS7

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Pyrene	330	3600	4800	29		NO
bis (2-Ethylhexyl) phthalate	330	7200	6300	13		NO

TABLE E.23 (Continued)

UANG City Drain CW3 and UANG City Drain CW4

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
Phenol	10	2	1		1	NO
1,3-Dichlorobenzene	10	2	2		0	NO
Napthalene	10	1	1		0	NO
2-Methylnapthalene	10	2	2		0	NO
bis (2-Ethylhexyl) phthalate	10	4	ND		4	NO

UANG-S2-SB3 (4.5-6.5) and UANG-S2-SB3 (6.5-8.5)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
2-Methylnapthalene	330	ND	730		730	NO
Phenanthrene	330	58	260		202	NO
Fluoranthene	330	ND	88		88	NO
Fluorene	330	ND	55		55	NO
Chrysene	330	ND	120		120	NO
bis (2-Ethylhexyl) phthalate	330	190	190		0	NO

UANG-S3-SB3 (4-6) and UANG-S3-SB3 (6-8)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
bis (2-Ethylhexyl) phthalate	330	ND	160		160	NO

UANG-S3-MW1 and UANG-S3-MW3

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
Phenol	10	ND	4		4	NO
1,4-Dichlorobenzene	10	7	ND		7	NO
1,2-Dichlorobenzene	10	4	ND		4	NO
4-Methylphenol	10	ND	2		2	NO

UANG-S4-SB4 (6.5-9) and UANG-S4-SB4 (9-11)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Di-n-Butylphthalate	330	ND	540		540	NO

UANG-S5-SB3 (6-8.5) and UANG-S5-SB3 (8.5-11)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
bis (2-Ethylhexyl) phthalate	330	ND	120		120	NO

TABLE E.23 (Continued)

UANG-S6-SB6 (6-8.5) and UANG-S6-SB6 (8.5-11)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
bis (2-Ethylhexyl) phthalate	330	32	ND		32	NO

UANG-S4-SB5 (5-7) and UANG-S4-SB5 (7-9) (No analytes detected)

UANG-S6-SB4 (6-8.5) and UANG-S6-SB4 (8.5-11) (No analytes detected)

UANG-S6-SB9 (6-8.5) and UANG-S6-SB9 (8.5-11) (No analytes detected)

UANG-S7-SB9 (2.5-4.5) and UANG-S7-SB9 (8.5-9.5) (No analytes detected)

Fraction: Total Recoverable Petroleum Hydrocarbons

UANG City Drain CS6 and UANG City Drain CS7

PQL (mg/kg)	[Sample] (mg/kg)	[Duplicate] (mg/kg)	RPD (%)	Diff. (mg/kg)	Out of Limit
100	1300	1600	21		NO

UANG-S2-SB3 (4.5-6.5) and UANG-S2-SB3 (6.5-8.5)

PQL (mg/kg)	[Sample] (mg/kg)	[Duplicate] (mg/kg)	RPD (%)	Diff. (mg/kg)	Out of Limit
100	63	700	167	637	YES

UANG-S4-SB5 (5-7) and UANG-S4-SB5 (7-9)

PQL (mg/kg)	[Sample] (mg/kg)	[Duplicate] (mg/kg)	RPD (%)	Diff. (mg/kg)	Out of Limit
100	60	ND		60	NO

UANG-S3-SB3 (4-6) and UANG-S3-SB3 (6-8) (No analytes detected)

UANG-S4-SB4 (6.5-9) and UANG-S4-SB4 (9-11) (No analytes detected)

UANG-S5-SB3 (6-8.5) and UANG-S5-SB3 (8.5-11) (No analytes detected)

UANG-S6-SB4 (6-8.5) and UANG-S6-SB4 (8.5-11) (No analytes detected)

UANG-S6-SB6 (6-8.5) and UANG-S6-SB6 (8.5-11) (No analytes detected)

UANG-S6-SB9 (6-8.5) and UANG-S6-SB9 (8.5-11) (No analytes detected)

UANG-S7-SB9 (2.5-4.5) and UANG-S7-SB9 (8.5-9.5) (No analytes detected)

TABLE E.23 (Continued)

UANG City Drain CW3 and UANG City Drain CW4 (No analytes detected)

Fraction: Pesticides/PCBs

UANG City Drain CW3 and UANG City Drain CW4

Analyte	CRQL (ug/L)	[Sample] (ug/L)	[Duplicate] (ug/L)	RPD (%)	Diff. (ug/L)	Out of Limit
Dieldrin	0.05	0.021	0.031	-38	0.01	NO
Aldrin	0.05	0.05	0.042	17	-0.008	NO

UANG-S1-MW1 and UANG-S1-MW2 (No analytes detected)

UANG-S1-SB3 (4-6.5) and UANG-S1-SB3 (6.5-8.5)

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
Beta BHC	1.70	16.00	1.70	162	-14.3	YES

UANG City Drain CS6 and UANG City Drain CS7

Analyte	CRQL (ug/kg)	[Sample] (ug/kg)	[Duplicate] (ug/kg)	RPD (%)	Diff. (ug/kg)	Out of Limit
4,4-DDE	3.30	130.00	46.00	95	-84	YES

UANG-S1-SB8 (7-9) and UANG-S1-SB8 (5-7) (No analytes detected)

UANG-S1-SB6 (3-5) and UANG-S1-SB6 (1-3) (No analytes detected)

E.3 DATA QUALITY ASSESSMENT

The data quality assessment is based on accuracy, precision, completeness, and representativeness. A discussion of each follows.

E.3.1 PRECISION

The precision of a measurement is the agreement of multiple measurement values of the sample property, conducted under similar conditions. Analytical precision is expressed as the percentage of the difference between results of duplicate samples for a given compound or analyte. The RPD is calculated by the equation:

$$RPD = \frac{V1 - V2}{(V1 + V2)/2} \times 100\%$$

where V1, V2 = the two values obtained by analyzing the duplicate samples.

Acceptable levels of precision will vary according to the sample matrix, the specific analytical method, and the analytical concentration relative to the MDL.

Laboratory precision was determined using MS/MSD pairs for the organic fractions and LCS/LCSDs when provided. Rarely was data qualified for RPD being out of control limits, showing a high degree of precision.

E.3.2 ACCURACY

Accuracy is defined as the degree to which the measured value represents the true value of that parameter. Analytical accuracy is expressed as the %R of a compound or element that has been added to the environmental sample at a known concentration before analyses. The %R is calculated as follows:

$$\%R = \frac{Ss - So}{Sa} \times 100\%$$

where

So = the background value, obtained by analyzing the sample prior to spiking;

Sa = concentration of the spike added to the sample; and

Ss = value obtained by analyzing the sample with the spike added.

The laboratory objective for accuracy is to equal or exceed the accuracy demonstrated for the applied analytical methods on samples of similar matrix and concentration of contaminants. Method blank surrogate recoveries, initial and continuing calibrations, LCS, and MS/MSD results are used to evaluate the laboratory accuracy. The degree of accuracy and the percent recovery expected from the analysis of QA samples and spiked samples depend on the matrix, method of analysis, and compound or element determined. From %R data indicated on Table E.24, it is clear that the overall accuracy of the analysis was very good.

TABLE E.24

PERCENT OF ACCEPTABLE ACCURACY AND PRECISION RESULTS

Fraction	Matrix	Number of Samples	MS/MSD Pairs	MS/MSD %R (1)	LCS\ LCS pairs	LCS\ LCS %R (1)	LCS\ LCS Surrogate %R (1)
Inorganic Metal	Water	31	3	82.0	NA	98.7	NA
Inorganic Metal	Soil	67	5	66.2	NA	95.6	NA
Volatile	Water	9	0	NA	2	100	95.8
Volatile	Soil	52	5	100	5	100	98.0
SW8010/SW8020	Water	51	3	100	11	100	100
SW8010/SW8020	Soil	87	6	100	11	100	100
Semivolatile	Water	43	2	81.8	15	94.2	98.5
Semivolatile	Soil	127	8	92.6	15	97.6	99.6
Pesticide/PCB	Water	25	2	97.8	6	100	89
Pesticide/PCB	Soil	41	3	83	5	100	100
TRPH	Water	22	2	100	NA	NA	NA
TRPH	Soil	129	9	98.9	NA	NA	NA
SW8015M (Diesel)	Soil	8	1	100	1	100	*
SW8015M (Gas)	Soil	8	1	100	1	100	81
Resampling Event							
SW8010	Soil	16	1	100	1	100	95
SW8080	Soil	16	1	83	1	100	42.5
SW8080	Water	3	1	100	1	100	100

(1) Percentage of results within QC limits.

* No surrogate analysis was performed due to analyst oversight.

E.3.3 REPRESENTATIVENESS

Representativeness expresses the degree the data accurately and precisely represent a characteristic of a population, parameter variations at a sampling point, a process, or an environmental condition.

Sample selection and handling procedures were intended to obtain the most representative sample possible. Representativeness of specific samples were achieved using the following methods:

- Collecting samples from locations representative of site conditions;
- Using appropriate sampling procedures and equipment;
- Using appropriate analytical methodologies for parameters and detection limits required; and
- Analyzing within appropriate holding times.

To assess the representativeness of the sample collection procedures, some samples were collected in duplicate. One of the duplicates was given a coded (false) sample identifier, and both the original sample and the duplicate were analyzed. The RPD values of each analyte in the sample and the corresponding coded duplicate are a measure of representativeness. Acceptable levels of RPD will vary according to the sample matrix, the specific analytical method, and the analytical concentration. A second QC sample type used to evaluate representativeness is the blank. Field and laboratory QC blanks are used to evaluate concentrations of possible interference to target compound analyses and quantitation. Twelve out of 39 analytes detected in duplicates were out of control for field duplicates. Seven of the 12 out of control results, were due to non-detect (ND) in the samples. Overall sampling shows good representativeness.

E.3.4 COMPLETENESS

The completeness of the data was determined by comparing the amount of valid data obtained with the amount of data expected from the field or laboratory management system. It is expressed as percent completeness (%C), calculated according to the following equation:

$$\%C = \frac{N_A}{N_I} \times 100$$

where

N_A = the actual number of valid analytical results obtained, and

N_I = the theoretical number of results obtainable under ideal conditions.

The specific objective for completeness for this project is greater than 90 percent. Overall results shown on Table E.25 indicate a completeness of 99.06% with none of the specific fraction results falling below 95%.

TABLE E.25
SUMMARY OF PERCENT COMPLETENESS

Fraction (# of Analytes)	Samples Analyzed	Unusable Analyses (R flag)	Percent Completeness
Inorganic Metal (13)	82	48	95.5
VOCs (39)	52	65	96.8
Halogenated/Aromatics (36/8)	121	0	100
Semivolatile (65)	150	45	99.5
Pesticide/PCB (20)	37	0	100
TRPH (1)	129	1	99.2
Diesel	8	0	100
Gasoline	8	0	100
Resampling Event			
Halogenated/Aromatics (24)	16	0	100
Pesticide/PCB (26)	19	0	100
Overall			99.06

A list indicating samples that were considered as unusable is included as Table E-2.

E.4 CONCLUSION

The QC criteria established for this project were met overall. Guidelines for each method were followed by the laboratory and the results show a high degree of precision, accuracy, and completeness. With the exception of the rejected data, the values generated through the analysis can be applied confidently within the qualifications discussed.

FINAL

End of QA/QC Report No. 1

QA/QC Report No. 2
Data Validation Summary
1995

QA/QC REPORT NO. 2

TABLE OF CONTENTS

LIST OF TABLES.....	iii
LIST OF ACRONYMS	iv
E.1 INTRODUCTION	E2-1
E.1.1 Criteria Used to Assess Laboratory Data Quality	E2-2
E.1.2 Data Validation Qualifiers	E2-2
E.1.3 Holding Time Compliance.....	E2-2
E.2 QUALITY CONTROL ASSESSMENT	E2-4
E.2.1 Metals Analysis Using EPA Methods SW6010, SW7060, SW7421, SW7470/71, SW7740 and SW7841	E2-4
E.2.1.1 Introduction.....	E2-4
E.2.1.2 Technical Holding Times.....	E2-4
E.2.1.3 Initial and Continuing Calibration Verification.....	E2-4
E.2.1.4 Blanks	E2-5
E.2.1.5 Matrix Spike/Matrix Spike Duplicates	E2-7
E.2.1.6 Interference Check Sample	E2-8
E.2.1.7 Laboratory Control Samples	E2-8
E.2.1.8 Duplicate Sample Analysis	E2-8
E.2.1.9 ICP Serial Dilution.....	E2-9
E.2.1.10 Graphite Furnace Atomic Absorption.....	E2-9
E.2.1.11 Other Comments	E2-9
E.2.2 Semivolatile Organic Analysis by GC/MS Using EPA Method SW8270	E2-10
E.2.2.1 Introduction.....	E2-10
E.2.2.2 Holding Times	E2-11
E.2.2.3 GC/MS Instrument Performance Check	E2-11
E.2.2.4 Initial Calibration.....	E2-12
E.2.2.5 Continuing Calibration	E2-12
E.2.2.6 Blanks	E2-12
E.2.2.7 Surrogate Spike Compounds.....	E2-12
E.2.2.8 Matrix Spikes/Matrix Spike Duplicates.....	E2-15
E.2.2.9 Laboratory Control Spikes/Laboratory Control Spike Duplicates	E2-16
E.2.2.10 Internal Standards	E2-16
E.2.2.11 Field Duplicates	E2-16
E.2.3 Total Recoverable Petroleum Hydrocarbons Using EPA Method 418.1.....	E2-16

E.2.3.1	Introduction.....	E2-16
E.2.3.2	Technical Holding Time	E2-16
E.2.3.3	Initial Calibration.....	E2-17
E.2.3.4	Continuing Calibration Verification	E2-17
E.2.3.5	Blanks	E2-17
E.2.3.6	Matrix Spike/Matrix Spike Duplicates	E2-17
E.2.3.7	Laboratory Control Sample.....	E2-17
E.2.3.8	Field Duplicates	E2-17
E.2.4	Purgable Halogenated Volatile Organic and Purgable Aromatic Volatile Organic Analyses by GC Using Methods SW8010 and SW8020	E2-18
E.2.4.1	Introduction.....	E2-18
E.2.4.2	Technical Holding Times.....	E2-18
E.2.4.3	Initial Calibration.....	E2-19
E.2.4.4	Continuing Calibration	E2-19
E.2.4.5	Blanks	E2-19
E.2.4.6	Surrogate Spikes	E2-22
E.2.4.7	Matrix Spike/Matrix Spike Duplicate	E2-22
E.2.4.8	Laboratory Control Standard (LCS)	E2-23
E.2.4.9	Field Duplicates	E2-23
E.2.4.10	Additional Comments	E2-24
E.2.5	Pesticides and PCB Analysis Using EPA Method SW8080.....	E2-25
E.2.5.1	Introduction.....	E2-25
E.2.5.2	Technical Holding Times.....	E2-25
E.2.5.3	Initial Calibration.....	E2-25
E.2.5.4	Continuing Calibration	E2-25
E.2.5.5	Blanks	E2-26
E.2.5.6	Surrogate Spike Compounds.....	E2-26
E.2.5.7	Laboratory Control Samples (LCS)	E2-26
E.2.5.8	Matrix Spikes/Matrix Spike Duplicates.....	E2-27
E.2.5.9	Coded Field Duplicates.....	E2-28

QA/QC REPORT NO. 2

LIST OF TABLES

No.	Title	Page
E.1	EPA Qualifiers Assigned to Analytical Results	E2-3
E.2	Field Blank Contamination	E2-6
E.3	Preparation Methods for Semivolatile Data.....	E2-10
E.4	Performance Check Using Decafluorotriphenylphosphine.....	E2-11
E.5	Surrogate Recovery Limits	E2-13
E.6	Base/Neutral/Acid Surrogate Compounds With Associated Target Analytes	E2-14
E.7	Semivolatile Organic MS/MSD Criteria.....	E2-15
E.8	Trip Blank Contamination	E2-20
E.9	Field and Rinse Blank Contamination	E2-21
E.10	Surrogate Recovery Limits	E2-22
E.11	DataChem Laboratory MS/MSD Criteria.....	E2-22
E.12	DataChem Laboratory LCS Criteria	E2-23
E.13	Pesticide/PCB Surrogate Recoveries	E2-26
E.14	LCS/LCSD Requirements for Pesticide Analysis.....	E2-27
E.15	MS/MSD Criteria for Pesticide Analysis.....	E2-27
E.1.2.1	Table of Estimated Data - Analytical Data Summary	
E.1.2.2	Table of Unusable Data - Analytical Data Summary	

QA/QC REPORT NO. 2

ACRONYMS

Associated Samples	Any sample related to a particular QC analysis, for example: <ul style="list-style-type: none">• For ICV, all samples run under the same calibration curve.• For duplicate RPD, all SDG sample digested/distilled of the same matrix.• For field blank, all samples collected, stored and shipped with the field blank.
AA	Atomic Absorption - instrument utilized in the analysis of metals
BFB	Bromofluorobenzene - a non-target standard used to check the tuning of the GC/MS instrument used for volatile organic analysis
BNA	Base/Neutral/Acids Compounds - the chemical properties of target analytes which comprise the complete semivolatile organic list of analytes.
Calibration Curve	A plot of responses versus concentration of multi concentration standards.
CCB	Continuing Calibration Blank - a deionized water sample run every ten samples designed to detect any carryover contamination.
CCV	Continuing Calibration Verification - a standard run every ten samples designed to test instrument performance.
CLP	Contract Laboratory Program - a USEPA program designed to audit and qualify laboratories to participate in the analysis of samples generated under superfund effort.
CRDL	Contract Required Detection Limit.
CV	Cold Vapor - mercury analysis technique.
CVAA	Cold Vapor Atomic Absorption - see CV
DFTPP	Decafluorotriphenylphosphine - a non target standard used to check the tuning of the GC/MS instrument used in semivolatile organic analysis.
Field Blank	Field blanks are intended to identify contaminants that may have been introduced in the field. Examples are trip blanks, travel blanks, rinseate blanks, and decontamination blanks.
Field Duplicate	A duplicate sample generated in the field, not in the laboratory. They are two separated samples taken from the same source, stored in separate containers and analyzed independently.
GC	Gas Chromatography - organics analysis instrumentation.

GC/MS	Gas Chromatography/Mass Spectrometry - organics analysis instrumentation.
GFAA	Graphite Furnace Atomic Absorption - low level metals analysis techniques.
Holding Time	The time from sample collection to laboratory preparation and/or analysis.
ICB	Initial Calibration Blank - first blank standard run to confirm the calibration curve.
ICP	Inductively Coupled Plasma - instrument utilized in the simultaneous analysis of target metals.
ICAL	Initial Calibration - see calibration curve
ICS	Interference Check Sample - spike sample containing known interfering compounds (metals) to demonstrate instrument performance and separation.
ICV	Initial Calibration Verification - first standard run to confirm the calibration of the instrument is stable.
IDL	Instrument Detection Limit - the lowest detection observed greater than five times the instrument background noise level.
Initial Calibration	The establishment of a calibration curve with the appropriate number of standards and concentration range. The calibration curve plots absorbance or emission versus concentration of standards.
IS	Internal Standard - Non-target standard spiked into all samples, after sample preparation, but prior to analysis.
LCS	Laboratory Control Sample - a spiked laboratory generated sample to demonstrate the precision and accuracy of all facets of the analysis (sample preparation, through analysis and quantitation).
Matrix	The component or substrate (e.g. surface water, sediment) which contains the analyte of interest.
MB	Method Blank - An analyte-free matrix to which all reagents are added in the same volumes or proportions as used in sample processing. The method blank is prepared and analyzed along with the investigative samples and is used to document contamination resulting from the analytical process.
MD	Matrix Duplicate - an intralaboratory split sample which is used to document the precision of a method in a given sample matrix.
MDL	Method Detection Limit - the minimum concentration of a substance that can be measured and reported with 99% confidence

	that the analyte concentration is greater than zero and is determined from analysis of a sample in a given matrix type containing the analyte.
MS	Matrix Spike - introduction of a known concentration of analyte into a sample to provide information about the effect of the sample matrix on the sample preparation and measurement methodology.
MSA	Method of Standard Addition - known spike amounts introduced into aliquots of a field sample at a minimum of four different concentrations in order to establish matrix affects and quantitate a metal using the graphite furnace technique.
MSD	Matrix Spike Duplicates - intralaboratory split samples spiked with identical concentrations of target analyte(s). The spiking occurs prior to sample preparation and analysis. They are used to document the precision and bias of a method in a given sample matrix.
%D	Percent Difference - the calculated difference between the observed and expected concentrations.
%R	Percent Recovery - the calculated result as a percentage of the expected concentration.
PDS	Post Digestion Spike - The addition of a known amount of standard after digestion. (Also identified as analytical spike, or spike, for furnace analyses.)
PRDL	Project Required Detection Limit - the detection limits established between the laboratory and project requirements to ensure usable data.
PRL	Project Reporting Limit - the laboratory established reporting limits based on analytical method and laboratory performance.
QA	Quality Assurance
QC	Quality Control
r	Correlation Coefficient
RPD	Relative Percent Difference - the measured value calculated using the difference between two results divided by the average of the two results and multiplied by 100.
RRF	Relative Response Factor - comparison of target analyte response to response of associated internal standard.
RSD	Relative Standard Deviation - calculated value determined by the result of the standard deviation observed by two results divided by their average multiplied by 100.

SDG	Sample Delivery Group - defined by one of the following, whichever occurs first: <ul style="list-style-type: none"> • Case of field samples • each twenty field samples in a Case • each 14-day calendar period during which field samples in a Case are received, beginning with receipt of the first sample in the SDG.
Serial Dilution	A sample run at a specific dilution to determine whether any significant chemical or physical interferences exist due to sample matrix effects. (ICP only)
SOP	Standard Operating Procedures - laboratory specific methodology based on published method.
SOW	Statement of Work - USEPA CLP laboratory analytical methodology.
Surrogate	Non-target compounds spiked into the sample prior to preparation and analysis. Sample specific quality control check to ensure sample extraction efficiency and analytical procedures are in control.
SVOC	Semivolatile Organic Compounds
SW	USEPA Test Methods for Evaluating Solid Wastes Physical/Chemical Methods - reference document for analytical methodology.
TPH	Total Petroleum Hydrocarbons
TRPH	Total Recoverable Petroleum Hydrocarbons
VOC	Volatile Organic Compounds

This page intentionally left blank.

E.1 INTRODUCTION

Soil and groundwater samples were collected to determine the presence and/or absence, and the extent of contamination present at sites 1-7, at the Utah Air National Guard (UANG) Base. There were 25 investigative samples, three field duplicates, six trip blanks, two field blanks and three rinse blanks collected and analyzed. Original collection of samples occurred between August 16, 1995 and August 28, 1995. However, the laboratory did not, correctly, follow procedures and instructions contained in the analytical methods and/or specific methods for this project. Re-sampling was done on 11/8/95 for Site 6 and 11/6/95 for Site 1,2,3. Re-sampling and re-analyses was performed at the following sites:

<u>Site</u>	<u>Re-analysis</u>	<u>Reason</u>
UANG-S1-MW01-GW2	SW8010/8020	No 2nd column confirmation of positive hits
UANG-S1-MW02-GW2	SW8010/8020	No 2nd column confirmation of positive hits
UANG-S2-MW01-GW2	SW8010/8020	No 2nd column confirmation of positive hits
UANG-S2-MW02-GW2	SW8010/8020	No 2nd column confirmation of positive hits
UANG-S2-MW03-GW2	SW8010/8020	No 2nd column confirmation of positive hits
UANG-S3-MW01-GW2	SW8010/8020	No 2nd column confirmation of positive hits
UANG-S6-MW01	arsenic	Improper preparation method
UANG-S6-MW02	arsenic	Improper preparation method
UANG-S6-MW03	arsenic	Improper preparation method
UANG-S6-MW04	arsenic	Improper preparation method

Soil and water samples were collected for semivolatile organic compounds, purgable halogenated and aromatic, volatile compounds, total recoverable petroleum hydrocarbons (TRPH), pesticides and polychlorinated biphenyls (PCBs) and metals analysis. The samples were analyzed by Data Chem Laboratories of Salt Lake City, Utah.

The laboratory analyzed the samples using the following methods:

- 13 Priority Pollutant Metals, Metals by SW6010 and the appropriate SW7000 Series prepped by Method SW3010, 3020 or 3050.
- Purgable halogenated volatile organics by Method SW8010,
- Purgable aromatic volatile organics by Method SW8020,
- Semivolatile organic compounds (SVOCs) [Base/Neutral/Acids (BNAs)] by Method SW8270,
- PESTs/PCBs by Method SW8080,
- TRPH by Method 418.1,

The analysis methods used are specified in USEPA, 1986a, *Test Methods for Evaluating Solid Wastes*, SW846, 3rd Edition ("SW" Methods); and *Methods for Chemical Analysis of Water and Wastes*, EPA 600/4-79-0202 ("E" methods).

Level C data review and validation was performed using guidelines specified in Section 6.2 of DOE/HWP-65/R1. Specific criteria used for data assessment were based on the EPA CLP *National Functional Guidelines for Organic Data Review*, dated December 1990; and *Laboratory Data Validation Functional Guidelines for Evaluating Inorganics Analysis*, dated February 1994.

E.1.1 Criteria Used to Assess Laboratory Data Quality

The Quality Control (QC) criteria used to assess data quality included technical holding times, initial instrument calibration (ICAL), initial and continuing calibration verification (ICV and CCV), preparation blanks (PB), initial and continuing calibration blank (ICBs and CCBs), matrix spike/matrix spike duplicates (MS/MSDs), inductively coupled plasma analysis (ICP) interference check samples (ICSs), laboratory control samples (LCSs), matrix duplicate sample analysis, ICP serial dilution, graphite furnace atomic absorption (GFAA) and post digestion spike results.

E.1.2 Data Validation Qualifiers

Specific sample analytes traceable to QC violations were qualified as estimated ("J"), undetected ("U"), estimated as undetected ("UJ"), or unusable ("R"). Estimated and estimated as undetected field sample data are shown in Table E.1.2.1. Unusable field sample data are shown in Table E.1.2.2. The EPA qualifiers assigned to analytical results are shown in Table E.1

E.1.3 Holding Time Compliance

Specific holding time criteria is presented in the individual analysis sections. All holding times, for each fraction, for this project were met except re-analyzed, diluted analytes for certain VOCs (See Section E.2.4.2).

TABLE E.1
EPA QUALIFIERS ASSIGNED TO ANALYTICAL RESULTS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Organic Data Validation Qualifiers	
U	The analyte is not present above the level of the associated value. The associated numerical value indicates the approximate concentration necessary to detect the analyte in this sample (e.g., the reporting limit).
J	The analyte is positively identified, but the associated numerical value may not reflect the amount actually present in the environmental sample. The data can be used for many purposes. This data should be seriously considered for decision making.
R	The data are unusable for all purposes. The presence or absence of the analyte has not been verified. Re-sampling and re-analysis are necessary to confirm or deny its presence.
UJ	Combines the "U" and "J" qualifiers. The analyte was not present above the level of the associated value. The associated numerical value may not accurately or precisely represent the concentration in the sample.
N	The analysis indicates that an analyte is present. There are strong indications that the identity is correct.
NJ	Combines the "N" and "J" qualifiers. The analysis indicates that the analyte is "tentatively identified". The associated numerical value may not reflect the amount actually present in the environmental sample.
Inorganic Data Validation Qualifiers	
U	The material was not detected above the level of the associated value. The associated value is the project reporting level (<i>e.g., the non-detect level</i>).
J	The associated value is an estimated quality [<i>e.g., the value falls between the method detection limit (MDL) and the practical quantitation limit (PQL)</i>].
R	The data are unusable. (<i>Note: Analyte may or may not be present</i>).
UJ	The material was not detected. The associated value is an estimate and may be inaccurate or imprecise.

E.2 QUALITY CONTROL ASSESSMENT

E.2.1 Metals Analysis Using EPA Methods SW6010, SW7060, SW7421, SW7470/71, SW7740 and SW7841

E.2.1.1 Introduction

Twelve field samples, four soil and eight aqueous, two rinseate blanks and two field blanks were analyzed for the 13 priority pollutant metals included in this analytical program. Additionally, eleven field samples were analyzed for arsenic only. ICP analysis (SW846, Method 6010) was performed for all metal analytes except arsenic (As), lead (Pb), Selenium (Se) and thallium (Tl), which were analyzed using graphite furnace atomic absorption, and mercury (Hg), which was analyzed by cold vapor atomic absorption.

Samples were to be digested using SW846 Methods 3010, 3020 and 3050, however the laboratory used a variety of other methods. The laboratory was instructed to re-digest and re-analyze the samples using the appropriate digestion procedure. All samples were re-digested and re-analyzed except UANG-S6-MW05-GW2, UANG-BG-MW02-GW2 and UANG-RB01-GW2. Validation for these samples was performed on the original data. These samples were digested using CLP Method SOW ILM04.0 or SW3015. Four samples, UANG S6-MW01-GW2, UANG-S6-MW02-GW2, UANG-S6-MW03-GW2, and UANG-S6-MW04-GW2 were re-sampled on November 8, 1995 and re-analyzed.

E.2.1.2 Technical Holding Times

Holding times were measured from the date of collection to the date of analysis. Chain-of-custody forms were used to verify technical holding times. The specified holding times for preserved aqueous and soil/sediment samples for metals are 28 days for mercury and 180 days for all other analytes. All samples met technical holding times.

E.2.1.3 Initial and Continuing Calibration Verification

For ICP analysis, a blank and at least one standard must be used in establishing the calibration curve. The GFAA ICAL required a blank and three standards, one of which represents the contract required detection limit (CRDL). The ICAL curve for CVAA calibration, used in analysis of mercury, requires one blank and four standards. The multi-standard ICAL curves generated must produce a linear least squares correlation coefficient (r) greater than or equal to 0.995. All of the calibration requirements were met.

To verify the accuracy of the ICAL, an ICV standard (prepared from a standard source other than the source used to prepare the ICAL standards) is analyzed. A CCV standard, of a known concentration, must be analyzed at a 10% frequency for all analytes and after the last analytical sample in each run. The accuracy of the ICV and the CCV is based on the percent recoveries (%R). The %R range criterion is 80-120% for Hg and 90-110% for all other metals. All ICV and CCV results met the established control criteria.

E.2.1.4 Blanks

Three types of blanks, field blanks, laboratory blanks and method preparation blanks, were used to qualify data. Method blanks were prepared and analyzed at a frequency of one per batch of twenty samples. Qualification of results were made if analyte contaminant concentration in the associated blank is above the detection limit and if the lowest analyte concentration is less than five times the blank concentration.

At least one method preparation blank was prepared with each batch of samples. All method blanks were found to be free of contamination except:

<u>Blank</u>	<u>Analyte</u>	<u>Conc.</u>	<u>Affected Samples</u>	<u>Action</u>
Prep Blank (9/24/95)	cadmium	-2.01 µg/L	UANG-RB1-GW2, UANG-BG-MW02-GW2	"UJ"
	copper	2.7 µg/L	UANG-RB1-GW2, UANG-BG-MW02-GW2	"U"
Prep Blank (8/31/95)	mercury	-0.088 µg/L	UANG-RB1-GW2	"UJ"
Prep Blank (11/22/95)	lead	1.69 µg/L	UANG-S4-MW01-GW2	"U"
			UANG-S7-MW02-GW2	"UJ"
			UANG-RB03-GW2	"U"
			UANG-S2-MW02-GW2	"U"
			UANG-S2-MW03-GW2	"U"
			UANG-S2-MW01-MW2	"U"
			UANG-BG-MW01-GW2	"U"
			UANG-FB03-GW2	"U"
Prep Blank (9/8/95)	mercury	-0.052 µg/L	UANG-BG-MW2-GW2	"UJ"
			UANG-RB03-GW2	"UJ"
			UANG-S2-MW01-GW2	"UJ"
			UANG-FB03-GW2	"UJ"
			UANG-S7-MW02-GW2	"UJ"
			UANG-S4-MW01-GW2	"UJ"
			UANG-FB02-GW2	"UJ"
			UANG-S7-MW01-GW2	"J"
			UANG-S2-MW02-GW2	"J"
			UANG-BG-MW01-GW2	"J"
			UANG-S2-MW03-GW2	"J"
Prep Blank (10/30/95)	zinc	4.23 µg/L	UANG-S7-MW02-GW2	"U"
			UANG-FB02-GW2	"U"
			UANG-RB03-GW2	"U"
			UANG-S2-MW02-GW2	"U"
			UANG-S2-MW03-GW2	"U"
			UANG-BG-MW01-GW2	"U"

The listed affected samples that were qualified as non-detect "U" contained less than five times the blank value. Affected samples qualified "J" or "UJ" are considered estimated values due to a negative blank result.

One laboratory blank must be analyzed for every ten samples and after each CCV for ICP, CVAA and GFAA analysis. Qualification of analytes in field samples is required if identifiable quantities of target compounds are found in the laboratory blanks and the analytical results are less than five times the absolute value of the associated blank results. All ICBs and CCBs were free of contamination except:

<u>Blank</u>	<u>Analyte</u>	<u>Conc.</u>	<u>Affected Samples</u>	<u>Action</u>
CCB (11/21/95)	cadmium	1.59 µg/L	None	None
ICB (8/31/95)	mercury	-0.08 µg/L	UANG-RB1-GW2	"UJ"
ICB(9/24/95)	copper	2.69 µg/L	UANG-RB1-GW2	"U"
CCB(9/24/95)	copper	2.69 µg/L	UANG-RB1-GW2, UANG-BG-MW02	"U" "U"
CCB(10/30/95)	antimony	32.02 µg/L	UANG-S4-MW01 UANG-FB03	"U" "U"
CCB(10/20/95)	beryllium	0.018 µg/L	None	None
CCB1(9/8/95)	mercury	-0.035 µg/L	UANG-BG-MW02	"UJ"
CCB2 (9/8/95)	mercury	0.02 µg/L	None	None

The listed affected samples that were qualified as non-detect "U" contained less than five times the blank value. Affected samples qualified "J" or "UJ" are considered estimated values due to a negative blank result. No action was taken if the concentration in the samples exceeded five times the blank concentration or the sample concentration was non-detect.

Field QC blanks were analyzed to verify that no contamination occurred during sampling. These field QC blanks (analyzed for this fraction) were equipment rinseate blanks and field blanks. Nine samples were qualified as having non-detect results "U" due to the following field blank contamination:

TABLE E.2
FIELD BLANK CONTAMINATION

<u>Analyte</u>	<u>CONCENTRATION (µg/L)</u>			
	<u>RB1</u>	<u>RB3</u>	<u>FB2</u>	<u>FB3</u>
cadmium	nd	nd	nd	2.8
chromium	77	nd	nd	3.8
zinc	14	nd	nd	500
selenium	nd	16J	13J	nd
nickel	39	nd	nd	nd

nd=non-detect

<u>Blank</u>	<u>Analyte</u>	<u>Concentration</u>	<u>Affected Samples</u>	<u>Action</u>
FB02	selenium*	13 µg/L	None	None
FB3	cadmium*	2.8 µg/L	None	None
	chromium	3.8 µg/L	UANG-BG-MW1-GW2	"U"
			UANG-S2-MW1-GW2	"U"
			UANG-S2-MW2-GW2	"U"
			UANG-S2-MW03-GW2	"U"
	zinc	500 µg/L	UANG-RB3-GW2	"U"
			UANG-S2-MW2-GW2	"U"
			UANG-BG-MW01-GW2	"U"
			UANG-S2-MW3-GW2	
			UANG-S2-MW1-GW2	"U"
RB1	chromium	77 µg/g	UANG-BG-MW2(0-2)	"U"
			UANG-BG-MW2(2-4)	"U"
			UANG-BG-MW2(4-6)	"U"
			UANG-BG-MW2(6-8)	"U"
	zinc	14 µg/g	None	"U"
	nickel	39 µg/g	UANG-BG-MW2(0-2)	"U"
			UANG-BG6-MW2(2-4)	"U"
			UANG-BG-MW2(4-6)	"U"
			UANG-BG-MW2(6-8)	"U"
RB3	selenium*	16 µg/L	None	

* No detectable levels of analyte found in associated sample(s) so no action was required.

E.2.1.5 Matrix Spike/Matrix Spike Duplicates

An MS or MSD must be included for every ten samples (one MS/MSD pair per 20 samples), for each matrix analyzed. Spiked-sample analysis provides information about the effect of each sample matrix on digestion and measurement methodologies. Samples identified as field blanks cannot be used for spiked-sample analysis. The %R values for all elements must be within the limits of 75-125%. If the measured %R value falls outside of this range, all associated samples must be qualified as estimated. If the analytical results for an analyte fall below 30%, these results must be deemed unusable in all associated samples. Field blanks are not considered investigative field samples and are, therefore, not qualified based on MS/MSD results.

The 10% frequency requirement for both soil and water matrices was met. The %R fell outside of the QC criteria windows for several MS/MSDs requiring the qualification of 25 sample values as "J" (\geq MDL) or "UJ" ($<$ MDL). The %R for the MS/MSDs were less than 30% warranting specific analytes in several samples be deemed unusable. Unusable "R" flags were applied to five antimony results for possible matrix effects resulting in the MS/MSD recoveries below 30%.

Sample UANG-RB1-GW2 was run as a matrix spike/matrix spike duplicate. No water samples were associated with this sample, and no qualifications were based on the results.

The laboratory supplied results for MS/MSD RPDs. Fifteen field samples were qualified "J", "UJ" due to MS/MSD RPD outliers.

E.2.1.6 Interference Check Sample

The ICP Interference Check Sample (ICS) verifies the laboratory's ICP inter-element and background correction factors. Verification of the interelement and background correction factors was performed at the beginning and the end of each analytical run. As per the case narratives, all interference check analytes were within quality control limits.

E.2.1.7 Laboratory Control Samples

An LCS is a laboratory reagent blank spiked with known concentrations of the target analytes and is processed with samples through sample preparation procedures. The LCS spike recovery indicate accuracy relevant to all samples and matrices within an analytical batch and are strictly a measure of analytical accuracy, conditions independent of samples and matrices. A successful result required that the %Rs for all analytes fall within the control limits of 80-120%. All Laboratory Control Samples were within the required limits.

E.2.1.8 Duplicate Sample Analysis

One laboratory duplicate sample is analyzed for every 10 samples and for each matrix in the sample delivery group (SDG). The resulting relative percent difference (RPD) should be less than or equal to 20% for aqueous samples and less than or equal to 35% for soil and sediment samples, where measured analyte results are greater than five times the CRDL. Therefore, samples that are identified as field blanks are not used. Duplicate analyses are indicators of overall precision based on each sample matrix. For duplicate analyte concentrations less than five times the CRDL, the difference between the two reported results should be less than the CRDL for aqueous samples and two times the CRDL for soil/sediment samples.

Four water samples were qualified as either "J" or "UJ" due to a matrix duplicate RPD outlier for arsenic. In addition, four soil samples were qualified "J" or "UJ" due to an arsenic matrix duplicate RPD outlier. No matrix duplicate for arsenic was associated with sample UANG-S6-MW5-GW2. This sample was qualified "J".

No mercury matrix duplicate was performed. No qualifications were made for mercury results due to matrix duplicates non-compliance. However, qualifications were made based on MS/MSD outliers.

No matrix duplicate was run for any analyte in sample UANG-BG-MW2-GW2. As this is a project requirement, all results were qualified "J", "UJ".

Sample UANG-FB02-GW2 was used as a matrix duplicate. Samples identified as field blanks cannot be used for duplicate sample analysis as the matrix duplicate is used

to demonstrate acceptable sample matrix precision by the laboratory at the time of analysis. No results were qualified based on these results.

Field duplicates are analyzed to determine the representativeness of sampling procedures. One member of the duplicate pair is given a coded (false) identifier so that the sample analysis is not biased during analysis. Three sets of field duplicates collected and were analyzed for metals. UANG-BGMW2(6-8) is a soil field duplicate of UANG-BG-MW2(4-6). UANG-S2-MW3-GW2 is a field duplicate of UANG-S2-MW2-GW2 and UANG-S5MW2-GW2 is a field duplicate of UANG-S5-MW01-GW2. Any QC outliers will qualify only the pair of samples. All field duplicates met the above QC criteria.

E.2.1.9 ICP Serial Dilution

One serial dilution is performed for every ten samples and for each matrix. A serial dilution is performed for metals analyzed by ICP to determine if any physical or chemical interferences exist in the sample matrix. If the concentration in the original sample is greater than 50 times the IDL, a five-fold dilution must agree within $\pm 10\%$ of the difference between the dilution and the original result. Four soil samples were qualified as "J" or "UJ" because copper values did not meet serial dilution criteria.

E.2.1.10 Graphite Furnace Atomic Absorption

GFAA duplicate injections percent relative standard deviation (%RSD) must be less than 20% with a Post Digestion Spike (PDS) %R between 85-115%. Level C validation does not require the review of graphite duplicate %RSD from the raw data.

Criteria for validation of PDS is based on SW846, Section 7000. Nineteen sample results were estimated due to a post digestion spike not being performed. All Method of Standard Addition results were compliant.

E.2.1.11 Other Comments

The laboratory flagged several samples "B" as a reported value which falls between the CRDL and the MDL. The "B" flag was replaced by a "J" flag for consistency with similar findings with the organic analytes. The following lists those samples.

<u>Sample</u>	<u>Analyte</u>
UANG-BGMW2(0-2)	thallium
UANG-BGMW2(2-4)	thallium
UANG-BGMW2(4-6)	thallium
UANG-RB03-GW2	selenium

The limits selected for reporting are the laboratory's method detection limits rather than the higher CRDLs. Selenium has an elevated detection of 12 $\mu\text{g/L}$ due to dilutions, except for UANG-RB1-GW2 (1.2 $\mu\text{g/L}$). However, it should be noted, that sample UANG-BG-MW02-GW2 underwent an even greater dilution rendering a selenium detection limit of 60 $\mu\text{g/L}$ due to severe matrix interference.

E.2.2 SEMIVOLATILE ORGANIC ANALYSIS BY GC/MS USING EPA METHOD SW8270

E.2.2.1 Introduction

The Semivolatile Organic Compounds, also called BNAs, are assessed by QC criteria similar to those used for the volatile fraction. The EPA method of SVOCs requires analysis by GC/MS. A total of 25 samples including four soil/sediment and 21 aqueous samples, including field blanks, were analyzed for 65 target compounds. Laboratory QC data were reviewed for technical holding time, GC/MS instrument performance check, ICAL and CCAL, blanks, surrogate spike compounds, and MS/MSDs.

Three different preparation methods were used to extract the samples. The following table lists the preparation method for the samples reviewed and the quality control samples associated with these samples:

**TABLE E.3
PREPARATION METHODS FOR
SEMIVOLATILE DATA**

Prep Method		
3550	3510	3520
BGMW2(0-2)	UANG-RB1*	R1303-GW2
BGMW2(2-4)	S6-MW01-GW2	S2-MW01-GW2
BGMW2(4-6)	S6-MW02-GW2	S2-MW02-GW2
BGMW2(6-8)	S6-MW03-GW2	S2-MW03-GW2
	S6-MW04-GW2	BG-MW01-GW2
	S6-MW05-GW2	FB03-GW2
	S3-MW01-GW2	
	S3-MW02-GW2	
	BG-MW02-GW2	
	S7-MW02-GW2	
	S7-MW01-GW2	
	S4-MW01-GW2	
	S5-MW01-GW2	
	FB02-GW2	
	SS-MW02-GW2	
Method Blank (1)	Method Blank (3)	Method Blank (1)
Lab Control Standard (1)	Lab Control Standard (3)	Lab Control Standard (1)
MS/MSD	MS/MSD	MS/MSD

*Associated with soil samples.

SAMPLES

QA/QC

E.2.2.2 Holding Times

Holding times are measured from the time of collection to the time of extraction and analysis. The technical holding times are seven days for aqueous samples and 14 days for soil samples from time of collection to extraction. Sample extracts must then be analyzed 40 days from the date of extraction. The technical holding times were met for all samples.

E.2.2.3 GC/MS Instrument Performance Check

Decafluorotriphenylphosphine (DFTPP) is used as the tuning standard for BNA analysis. A performance check was performed every 12 hours. In all cases the DFTPP performance check was performed and met the following criteria indicated on Table E.4. All standards, samples, blanks and QC samples were analyzed within 12 hours of the injection of the DFTPP check standards as required.

TABLE E.4
PERFORMANCE CHECK USING
DECAFLUOROTRIPHENYLPHOSPHINE

m/z	Ion Abundance Criteria
51	30.0 - 60.0% of m/z 198
68	Less than 2.0% of m/z 69
69	Present
70	Less than 2.0% of m/z 69
127	40.0 - 60.0% of m/z 198
197	Less than 1.0% of m/z 198
198	Base peak, 100% relative abundance
199	5.0 - 9.0% of m/z 198
275	10.0 - 30.0% of m/z 198
365	Greater than 1.0% of m/z 198
441	Present, but less than m/z 443
442	Greater than 40.0% of m/z 198
443	17.0 - 23.0% of m/z 442

E.2.2.4 Initial Calibration

Calibration curves, consisting of one blank and five standards were prepared. Standards of 20, 50, 80, 120 and 160 µg/L were made containing target compounds, internal standards and system monitoring compounds. The instrument must demonstrate an RRF of greater than or equal to 0.05 for each compound and a %RSD result of less than or equal to 30%. Twenty-five samples were qualified "J" or "UJ" due to %RSD values greater than 30%.

E.2.2.5 Continuing Calibration

A CCAL must be analyzed at the beginning of each 12-hour analysis period after the analysis of the instrument performance check but before the analysis of any blanks of samples. A midrange standard is used for the CCAL analysis. The RRF for each target analyte must be greater than or equal to 0.05. The %D between the mean ICAL RRF and the CCAL RRF for each compound must be within $\pm 25\%$. Nineteen samples were qualified "J" or "UJ" because the %D criterion was exceeded.

E.2.2.6 Blanks

Qualification of data may be based on the method blank analysis. If concentrations of analytes in the field samples are greater than the detection limit but are less than five times the contaminant concentration in the associated laboratory blanks (10 times for common laboratory contaminants), the analyte is qualified as non-detect "U" at the value reported. If concentrations of analytes in the field samples are less than five/ten times the contaminant concentration in the associated laboratory blanks and are also less than the detection limit, the results are qualified non-detect "U" at the detection limit. Seven samples were qualified for contamination of di-n-butylphthalate.

Field QC blanks are analyzed to verify that no contamination occurred during sampling. Field QC blanks analyzed for the semivolatile fraction include equipment rinse blanks and field blanks. No contamination was found in any field blank.

E.2.2.7 Surrogate Spike Compounds

Six surrogate spike compounds are used to calculate the %R for BNA analytes (See Table E.5 for BNA surrogates and Table E.6 for associated target analytes). Qualification is only applied to samples if two surrogates in the same fraction exceed the control limits, or if a single surrogate has a recovery of less than 10%. Sample re-analysis is to be performed if the surrogate %R results are outside the recovery criteria shown on the following table:

TABLE E.5
SURROGATE RECOVERY LIMITS

Surrogate	Water %R	Soil/Sediment %R
2-fluorophenol	21-100	25-121
phenol-d5	10-94	24-113
nitrobenzene-d5	35-114	23-120
2-fluorobiphenyl	43-116	30-115
2,4,6-tribromophenol	10-123	19-122
terphenyl-d14	33-141	18-137

One sample S6-MW01-GW2 did not meet the surrogate recovery criteria for the base/neutral fraction. All B/N compounds were qualified "UJ" (< MDL) as estimated, non-detected results. 2-fluorophenol did not meet %R criteria in the preparation blank BL-99633-1. Professional judgment deemed this an isolated occurrence and no qualification action was required.

TABLE E.6
BASE/NEUTRAL/ACID SURROGATE COMPOUNDS
WITH ASSOCIATED TARGET ANALYTES

Base/Neutral (B/N) Fraction Surrogates:

Nitrobenzene-d₅ (NBZ)

Terphenyl-d₁₄ (TPH)

2-fluorobiphenyl (FBP)

Base/Neutral (B/N) Fraction Target Compounds:

dibenzofuran

2,4-dinitrotoluene

diethylphthalate

4-chlorophenyl-phenylether

fluorene

4-nitroaniline

n-nitrosodiphenylamine

4-bromophenyl-phenylether

hexachlorobenzene

phenanthrene

anthracene

carbazole

di-n-butylphthalate

fluoranthene

pyrene

butylbenzylphthalate

3,3'-dichlorobenzidine

benzo(a)anthracene

chrysene

bis(2-ethylhexyl)phthalate

di-n-octylphthalate

benzo(b)fluoranthene

benzo(k)fluoranthene

benzo(a)pyrene

hexachlorobutadiene

indeno(1,2,3-cd)pyrene

dibenz(a,h)anthracene

benzo(g,h,i)perylene

bis(2-chloroethyl)ether

1,3-dichlorobenzene

1,4-dichlorobenzene

1,3-dichlorobenzene

2,2'-oxybis(1-chloropropane)

N-nitroso-di-n-propylamine

hexachloroethane

nitrobenzene

isophorone

bis(2-chloroethoxy)methane

1,2,4-trichlorobenzene

naphthalene

4-chloroaniline

hexachlorocyclopentadiene

2-chloronaphthalene

2-nitroaniline

dimethylphthalate

acenaphthylene

2,6-dinitrotoluene

3-nitroaniline

acenaphthene

2-methylnaphthalene

Acid (A) Fraction Surrogates:

phenol-d₅ (PHL)

2,4,6-tribromophenol

2-fluorophenol (2FP)

Acid (A) Fraction Target Compounds:

2,4-dinitrophenol

4-nitrophenol

4,6-dinitro-2-methylphenol

pentachlorophenol

phenol

2-chlorophenol

2-methylphenol

4-methylphenol

2-nitrophenol

2,4-dimethylphenol

2,4-dichlorophenol

4-chloro-3-methylphenol

2,4,6-trichlorophenol

2,4,5-trichlorophenol

E.2.2.8 Matrix Spikes/Matrix Spike Duplicates

A matrix Spike (MS) or matrix spike duplicate (MSD) is to be run for every 10 samples (one MS/MSD pair per 20 samples) and should be analyzed for all matrices present in every SDG. One soil/sediment sample and two aqueous samples were spiked with the standard MS/MSD solution to meet the frequency limits and control criteria listed on the following table.

TABLE E.7
SEMIVOLATILE ORGANIC MS/MSD CRITERIA

Compound	Water		Soil/Sediment	
	%R	RPD	%R	RPD
1,2,4-trichlorobenzene	52-115	28	44-142	50
1,4-dichlorobenzene	20-124	28	20-124	50
2,4-dinitrotoluene	39-139	38	39-139	50
2-chlorophenol	23-134	40	23-134	50
4-chloro-3-methylphenol	22-147	42	22-147	50
4-nitrophenol	3-132	50	3-139	50
acenaphthene	47-145	31	47-145	50
N-nitrosodipropylamine	2-230	38	2-230	50
pentachlorophenol	14-176	50	14-176	50
phenol	5-112	42	5-112	50
pyrene	52-115	31	52-115	50

All MS and MSD %R were within control limits except:

<u>Sample</u>	<u>Analyte</u>	<u>MS %R</u>	<u>MSD %R</u>	<u>RPD</u>
S6-MW01-GW2	1,2,4-trichlorobenzene	34.2	41	-
	2,4-dinitrotoluene	38.6	-	-
	acenaphthene	35.8	41.7	-
	pyrene	44.8	-	-
S2-MW01-GW2	phenol	-	38.5	64

- within acceptable control limits

Samples are not qualified based on MS/MSD results, alone, but in conjunction with the laboratory control sample (LCS). Since the laboratory control spike samples were within the quality control limits, the low recoveries noted above are judged to be sample matrix related and not due to difficulties in the laboratory procedures. No qualifications were applied since the low recoveries were not observed consistently between the MS and MSD implying the MS/MSD results may not be indicative of a low bias which may potentially affect other associated samples.

E.2.2.9 Laboratory Control Spikes/Laboratory Control Spike Duplicates

LCS/LCSDs are performed for every 10 samples analyzed to check the proficiency of the analysis. The data can determine if the MS/MSD is out of control, related to the system, or is a matrix effect. The LCS, in conjunction with the MS/MSD, is used to qualify data. All laboratory control spikes met the laboratory compliance criteria.

E.2.2.10 Internal Standards

Six internal standard (IS) compounds are used in SVOC analysis; each is associated with a group of analytes. The IS performance criteria ensures that GC/MS sensitivity and responses are stable during each analysis. The IS area counts must not vary more than a factor of two (-50% to + 100%) for the associated standard. The relative retention time of the IS must not vary more than ± 30 seconds from the relative retention time of the associated calibration standard. A review of raw data indicates that all internal standard met criteria.

E.2.2.11 Field Duplicates

Field duplicates are analyzed to determine the representativeness of the sampling procedure. Out of each duplicate pair, one is given a coded (false) identifier so that the laboratory results will not be biased. For aqueous samples, sample UANG-S2-MW03-GW2 is a field duplicate of UANG-S2-MW02-GW2 and sample UANG-S5-MW02-GW2 is a field duplicate of UANG-S5-MW01-GW2. Both duplicate pairs had no positive results. Sample UANG-BG-MW2(6-8) is a soil duplicate of UANG-B6MW2(4-6). Both samples had no positive results. No qualifications were made based on field duplicates.

E.2.3 TOTAL RECOVERABLE PETROLEUM HYDROCARBONS USING EPA METHOD 418.1

E.2.3.1 Introduction

The total recoverable petroleum hydrocarbons (TRPH) were analyzed using infrared (IR) spectroscopy. The concentrations were determined by direct comparison with standards. Twelve samples, including four soil and eight aqueous, were analyzed by USEPA Method 418.1. Quality data validation includes the assessment of technical holding times, calibrations, ICALs, CCALs, blanks, MS/MSDs, field duplicates and LCSs.

E.2.3.2 Technical Holding Time

The technical holding time for TRPH analysis is 28 days from the day of collection for water samples that are preserved and refrigerated. Holding times for water were not exceeded. No holding times are cited for soils. However, eight aqueous samples were not properly preserved. These samples were qualified "UJ" as estimated non-detects.

E.2.3.3 Initial Calibration

Instrument performance criteria are established to ensure that correct IR detection limits and wavelengths are set on the spectrophotometer. One calibration must be performed on the instrument every 24 hours or each time the instrument is set up. An ICAL curve is established using a series of six calibration standards of 80, 200, 400, 800, 2000 and 4000 µg/L. The resulting ICAL curve must have an r value greater than or equal to 0.995. All ICAL results met these requirements.

E.2.3.4 Continuing Calibration Verification

CCAL verification is performed after the ICAL at a frequency of one for every 10 samples. The CCAL %R must fall within the range of 85-115%. CCAL %Rs were within these limits for all samples.

E.2.3.5 Blanks

One laboratory method blank must be analyzed with every batch of 20 samples or at least one per day. Instrument blanks must be analyzed at a frequency of one for every 10 sample analyses and one after the last CCAL. Target analyte concentrations should not be found in any blank above the Contract Required Detection Limit (CRDL). No target analyte was detected in any of the laboratory blanks.

Field QC blanks were analyzed to verify that no contamination occurred during sampling. Two equipment rinseate blanks and two field blanks were analyzed for this fraction. No analyte contamination was detected.

E.2.3.6 Matrix Spike/Matrix Spike Duplicates

One MS or MSD must be included for every 10 samples (one MS/MSD pair per 20 samples) for each matrix analyzed. The MS %R results should fall in the range of 75-125% for both aqueous samples and soil samples for this fraction. The RPD results between the MS and MSD should be below 20%. One MS/MSD soil sample and one aqueous sample was associated with these samples. All matrix spike/matrix spike duplicate results met established criteria.

E.2.3.7 Laboratory Control Sample

Laboratory Control Samples (LCS) were run to monitor the overall performance of the analysis.

Qualifications of data are not made due to blank spike %R results alone. However, in conjunction with MS/MSD results, blank spikes are used to assess reproducibility and are used to qualify results only when the MS/MSD results are out of control limits. All LCS results were within the established criteria, (75.0 - 125%R).

E.2.3.8 Field Duplicates

Field duplicates are analyzed to determine the representativeness of the sampling procedures. One of each duplicate is given a coded (false) identifier so that the laboratory

will not bias the analytical results. Samples were not qualified due to duplicate results. One soil field duplicate was analyzed. All duplicate results were non-detect for TRPH.

E.2.4 PURGABLE HALOGENATED VOLATILE ORGANIC AND PURGABLE AROMATIC VOLATILE ORGANIC ANALYSES BY GC USING METHODS SW8010 AND SW8020

E.2.4.1 Introduction

Twenty-three field samples, (four soil samples and nineteen water samples), six trip blanks, two field blanks and three equipment rinseate blanks were analyzed for twenty-five target analytes, using Method SW8010 and nine target analytes using SW8020. Laboratory data was reviewed for technical holding times, ICALs, CCALs, laboratory blank and field blank contamination, surrogates, matrix spikes and matrix spike duplicates and laboratory control samples.

The following samples were re-sampled and re-analyzed due to positive detectable results in the original data but which had no second column confirmation performed in order to properly determine it's detection: UANG-S1-MW1-GW2, UANG-S1-MW2-GW2, UANG-S2-MW2-GW2, UANG-S2-MW1-GW2, UANG-S3-MW1-GW2 and associated field blanks UANG-RB2-GW2 and UANG-TB6-GW2.

E.2.4.2 Technical Holding Times

Holding times are measured from the time of sample collection to the time of analysis. The required holding times for EPA Methods 8010 and 8020, for both soil samples and water samples, is 14 days. All samples met the required holding times except:

<u>Sample</u>	<u>Date of Sampling</u>	<u>Date of Analysis</u>	<u>Affected Analyte</u>
UANG-S1-MW2-GW2	02-NOV-95	22-NOV-95	trichloroethene, tetrachloroethene, 1,2-dichloroethene
UANG-S2-MW2-GW2	02-NOV-95	22-NOV-95	trichloroethene, 1,2-dichloroethene
UANG-S2-MW1-GW2	02-NOV-95	22-NOV-95	trichloroethene, tetrachloroethene, 1,2-dichloroethene
UANG-S2-MW3-GW2	02-NOV-92	22-NOV-95	trichloroethene, 1,2-dichloroethene

The affected analytes had concentrations greater than the calibrated range. The samples were diluted and re-analyzed outside of the holding times for the affected analytes only. The results for these affected analytes noted above were qualified "J" as estimated values.

E.2.4.3 Initial Calibration

A five point initial calibration is performed for each compound at concentrations ranging from 0.50 µg/L to 50 µg/L. Linear regression method is used for sample quantitation. The linear regression correlation coefficient, (r), must be greater than or equal to 0.995. Twenty-nine results, affecting five samples, were qualified as estimated "U" or "UJ" due to an r value less than 0.995. In addition a qualification (estimated "J", "UJ") was applied if an analyte was being quantitated off a curve composed of less than five points. The analytical method requires a minimum of a five point calibration curve be analyzed.

An Initial Calibration Verification (ICV) standard was analyzed to verify the accuracy of the curve. The acceptance recovery range is 85%-115%. One or more analytes in each of the twenty-three field samples, six trip blanks, two field blanks and three rinse blanks required qualification due to ICV standard non-compliance affecting 139 results.

E.2.4.4 Continuing Calibration

A mid-range Continuing Calibration Verification (CCV) standard containing all the target compounds must be analyzed at the beginning of each 12-hour analysis or one per ten samples, whichever is more frequent. The CCAL was analyzed following the calibration of the instrument and prior to the analysis of any blanks or samples. The CCAL acceptance recovery range is 85%-115%. One or more analytes in each of the twenty-three field samples, six trip blanks, two field blanks and three rinse blanks required qualification due to CCV standard non-compliance, affecting 112 sample results.

E.2.4.5 Blanks

Blanks provide a measure of contamination that may have been introduced into a sample set during the field work, while samples were being collected or transported to the laboratory, or in the laboratory. If a blank is contaminated with a target compound at a concentration above the CRDL and the associated samples contain less than ten times the blank concentration of compounds considered to be common laboratory contaminants or less than five times the blank concentration for other target compounds, the analyte is qualified as undetected. However, if the detected analyte is greater than the CRDL yet below the action level for qualification employing the 5X or 10X rule, the result is reported non-detect "U" at the value observed. If a compound in a sample is greater than five or ten times the contamination of a compound found in an associated blank, no action was taken.

One laboratory method blank was analyzed for every ten samples and for each matrix type in every SDG. All laboratory method blanks were found to be free of analyte contamination except:

<u>Blank</u>	<u>Analyte</u>	<u>Conc.</u>	<u>Affected Samples</u>
PBLK-103470-1	chloromethane	2.9 µg/L	UANG-S1-MW1-GW2, UANG-S2-MW2-GW2, UANG-S2-MW3-GW2
	dichlorodifluoromethane	2.9 µg/L	
PBLK-103470-2	toluene	0.14 µg/L	None

Affected samples were qualified "U" as they contained less than five times the concentration found in the method blank.

Quality control field blanks analyzed for this fraction included equipment rinseate blanks, field blanks, and trip blanks. The following tables lists the field blanks and contamination found.

TABLE E.8
TRIP BLANK CONTAMINATION

<u>Analyte</u>	<u>CONCENTRATION (µg/L)</u>					
	<u>TB1</u>	<u>TB2</u>	<u>TB3</u>	<u>TB4</u>	<u>TB5</u>	<u>TB6</u>
1,2-dichloroethane	-	-	-	-	-	0.16
dichloromethane	0.71	-	-	-	-	0.92
trichloroethene	-	-	-	-	5.8	6.9
1,2-dichloroethane (total)	-	-	-	-	-	0.20
chlorobenzene	-	0.014	-	-	-	-

- no detectable level of analyte present

TABLE E.9
FIELD AND RINSE BLANK CONTAMINATION

Analyte	CONCENTRATION (µg/L)				
	RB1	RB2	RB3	FB2	FB3
benzene	-	0.12	-	-	-
toluene	-	1.3	-	-	-
o-xylene	-	0.23	-	-	-
1,4-dichlorobenzene	-	0.47	0.88	-	-
dichloromethane	0.78	-	-	-	-
toluene	2.0	-	2.7	0.083	-
chlorobenzene	-	-	-	0.13	-
bromodichloromethane	-	-	-	-	5.6
chloroform	-	-	-	-	20
trichloroethene	-	-	-	-	1.8
2-chloroethylvinylether	-	-	-	-	0.57
m/p xylene	-	-	0.29	-	-
styrene	-	-	2.8	-	-

- no detectable level of analyte present.

Samples were not affected by field blank contamination if they had non-detected results or results greater than five times (10 times for common lab contaminants) the contaminant concentration. The following is a list of samples affected by field blank contamination:

<u>Blank</u>	<u>Analyte</u>	<u>Conc.</u>	<u>Affected Samples</u>
TB02	chlorobenzene	0.14	UANG-S5-MW02-GW2, UANG-FB02-GW2
RB01	toluene	2.0	UANG-BGMW2(0-2)-GW2
TB5	trichloroethene	5.8	UANG-FB03-GW2
TB06	1,2-dichloroethane	0.16	UANG-S2-MW2-GW2 UANG-S2-MW3-GW2
	dichloromethane	0.92	UANG-S2-MW1-GW2
	trichloroethene	6.9	UANG-S1-MW1-GW2
RB02	benzene	0.12	UANG-S1-MW2-GW2, UANG-S3-MW1-GW2

The listed affected samples were qualified "U", as non-detect, as they contained less than five or ten times the blank value and were below the CRDL.

E.2.4.6 Surrogate Spikes

H-2,6-dichlorotoluene and H-chlorofluorobenzene were used as surrogates for method SW8010. Fluorobenzene, P-2,6-dichlorotoluene and P-chlorofluorobenzene were used as surrogates for Method SW8020. The QC limits were set by the laboratory and presented in the following table:

TABLE E.10
SURROGATE RECOVERY LIMITS

Compound	%R QC Limits	
	WATER	SOIL
H-2,6-dichlorotoluene	71.2-128%	46.1-142
H-chlorofluorobenzene	57.6-133%	39.1-139
fluorobenzene	85.6-119%	44.2-156
P-2,6-dichlorotoluene	88-123%	61.0-154
p-chlorofluorobenzene	81.5-113%	59.4-139

Samples were qualified, "J" or "UJ", if one or more surrogates for SW8010, or two or more surrogates for SW8020 were outside control limits. SW8010 compounds for 13 samples were qualified, and SW8020 compounds for one sample, (UANG-TB05-GW2) were qualified due to surrogate outliers.

E.2.4.7 Matrix Spike/Matrix Spike Duplicate

A matrix spike and matrix spike duplicate were run at a frequency of one pair per twenty samples. Data from MS/MSD are generated to determine the long term precision and accuracy of the analytical method for various matrices, and demonstrate acceptable compound recovery, by the laboratory, at the time of sample analysis. Qualification of field samples is not based on the results of the MS/MSD alone. The %R and RPD for the analytes used as the matrix spike compounds are presented in the following table:

TABLE E.11
DATA CHEM LABORATORY MS/MSD CRITERIA

COMPOUND	SOIL MS/MSD/RPD VALUES	WATER MS/MSD/RPD VALUES
benzene	0.744-192/12.7	79.2-106/6.34
ethyl benzene	36.6-147/16.3	81.6-116/5.97
chloroform	49.81-147/21.7	65.6-135/15.9
trichloroethene	31.3-136/15.6	47.1-132/16.1
tetrachloroethene	24.5-145/20.0	48.7-130/19.7
t-1,2-dichloroethene	50.7-111/23.3	49.3-122/16.2

Samples UANG-S6-MW01-GW2, UANG-S2-MW01-GW2, UANG-S1-MW1-GW2 and UANG-S3-MW1-GW2 were analyzed as water MS/MSDs. Sample UANG-BG-MW2(0-2)-GW2 was used as the soil MS/MSD. All MS/MSD QC compounds were compliant with established laboratory QC limits.

E.2.4.8 Laboratory Control Standard (LCS)

A LCS was run at a frequency of one for every ten samples. The LCS analysis serves as a monitor of the overall performance of all steps in the analysis, including sample preparation. It also serves as a control criteria to confirm matrix interferences. No action was taken based on LCS results, alone, but outliers are noted below. Data was only qualified as a result of the LCS if the MS/MSD %R is out of control. The %R, established by the laboratory, are presented on the following table:

TABLE E.12
DATA CHEM LABORATORY LCS CRITERIA

COMPOUND	SOIL LCS QC LIMITS	WATER LCS QC LIMITS
benzene	67.9-110	78.1-110
ethyl benzene	68.5-116	86.0-111
chloroform	57.8-137	71.4-127
tetrachloroethene	46.5-113	48.3-123
trichloroethene	43.4-114	60.0-111
t-1,2-dichloroethene	50.8-105	45.3-119

The following lists non-compliant LCS compounds:

<u>LCS ID</u>	<u>Analyte</u>	<u>LCS %R</u>	<u>Action/Affected Samples</u>
QC 997851	chloroform	67.2	None - MS/MSD compliant
	trans 1,2-dichloroethene	41.5	None - MS/MSD compliant
QC 98972	tetrachloroethene	114	None - MS/MSD compliant

E.2.4.9 Field Duplicates

Field duplicates are analyzed to determine the representativeness of the sampling procedure. Two aqueous sample pairs and one soil sample pair was analyzed as the field duplicate. UANG-S2-MW3-GW2 was a field duplicate of UANG-S2-MW2-GW2, UANG-S5-MW2-GW2 was a field duplicate of UANG-S5-MW1-GW2 and UANG-BGMW2(4-6) was a field duplicate of UANG-BGMW2(6-8). Analyte percent comparisons between the primary and duplicate samples were reviewed. All compounds were within $\pm 20\%$ RPD for water duplicate pairs. All soil results were non-detect. Samples were not qualified due to duplicate results for either matrix.

E.2.4.10 Additional Comments

Several samples were qualified "J" due to a positive analytical response not being verified on the confirmation analysis. The following lists the sample and associated analytes:

<u>Sample</u>	<u>Analyte</u>
UANG-RB2-GW2	toluene
UANG-S2-MW1-GW2	1,2-dichlorobenzene, 1,1-dichloroethane trans 1,3-dichloropropene
UANG-S1-MW2-GW2	1,2-dichloroethane
UANG-S3-MW1-GW2	1,2-dichlorobenzene 1,3-dichlorobenzene 1,4-dichlorobenzene

1,2-dichloroethene was reported as total and not split into the project requested cis-1,2-dichloroethene and trans 1,2-dichloroethene. The standard curve used the total compound response to quantitate data for 1,2-dichloroethene for the following samples: UANG-S1-MW01-GW2, UANG-S2-MW02-GW2, UANG-S2-MW01-GW2, UANG-S2-MW03-GW2, UANG-TB06-GW2. No further qualifications, beyond those previously mentioned were applied.

During the analytical process certain compounds exhibited a condition known as coeluting, whereby two or more compounds would combine to display one analytical peak. Samples which had a positive result and coeluting analytes, neither of which were confirmed by a second source, were re-sampled (refer to Section E.2.4.1). Compounds with a positive value, greater than the MDL but less than the CRDL which were also coelutions were flagged "J" as estimated values. No action was taken for coeluting analytes which were non-detected.

E.2.5 PESTICIDES AND PCB ANALYSIS USING EPA METHOD SW8080

E.2.5.1 Introduction

EPA Method SW8080 was used to analyze for pesticides and PCBs using dual column capillary gas chromatography with electron capture detectors. A total of 12 samples were analyzed for 26 compounds, including four soil samples, four aqueous samples, two field blanks and two rinse blanks. Detected pesticide levels must be confirmed by analyzing the sample extracts on a second dissimilar column, however, no detectable PCB or Pesticide levels were found in any sample.

Soil samples were extracted using SW3550. Water samples were extracted using SW3510. Quality Control assessment of pesticides and PCBs included evaluation of technical holding times, Instrument Calibrations, ICALs, CCALs, method blanks, surrogate spike compounds, MS/MSD and LCSs. Instrument performance checks and pesticide clean-up check QC are not required deliverables for this project, and were not received.

E.2.5.2 Technical Holding Times

Technical holding times for pesticides and PCB analyses are seven days from sample collection to extraction for water samples, and 14 days from collection to extraction for soil/sediment samples. The maximum holding time between extraction and analysis is 40 days for both matrices. All samples met holding times.

E.2.5.3 Initial Calibration

Gas chromatograph (GC) calibration is established by injecting standard mixtures. These mixtures contain all the single component pesticides, PCBs (arochlors) and surrogates, at a minimum of five concentrations for each parameter of interest, and for each GC column used. Standards were prepared in concentrations of 2,5,10,50,10 and 200 µg/L. A criterion of greater than or equal to 0.995 was used for the *r* value, (correlation coefficient) of the initial calibration curve. This criterion was met during the initial calibration for all single component analytes. However, only one point calibration was performed for the multicomponent analytes toxaphene, chlordane and the arochlors. The results of these multicomponent analytes in the associated samples were considered estimated and flagged "UJ".

E.2.5.4 Continuing Calibration

An instrument blank and a standard at a 50 µg/L or 100 µg/L concentration are analyzed to bracket the front end of a 12-hour period during which samples are analyzed. The QC limits of %D between the calculated amount and the true amount of each of the pesticides and surrogates is ±15%.

One pesticide compound had a %D greater than the QC limits (endrin 82.2% D) on one of the two columns for which it was analyzed. This resulted in the qualification of sample UANG-BG-MW2(6-8) as estimated, "UJ".

E.2.5.5 Blanks

A method blank analysis must be performed for every 10 samples for each matrix type in every SDG. If concentrations of analytes in field samples are less than five times the contaminant concentration in the associated laboratory blanks, the results are qualified as "U". Contamination was not detected in any of the laboratory blanks for any analytes.

Field QC blanks are analyzed to verify that no contamination occurred during sampling. Field QC blanks analyzed for this fraction are equipment rinseate blanks and field blanks and qualify data using the same criteria as laboratory blanks. No analytes were detected in any field or rinse blank.

E.2.5.6 Surrogate Spike Compounds

Two surrogate spikes, tetrachloro-m-xylene (TCX) and dibutylchlorodate (DBC) are added to all samples to measure their recovery in sample and blank matrices. The laboratory limits for %R of the surrogates TCX and DBC are as follows:

**TABLE E.13
PESTICIDE/PCB SURROGATE RECOVERIES**

Surrogate	%R Water	%R Soil
tetrachloro-m-xylene	39-137	58.7-119
dibutylchlorodate	28.3-180	31.6-161

The surrogate recoveries in all samples met the QC limits.

E.2.5.7 Laboratory Control Samples (LCS)

LCS analysis serves as a monitor of the overall performance of all steps in the analysis, including the sample preparation. It also serves as a control to confirm matrix interferences in the instance where the MS/MSD are not within established control limits. The LCSs are used in conjunction with the additional QC samples analyzed to evaluate precision and accuracy. Four LCSs were prepared for the aqueous samples, and one for the soil sample. The %R criteria established by the laboratory are:

TABLE E.14

LCS/LCSD REQUIREMENTS FOR PESTICIDE ANALYSIS

Compound	Aqueous %R	Soils %R
aldrin	65.4-132	75-136
4,4'-DDT	55.7-113	57.8-141
dieldrin	67.9-138	71.2-145
endrin	79-153	77.7-166
heptachlor	64.5-143	66.7-145
lindane	70.9-133	68.6-133

All LCS samples were within the control criteria except endrin for QC-98977-1 (78.6%R). Professional judgment deemed that no action was required because MS/MSD endrin results for this batch were within accepted criteria and the recovery reported was less than 1% below the QC limit.

E.2.5.8 Matrix Spikes/Matrix Spike Duplicates

Data from MS/MSDs are generated to determine the long term precision and accuracy of the analytical method for various matrices, and to demonstrate acceptable compound recovery by the laboratory at the time of sample analysis. The MS/MSDs are used in conjunction with information or other deficiencies to evaluate precision and accuracy. One MS or MSD was run for each 10 samples (one MS/MSD pair per 20 samples). One soil sample and one water sample were analyzed as the MS/MSD pair. The %R and RPD criteria is presented below:

TABLE E.15

MS/MSD CRITERIA FOR PESTICIDE ANALYSIS

Compound	Water %R/RPD	Soil %R/RPD
aldrin	21.8-154/15/6	53.2-135/13.1
4,4'-DDT	17.9-128/16	25/160/34
dieldrin	39.5-159/12.8	38.6-158/13.5
endrin	60.5-173/14.2	45.7-192/17.7
heptachlor	34.5-160/13.5	53.3-145/13.7
lindane	60.4-134/12.7	48.7-139/13.7

UANG-RB03-GW2 was used as the aqueous MS/MSD. This rinse blank was labeled SXS 1314 by the lab, and may not have been identified to the lab as a field blank. All MS/MSD recoveries were within the specified QC limits. Yet the objective of the MS/MSD analysis is to determine both precision and accuracy of the laboratory based on the specific sample matrix which was not met in this case. It should be noted since a non-investigative sample was selected, the results do not provide the site specific matrix information, therefore the MS/MSD results cannot be used to judge the associated water samples. No qualifications were applied.

UANG-BG-MW2(0-2) was used as the soil MS/MSD. All analyte recoveries were within the specified QC limits.

E.2.5.9 Coded Field Duplicates

Field duplicates are analyzed to determine the representativeness of the sampling procedures. One of each duplicate pair is given a coded (false) identifier so that the laboratory will not bias the analytical results. One field duplicate pair was analyzed with this fraction, UANG-BGMW2(6-8) is a soil duplicate of UANG-BE-MW2(4-6). No analytes were found at detectable levels. Samples were not qualified based on field duplicate results.

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-RB03-GW2			UANG-S2-MW02-GW2			UANG-S2-MW03-GW2			UANG-S2-MW01-GW2		
LAB ID	SXS 01314			SXS 01315			SXS 01316			SXS 01317		
DATE COLLECTED	28-Aug-95			28-Aug-95			28-Aug-95			28-Aug-95		
SAMPLE MATRIX	Water			Water			Water			Water		
SEMI-VOLATILE	CONCENTRATION			CONCENTRATION			CONCENTRATION			CONCENTRATION		
COMPOUNDS 8270	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C
2,4-Dinitrophenol	50	UJ	B	50	UJ	B	50	UJ	B	50	UJ	B
Di-n-butyl-phthalate	—			10	U	E	10	U	E	10	U	E
TPH	100	UJ	I	—			—			—		
VOLATILE												
COMPOUNDS 8010/8020												
1,1,1,2-Tetrachloroethane	0.50	UJ	J	—			—			—		
1,1,2,2-Tetrachloroethane	0.50	UJ	J	—			—			—		
1,1,2-Trichloroethane	0.50	UJ	J	—			—			—		
1,1-Dichloroethane	0.50	UJ	J	—			—			—		
1,1-Dichloroethene	0.50	UJ	C,J	—			—			—		
1,2-Dichloroethane	0.50	UJ	J,L	—			—			—		
1,2-Dichloropropane	0.50	UJ	J	—			—			—		
2-Chloroethyl Vinyl Ether	0.50	UJ	B,J	—			—			—		
Bromodichloromethane	0.50	UJ	J	—			—			—		
Bromoform	0.50	UJ	J	—			—			—		
Bromomethane	2.0	UJ	B,C,J,L	—			—			—		
Carbon Tetrachloride	0.50	UJ	J	—			—			—		
Chloroethane	0.50	UJ	J	—			—			—		
Chloroform	0.50	UJ	J	—			—			—		
Chloromethane	0.50	UJ	,C,J,L,	—			—			—		
Cis-1,2-Dichloroethene	0.50	UJ	J	—			—			—		
Dibromochloromethane	0.50	UJ	J	—			—			—		
Dichlorodifluoromethane	0.50	UJ	,C,J,L,	—			—			—		
Dichloromethane	0.50	UJ	J	—			—			—		
M-xylene + P-xylene	0.29	J	A,J,M	—			—			—		
Tetrachloroethene	0.50	UJ	J	—			—			—		
Trans-1,2-Dichloroethene	0.50	UJ	J	—			—			—		
Trans-1,3-Dichloropropene	0.50	UJ	J	—			—			—		
Trichloroethene	0.50	UJ	C,J	—			—			—		
Trichlorofluoromethane	0.50	UJ	J	—			—			—		
Vinyl Chloride	0.50	UJ	B,C,J,L	—			—			—		
METALS												
Arsenic	2.0	UJ	H	—			6.9	J	H	—		
Chromium	—			4.4	U	P	3.8	U	P	5.1	U	P
Lead	1.4	UJ	E,H	3.5	UJ	D,E,F,H	3.9	UJ	D,E,F,H	4.8	UJ	D,E,F,H
Mercury	0.02	UJ	E	0.049	J	E	0.056	J	E	0.02	UJ	E
Selenium	16	J	A,H	12	UJ	H	—			12	UJ	H
Thallium	1.2	UJ	H	1.2	UJ	D,F	1.2	UJ	D,F,H	1.2	UJ	D,F,H
Zinc	15	U	E,P	13	U	E,P	8.9	U	E,P	22	U	P
PESTICIDES/PCBs												
Aroclor 1016	1.0	UJ	B	—			—			—		
Aroclor 1221	1.0	UJ	B	—			—			—		
Aroclor 1232	1.0	UJ	B	—			—			—		
Aroclor 1242	1.0	UJ	B	—			—			—		
Aroclor 1248	1.0	UJ	B	—			—			—		
Aroclor 1254	1.0	UJ	B	—			—			—		
Aroclor 1260	1.0	UJ	B	—			—			—		
Chlordane	0.10	UJ	B	—			—			—		
Toxaphene	2.0	UJ	B	—			—			—		

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-BG-MW01-GW2			UANG-FB03-GW2			UANG-TB05-GW2		
LAB ID	SXS 01318			SXS 01319			SXS 01320		
DATE COLLECTED	28-Aug-95			28-Aug-95			28-Aug-95		
SAMPLE MATRIX	Water			Water			Water		
SEMI-VOLATILE	CONCENTRATION			CONCENTRATION			CONCENTRATION		
COMPOUNDS 8270	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C
2,4-Dinitrophenol	50	UJ	B	50	UJ	B	---		
Di-n-butyl-phthalate	---			10	U	E	---		
TPH	100	UJ	I	100	UJ	I	---		
VOLATILE									
COMPOUNDS 8010/8020									
1,1,1,2-Tetrachloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
1,1,2,2-Tetrachloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
1,1,2-Trichloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
1,1-Dichloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
1,1-Dichloroethene	0.50	UJ	C,J	0.50	UJ	C,J	0.50	UJ	C,J
1,2-Dichlorobenzene	---			---			0.50	UJ	J
1,2-Dichloroethane	0.50	UJ	J,L	0.50	UJ	J,L	0.50	UJ	J,L
1,2-Dichloropropane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
1,3-Dichlorobenzene	---			---			0.50	UJ	J
1,4-Dichlorobenzene	---			---			0.50	UJ	J
2-Chloroethyl Vinyl Ether	0.50	UJ	B,J	0.57	UJ	B,J	0.50	UJ	B,J
Benzene	---			---			0.50	UJ	J
Bromodichloromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Bromoform	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Bromomethane	2.0	UJ	B,C,J,L	2.0	UJ	B,C,J,L	2.0	UJ	B,C,J,L
Carbon Tetrachloride	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Chlorobenzene	---			---			0.50	UJ	J
Chloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Chloroform	0.50	UJ	J	20	J	J	0.50	UJ	J
Chloromethane	0.50	UJ	,C,J,L	0.50	UJ	,C,J,L	0.50	UJ	,C,J,L,Q
Cis-1,2-Dichloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Dibromochloromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Dichlorodifluoromethane	0.50	UJ	,C,J,L	0.50	UJ	,C,J,L	0.50	UJ	,C,J,L,Q
Dichloromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Ethyl benzene	---			---			0.50	UJ	J
M-xylene + P-xylene	---			---			---		
O-xylene	---			---			0.50	UJ	J
Styrene	---			---			0.50	UJ	J
Tetrachloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Toluene	---			---			0.50	UJ	J
Trans-1,2-Dichloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Trans-1,3-Dichloropropene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Trichloroethene	0.50	UJ	J	1.8	U	P	5.8	J	J
Trichlorofluoromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J
Vinyl Chloride	0.50	UJ	B,C,J,L	0.50	UJ	B,C,J,L	0.50	UJ	B,C,J,L
METALS									
Antimony	---			33	U	O	---		
Arsenic	---			2.0	UJ	H	---		
Chromium	5.0	U	P	---			---		
Lead	4.8	UJ	D,E,F	2.1	UJ	E,H	---		
Mercury	0.024	J	E	0.02	UJ	E	---		
Selenium	12	UJ	H	12	J	H	---		
Thallium	1.2	UJ	D,F,H	1.2	UJ	H	---		
Zinc	4.1	U	E,P	---			---		
PESTICIDES/PCBs									
Aroclor 1016	1.0	UJ	B	1.0	UJ	B	---		
Aroclor 1221	1.0	UJ	B	1.0	UJ	B	---		
Aroclor 1232	1.0	UJ	B	1.0	UJ	B	---		
Aroclor 1242	1.0	UJ	B	1.0	UJ	B	---		
Aroclor 1248	1.0	UJ	B	1.0	UJ	B	---		
Aroclor 1254	1.0	UJ	B	1.0	UJ	B	---		
Aroclor 1260	1.0	UJ	B	1.0	UJ	B	---		
Chlordane	0.10	UJ	B	0.10	UJ	B	---		
Toxaphene	2.0	UJ	B	2.0	UJ	B	---		

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-RB1-GW2			UANG-BG-MW2 (0-2)			UANG-BG-MW2 (2-4)			UANG-BG-MW2 (4-6)		
LAB ID	SXS 01260			SXS 01256			SXS 01257			SXS 01258		
DATE COLLECTED	16-Aug-95			16-Aug-95			16-Aug-95			16-Aug-95		
SAMPLE MATRIX	Water			Soil			Soil			Soil		
SEMI-VOLATILE	CONCENTRATION			CONCENTRATION			CONCENTRATION			CONCENTRATION		
COMPOUNDS 8270	(ug/l)	Q	C	(ug/kg)	Q	C	(ug/kg)	Q	C	(ug/kg)	Q	C
2-Nitroaniline	50	UJ	C	3300	UJ	C	3300	UJ	C	3300	UJ	C
3-Nitroaniline	50	UJ	C	---			---			---		
4-Nitroaniline	50	UJ	C	---			---			---		
4-Nitrophenol	50	UJ	C	---			---			---		
Benzoic acid	50	UJ	B,C	3300	UJ	B	3300	UJ	B	3300	UJ	B
Bis(2-chloroethyl)ether	10	UJ	C	---			---			---		
Bis(2-chloroisopropyl)ether	10	UJ	C	660	UJ	C	660	UJ	C	660	UJ	C
N-nitroso-di-n-propylamine	10	UJ	C	---			---			---		
TPH	100	UJ	I	---			---			---		
VOLATILE												
COMPOUNDS 8010/8020												
1,1,1,2-Tetrachloroethane	---			0.62	UJ	J	---			---		
1,1,1-Trichloroethane	---			0.62	UJ	J	---			---		
1,1,2,2-Tetrachloroethane	0.50	UJ	B,C,L	0.62	UJ	B,C,J,L	0.60	UJ	B,C,L	0.61	UJ	B,C,L
1,1,2-Trichloroethane	---			0.62	UJ	J	---			---		
1,1-Dichloroethane	---			0.62	UJ	J	---			---		
1,1-Dichloroethene	---			0.62	UJ	J	---			---		
1,2-Dichloroethane	---			0.62	UJ	J	---			---		
1,2-Dichloropropane	---			0.62	UJ	J	---			---		
1,3-Dichlorobenzene	---			0.62	UJ	J	---			---		
2-Chloroethyl Vinyl Ether	0.50	UJ	B	0.62	UJ	B,J	0.60	UJ	B	0.61	UJ	B
Bromodichloromethane	---			0.62	UJ	J	---			---		
Bromoform	---			0.62	UJ	J	---			---		
Bromomethane	2.0	UJ	C,L	2.5	UJ	C,J,L	2.4	UJ	C,L	2.4	UJ	C,L
Carbon Tetrachloride	---			0.62	UJ	J	---			---		
Chloroethane	0.50	UJ	B,L	0.62	UJ	B,J,L	0.60	UJ	B,L	0.61	UJ	B,L
Chloroform	---			0.62	UJ	J	---			---		
Chloromethane	0.50	UJ	B,C,L	0.62	UJ	B,C,J,L	0.60	UJ	B,C,L	0.61	UJ	B,C,L
Cis-1,2-Dichloroethene	---			0.62	UJ	J	---			---		
Dibromochloromethane	---			0.62	UJ	J	---			---		
Dichlorodifluoromethane	0.50	UJ	B,C,L	0.62	UJ	B,C,J,L	0.60	UJ	B,C,L	0.61	UJ	B,C,L
Dichloromethane	---			0.62	UJ	J	---			---		
Tetrachloroethene	0.50	UJ	C	0.62	UJ	C,J	0.60	UJ	C	0.61	UJ	C
Toluene	---			0.62	UJ	J,P	---			---		
Trans-1,2-Dichloroethene	---			0.62	UJ	J	---			---		
Trans-1,3-Dichloropropene	---			0.62	UJ	J	---			---		
Trichloroethene	---			0.62	UJ	J	---			---		
Trichlorofluoromethane	0.50	UJ	B,C	0.62	UJ	B,C,J	0.60	UJ	B,C	0.61	UJ	B,C
Vinyl Chloride	0.50	UJ	B,C,L	0.62	UJ	B,C,J,L	0.60	UJ	B,C,L	0.61	UJ	B,C,L
METALS												
Arsenic	2.0	UJ	H	4100	J	D,F	3700	J	D,F	11000	J	D,F
Cadmium	0.97	UJ	E	---			---			---		
Chromium	---			14000	U	P	11000	U	P	12000	U	P
Copper	3.1	U	E,O	21000	J	G	21000	J	G	26000	J	G
Lead	---			14000	J	D	9800	J	D	11000	J	D
Mercury	0.019	UJ	E,O	---			---			---		
Nickel	---			9500	U	P	6900	U	P	8900	U	P
Selenium	---			---			---			---		
Thallium	---			310	J	A	200	J	A	210	J	A
PESTICIDES/PCBs												
Aroclor 1016	1.0	UJ	B	41	UJ	B	39	UJ	B	41	UJ	B
Aroclor 1221	1.0	UJ	B	83	UJ	B	80	UJ	B	83	UJ	B
Aroclor 1232	1.0	UJ	B	41	UJ	B	39	UJ	B	41	UJ	B
Aroclor 1242	1.0	UJ	B	41	UJ	B	39	UJ	B	41	UJ	B
Aroclor 1248	1.0	UJ	B	41	UJ	B	39	UJ	B	41	UJ	B
Aroclor 1254	1.0	UJ	B	41	UJ	B	39	UJ	B	41	UJ	B
Aroclor 1260	1.0	UJ	B	41	UJ	B	39	UJ	B	41	UJ	B
Chlordane	0.10	UJ	B	21	UJ	B	20	UJ	B	21	UJ	B
Toxaphene	2.0	UJ	B	210	UJ	B	200	UJ	B	210	UJ	B

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-BG-MW2 (6-8)			UANG-TB1-GW2		
LAB ID	SXS 01259			SXS 01261		
DATE COLLECTED	16-Aug-95			16-Aug-95		
SAMPLE MATRIX	Soil			Soil		
SEMI-VOLATILE COMPOUNDS 8270	CONCENTRATION (ug/kg)	Q	C	CONCENTRATION (ug/l)	Q	C
2-Nitroaniline	3300	UJ	C	---		
Benzoic acid	3300	UJ	B	---		
Bis(2-chloroisopropyl)ether	660	UJ	C	---		
VOLATILE COMPOUNDS 8010/8020						
1,1,2,2-Tetrachloroethane	0.62	UJ	B,C,L	0.50	UJ	B,C,L
2-Chloroethyl Vinyl Ether	0.62	UJ	B	0.50	UJ	B
Bromomethane	2.5	UJ	C,L	2.0	UJ	C,L
Chloroethane	0.62	UJ	B,L	0.50	UJ	B,L
Chloromethane	0.62	UJ	B,C,L	0.50	UJ	B,C,L
Dichlorodifluoromethane	0.62	UJ	B,C,L	0.50	UJ	B,C,L
Tetrachloroethene	0.62	UJ	C	0.50	UJ	C
Trichlorofluoromethane	0.62	UJ	B,C	0.50	UJ	B,C
Vinyl Chloride	0.62	UJ	B,C,L	0.50	UJ	B,C,L
METALS						
Antimony	---			---		
Arsenic	8400	J	D,F	---		
Cadmium	---			---		
Chromium	12000	U	P	---		
Copper	26000	J	G	---		
Lead	9800	J	D	---		
Mercury	---			---		
Nickel	7500	U	P	---		
Selenium	---			---		
Thallium	---			---		
PESTICIDES/PCBs						
Aroclor 1016	41	UJ	B	---		
Aroclor 1221	83	UJ	B	---		
Aroclor 1232	41	UJ	B	---		
Aroclor 1242	41	UJ	B	---		
Aroclor 1248	41	UJ	B	---		
Aroclor 1254	41	UJ	B	---		
Aroclor 1260	41	UJ	B	---		
Chlordane	21	UJ	B	---		
Endrin	21	UJ	C	---		
Toxaphene	210	UJ	B	---		

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID LAB ID DATE COLLECTED SAMPLE MATRIX	UANG-S7-MW02-GW2 SXS 01262 22-Aug-95 Water			UANG-S7-MW01-GW2 SXS 01263 22-Aug-95 Water			UANG-S4-MW01-GW2 SXS 01264 22-Aug-95 Water			UANG-S5-MW01-GW2 SXS 01265 22-Aug-95 Water		
SEMI-VOLATILE COMPOUNDS 8270	CONCENTRATION (ug/l) Q C			CONCENTRATION (ug/l) Q C			CONCENTRATION (ug/l) Q C			CONCENTRATION (ug/l) Q C		
2-Nitroaniline	50	UJ	C	50	UJ	C	50	UJ	C	50	UJ	C
3-Nitroaniline	50	UJ	C	50	UJ	C	50	UJ	C	50	UJ	C
4-Nitroaniline	50	UJ	C	50	UJ	C	50	UJ	C	50	UJ	C
4-Nitrophenol	50	UJ	C	50	UJ	C	50	UJ	C	50	UJ	C
Benzoic acid	50	UJ	B,C	50	UJ	B,C	50	UJ	B,C	50	UJ	B,C
Bis(2-chloroethyl)ether	10	UJ	C	10	UJ	C	10	UJ	C	10	UJ	C
Bis(2-chloroisopropyl)ether	10	UJ	C	10	UJ	C	10	UJ	C	10	UJ	C
N-nitroso-di-n-propylamine	10	UJ	C	10	UJ	C	10	UJ	C	10	UJ	C
TPH	100	UJ	I	100	UJ	I	---			---		
VOLATILE COMPOUNDS 8010/8020												
1,1,1,2-Tetrachloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
1,1,1-Trichloroethane	0.50	UJ	B,J	0.50	UJ	B,J	0.50	UJ	B,J	0.50	UJ	B
1,1,2,2-Tetrachloroethane	1.0	UJ	J	1.0	UJ	J	1.0	UJ	J	---		
1,1,2-Trichloroethane	0.50	UJ	C,J	0.50	UJ	C,J	0.50	UJ	C,J	0.50	UJ	C
1,1-Dichloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
1,1-Dichloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
1,2-Dichloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
1,2-Dichloropropane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
1,3-Dichlorobenzene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
2-Chloroethyl Vinyl Ether	0.50	UJ	B,J	0.50	UJ	B,J	0.50	UJ	B,J	0.50	UJ	B
Bromodichloromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Bromoform	0.50	UJ	C,J	0.50	UJ	C,J	0.50	UJ	C,J	0.50	UJ	C
Bromomethane	2.0	UJ	B,J	2.0	UJ	B,J	2.0	UJ	B,J	2.0	UJ	B
Carbon Tetrachloride	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Chloroethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Chloroform	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Chloromethane	1.0	UJ	J	1.0	UJ	J	1.0	UJ	J	---		
Cis-1,2-Dichloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Dibromochloromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Dichlorodifluoromethane	1.0	UJ	J	1.0	UJ	J	1.0	UJ	J	---		
Dichloromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Tetrachloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Trans-1,2-Dichloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Trans-1,3-Dichloropropene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Trichloroethene	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Trichlorofluoromethane	0.50	UJ	J	0.50	UJ	J	0.50	UJ	J	---		
Vinyl Chloride	0.50	UJ	B,J	0.50	UJ	B,J	0.50	UJ	B,J	0.50	UJ	B
METALS												
Antimony	---			---			44	U	O	---		
Arsenic	---			---			---			2.0	UJ	H
Lead	1.80	UJ	D,E,F	0.88	UJ	D,F	1.5	UJ	D,E,F	---		
Mercury	0.02	UJ	E	0.038	J	E	0.02	UJ	E	---		
Thallium	1.2	UJ	D,F	1.2	UJ	D,F	1.2	UJ	D,F	---		
Zinc	6.8	U	E	---			---			---		

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID LAB ID DATE COLLECTED SAMPLE MATRIX	UANG-FB02-GW2 SXS 01267 22-Aug-95 Water			UANG-S5-MW02-GW2 SXS 01268 22-Aug-95 Water			UANG-TB02-GW2 SXS 01266 22-Aug-95 Water		
SEMI-VOLATILE COMPOUNDS 8270	CONCENTRATION (ug/l) Q C			CONCENTRATION (ug/l) Q C			CONCENTRATION (ug/l) Q C		
2-Nitroaniline	50	UJ	C	50	UJ	C	---		
3-Nitroaniline	50	UJ	C	50	UJ	C	---		
4-Nitroaniline	50	UJ	C	50	UJ	C	---		
4-Nitrophenol	50	UJ	C	50	UJ	C	---		
Benzoic acid	50	UJ	B,C	50	UJ	B,C	---		
Bis(2-chloroethyl)ether	10	UJ	C	10	UJ	C	---		
Bis(2-chloroisopropyl)ether	10	UJ	C	10	UJ	C	---		
N-nitroso-di-n-propylamine	10	UJ	C	10	UJ	C	---		
TPH	100	UJ	I	---			---		
VOLATILE COMPOUNDS 8010/8020									
1,1,1,2-Tetrachloroethane	---			0.50	UJ	J	---		
1,1,1-Trichloroethane	0.50	UJ	B	0.50	UJ	B,J	0.50	UJ	B
1,1,2,2-Tetrachloroethane	---			1.0	UJ	J	---		
1,1,2-Trichloroethane	0.50	UJ	C	0.50	UJ	C,J	0.50	UJ	C
1,1-Dichloroethane	---			0.50	UJ	J	---		
1,1-Dichloroethene	---			0.50	UJ	J	---		
1,2-Dichloroethane	---			0.50	UJ	J	---		
1,2-Dichloropropane	---			0.50	UJ	J	---		
1,3-Dichlorobenzene	---			0.50	UJ	J	---		
2-Chloroethyl Vinyl Ether	0.50	UJ	B	0.50	UJ	B,J	0.50	UJ	B
Bromodichloromethane	---			0.50	UJ	J	---		
Bromoform	0.50	UJ	C	0.50	UJ	C,J	0.50	UJ	C
Bromomethane	2.0	UJ	B	2.0	UJ	B,J	2.0	UJ	B
Carbon Tetrachloride	---			0.50	UJ	J	---		
Chlorobenzene	0.50	UJ	P	0.50	UJ	J,P	---		
Chloroethane	---			0.50	UJ	J	---		
Chloroform	---			0.50	UJ	J	---		
Chloromethane	---			1.0	UJ	J	---		
Cis-1,2-Dichloroethene	---			0.50	UJ	J	---		
Dibromochloromethane	---			0.50	UJ	J	---		
Dichlorodifluoromethane	---			1.0	UJ	J	---		
Dichloromethane	---			0.50	UJ	J	---		
Tetrachloroethene	---			0.50	UJ	J	---		
Trans-1,2-Dichloroethene	---			0.50	UJ	J	---		
Trans-1,3-Dichloropropene	---			0.50	UJ	J	---		
Trichloroethene	---			0.50	UJ	J	---		
Trichlorofluoromethane	---			0.50	UJ	J	---		
Vinyl Chloride	0.50	UJ	B	0.50	UJ	B,J	0.50	UJ	B
METALS									
Arsenic	2.0	UJ	H	6.6	J	H	---		
Mercury	0.02	UJ	E	---			---		
Zinc	5.3	U	E	---			---		
PESTICIDES/PCBs									
Aroclor 1016	1.0	UJ	B	---			---		
Aroclor 1221	1.0	UJ	B	---			---		
Aroclor 1232	1.0	UJ	B	---			---		
Aroclor 1242	1.0	UJ	B	---			---		
Aroclor 1248	1.0	UJ	B	---			---		
Aroclor 1254	1.0	UJ	B	---			---		
Aroclor 1260	1.0	UJ	B	---			---		
Chlordane	0.10	UJ	B	---			---		
Toxaphene	2.0	UJ	B	---			---		

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-S3-MW01-GW2			UANG-S3-MW02-GW2			UANG-BG-MW02-GW2		
LAB ID	SXS 01277			SXS 01278			SXS 01279		
DATE COLLECTED	25-Aug-95			25-Aug-95			25-Aug-95		
SAMPLE MATRIX	Water			Water			Water		
SEMI-VOLATILE COMPOUNDS 8270	CONCENTRATION			CONCENTRATION			CONCENTRATION		
	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C
1,4-Dichlorobenzene	3.3	J	A	—			—		
2,4-Dinitrophenol	50	UJ	B,C	50	UJ	B,C	50	UJ	B,C
4,6-Dinitro-2-methyl phenol	50	UJ	C	50	UJ	C	50	UJ	C
Benzoic acid	50	UJ	C	50	UJ	C	50	UJ	C
Di-n-butylphthalate	10	U	E	10	U	E	10	U	E
TPH	—			—			100	UJ	I
VOLATILE COMPOUNDS 8010/8020									
1,1,1-Trichloroethane	—			0.50	UJ	B	0.50	UJ	B
1,1,2-Trichloroethane	—			0.50	UJ	C	0.50	UJ	C
2-Chloroethyl Vinyl Ether	—			0.50	UJ	B	0.50	UJ	B
Bromoform	—			0.50	UJ	C	0.50	UJ	C
Bromomethane	—			2.0	UJ	B	2.0	UJ	B
Vinyl Chloride	—			0.50	UJ	B	0.50	UJ	B
METALS									
Antimony	—			—			60	UJ	D,F
Arsenic	7.1	J	H	5.3	J	H	2.0	UJ	F,H
Beryllium	—			—			0.63	UJ	F
Cadmium	—			—			0.97	UJ	E,F
Chromium	—			—			3.6	UJ	F
Copper	—			—			12	UJ	E,F,O
Lead	—			—			4.4	UJ	D,F
Mercury	—			—			0.02	UJ	E,F,O
Nickel	—			—			11	UJ	F
Selenium	—			—			60	UJ	F,H
Silver	—			—			5.5	UJ	F
Thallium	—			—			1.2	UJ	D,F
Zinc	—			—			3.6	UJ	F
PESTICIDES/PCBs									
Aroclor 1016	—			—			1.0	UJ	B
Aroclor 1221	—			—			1.0	UJ	B
Aroclor 1232	—			—			1.0	UJ	B
Aroclor 1242	—			—			1.0	UJ	B
Aroclor 1248	—			—			1.0	UJ	B
Aroclor 1254	—			—			1.0	UJ	B
Aroclor 1260	—			—			1.0	UJ	B
Chlordane	—			—			0.10	UJ	B
Toxaphene	—			—			2.0	UJ	B

FIELD ID	UANG-TB04-GW2		
LAB ID	SXS 01282		
DATE COLLECTED	25-Aug-95		
SAMPLE MATRIX	Water		
VOLATILE COMPOUNDS 8010/8020	CONCENTRATION		
	(ug/l)	Q	C
1,1,1-Trichloroethane	0.50	UJ	B
1,1,2-Trichloroethane	0.50	UJ	C
2-Chloroethyl Vinyl Ether	0.50	UJ	B
Bromoform	0.50	UJ	C
Bromomethane	2.0	UJ	B
Vinyl Chloride	0.50	UJ	B

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-S6-MW02-GW2			UANG-S6-MW03-GW2			UANG-S6-MW04-GW2			UANG-S6-MW05-GW2		
LAB ID	SXS 01272			SXS 01273			SXS 01274			SXS 01275		
DATE COLLECTED	24-Aug-95			24-Aug-95			24-Aug-95			24-Aug-95		
SAMPLE MATRIX	Water			Water			Water			Water		
SEMI-VOLATILE	CONCENTRATION			CONCENTRATION			CONCENTRATION			CONCENTRATION		
COMPOUNDS 8270	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C
2-Nitroaniline	50	UJ	C	50	UJ	C	50	UJ	C	50	UJ	C
Benzoic acid	50	UJ	B	50	UJ	B	50	UJ	B	50	UJ	B
Bis(2-chloroisopropyl)ether	10	UJ	C	10	UJ	C	10	UJ	C	10	UJ	C
VOLATILE												
COMPOUNDS 8010/8020												
1,1,1,2-Tetrachloroethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
1,1,1-Trichloroethane	0.50	UJ	B,J	0.50	UJ	B	0.50	UJ	B,J	0.50	UJ	B,J
1,1,2,2-Tetrachloroethane	1.0	UJ	J	---			1.0	UJ	J	1.0	UJ	J
1,1,2-Trichloroethane	0.50	UJ	C,J	0.50	UJ	C	0.50	UJ	C,J	0.50	UJ	C,J
1,1-Dichloroethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
1,1-Dichloroethene	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
1,2-Dichloroethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
1,2-Dichloropropane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
1,3-Dichlorobenzene	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
2-Chloroethyl Vinyl Ether	0.50	UJ	B,J	0.50	UJ	B	0.50	UJ	B,J	0.50	UJ	B,J
Bromodichloromethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Bromoform	0.50	UJ	C,J	0.50	UJ	C	0.50	UJ	C,J	0.50	UJ	C,J
Bromomethane	2.0	UJ	B,J	2.0	UJ	B	2.0	UJ	B,J	2.0	UJ	B,J
Carbon Tetrachloride	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Chloroethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Chloroform	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Chloromethane	1.0	UJ	J	---			1.0	UJ	J	1.0	UJ	J
Cis-1,2-Dichloroethene	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Dibromochloromethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Dichlorodifluoromethane	1.0	UJ	J	---			1.0	UJ	J	1.0	UJ	J
Dichloromethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
M-xylene + P-xylene	---			0.33	J	Q	---			---		
Tetrachloroethene	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Trans-1,2-Dichloroethene	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Trans-1,3-Dichloropropene	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Trichloroethene	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Trichlorofluoromethane	0.50	UJ	J	---			0.50	UJ	J	0.50	UJ	J
Vinyl Chloride	0.50	UJ	B,J	0.50	UJ	B	0.50	UJ	B,J	0.50	UJ	B,J
METALS												
Arsenic	45	J	F	140	J	F,H	91	J	F,H	340	J	H

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-S6-MW01-GW2		
LAB ID	SXS MW01-GW2		
DATE COLLECTED	24-Aug-95		
SAMPLE MATRIX	Water		
SEMI-VOLATILE	CONCENTRATION		
COMPOUNDS 8270	(ug/l)	Q	C
1,2,4-Trichlorobenzene	10	UJ	J
1,2-Dichlorobenzene	10	UJ	J
1,3-Dichlorobenzene	10	UJ	J
1,4-Dichlorobenzene	10	UJ	J
2,4-Dichlorophenol	10	UJ	J
2,4-Dinitrotoluene	10	UJ	J
2,6-Dinitrotoluene	10	UJ	J
2-Chloronaphthalene	10	UJ	J
2-Methylnaphthalene	10	UJ	J
2-Nitroaniline	50	UJ	C,J
3,3-Dichlorobenzidine	20	UJ	J
3-Nitroaniline	50	UJ	J
4,6-Dinitro-2-methyl phenol	50	UJ	J
4-Bromophenyl phenyl ether	10	UJ	J
4-Chloroaniline	20	UJ	J
4-Chlorophenyl phenyl ether	10	UJ	J
4-Nitroaniline	50	UJ	J
Acenaphthene	10	UJ	J
Acenaphthylene	10	UJ	J
Anthracene	10	UJ	J
Benzo (a) anthracene	10	UJ	J
Benzo (a) pyrene	10	UJ	J
Benzo (b) fluoranthene	10	UJ	J
Benzo (ghi) perylene	10	UJ	J
Benzo (k) fluoranthene	10	UJ	J
Benzoic acid	50	UJ	B,J
Bis (2-chloroethoxy) methane	10	UJ	J
Bis (2-chloroethyl) ether	10	UJ	C,J
Bis (2-chloroisopropyl) ether	10	UJ	J
Bis (2-ethylhexyl) phthalate	10	UJ	J
Butylbenzylphthalate	10	UJ	J
Chrysene	10	UJ	J
Di-n-butylphthalate	10	UJ	J
Di-n-octylphthalate	10	UJ	J
Dibenz (a,h) anthracene	10	UJ	J
Dibenzofuran	10	UJ	J
Diethylphthalate	10	UJ	J
Dimethylphthalate	10	UJ	J
Fluoranthene	10	UJ	J
Fluorene	10	UJ	J
Hexachlorobenzene	10	UJ	J
Hexachlorobutadiene	10	UJ	J
Hexachlorocyclopentadiene	10	UJ	J

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	NG-S6-MW01-GW2 (cont.)		
LAB ID	SXS MW01-GW2		
DATE COLLECTED	24-Aug-95		
SAMPLE MATRIX	Water		
SEMI-VOLATILE	CONCENTRATION		
COMPOUNDS 8270	(ug/l)	Q	C
Hexachloroethane	10	UJ	J
Indeno (1,2,3-cd) pyrene	10	UJ	J
Isophorone	10	UJ	J
N-nitroso-di-n-propylamine	10	UJ	J
N-nitroso-dimethylamine	10	UJ	J
N-nitrosodiphenylamine	10	UJ	J
Naphthalene	10	UJ	J
Nitrobenzene	10	UJ	J
Phenanthrene	10	UJ	J
Pyrene	10	UJ	J
VOLATILE			
COMPOUNDS 8010/8020			
1,1,1,2-Tetrachloroethane	0.50	UJ	J
1,1,1-Trichloroethane	0.50	UJ	B,J
1,1,2,2-Tetrachloroethane	1.0	UJ	J
1,1,2-Trichloroethane	0.50	UJ	C,J
1,1-Dichloroethane	0.50	UJ	J
1,1-Dichloroethene	0.50	UJ	J
1,2-Dichloroethane	0.50	UJ	J
1,2-Dichloropropane	0.50	UJ	J
1,3-Dichlorobenzene	0.50	UJ	J
2-Chloroethyl Vinyl Ether	0.50	UJ	B,J
Bromodichloromethane	0.50	UJ	J
Bromoform	0.50	UJ	C,J
Bromomethane	2.0	UJ	B,J
Carbon Tetrachloride	0.50	UJ	J
Chloroethane	0.50	UJ	J
Chloroform	0.50	UJ	J
Chloromethane	1.0	UJ	J
Cis-1,2-Dichloroethene	0.50	UJ	J
Dibromochloromethane	0.50	UJ	J
Dichlorodifluoromethane	1.0	UJ	J
Dichloromethane	0.50	UJ	J
Tetrachloroethene	0.50	UJ	J
Trans-1,2-Dichloroethene	0.50	UJ	J
Trans-1,3-Dichloropropene	0.50	UJ	J
Trichloroethene	0.50	UJ	J
Trichlorofluoromethane	0.50	UJ	J
Vinyl Chloride	0.50	UJ	B,J
METALS			
Arsenic	190	J	F,H

FIELD ID	UANG-TB03-GW2		
LAB ID	SXS 01276		
DATE COLLECTED	24-Aug-95		
SAMPLE MATRIX	Water		
VOLATILE	CONCENTRATION		
COMPOUNDS 8010/8020	(ug/l)	Q	C
1,1,1-Trichloroethane	0.50	UJ	B
1,1,2-Trichloroethane	0.50	UJ	C
2-Chloroethyl Vinyl Ether	0.50	UJ	B
Bromoform	0.50	UJ	C
Bromomethane	2.0	UJ	B
Vinyl Chloride	0.50	UJ	B

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

FIELD ID	UANG-S1-MW1-GW2			UANG-S1-MW2-GW2			UANG-S2-MW2-GW2			UANG-S2-MW1-GW2			UANG-S2-MW3-GW2		
LAB ID	SXS 01660			SXS 01661			SXS 01662			SXS 01663			SXS 01664		
DATE COLLECTED	6-Nov-95			6-Nov-95			6-Nov-95			6-Nov-95			6-Nov-95		
SAMPLE MATRIX	Water			Water			Water			Water			Water		
VOLATILE	CONCENTRATION			CONCENTRATION			CONCENTRATION			CONCENTRATION			CONCENTRATION		
COMPOUNDS 8010/8020	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C
1,1-Dichloroethane	---			---			---			1.0	J	T	---		
1,2-Dichlorobenzene	---			0.20	J	A	---			---			---		
1,2-Dichloroethane	---			2.5	J	T	0.50	U	P	1.6	J	T	0.50	U	P
1,2-Dichloroethene	---			400	J	S	76	J	S	230	J	S	59	J	S
Benzene	---			0.50	U	P	---			---			---		
Bromomethane	2.0	UJ	C	2.0	UJ	C	2.0	UJ	C	2.0	UJ	C	2.0	UJ	C
Chlorobenzene	---			0.18	J	A	---			0.27	J	A	---		
Chloroform	---			---			9.4	J	B,C	---			10	J	B,C
Chloromethane	3.1	U	E	---			3.1	U	E	---			3.0	U	E
Dichlorodifluoromethane	3.1	U	E	---			3.1	U	E	---			3.0	U	E
Dichloromethane	0.50	UJ	B	0.50	UJ	B	0.50	UJ	B	0.50	UJ	B,P	0.50	UJ	B
Tetrachloroethene	---			12	J	C,S	---			31	J	C,S	2.1	J	S
Trans-1,3-Dichloropropene	---			---			---			0.89	J	T	---		
Trichloroethene	0.59	U	P	37	J	C,S	490	J	C,S	1200	J	C,S	480	J	C,S

FIELD ID	UANG-S3-MW1-GW2			UANG-RB2			UANG-TB06		
LAB ID	SXS 01665			SXS 01666			SXS 01667		
DATE COLLECTED	7-Nov-95			7-Nov-95			7-Nov-95		
SAMPLE MATRIX	Water			Water			Water		
VOLATILE	CONCENTRATION			CONCENTRATION			CONCENTRATION		
COMPOUNDS 8010/8020	(ug/l)	Q	C	(ug/l)	Q	C	(ug/l)	Q	C
1,2-Dichlorobenzene	2.3	J	T	---			---		
1,2-Dichloroethane	---			---			0.16	J	A
1,2-Dichloroethene	---			---			0.20	J	A
1,3-Dichlorobenzene	0.62	J	T	---			---		
1,4-Dichlorobenzene	4.6	J	T	0.47	J	A	---		
Benzene	0.50	U	P	0.12	J	A	---		
Bromomethane	2.0	UJ	C	2.0	UJ	C	2.0	UJ	C
Dichloromethane	0.50	UJ	B	0.50	UJ	B	0.92	J	B
O-xylene	---			0.23	J	A	---		
Toluene	---			1.3	J	T	---		
Trichloroethene	---			---			6.9	J	C

FIELD ID	UANG-S1-MW02-GW2			UANG-S1-MW01-GW2		
LAB ID	SXS 01281			SXS 01280		
DATE COLLECTED	25-Aug-95			25-Aug-95		
SAMPLE MATRIX	Water			Water		
PESTICIDES/PCBs	CONCENTRATION			CONCENTRATION		
	(ug/l)	Q	C	(ug/l)	Q	C
Aroclor 1016	1.0	UJ	B	1.0	UJ	B
Aroclor 1221	1.0	UJ	B	1.0	UJ	B
Aroclor 1232	1.0	UJ	B	1.0	UJ	B
Aroclor 1242	1.0	UJ	B	1.0	UJ	B
Aroclor 1248	1.0	UJ	B	1.0	UJ	B
Aroclor 1254	1.0	UJ	B	1.0	UJ	B
Aroclor 1260	1.0	UJ	B	1.0	UJ	B
Chlordane	0.10	UJ	B	0.10	UJ	B
Toxaphene	2.0	UJ	B	2.0	UJ	B

TABLE E.1.2.1
TABLE OF ESTIMATED DATA
ANALYTICAL DATA SUMMARY

Qualifiers (Cause Codes)

- A = Reported value is between CRQL and the MDL or the CRDL and the IDL.
- B = Initial calibration is out of control.
- C = Continuing calibration is out of control.
- D = Matrix spike recovery is outside of QC limit or none run.
- E = The sample concentration was estimated due to contribution by the method blank.
- F = Laboratory duplicate was out of control or not run.
- G = Serial dilution %D was out of control or not run.
- H = Post spike recovery was outside of the QC limit.
- I = Sample preservation method unclear.
- J = Surrogate recovery is outside of QC limits.
- K = Laboratory Control Sample was out of control.
- L = $r < 0.995$ or less than 5 point curve.
- M = M-xylene + P-xylene coeluted samples
- N = No MS/MSD recovery due to dilution.
- O = Initial or continuing calibration blank out of control.
- P = Sample concentration estimated due to contribution by the trip, equipment, rinse, or field blank.
- Q = Coelution of analytes.
- S = Analyzed beyond holding time.
- T = Response was not verified on the confirmation analysis.
- = No qualification to the result or analysis not required.

TABLE E.1.2.2
TABLE OF UNUSABLE DATA
ANALYTICAL DATA SUMMARY

UTAH AIR NATIONAL GUARD
SALT LAKE CITY, UTAH

FRACTION	FIELD ID	LAB ID	ANALYTE	CAUSE
METALS	UANG-BG-MW02-GW2	SXS 01279	Antimony	MS/MSD %R <30%
	UANG-BG-MW2 (0-2)	SXS 01256R	Antimony	MS/MSD %R <30%
	UANG-BG-MW2 (2-4)	SXS 01257R	Antimony	MS/MSD %R <30%
	UANG-BG-MW2 (4-6)	SXS 01258R	Antimony	MS/MSD %R <30%
	UANG-BG-MW2 (6-8)	SXS 01259R	Antimony	MS/MSD %R <30%
VOCs	UANG-S1-MW1-GW2	SXS 01660	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration
	UANG-S1-MW2-GW2	SXS 01661	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration
	UANG-S2-MW2-GW2	SXS 01662	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration
	UANG-S2-MW1-GW2	SXS 01663	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration
	UANG-S2-MW3-GW2	SXS 01664	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration
	UANG-S3-MW1-GW2	SXS 01665	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration
	UANG-RB2-GW2	SXS 01666	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration
	UANG-TB06-GW2	SXS 01667	1,1,2,2-Tetrachloroethane 2-Chloroethyl Vinyl Ether Styrene	ICV %R No Calibration No Calibration

APPENDIX F
PIEZOMETER CONSTRUCTION DETAILS AND LOGS

APPENDIX F
TABLE OF CONTENTS

Basewide Piezometer Logs F-1

LIST OF TABLES


Table F.1 - Construction Details for Basewide Piezometers F-11

Basewide Piezometer Logs

Log of Piezometer: PI-1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 5
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 895639.29
GROUND ELEVATION: 4215.09 ft-MSL	EAST COORDINATE: 1873107.99
WELL DEPTH: 15.5 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.73 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4208.95 ft-MSL	DRILLER: Dean Walton
DATE MEASURED: 12/28/92	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4214.68 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 15.50 ft-BGL	SAMPLING METHOD: 5 foot long, 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 10/20/92	END COMPLETION: 10/20/92



Log of Piezometer: PI-2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 6
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 896103.90
GROUND ELEVATION: 4212.86 ft-MSL	EAST COORDINATE: 1874517.22
WELL DEPTH: 15.5 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 4.20 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4208.36 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4212.56 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 15.5 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 10/21/92	END COMPLETION: 10/21/92

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	P10 HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1			0.0	SAND, and GRAVEL, some CLAY: fill material	GC		<p>Concrete Pad</p> <p>Borehole Dia. 10-1/4 inches</p> <p>1-inch Diam. PVC Casing</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>1-inch Diam. PVC Casing w/ End Cap</p>
2			0.0	SILT, and CLAY: (5Y 4/1) dk. gray, roots	ML		
3			0.0	CLAY, trace SILT: (5Y 3/1) v. dk. gray, soft, slightly plastic, moist at bottom	CL		
4			0.0				
5			0.0				
6			0.0				
7			0.0				<p>Concrete Pad</p> <p>Borehole Dia. 10-1/4 inches</p> <p>1-inch Diam. PVC Casing</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>1-inch Diam. PVC Casing w/ End Cap</p>
8			0.0	SAND, fine, and SILT: (5Y 6/2) lt. olive gray, slightly plastic, blobs of 2.5Y 5/6 lt. olive brown stained soil	SM		
9			0.0				
10			0.0				
11			0.0				
12			0.0	SAND, medium: (5Y 4/1) dk. gray, soft, loose, well sorted, saturated, mica, wood chips at the bottom saturated	SM		
13			0.0				<p>Concrete Pad</p> <p>Borehole Dia. 10-1/4 inches</p> <p>1-inch Diam. PVC Casing</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>1-inch Diam. PVC Casing w/ End Cap</p>
14			0.0	SAND, medium to coarse: (5Y 4/1) dk. gray, soft, loose, well sorted, subround quartz and mica	SM		
15			0.0				
16			0.0	Total depth = 15.5 ft.			
17			0.0				
18			0.0				
19			0.0				<p>Concrete Pad</p> <p>Borehole Dia. 10-1/4 inches</p> <p>1-inch Diam. PVC Casing</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>1-inch Diam. PVC Casing w/ End Cap</p>
20			0.0				
21			0.0				

Log of Piezometer: PI-3

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-3
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 8,9
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 894223.22
GROUND ELEVATION: 4217.42 ft-MSL	EAST COORDINATE: 1873435.55
WELL DEPTH: 15.5 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.27 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4212.01 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4217.28 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 15.5 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 10/22/92	END COMPLETION: 10/23/92

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1					NA		<p>Concrete Pad</p> <p>Borehole Dia. 10-1/4 inches</p> <p>1-inch Diam. PVC Casing</p> <p>BENTONITE SEAL</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>1-inch Diam. PVC Casing w/ End Cap</p>
2			0.0	CLAY, and SILT, some SAND, fine: (5Y 5/2) olive gray w/ rust and black discoloration, moist, non-plastic, roots	CL		
3					CL		
4			0.0	CLAY, and SILT, some SAND, fine: (5Y 4/2) olive gray, soft, shells @ 3 feet, thin sand zone @ 3.5 feet	CL		
5					NA		
6							
7							
8							
9			0.0	CLAY, and SILT: (5Y 4/2) olive gray, saturated, slightly plastic, shells, soft, fine sand at bottom	CL		
10					CL		
11			0.0	CLAY, some SILT: (5Y 5/2) olive gray, mottled w/ (2.5Y 6/6) olive yellow, more silt at bottom	CL		
12					CL		
13			0.0	CLAY: (5Y 6/2) lt. olive gray, soft, saturated, spreads easily	CL		
14							
15			0.0	SAND: (5Y 6/2) lt. olive gray,	SW		
16				CLAY: (2.5Y 2/0) black, soft	CL		
17				Total depth = 15.5 ft.			
18							
19							
20							
21							

Log of Piezometer: PI-4

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-4
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 6,7
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 894905.41
GROUND ELEVATION: 4215.14 ft-MSL	EAST COORDINATE: 1874539.88
WELL DEPTH: 20.0 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 6.61 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4208.18 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4214.79 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 20.0 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 10/21/92	END COMPLETION: 10/21/92



Log of Piezometer: PI-5

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-5
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 9-11
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 895442.95
GROUND ELEVATION: 4214.44 ft-MSL	EAST COORDINATE: 1873574.26
WELL DEPTH: 15.0 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: Not Measured on this Date ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: Not Measured on this Date ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4214.29 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 15.0 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 10/22/92	END COMPLETION: 10/23/92



Log of Piezometer: PI-6

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-6
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 8,9
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893032.71
GROUND ELEVATION: 4218.06 ft-MSL	EAST COORDINATE: 1873490.58
WELL DEPTH: 15.0 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 6.72 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4211.13 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4217.85 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 15.0 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 10/22/92	END COMPLETION: 10/22/92



Log of Piezometer: PI-7

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-7
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 57
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 896901.99
GROUND ELEVATION: 4216.68 ft-MSL	EAST COORDINATE: 1873471.49
WELL DEPTH: 15.5 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 10.00 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4209.57 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Acker Soil Max
TOC ELEVATION: 4219.57 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 15.5 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 12/18/92	END COMPLETION: 12/18/92



Log of Piezometer: PI-8

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-8
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 57,58
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 895657.32
GROUND ELEVATION: 4215.38 ft-MSL	EAST COORDINATE: 1874236.48
WELL DEPTH: 15.5 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 10.02 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4208.27 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Acker Soil Max
TOC ELEVATION: 4218.29 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 15.5 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 12/18/92	END COMPLETION: 12/18/92



Log of Piezometer: PI-9

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-9
PROJECT NUMBER: UT014	REF. LOGBOOK: 6, pg. 2
CLIENT/PROJECT: HAZWRAP/NG8	NORTH COORDINATE: 894365.88
GROUND ELEVATION: 4216.84 ft-MSL	EAST COORDINATE: 1874093.92
WELL DEPTH: 15.5 ft-BGL	LOGGED BY: R.W. Graves
WATER LEVEL: 10.31 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4209.73 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Acker Soil Max
TOC ELEVATION: 4220.04 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 17.0 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 12/21/92	END COMPLETION: 12/21/92

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1	X			CLAY, some SAND, trace GRAVEL: (5Y 6/3) pale olive, dry	CL		
2	X				NA		
3	X			SILT: (5Y 6/3) pale olive, CLAY: (5Y 6/3) pale olive, dry	ML CL		
4	X			SAND, fine to med: (5Y 6/3) pale olive and (10YR 6/8) brownish yellow	SW		
5	X			CLAY: (5Y 6/3) pale olive, moist, plastic, interlayered with silt containing mica grains	CL		
6	X			SILT: (5Y 6/3) pale olive	ML		
7	X			CLAY: (5Y 6/3) pale olive interlayered with fine-grained (2.5YR 4/6) red sand, saturated	CL		
8	X			CLAY: (5Y 6/3) pale olive, homogenous, worm holes, shells, (2.5YR 4/6) red mottling	CL		
9	X						
10	X			CLAY: (5Y 6/4) olive, plastic, moist to saturated, worm holes			
11	X						
12	X			SAND, fine: (5Y 6/4) pale olive	SW		
13	X			CLAY, little SAND, fine: (5Y 5/4) olive, well sorted, loose	CL		
14	X			CLAY: (5GY 6/1) greenish gray, saturated	CL		
15	X			CLAY, trace SAND: (5GY 6/1) greenish gray, some black clay, saturated	CL		
16							
17				Total depth = 17.0 ft.			
18							
19							
20							
21							

Log of Piezometer: PI-10

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Basewide Piezometer PI-10
PROJECT NUMBER: UT014	REF. LOGBOOK: 6, pg. 2
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893052.93
GROUND ELEVATION: 4218.96 ft-MSL	EAST COORDINATE: 1873973.60
WELL DEPTH: 15.5 ft-BGL	LOGGED BY: R.W. Graves
WATER LEVEL: 7.29 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4211.54 ft-MSL	DRILLER: Steve Mott
DATE MEASURED: 12/28/92	DRILLING RIG: Acker Soil Max
TOC ELEVATION: 4218.83 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 16.0 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 12/21/92	END COMPLETION: 12/21/92




TABLE F.1
CONSTRUCTION DETAILS FOR BASEWIDE PIEZOMETERS
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Station	Land Surface Elevation (feet above MSL)	Top of Casing Elevation (feet above MSL)	Borehole Depth (feet BLS)	Well Depth (feet BLS)	Screened Interval (feet BLS)
PI-1	4215.09	4214.68	15.5	15.5	10.0-15.0
PI-2	4212.86	4212.56	15.5	15.5	10.0-15.0
PI-3	4217.42	4217.28	15.5	15.5	10.0-15.0
PI-4	4215.14	4214.79	20.0	20.0	14.5-19.5
PI-5	4214.44	4214.29	15.0	15.0	9.5-14.5
PI-6	4218.06	4217.85	15.0	15.0	9.5-14.5
PI-7 (1)	4216.68	4219.57	15.5	15.5	10.0-15.0
PI-8 (1)	4215.38	4218.29	15.5	15.5	10.0-15.0
PI-9 (1)	4216.84	4220.04	17.0	15.5	10.0-15.0
PI-10	4218.96	4218.83	16.0	15.5	10.0-15.0

MSL = Mean Sea Level

BLS = Below Land Surface

(1) Above Ground Well Casing

APPENDIX G
MONITORING WELL CONSTRUCTION DETAILS AND LOGS
AND SOIL BORING LOGS

APPENDIX G

TABLE OF CONTENTS

Background Soil Boring/Monitoring Well(s)	G-1
Site 1 Former Pesticide Dump	G-3
Site 2 Waste POL Fuel Spill	G-15
Site 3 Drum Burial Locations	G-23
Site 4 Fire Training Area 1	G-30
Site 5 Fire Training Area 2	G-40
Site 6 Ramp Washdown	G-48
Site 7 Oil Sledge Pond	G-63
Site 10 Petroleum, Oils, and Lubricants Facility	G-75

LIST OF TABLES


Table G.1 Monitoring Well Construction Details	G-82
--	------

Background Soil Boring/Monitoring Well(s)

Log of Monitoring Well: BGMW1

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Background
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 83
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893043.2165
GROUND ELEVATION: 4219.11 ft-MSL	EAST COORDINATE: 1873983.7638
WELL DEPTH: 16.85 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 6.29 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4213.44 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4218.74 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 18.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/13/93	END COMPLETION: 01/13/93



Log of Monitoring Well: BGMW2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Background
PROJECT NUMBER: UT014	REF. LOGBOOK: 3, pg.6
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 896871.93
GROUND ELEVATION: 4215.54 ft-MSL	EAST COORDINATE: 1873328.04
WELL DEPTH: 14.50 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 9.83 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: 4208.26 ft-MSL	DRILLER: Russ Werner
DATE MEASURED: 8/25/95	DRILLING RIG: CME 75
TOC ELEVATION: 4218.09 ft-MSL	DRILLING METHOD: 4 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 14.50 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split spoon
BEGIN COMPLETION: 8/17/95	END COMPLETION: 8/17/95




Site 1 - Former Pesticide Dump

Log of Monitoring Well: S1MW1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1, Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg.81
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893082.1260
GROUND ELEVATION: 4218.32 ft-MSL	EAST COORDINATE: 1873686.2852
WELL DEPTH: 17.35 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.72 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4213.01 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/21/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4218.02 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 18.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/12/93	END COMPLETION: 01/12/93



Log of Monitoring Well: S1MW2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1, Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 3, pg.2
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893026.13
GROUND ELEVATION: 4217.93 ft-MSL	EAST COORDINATE: 1873616.75
WELL DEPTH: 14.5 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 6.18 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: 4211.50 ft-MSL	DRILLER: Russ Werner
DATE MEASURED: 8/25/95	DRILLING RIG: CME 75
TOC ELEVATION: 4217.68 ft-MSL	DRILLING METHOD: 4 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 14.5 ft-BGL	SAMPLING METHOD: 3 in. ID CME core
BEGIN COMPLETION: 8/15/95	END COMPLETION: 8/15/95

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	P10 HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1				SAND, and GRAVEL, some SILT and CLAY: (2.5Y 4/2), dk. grayish brown, hard, dry, minor organic silt	GC		
2			3.8	SAND, and CLAY: (5Y 5/2), olive gray to (5Y 5/3) olive, (10 YR 4/6), dk. yellowish brown staining, firm, layers that are more sandy	SC		
3				CLAY, little sand: (5Y 5/3), olive, soft, non-plastic, moist	CL		
4				SAND, and CLAY: (5Y 5/3), olive, mottled with (10YR 4/6), dk. yellowish brown, some hollow cavities with decomposed dark organic matter, firm	SC		
5			1.2	SAND: fine to med, (5Y 5/2), olive gray, firm, saturated	SW		
6				CLAY: (5Y 5/3), olive, soft, non-plastic	CL		
7				SAND, and CLAY: (5Y 5/3), olive, saturated, soft to firm	SC		
8							
9							
10							
11							
12			3.2	SAND, medium to coarse: (5Y 5/1), gray, loose, granitic origin, mica and quartz, some dark ferromagnesian silicate minerals, subangular and moderate sorting	SW		
13				Total depth = 14.5 ft.			
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1, Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 40
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 892953.95	DRILLER: Steve Mott
EAST COORDINATE: 1873653.15	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4218.17 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/11/92 @ 0945 END: 12/11/92 @ 1015	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	P10 HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			108	SAND, and GRAVEL: fill material	GW		ID: UANG-S1-SB1 (0-2) Headspace @ 0.75 ft
2				SILT: (5Y 2.5/1), black, organic, soft, shells, non-plastic CLAY, and SILT, some SAND: (5Y 4/2), olive gray, soft, moist, non-plastic	OL CL		
3				CLAY, and SILT: (5Y 6/2), lt. olive gray, firm, plastic, thin sand zone @ 3.5 feet,	CL		
4			16.0	CLAY: (5Y 6/2), lt. olive gray, soft, moist	CL		Headspace @ 3.5 ft
5				CLAY: (5Y 7/2), lt. gray, stiff, cracked, and dry	CL		
6				CLAY: (5Y 5/2), olive gray, mottled with (2.5Y 5/6), lt. olive brown, saturated	CL		
7				Total depth=6.5 ft.			ID: UANG-S1-SB1 (4.0-6.5) Headspace @ 5.0 ft Sampled in dessicated hard, light gray clay
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1, Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 40
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 892983.06	DRILLER: Steve Mott
EAST COORDINATE: 1873650.90	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4218.16 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/11/92 @ 1030	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers
END: 12/11/92 @ 1055	

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HOSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				SILT: (5Y 2.5/1), black, organic, shells, soft, non-plastic gravel at very top	OL		
2			14.5	SILT, some clay, little SAND: (2.5Y 4/2), dk. grayish brown soft, non-plastic, moist	ML		ID: UANG-S1-SB2 (0-2) Headspace @ 1.50 ft
3				CLAY, some SILT, some SAND: (5Y 6/2), lt. olive gray, soft, moist, non-plastic	CL		
4			17.0	CLAY: (5Y 6/2), lt. olive gray, soft, moist,	CL		Headspace @ 4.0 ft
5			12.9	CLAY, little SAND: (5Y 7/2), lt. gray, firm, brittle, damp	CL		ID: UANG-S1-SB2 (4.0-6.5) Headspace @ 5.0 ft
6				CLAY, some SAND: (5Y 5/2), olive gray, mottled with (2.5Y 5/6), lt. olive brown, saturated	CL		Collected MS and MSD
7				Total depth=6.5 ft.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1, Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 41
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893012.04	DRILLER: Steve Mott
EAST COORDINATE: 1873655.19	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4218.38 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/11/92 @ 1100 END: 12/11/92 @ 1125	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			8.7	CLAY, and SILT, some SAND: (5Y 5/2), olive gray, soft, gravel at top	CL		Headspace @ 1.00 ft
2				SILT, some CLAY, some SAND: (2.5Y 6/2), lt. brownish gray, soft crumbly	ML		
3			7.1	SAND, and SILT: (5Y 6/2), lt. olive gray, soft, moist, crumbly, more sand at bottom of interval	SM		ID: UANG-S1-SB3 (2-4) Headspace @ 3.0 ft
4			12.0	CLAY: (5Y 5/2), olive gray, soft, non-plastic,	CL		ID: UANG-S1-SB3 (4.0-6.5) Headspace @ 4.5 ft
5							Collected duplicate UANG-S1-SB3 (6.5-8.5)
6				Total depth=6.5 ft.			
7							
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1 - Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 8 pg 33
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 9.5' ft-BGL
LOGGED BY: A. Graves	DRILLING CONTRACTOR: P C Exploration
NORTH COORDINATE: 893043.2699	DRILLER: Jim Peterson
EAST COORDINATE: 1873698.5399	DRILLING RIG: B-61
GROUND ELEVATION: 4218.21 ft-MSL	DRILLING METHOD: 4.25" ID. Hollow Stem Auger
DRILLING BEGIN: 09:26 26 Oct 94 END: 10:57 26 Oct 94	SAMPLING METHOD: 2.50" ID X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PTD HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1	☒		0.0	Asphalt	NA		
2				Road Base	NA		
3	☒	☒	0.0	CLAY some SILT: (5Y 6/3) pale olive, red mottling, dry, hard, plastic to 1.75', moist sandy clay to 1.95', moist, soft, plastic silty clay with sand to 2.3'	CL		
4	☒	☒	0.0	SAND, fine to coarse, and CLAY: (5Y 6/2) light olive gray, moist, plastic, grading to clay with sand (7.5YR 5/8) strong brown.			SAMPLE ID: UANG-S1-SB4 (3.5-5.5)
5	☒		0.0	CLAY: (5Y 6/3) pale olive, mottled with (5Y 7/2) light gray, moist, plastic, some thin sand bedding with red mottling, some black staining			
6	☒						
7	☒	☒	0.0	SAND, very fine, and CLAY, some SILT: (5Y 5/3) olive, saturated, red mottling.	SC		SAMPLE ID: UANG-S1-SB4 (7.5-9.5)
8							
9							
10				Total depth 9.5 ft BGL			
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1 - Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 8 pg 33
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 9.0' ft-BGL
LOGGED BY: A. Graves	DRILLING CONTRACTOR: P C Exploration
NORTH COORDINATE: 893089.3412	DRILLER: Jim Peterson
EAST COORDINATE: 1873730.9641	DRILLING RIG: B-61
GROUND ELEVATION: 4217.84 ft-MSL	DRILLING METHOD: 4.25" ID. Hollow Stem Auger
DRILLING BEGIN: 11:14 26 Oct 94 END: 11:58 26 Oct 94	SAMPLING METHOD: 2.50" ID X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PTD HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Asphalt	NA		
2				Road Base	NA		
3			0.0	SAND and some CLAY: (5Y 5/2) olive gray, with red mottling, moist, 15% organics (roots), clay content increasing with depth.	SC		SAMPLE ID: UANG-S1-SB5 (1-3)
4			0.0	SAND, fine to coarse, and CLAY, thinly bedded: (5Y 6/3) pale olive, red mottling, wet, slightly plastic, some mica, clay content increasing with depth.	SC		
5				CLAY, some SILT: (5Y 6/2) light olive gray, moist, 1/2 inch black organic stained zone at 5'8", red mottling.	CL		SAMPLE ID: UANG-S1-SB5 (5-7)
6			0.0				
7				CLAY: (5Y 6/2) light olive gray, moist.	CL		
8			0.0	CLAY and SAND: (5Y 6/2) light olive gray, moist, red mottling and rootlets.			
9				Total depth 9.0 ft BGL			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-6

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1 - Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 8 pg 33
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 9.0' ft-BGL
LOGGED BY: A. Graves	DRILLING CONTRACTOR: P C Exploration
NORTH COORDINATE: 892946.7361	DRILLER: Jim Peterson
EAST COORDINATE: 1873690.1406	DRILLING RIG: B-61
GROUND ELEVATION: 4217.83 ft-MSL	DRILLING METHOD: 4.25" ID. Hollow Stem Auger
DRILLING BEGIN: 13:04 26 Oct 94	END: 13:36 26 Oct 94
	SAMPLING METHOD: 2.50" ID X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Asphalt	NA		
2				Road Base	NA		
3			0.0	Topsoil 1" (10YR 4/1) dark gray, SAND, fine, some CLAY: (5Y 6/3) pale olive, moist, poorly sorted, some mica, grading to thinly bedded sandy clay (5Y 6/3) pale olive.	SC		SAMPLE ID: UANG-S1-SB6 (1-3) Collected Duplicate: UANG-S1-SB6 (3-5)
4			0.0	CLAY, some SAND, medium to coarse: (5Y 6/2) light olive gray, moist.	CL		
5			0.0	SAND, coarse: (5Y 6/2) light olive gray, wet, poorly sorted.			
6			0.0	CLAY: (5Y 6/2) light olive gray, and SAND, medium (10YR 4/4) dark yellowish brown, wet, red mottling.	SC		SAMPLE ID: UANG-S1-SB6 (5-7)
7			0.0	CLAY, some SAND fine to medium: (5Y 6/2) light olive gray, wet.			
8			0.0	SAND, fine, some CLAY: (5Y 6/2) light olive gray, moist, red mottling.	CL		
9			0.0	SAND, medium some CLAY, (5Y 6/2) light olive gray, wet.			
10				CLAY, some SAND, medium (5Y 5/3) olive, moist			
11				CLAY, some SAND, medium (5Y 5/3) olive, moist, red mottling in sand, grading to more sand with depth.			
12				Total depth 9.0 ft BGL			
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-7

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1 - Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 8 pg 34
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 9 ft-BGL
LOGGED BY: A. Graves	DRILLING CONTRACTOR: P C Exploration
NORTH COORDINATE: 892983.9463	DRILLER: Jim Peterson
EAST COORDINATE: 1873684.2486	DRILLING RIG: B-61
GROUND ELEVATION: 4218.66 ft-MSL	DRILLING METHOD: 4.25" ID. Hollow Stem Auger
DRILLING BEGIN: 13:45 26 Oct 94	SAMPLING METHOD: 2.50" ID X 2.5' Split Spoon
END: 14:52 26 Oct 94	

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Asphalt	NA		
2				Road Base	NA		
3			20.4	CLAY, little silt, some SAND: (5G 5/1) greenish gray, dry, hard, slightly plastic, 1 large (3") well rounded quartzite pebble.	CL		SAMPLE ID: UANG-S1-SB7 (1-3)
4			23.5	CLAY, some SAND, medium: (2.5Y 5/3) light olive brown, moist, red and gray mottling, black staining.	SM		
5			34.2	SAND, coarse, and CLAY: (5G 6/1) greenish grey, moist, poorly sorted sand, interbedded with clay layers.	SM		
6				CLAY: (5G 6/1) greenish gray, moist, plastic, black staining.	CL		SAMPLE ID: UANG-S1-SB7 (5-7)
7				SAND, some SILT: (5G 6/1) greenish gray, red mottling.	SM		
8			0.0	SAND, coarse, some CLAY: (5Y 6/2) light olive gray, wet, poorly sorted.	SC		
9				CLAY, some SILT: (5Y 6/2) light olive gray, moist, plastic, thinly laminated, red mottling.	CL		
10				SAND, coarse: (5Y 6/2) light olive gray, wet, poorly sorted.	SP		
11				CLAY, some SILT: (5Y 6/2) light olive gray, wet, plastic, thinly bedded, red mottling.	CL		
12				Total depth 9.0 ft BGL			
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-8

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1 - Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 8 pg 34
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 7.0' ft-BGL
LOGGED BY: A. Graves	DRILLING CONTRACTOR: P C Exploration
NORTH COORDINATE: 892998.4288	DRILLER: Jim Peterson
EAST COORDINATE: 1873680.5249	DRILLING RIG: B-61
GROUND ELEVATION: 4218.84 ft-MSL	DRILLING METHOD: 4.25" ID. Hollow Stem Auger
DRILLING BEGIN: 15:02 26 Oct 94	END: 15:40 26 Oct 94
	SAMPLING METHOD: 2.50" ID X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Asphalt	NA		
2				Road Base	NA		
3			0.0	SILT, and SAND, fine (2.5Y 6/3) light yellowish brown, dry, hard, with 5% rootlets, mottled light gray.	ML		
4			0.0	CLAY, some SILT (5Y 5/1) gray, moist, hard, with 2% rootlets.	SM		
5				SAND, medium, some SILT (5Y 6/3) pale olive, moist, red mottling.	CL		
6			765.0	CLAY, some SILT (5Y 7/4) pale yellow, moist, laminated, red mottling.			
7				CLAY, some SILT (5GY 6/1) greenish gray, moist, plastic, with black staining.	SM		
8				SAND, fine, SILT (5GY 6/1) greenish gray, moist, poorly sorted, with red mottling, minor mica and rootlets.			
9				Total depth 7.0 ft BGL			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

SAMPLE ID: UANG-S1-SB8 (1-3)
Collected MS/MSD

SAMPLE ID: UANG-S1-SB8 (5-7)
Collected Duplicate:
UANG-S1-SB8 (7-9)

Log of Soil Boring: SB-9

ENGINEERING-SCIENCE, INC.










PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1 - Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 8 pg 34
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 7.0' ft-BGL
LOGGED BY: A. Graves	DRILLING CONTRACTOR: P C Exploration
NORTH COORDINATE: 892949.6566	DRILLER: Jim Peterson
EAST COORDINATE: 1873611.0514	DRILLING RIG: B-61
GROUND ELEVATION: 4217.76 ft-MSL	DRILLING METHOD: 4.25" ID. Hollow Stem Auger
DRILLING BEGIN: 16:20 26 Oct 94	END: 17:00 26 Oct 94
	SAMPLING METHOD: 2.50" ID X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1	☒		0.0	Asphalt	NA		
2				Road Base	NA		
3	☒	☒	0.0	SAND, coarse, some GRAVEL: (10YR 4/2) dark grayish brown, dry, poorly sorted, with 20% subangular to well rounded pebbles from <10mm to 4cm.	SP		
4				SAND, coarse, and GRAVEL: (10YR 4/2) dark grayish brown, dry, poorly sorted, with 60% subangular to well rounded pebbles from <10mm to 4cm.			SAMPLE ID: UANG-S1-SB9 (3-5)
5	☒	☒	0.0	CLAY, some SILT (2.5Y 6/2) light brownish gray, wet, with 10% small pebbles and some coarse sand.	CL		
6				CLAY (2.5Y 6/2) light brownish gray, moist, hard, plastic, with red mottling.	SM		
7				SAND, very fine, some SILT (2.5Y 6/2) light brownish gray, wet, with red mottling.	CL		SAMPLE ID: UANG-S1-SB9 (5-7)
8				CLAY, moist, hard, with red mottling.	SW		
9				SAND, fine, wet, well sorted, minor mica.			
10				Total depth 7.0 ft BGL			
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-10

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 1 - Former Pesticide Dump
PROJECT NUMBER: UT014	REF. LOGBOOK: 8 pg 34
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 7.0' ft-BGL
LOGGED BY: A. Graves	DRILLING CONTRACTOR: P C Exploration
NORTH COORDINATE: 893003.7006	DRILLER: Jim Peterson
EAST COORDINATE: 1873605.5886	DRILLING RIG: B-61
GROUND ELEVATION: 4217.40 ft-MSL	DRILLING METHOD: 4.25" ID. Hollow Stem Auger
DRILLING BEGIN: 17:10 26 Oct 94	END: 18:30 26 Oct 94
	SAMPLING METHOD: 2.50" ID X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			1.9	Asphalt	NA		
2			1.9	Road Base	NA		
3				CLAY, some SILT: (5Y 6/2) light olive gray, moist, plastic, thinly laminated, grading to (2.5Y 6/2) light grayish brown, red mottling.	CL		SAMPLE ID: UANG-S1-SB10 (1-3)
4							SAMPLE ID: UANG-S1-SB10 (3-5)
5				Total depth 5.0 ft BGL			
6							
7							
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Site 2 - Waste POL Fuel Spill

Log of Monitoring Well: S2MW1

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 2, Waste POL Fuel Spill
PROJECT NUMBER: UT014	REF. LOGBOOK: 2. PG.85
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893208.7959
GROUND ELEVATION: 4217.43 ft-MSL	EAST COORDINATE: 1873643.1380
WELL DEPTH: 17.27 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 4.77 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4212.87 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/22/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4217.16 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 18.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/14/93	END COMPLETION: 01/14/93

DEPTH (feet)	INTERVAL RECOVERY ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1		3.3	SAND, and SILT, trace GRAVEL and CLAY: (5Y 3/2), dk. olive gray, soft, crumbly	SM		<p>Concrete Pad</p> <p>Borehole Diam. 10-1/4 inches</p> <p>2-inch Diam. PVC Casing</p> <p>BENTONITE SEAL</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>Bottom Sump</p> <p>total depth = 18.0 ft.</p>
2			SAND, and SILT, some CLAY: (5Y 5/3), olive, mottled with (2.5Y 5/6), lt. olive brown, soft, non-plastic			
3		0.0				
4			CLAY, little SAND: (5Y 6/2), lt. olive gray, soft, saturated @ about 5.0 ft., layered (2.5Y 5/6), lt. olive brown laminations	CL		
5		7.7				
6						
7		6.4				
8						
9		10.1	SAND, fine, some SILT and CLAY: (5Y 5/3), olive, and (2.5Y 5/6), lt. olive brown,	ML		
10			CLAY, trace SAND: (5GY 5/1), greenish gray, roots and rhizomes, gray-purple color around rhizomes	CL		
11		12.1				
12			CLAY, and SAND: alternating layers of (N4/4), dark gray, sand is fine, contains mica,	CL		
13		6.8				
14			CLAY, trace SAND: (5GY 5/1), greenish gray, very soft,	CL		
15		7.0				
16						
17						
18						
19						
20						
21						

Log of Monitoring Well: S2MW2

ENGINEERING-SCIENCE, INC.













PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 2, Waste POL Fuel Spill
PROJECT NUMBER: UT014	REF. LOGBOOK: 3, pg.3
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893219.88
GROUND ELEVATION: 4217.75 ft-MSL	EAST COORDINATE: 1873587.04
WELL DEPTH: 14.50 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 4.57 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: 4212.88 ft-MSL	DRILLER: Russ Werner
DATE MEASURED: 8/28/95	DRILLING RIG: CME 75
TOC ELEVATION: 4217.45 ft-MSL	DRILLING METHOD: 4 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 14.5 ft-BGL	SAMPLING METHOD: 3 in. ID CME core
BEGIN COMPLETION: 8/15/95	END COMPLETION: 8/15/95



Log of Soil Boring: SB1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 2, Waste POL Fuel Spill
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 17
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 7.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893164.48	DRILLER: Steve Mott
EAST COORDINATE: 1873630.49	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4218.03 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/02/92 @ 1445 END: 12/02/92 @ 1530	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2			19.6	SILT, and CLAY, some SAND: (5Y 3/2), dk. olive gray, soft, dry, non-plastic	ML		ID: UANG-S2-SB1 (0.5-2.5) Headspace @ 2.00 ft
3			30.6	SAND, and CLAY: (5G 5/1), greenish gray, soft, damp, mica	SC		Headspace @ 3.5 ft
4				SILT, and SAND, some CLAY: (5G 5/1), greenish gray, mica grains, moist, non-plastic	ML		
5			NA	CLAY, some SAND, some SILT: (5G 5/1), greenish gray, saturated, semi-plastic, more sand @ bottom	NA CL		ID: UANG-S2-SB1 (5.0-7.0) Headspace not taken PID battery dead
6							
7				Total depth=7.0 ft.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 2, Waste POL Fuel Spill
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 17
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893125.50	DRILLER: Steve Mott
EAST COORDINATE: 1873641.09	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4218.15 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/02/92 @ 1610 END: 12/02/92 @ 1645	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1	✕		NA	ASPHALT:	NA		
2				GRAVEL, and SAND, some CLAY: reddish brown fill material	GC		
3				CLAY, and SILT: (5Y 6/2), lt. olive gray, damp, non-plastic	CL NA		Not enough sample for PID
4	✕	✕	1.9	SILT, and SAND, some CLAY: (5Y 6/3), pale olive, soft, moist, non-plastic	ML		ID: UANG-S2-SB2 (2.5-4.5) Headspace @ 4.0 ft
5	✕	✕	4.1	CLAY, and SAND, some SILT: mottled (5Y 5/2), olive gray, and (10YR 4/6), dk. yellow brown, saturated @ 6.0 ft, soft, non-plastic	CL		ID: UANG-S2-SB2 (4.5-6.5) Headspace @ 5.5 ft
6					NA		
7				Total depth=6.5 ft.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 2, Waste POL Fuel Spill
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 19
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893165.64	DRILLER: Steve Mott
EAST COORDINATE: 1873605.26	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4217.98 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/03/92 @ 1045 END: 12/03/92 @ 1200	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			NA	ASPHALT:	NA		No sample collected
				GRAVEL, and SAND, some CLAY: fill material	GC		
2					NA		
3			957	SAA	GC		ID: UANG-S2-SB3 (2.5-4.5) Headspace @ 3.25 ft
4				CLAY, and SILT, little SAND: (5G 5/1), greenish gray, moist, odor, semi-plastic	CL		
5							ID: UANG-S2-SB3 (4.5-6.5) Headspace @ 5.75 ft
6			45				
					NA		Collected duplicate- UANG-S2-SB3 (6.5-8.5)
7				Total depth=6.5 ft.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 2, Waste POL Fuel Spill
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 54
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893170.39	DRILLER: Steve Mott
EAST COORDINATE: 1873571.21	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4217.72 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Augers
DRILLING BEGIN: 12/17/92 @ 1050 END: 12/17/92 @ 1140	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			38.8	ASPHALT:	NA		Headspace @ 2.0 ft Headspace @ 3.50 ft ID: UANG-S2-SB4 (4.5-6.5) Headspace @ 5.50 ft
2				CLAY, and SAND, some SILT: (2.5Y 5/3), lt. olive brown, moist, soft, non-plastic	CL		
3				CLAY, and SAND: mottled (5Y 5/3), olive, and (2.5Y 6/6), olive yellow, soft, non-plastic, moist, saturated at bottom	CL		
4							
5				CLAY, some SAND: (5Y 5/3), olive, and olive yellow, soft, saturated,	CL		
6			33.3				
7				Total depth=6.5 ft.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 2, Waste POL Fuel Spill
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 69
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: J. F. Bernard	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893163.74	DRILLER: Dave Mott
EAST COORDINATE: 1873658.30	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4218.14 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/30/92 @ 1500 END: 12/30/92 @ 1535	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			0.0	ASPHALT:	NA		
				GRAVEL, and SAND: fill material	GC		
2				SILT, and SAND, fine, trace CLAY: (2.5Y 3/2), v. dk. grayish brown	SM		Headspace @ 1.5 ft
3			0.0	SAND, fine, trace SILT: (2.5Y 5/4), lt. olive brown,	SM		Headspace @ 3.50 ft
4							
5			0.0	CLAY: (5Y 6/3), pale olive, moist, plastic	CL		Headspace @ 5.50 ft
6							
7			4.5				ID: UANG-S2-SB5 (6.5-8.5) Headspace @ 7.5 ft
8				SAND, coarse: (2.5Y 5/6), lt. olive brown	SW		Sample intervals not recorded
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB6

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard

SITE LOCATION: Site 2, Waste POL Fuel Spill

PROJECT NUMBER: UT014

REF. LOGBOOK: 2, pg. 70

CLIENT/PROJECT: HAZWRAP/NGB

TOTAL DEPTH: 8.5 ft-BGL

LOGGED BY: J. F. Bernard

DRILLING CONTRACTOR: PC Exploration

NORTH COORDINATE: 893187.17

DRILLER: Dave Mott

EAST COORDINATE: 1873633.19

DRILLING RIG: Mobile B-57

GROUND ELEVATION: 4218.08 ft-MSL

DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger

DRILLING BEGIN: 12/30/92 @ 1540 END: 12/30/92 @ 1615

SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				CONCRETE:	NA		
2				GRAVEL, and SAND: fill material	GC		
3			0.0	SILT, and SAND, fine, trace CLAY: (2.5Y 3/2), v. dk. grayish brown	SM		Headspace @ 1.5 ft
4			0.0	SAND, fine, trace SILT: (2.5Y 5/4), lt. olive brown, moist	SM		Headspace @ 3.50 ft
5			0.4	CLAY: (5Y 6/3), pale olive, moist, plastic	CL		Headspace @ 5.50 ft
6			1.6				
7							
8				SAND, fine to coarse: (2.5Y 5/6), lt. olive brown	SW		ID: UANG-S2-SB6 (6.5-8.5) Headspace @ 7.5 ft
9				Total depth=8.5 ft.			Sample intervals not recorded
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Site 3 - Drum Burial Locations

Log of Monitoring Well: S3MW1

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 3, Drum Burial Locations
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg.78
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 896580.9640
GROUND ELEVATION: 4213.16 ft-MSL	EAST COORDINATE: 1874095.4623
WELL DEPTH: 17.13 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 3.51 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4212.15 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4215.43 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 19.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/07/93	END COMPLETION: 01/07/93

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1			31.3	SAND and GRAVEL, some SILT: (10YR 5/4) yellowish brown, fill material	GM		<p>Concrete Pad</p> <p>Borehole Diam. 10-1/4 inches</p> <p>2-inch Diam. PVC Casing</p> <p>GROUT</p> <p>BENTONITE SEAL</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>Bottom Sump</p>
2				SAND, and SILT: (5Y 4/2), olive gray, soft	SM		
3			20.3	SILT: (5Y 2.5/1), black, organic, shells, soft	OL		
4				SILT, and CLAY: (5Y 3/1), v. dk. gray, organic, shells, soft	OL		
5			21.1	CLAY, and SILT: (5Y 5/2), olive gray, firm, non-plastic, saturated @ bottom of spoon sample, moist, non-plastic	CL		
6				SILT, and SAND, fine: grades to sand @ bottom, (5Y 5/2), olive gray and (10YR 5/6), yellowish brown, (10YR 3/3) dk. brown modules	SM		
7			27.4				
8				SAND, coarse: (5Y 5/1), gray, granitic minerals	SP		
9			NA				
10				CUTTINGS: SAND, coarse, SAA	SP		
11							<p>Concrete Pad</p> <p>Borehole Diam. 10-1/4 inches</p> <p>2-inch Diam. PVC Casing</p> <p>GROUT</p> <p>BENTONITE SEAL</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>Bottom Sump</p>
12							
13							
14							
15							
16							
17							
18				CLAY @ 19 feet			
19				Total depth = 19.0 ft.			
20							
21							

Log of Monitoring Well: S3MW2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 3, Drum Burial Locations
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg.92
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 896486.6118
GROUND ELEVATION: 4216.25 ft-MSL	EAST COORDINATE: 1874122.0678
WELL DEPTH: 20.74 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 7.53 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4211.95 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4218.71 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 21.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/19/93	END COMPLETION: 01/20/93



Log of Soil Boring: SB1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 3, Drum Burial Locations
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 55
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 896522.63	DRILLER: Steve Mott
EAST COORDINATE: 1874101.71	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4213.49 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/17/92 @ 1410 END: 12/17/92 @ 1520	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				SAND, and GRAVEL, some SILT: brown	GM		
2			118	SILT, and SAND: (5Y 4/2), olive gray and (5Y 2.5/1), black firm, crumbly, damp	ML		Headspace @ 1.75 ft
3				SILT and CLAY: (5Y 2.5/1), black, organic, firm, crumbly, damp, odor	OL		
4			151	SILT and CLAY: (5Y 3/1), v. dk. gray, damp, odor	OL		Headspace @ 3.5 ft
5			176				ID: UANG-S3-SB1 (4-6) Headspace @ 5.0 ft
6				CLAY: (5GY 4/1), dk. greenish gray, soft, very moist, semi-plastic. shell fragments	CL		
7			32	CLAY: (5Y 5/2), olive gray, soft, saturated, shell fragments	CL		ID: UANG-S3-SB1 (6-8) Headspace @ 7.0 ft
8				SAND: Coarse, (5Y 4/1), dk. gray, well sorted, subrounded, loose	SP		
9				Total depth=8.0 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 3, Drum Burial Locations
PROJECT NUMBER: Ut014	REF. LOGBOOK: 2, pg. 56
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 896520.08	DRILLER: Steve Mott
EAST COORDINATE: 1874137.17	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4213.36 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/17/92 @ 1530 END: 12/17/92 @ 1610	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS	
1			24 9 74.8	SAND, and GRAVEL, and CLAY: (10YR 4/4), dk. yellowish brown, then (5Y 3/2), dk. olive gray, and (5Y 2.5/1), black, fill material	GC		Headspace @ 2.00 ft Headspace @ 3.5 ft ID: UANG-S3-SB2 (4.5-6.5) Headspace @ 5.5 ft Collected MS and MSD	
2								
3				SILT, and CLAY: (5Y 3/1), v. dk. gray, crumbly, soft, roots, damp	OL			
4				CLAY, and SILT: (5Y 3/2), dk. olive gray, soft, organic, moist	CL			
5				CLAY, and SILT: (5Y 6/3), pale olive, crumbly, moist	CL			
6				CLAY, and SILT, some SAND: (5Y 4/1), dk. gray, soft, sand @ bottom	CL			
7				Total depth=6.5 ft.				
8								
9								
10								
11								
12								
13								
14								
15								
16								
17								
18								
19								
20								
21								

Log of Soil Boring: SB3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 3, Drum Burial Locations
PROJECT NUMBER: Ut014	REF. LOGBOOK: 2, pg. 56
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 896405.67	DRILLER: Steve Mott
EAST COORDINATE: 1874351.77	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4213.51 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/17/92 @ 1630 END: 12/17/92 @ 1710	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			10.7	SAND, and GRAVEL, some CLAY: (2.5Y 4/2), dk. grayish brown, fill material	GC		Headspace @ 1.50 ft
2			15	SAND, and SILT, some GRAVEL: (2.5Y 3/2), v. dk. grayish brown, soft	SM		Headspace @ 2.75 ft
3							
4				SILT, and CLAY, trace GRAVEL: (5Y 5/3), olive, and (5Y 2.5/1), black, soft, moist	ML		
5			20.9	SILT, and CLAY: (5Y 2.5/1), black, organic, soft, moist, no shells	OL		ID: UANG-S3-SB3 (4-6) Headspace @ 5.0 ft
6				CLAY, and SAND: (5Y 5/3), olive, soft, moist	CL		Collected duplicate- UANG-S3-SB3 (6-8)
7				Total depth=6.0 ft.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB4

ENGINEERING-SCIENCE, INC.






PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 3, Drum Burial Locations
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 58
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 896580.33	DRILLER: Steve Mott
EAST COORDINATE: 1874125.37	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4212.78 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/18/92 @ 1410 END: 12/18/92 @ 1520	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				DEBRIS: Asphalt, etc, no recovery	NA		
2							
3			130	SILT, and CLAY, trace of GRAVEL: (5Y 3/1), v. dk. gray, soft, moist, organic, roots, non-plastic	OL		
4				CLAY, and SILT, trace SAND and GRAVEL: (5Y 4/1), dk. gray, soft	CL		Headspace @ 3.00 ft
5			NA	CLAY, and SILT, trace GRAVEL: (5Y 5/2), olive gray, soft, odor, slightly plastic	CL		Headspace @ 5.0 ft
6							
7			NA	CLAY, and SILT, some SAND: (5Y 5/3), olive, and zones of (2.5Y 4/4), olive brown, some mica, soft, non-plastic	CL		ID: UANG-S3-SB4 (6-8) Headspace @ 7.0 ft
8				Total depth=8.0 ft.			
9							PID not functioning properly-H2O vapor rise
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 3, Drum Burial Locations
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 69
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.0 ft-BGL
LOGGED BY: J. F. Bernard	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 896543.09	DRILLER: Dave Mott
EAST COORDINATE: 1874073.97	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4213.53 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Augers
DRILLING BEGIN: 12/30/92 @ 1400 END: 12/30/92 @ 1450	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DRILLING BEGIN: 12/30/92 @ 1400' END: 12/30/92 @ 1400'							
DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			0.0	FILL	GC		ID: UANG-S3-SB5 (4-6) Analytical sample interval not recorded
2				SILT, and CLAY: (2.5Y 3/2), v. dk. grayish brown, moist to dry, shell fragments, semi-plastic	OL		
3			0.0	CLAY, and SILT: (2.5Y 6/3), lt. yellowish brown, plastic, moist to dry	CL		
4				SAND, fine, and SILT, trace GRAVEL: (2.5Y 6/3), lt. yellowish brown, moist	SM		
5			0.0				
6			0.0				
7			0.0				
8				Total depth=8.0 ft.			
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Site 4 - Fire Training Area 1

Log of Monitoring Well: S4MW1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg.75
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 895287.9446
GROUND ELEVATION: 4214.41 ft-MSL	EAST COORDINATE: 1874350.6717
WELL DEPTH: 17.35 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.97 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4210.18 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4214.06 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 20.0 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/06/93	END COMPLETION: 01/07/93

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1				ASPHALT	NA		
2			34	SAND, and GRAVEL, some SILT: (10YR 5/3), brown, fill material	GM		
3				SAND, and GRAVEL, some SILT: (5Y 4/2), olive gray	GM		
4			9.7	SILT, and CLAY: (5GY 6/1), greenish gray, soft	ML		
5				SILT, and CLAY, trace SAND: (5Y 6/2), lt. olive gray, mottled with (5GY 6/1), greenish gray, moist	ML		
6			51.6	SILT: (5Y 2.5/1), black, organic, shells, soft	OL		
7				CLAY, and SILT: (5Y 4/1), dk. gray, to (5Y 5/2), olive gray, soft, moist	CL		
8			27.2	CLAY, and SILT: (5Y 6/3), pale olive, with (2.5Y 5/6), lt. olive brown, saturated, soft	CL		
9				SAND, fine, and SILT: (5Y 5/1), gray, soft, mica, saturated	SM		
10			42.8	CUTTINGS: SAND,	SW		
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							
				Total depth = 20.0 ft. Clay @ 20 ft			

Log of Soil Boring: SB1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 23
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895163.41	DRILLER: Steve Mott
EAST COORDINATE: 1874386.03	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.95 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Augers
DRILLING BEGIN: 12/04/92 @ 1350 END: 12/04/92 @ 1450	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	P10 HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2				GRAVEL: fill material	GC		
3				SILT, and CLAY: (5G 5/1), greenish gray, soft, damp, crumbly, semi-plastic	ML		
4			44	SILT, and CLAY: (5Y 3/1), v. dk. gray, organic, gastropod shells, soft, damp, reducing environment	OL		ID: UANG-S4-SB1 (2.5-4.5) Headspace @ 3.50 ft
5			370				Headspace @ 5.0 ft
6							
7					NA		
8			40	SILT, and CLAY: (5Y 4/1), dk. gray, soft, saturated @ 8.0 ft,	ML		ID: UANG-S4-SB1 (6.5-9.0) Headspace @ 8.0 ft
9				SAND, fine: (5Y 4/1), dk. gray,	SW		
10				Total depth=9.0 ft.			
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 25
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895188.09	DRILLER: Steve Mott
EAST COORDINATE: 1874359.80	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.85 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/07/92 @ 0925	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers
END: 12/07/92 @ 1030	

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2				GRAVEL: fill material	GC		No sample collected
3				SILT, and CLAY: (5G 5/2), grayish green w/ black streaks, soft, damp, non-plastic	ML		ID: UANG-S4-SB2 (2.5-4.5) Headspace @ 3.50 ft
4			1123	SILT, and CLAY: (5Y 2.5/1), black, organic, gastropod shells, roots, soft, damp, non-plastic, reducing environment	OL		Headspace @ 5.0 ft
5			0.0	SILT, and CLAY: (5Y 4/1), dk. gray, soft, moist, more silt @ the bottom of the interval	ML		
6				SAND, fine, and SILT: (5Y 4/1), dk. gray, loose, mica, saturated	SM		ID: UANG-S4-SB2 (6.5-9.0) Headspace @ 7.0 ft
7			0.0				
8							
9				Total depth=9.0 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard

SITE LOCATION: Site 4, Fire Training Area I

PROJECT NUMBER: UT014

REF. LOGBOOK: 2, pg. 26

CLIENT/PROJECT: HAZWRAP/NGB

TOTAL DEPTH: 9.0 ft-BGL

LOGGED BY: T. M. Jensen

DRILLING CONTRACTOR: PC Exploration

NORTH COORDINATE: 895192.26

DRILLER: STEve Mott

EAST COORDINATE: 1874408.32

DRILLING RIG: Acker Soil Max

GROUND ELEVATION: 4214.86 ft-MSL

DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger

DRILLING BEGIN: 12/07/92 @ 1050 END: 12/07/92 @ 1150

SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2					NA		
3				GRAVEL: fill material	GC		No sample collected
4			2.0	SAND, and SILT: (5Y 4/2), olive gray,	SM		
5				SILT, and SAND: (5Y 2.5/1), black,	ML		ID: UANG-S4-SB3 (2.5-4.5) Headspace @ 3.50 ft
6				CLAY, and SILT: (5G 5/1), greenish gray, soft, damp, non-plastic	CL		
7			9.2	SAND, fine, and SILT: (5Y 3/1), v. dk. gray, soft, damp	SM		
8				SILT, some CLAY: (5Y 2.5/1), black, organic, shells, soft, non-plastic	OL		Headspace @ 5.5 ft
9				CLAY, and SILT, some SAND: (5Y 4/1), dk. gray, soft, damp, non-plastic	CL		
10			0.0	SAND, fine, and SILT: (5Y 5/1), gray, and (5Y 5/2), olive gray, at the bottom of the interval, soft, loose, iron oxide stains, saturated @ 8.0 ft.,	SM		ID: UANG-S4-SB3 (6.5-9.0) Headspace @ 7.5 ft
11				Total depth=9.0 ft.			
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 26
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895219.43	DRILLER: Steve Mott
EAST COORDINATE: 1874383.54	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.70 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/07/92 @ 1340 END: 12/07/92 @ 1435	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			10	ASPHALT:	NA		No sample collected
2				GRAVEL: fill material	GC		
3			5.0	SILT: (5Y 3/1), v. dk. gray, soft,	ML		ID: UANG-S4-SB4 (2.5-4.5) Headspace @ 3.50 ft
4				SILT, and CLAY: (5Y 3/2), dk. olive gray, mottled with (5G 5/2), gray green, very soft, moist, plastic	ML		
5				SILT: (5Y 2.5/1), black, organic, shells, soft, moist, non-plastic	OL		
6			8.1	SILT: (5Y 5/1), gray, moist, non-plastic	ML		Headspace @ 6.0 ft
7				SAND, fine, and SILT: (5Y 4/1), dk. gray, soft, mica, moist to saturated	SM		
8			8.1				ID: UANG-S4-SB4 (6.5-9.0) Headspace @ 8.0 ft
9							
10				Total depth=9.0 ft.			Collected duplicate sample UANG-S4-SB4 (9-11)
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 47
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 7.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895137.22	DRILLER: Steve Mott
EAST COORDINATE: 1874388.31	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.01 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/15/92 @ 1345 END: 12/15/92 @ 1415	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PTD HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2			2.5	CLAY, some SILT: (5Y 6/3), pale olive, dry, soft to firm, non-plastic, some (5Y 3/1), v. dk. gray inclusions	CL		Headspace @ 2.00 ft
3				SILT: (5Y 2.5/1), black, organic, gastropod shells, soft, damp, non-plastic	OL		
4			3.4	CLAY, some SILT: (5Y 6/2), lt. olive gray, soft, med plasticity, saturated @ 4.5 feet	CL		Headspace @ 4.0 ft
5				CLAY, and SILT, some SAND: (5Y 4/1), dk. gray, shells, soft, non-plastic	CL		
6			10.7				ID: UANG-S4-SB5 (5-7) Headspace @ 6.0 ft
7				Total depth=7.0 ft.			Collected duplicate sample UANG-S4-SB5 (7-9)
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB6

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 48
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895191.14	DRILLER: Steve Mott
EAST COORDINATE: 1874316.50	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.49 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/15/92 @ 1420 END: 12/15/92 @ 1510	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS		
1			8.0	ASPHALT:	NA		Headspace @ 1.5 ft		
				GRAVEL, and SAND: fill material	NA				
2				CLAY, and SILT: (5Y 6/2), lt. olive gray, soft, crumbly, zones that are cohesive, damp	CL				
3					137	CLAY, and SILT: (5Y 5/2), olive gray, mottled with (5Y 4/1), dk. gray, soft, moist,	CL		ID: UANG-S4-SB6 (2.5-4.5) Headspace @ 3.50 ft
4				SILT: (5Y 2.5/1), black, organic, shells, soft, moist, non-plastic		OL			
			CLAY, and SILT: (5Y 4/1), dk. gray, moist, crumbly, shells	CL					
5					43.3	CLAY, and SAND, some SILT: (5Y 4/1), dk. gray, soft, crumbly, saturated, 3 in. GRAVEL zone @ 5.0 ft.	CL		Headspace @ 5.5 ft
6									
7			3.4	SAND, fine, and CLAY: (5Y 5/2). olive gray, soft, saturated	SC		ID: UANG-S4-SB6 (6.5-8.5) Headspace @ 7.5 ft		
8									
9				Total depth=8.5 ft.					
10									
11									
12									
13									
14									
15									
16									
17									
18									
19									
20									
21									

Log of Soil Boring: SB7

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 49
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 10.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895188.84	DRILLER: Steve Mott
EAST COORDINATE: 1874380.48	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.77 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/15/92 @ 1625 END: 12/15/92 @ 1700	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			75	ASPHALT:	NA		Headspace @ 2.00 ft
2				GRAVEL, and SAND: fill material	GC		
3				SILT, and CLAY: (5Y 4/1), dk. gray, soft, damp,	ML		
4			710	CLAY: (5GY 5/1), greenish gray, firm, moist, non-plastic	CL		Headspace @ 4.00 ft
5				SILT: (5Y 2.5/1), black, organic, shells,	OL		
6				CLAY, and SAND, some SILT: (5Y 5/1), gray, soft, crumbly, odor, saturated @ 5 ft to 6 ft	CL		
7			1705	CUTTINGS:	NA		ID: UANG-S4-SB7 (4.5-6.5) Collected MS and MSD Headspace @ 6.0 ft
8							
9							
10			59.1	SAND, fine, some SILT: (5Y 4/1), dk. gray, soft, mica, saturated	SW		Headspace @ 10.0 ft
11				Total depth=10.5 ft.			
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB8

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 67
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: J. F. Bernard	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895194.58	DRILLER: Dave Mott
EAST COORDINATE: 1874294.42	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4214.58 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/29/92 @ 1345 END: 12/29/92 @ 1450	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2			494	GRAVEL, and SAND: fill material	GC		ID: UANG-S4-SB8 0.5-2.5) Headspace @ 1.50
3				CLAY, and SILT: (5Y 5/2), olive gray, and (5YR 5/4), reddish brown, plastic, moist	CL		
4			88.3	SILT, some CLAY: (5Y 3/1). v. dk. gray, dry, slightly plastic	ML		Headspace @ 3.50 ft
5				SILT, and CLAY, trace GRAVEL: (5Y 5/1), gray, moist, plastic,	ML		ID: UANG-S4-SB8 (4.5-6.5) Headspace @ 5.5 ft
6			94.1				
7				SAND, fine to coarse, some SILT: (5Y 4/3), olive,	SM		Headspace @ 7.5 ft
8			2.0				Sample intervals not recorded
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB9

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 4, Fire Training Area 1
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 67
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: J. F. Bernard	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895226.37	DRILLER: Dave Mott
EAST COORDINATE: 1874347.50	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4214.50 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/29/92 @ 1515 END: 12/29/92 @ 1550	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers


DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2			0.0	SAND, coarse: washed sand fill material	GC		Headspace @ 1.50
3				SILT, and SAND, some CLAY: (10 YR 4/3), dk. brown,	SM		
4			4.7	SILT, and CLAY, trace SAND, fine: (2.5Y 5/3), lt. olive brown, moist	ML		ID: UANG-S4-SB9 (2.5-4.5) Headspace @ 3.50 ft
5				SAND, coarse: (5Y 3/1), v. dk. gray, saturated	SP		
6			0.0	SILT, some CLAY: (5Y 5/1), gray, shells, dry, non-plastic	ML		ID: UANG-S4-SB9 (4.5-6.5) Headspace @ 5.5 ft
7				CLAY, and SILT: (5Y 5/2), olive gray, moist	CL		Headspace @ 7.5 ft
8			0.0				
9				Total depth=8.5 ft.			Sample interval not recorded
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Site 5 - Fire Training Area 2

Log of Monitoring Well: S5MW1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 77
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 895689.0174
GROUND ELEVATION: 4215.05 ft-MSL	EAST COORDINATE: 1874522.7616
WELL DEPTH: 17.08 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.09 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4210.22 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4216.47 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 20.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers
BEGIN COMPLETION: 01/07/93	END COMPLETION: 01/07/93



Log of Soil Boring: SB1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 27
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895709.80	DRILLER: Steve Mott
EAST COORDINATE: 1874431.82	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.85 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/07/92 @ 1540 END: 12/07/92 @ 1630	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			0.0	SAND, some GRAVEL: (2.5Y 7/3), pale yellow, soft, more sand at the bottom of the interval, possibly non-native fill material	GM		ID: UANG-S5-SB1 (0-2) Headspace @ 1.00 ft
2					NA		Headspace not taken sample recovery low
3				SAND, fine, and SILT: (2.5Y 7/3), pale yellow, soft, damp, low recovery	SM		
4				SILT, some CLAY: (5Y 2.5/1), black, organic, soft, moist, shells	OL		
5			0.0	SILT, and SAND, fine: (2.5Y 7/2), lt. gray, very soft, roots, moist	ML		Headspace @ 5.5 ft
6				SILT, and SAND, fine: (2.5Y 5/2), gray brown, soft, moist	ML		
7			2.2	SAND, med, some SILT: (5Y 4/1), dk. gray, mica, iron oxide stains, saturated	SM		ID: UANG-S5-SB1 (6.0-8.5) Headspace @ 7.0 ft
8				Total depth=8.5 ft.			
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 29
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895757.40	DRILLER: Steve Mott
EAST COORDINATE: 1874424.51	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.38 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/08/92 @ 0905 END: 12/08/92 @ 1000	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring sampler

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PTD HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1					NA		
2				SAND, some SILT, some CLAY, little GRAVEL: (5Y 3/2), dk. olive gray, moist, soft, surface soil, appears non-native	GC		Headspace not taken
3					NA		
4			2.2	SAND, fine, and SILT: (5Y 7/3), pale yellow, dry, soft, crumbly	SM		ID: UANG-S5-SB2 (2-4)
5				SILT, some SAND: (5Y 3/2), dk. olive gray, soft, crumbly, damp, roots	ML		Headspace @ 3.5 ft
6					NA		
7				SILT, some CLAY: (5Y 2.5/1), black, organic, roots, soft, damp, non-plastic, white streaks, parts into thin slices	OL		Headspace @ 5.0 ft
8			8.0	SILT, and CLAY: (5Y 6/2), lt. olive gray, soft, moist, crumbly, some roots, non-plastic	ML		
9				SAND, fine to med, some SILT: (5Y 6/2), lt. olive gray, soft, loose, mica, saturated @ 6.5 feet	SM		ID: UANG-S5-SB2 (6.0-8.5)
10				Total depth=8.5 ft.			Headspace @ 8.0 ft
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 29
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895805.60	DRILLER: Steve Mott
EAST COORDINATE: 1874420.15	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.18 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/08/92 @ 1020 END: 12/08/92 @ 1100	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring sampler

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1					NA		
2			NA	SAND, some SILT, some CLAY, little GRAVEL: (5Y 3/2), dk. olive gray, moist, soft, surface soil, appears non-native	GC		Headspace not taken
3			3.0	SAND, fine, and SILT, some GRAVEL: (5Y 6/2), pale yellow, soft, loose, asphalt chunks, non-native	SM		ID: UANG-S5-SB3 (2-4) Headspace @ 3.0 ft
4							
5			2.0	SILT, some CLAY: (5Y 2.5/1), black, organic, soft, moist, shells, med-plastic, white secondary material	OL		Headspace @ 5.0 ft
6				SILT, and CLAY: (5Y 5/2), olive gray, soft, moist, non-plastic	ML		
7			1.0				ID: UANG-S5-SB3 (6.0-8.5) Headspace @ 7.0 ft
8				SAND, fine to med, some SILT: (5Y 4/1), dk. gray, soft, loose, mica, saturated	SM		Collected duplicate sample- UANG-S5-SB3 (8.5-11.0)
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 30
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895849.51	DRILLER: Steve Mott
EAST COORDINATE: 1874415.78	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.85 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/08/92 @ 1110 END: 12/08/92 @ 1200	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring sampler

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			5.0	SAND, some SILT, little GRAVEL: (5Y 4/2), olive gray, moist, soft,	GM		Headspace @ 0.75 ft
2				SAND, fine, some SILT: (5Y 6/3), pale olive, soft, loose	SM		
3				SAND, fine, and SILT, trace GRAVEL: (5Y 7/3), pale yellow, soft, some areas more dense	SM		
4			31.0	SILT, some CLAY: (5Y 2.5/1), black, organic, soft, moist, shells, roots, non-plastic,	OL		ID: UANG-S5-SB4 (2-4) Headspace @ 3.5 ft
5			36.0				Headspace @ 4.5 ft
6							
7				SILT, and CLAY: (5Y 5/2), olive gray, soft, moist, non-plastic	ML		
8			5.0	SAND, med, some SILT: (5Y 5/2), olive gray, soft, loose, mica, saturated	SM		ID: UANG-S5-SB4 (6.0-8.5) Headspace @ 8.0 ft
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 97
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 7.0 ft-BGL
LOGGED BY: T. M. JENSEN	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895904.51	DRILLER: DALLAS PRILL
EAST COORDINATE: 1874411.51	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4213.30 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 02/09/93 @ 1505 END: 02/09/93 @ 1530	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1					NA		
2				SAND, and SILT, some GRAVEL: (2.5Y 4/2), dk. grayish brown, soft,	SM		
3			BG	SILT, little SAND: (5Y 2.5/1), black, organic, soft, shells, roots,	OL		ID: UANG-S5-SB5 (1-3) Headspace @ 2.50 ft
4			BG	SILT, trace SAND: (5Y 4/1), dk. gray, soft, moist, some shells, saturated @ 5.5 feet to 7.0 feet			Headspace @ 3.5 ft
5							
6							
7			BG				ID: UANG-S5-SB5 (5.0-7.0) Headspace @ 6.5 ft
8				Total depth=7.0 ft.			BG=background levels
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB6

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 94
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 7.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895796.54	DRILLER: Dan Bowden
EAST COORDINATE: 1874351.21	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4215.75 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 02/08/93 @ 1225 END: 02/08/93 @ 1255	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1					NA		Began sampling @ 1 ft
2	⊗	⊗	0.0	SAND, and SILT, some GRAVEL: (5Y 3/2), dk. olive gray, moist, soft,	SM	⊗ ⊗ ⊗ ⊗	ID: UANG-S5-SB6 (1-3) Headspace @ 2.50 ft
3			0.0	SAND, and SILT: (5Y 5/3), olive,	SM NA	⊗ ⊗ ⊗ ⊗	Headspace @ 3.5 ft
4	⊗			SAND, and SILT, little GRAVEL: (5Y 4/3), olive, soft, crumbly, moist,	SM	⊗ ⊗ ⊗ ⊗	
5					NA		
6	⊗	⊗	0.0	SAND, and SILT, little GRAVEL: (2.5Y 4/3), olive brown, soft	SM	⊗ ⊗ ⊗ ⊗	ID: UANG-S5-SB6 (5.0-7.0) Headspace @ 6.5 ft
7				Total depth=7.0 ft.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB7

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 5, Fire Training Area 2
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 95
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 7.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895809.37	DRILLER: Dan Bowden
EAST COORDINATE: 1874496.76	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4214.79 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 02/09/93 @ 1320 END: 02/09/93 @ 1350	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1					NA		Began sampling @ 1 ft
2			BG	SAND, and SILT, some GRAVEL: (2.5Y 4/2), dk. grayish brown, soft, loose	GM		ID: UANG-S5-SB7 (1-3) Headspace @ 2.50 ft
3			BG		NA		Headspace @ 3.5 ft
4				SAND, and SILT, some GRAVEL: (2.5Y 4/2), dk. grayish brown, loose, moist	SM		
5				SAND, and SILT, little GRAVEL: (5Y 3/1, v. dk. gray, soft, saturated	SM		
6							
7			BG	SILT, little SAND: (2.5Y 6/2), lt. olive gray, firm, crumbly, saturated Total depth=7.0 ft.	ML		ID: UANG-S5-SB7 (5.0-7.0) Headspace @ 6.5 ft
8							BG=Background level
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Site 6 - Ramp Washdown

Log of Monitoring Well: S6MW1

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown Area
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 87
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893297.2779
GROUND ELEVATION: 4216.92 ft-MSL	EAST COORDINATE: 1873076.2208
WELL DEPTH: 17.24 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.70 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4211.78 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4216.71 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 18.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/15/93	END COMPLETION: 01/15/93

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1				CONCRETE	NA		Concrete Pad
2			3.7	SAND, and SILT, some CLAY: (5Y 5/2), olive gray, soft, moist	SM		BENTONITE SEAL
3							
4			3.6	SAND and SILT, some CLAY: (5Y 5/2), olive gray, and (2.5Y 5/6), lt. olive brown, soft, saturated	SM		Borehole Diam. 10-1/4 inches
5							2-inch Diam. PVC Casing
6			3.6	CLAY: (5Y 6/2), lt olive gray, soft, saturated	CL		
7							
8			2.7	CLAY, and SILT, some SAND: (5Y 5/1), gray, soft, saturated, some mica	ML		
9							
10			3.1	CLAY: (5Y 6/2), lt. olive gray, and (2.5Y 5/6), lt. olive brown, and (5Y 2.5/1), black, organic network, crumbly, soft	OL		
11							
12					SM		
13			2.9	SAND, fine, and SILT: (5Y 5/2), olive gray, and zones of (2.5Y 5/6), lt. olive brown			20/40 COLORADO SILICA SAND PACK
14							0.010 SLOTTED PVC SCREEN
15			3.3	CLAY: (N3/3), v. dark gray, soft, hydrogen sulfide smell, organic	OH		
16				CUTTINGS: CLAY, same as above	OH		Bottom Sump
17							
18				Total depth = 18.0 ft.			
19							
20							
21							

Log of Monitoring Well: S6MW2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown Area
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 89
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 894624.7535
GROUND ELEVATION: 4216.58 ft-MSL	EAST COORDINATE: 1873082.7674
WELL DEPTH: 17.26 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 7.34 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4210.42 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4216.32 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 18.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/18/93	END COMPLETION: 01/18/93



Log of Monitoring Well: S6MW3

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown Area
PROJECT NUMBER: UT014	REF. LOGBOOK: 2. pg. 90
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 895411.8149
GROUND ELEVATION: 4216.89 ft-MSL	EAST COORDINATE: 1873069.1046
WELL DEPTH: 16.75 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 8.01 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4209.43 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4219.29 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 18.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/18/93	END COMPLETION: 01/18/93

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1			3.7	SAND and GRAVEL, some SILT: (5Y 3/2), dk. olive gray	GM		
2				SILT, and CLAY, some SAND: (5Y 5/2), olive gray, and (5Y 3/1), v. dk. gray, moist	CL		
3			0.0				
4				SILT, and CLAY, some SAND: (5Y 3/1), olive, and (5Y 5/2), olive gray, moist, non-plastic	CL		
5			0.0				
6				SILT: (5Y 2.5/1), black, organic, shells	OL		
7			0.0	CLAY, and SILT: (2.5Y 6/2), lt. brown gray, non-plastic, saturated	CL		
8				CLAY, and SILT: (5Y 5/2), olive, soft, non-plastic	CL		
9			0.0	SAND, fine, and CLAY, some SILT: (2.5Y 5/2), gray brown, with (2.5Y 5/6), lt. olive brown, soft	SM		
10				SILT, some CLAY, some SAND: (5Y 5/2), olive gray, and (2.5Y 3/3), dk. olive brown, very soft, saturated	ML		
11			0.5				
12				SILT, and SAND, fine: (2.5Y 4/2), dk. gray brown, soft, mica	MH		
13			0.0				
14				SAND, fine: (5Y 5/1), gray, and (2.5Y 4/4), olive brown, mica	SW		
15			0.0				
16				CUTTINGS: SAND, same as above	SW		
17							
18				Total depth = 18.0 ft.			
19							
20							
21							

Log of Monitoring Well: S6MW4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 3, pg.4
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 893790.63
GROUND ELEVATION: 4214.86 ft-MSL	EAST COORDINATE: 1872969.02
WELL DEPTH: 14.5 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.97 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: 4208.72 ft-MSL	DRILLER: Russ Werner
DATE MEASURED: 8/24/95	DRILLING RIG: CME 75
TOC ELEVATION: 4214.69 ft-MSL	DRILLING METHOD: 4 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 14.5 ft-BGL	SAMPLING METHOD: 3 in. ID CME core
BEGIN COMPLETION: 8/17/95	END COMPLETION: 8/17/95



Log of Monitoring Well: S6MW5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 3, pg.4
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 894815.41
GROUND ELEVATION: 4214.78 ft-MSL	EAST COORDINATE: 1872974.49
WELL DEPTH: 14.0 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 7.04 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: 4207.49 ft-MSL	DRILLER: Russ Werner
DATE MEASURED: 8/24/95	DRILLING RIG: CME 75
TOC ELEVATION: 4214.53 ft-MSL	DRILLING METHOD: 4 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 14.0 ft-BGL	SAMPLING METHOD: 3 in.ID. CME core
BEGIN COMPLETION: 8/17/95	END COMPLETION: 8/17/95

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1				SAND, and CLAY, some GRAVEL: (5Y 5/3), olive, dry to moist near bottom	SC		
2			0.9				
3							
4				CLAY, some SAND: (5Y 5/3), olive, firm, dry	CL		
5							
6				SAND, some CLAY, little SILT: (5Y 5/3), olive, soft, moist to saturated	SC		
7			1.3				
8							
9							
10							
11				SAND, coarse, trace fines: (5Y 4/1), gray, loose, granitic origin	SP		
12			0.6				
13							
14				Total depth = 14.0 ft.			
15				Note: logged in darkness with lighting; bottom 2 ft. of annulus is natural sand formation due to sand flowing			
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 31
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895105.70	DRILLER: Steve Mott
EAST COORDINATE: 1872998.65	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.78 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/08/92 @ 1545 END: 12/08/92 @ 1640	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring sampler

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2			8.8	GRAVEL, and SAND: red brown fill material	GP		
3				SILT, and CLAY: (5Y 4/2), olive gray, soft, moist, crumbly, semi-plastic	ML		Headspace @ 1.5 ft
4			14.5				ID: UANG-S6-SB1 (2.5-4.5) Headspace @ 4.00 ft
5					NA		
6			5.0	CLAY, and SILT: (5Y 5/2), olive gray, moist, med plasticity, soft,	CL		Headspace @ 6.0 ft
7							
8			43.6	SAND, fine to medium, and SILT: (2.5Y 5/3), lt. olive brown, soft, loose, saturated	SM		ID: UANG-S6-SB1 (7.0-9.0) Headspace @ 8.0 ft
9				Total depth=9.0 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 33
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894973.42	DRILLER: Steve Mott
EAST COORDINATE: 1872996.69	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.46 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/09/92 @ 0920 END: 12/09/92 @ 1010	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PTD HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				GRAVEL: fill material	GP		
2			6.5	SAND, and SILT, some CLAY: (2.5Y 4/3), olive brown, soft, crumbly, moist	SM		Headspace @ 1.5 ft
3					NA		
4			6.0	SAND, fine, and SILT, some CLAY: (2.5Y 4/2), dk. grayish brown, semi-cohesive, soft, moist	SM		
5			4.5	CLAY, and SILT, some SAND: (5Y 6/3), pale olive, moist, soft, semi-plastic	CL		ID: UANG-S6-SB2 (2-4) Headspace @ 3.50 ft
6				SAND, and SILT, some CLAY: (5Y 3/2), dk. olive gray, soft, moist, somewhat loose, non-cohesive	SM		Headspace @ 4.5 ft
7			8.0	SILT: (5Y 2.5/1), black, organic, shells, soft, moist, non-plastic	OL		
8				SAND, and CLAY, some SILT: (2.5Y 4/2), dk. grayish brown, soft to firm, slightly cohesive, saturated @ 7.0 feet, mostly sand @ bottom of interval	SC		ID: UANG-S6-SB2 (8.0-8.5) Headspace @ 7.0 ft
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 33
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894795.26	DRILLER: Steve Mott
EAST COORDINATE: 1872996.94	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.62 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/09/92 @ 1040 END: 12/09/92 @ 1145	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2			11.0	SAND, and SILT, some CLAY: (5Y 3/2), dk. olive gray, moist, soft	SM		ID: UANG-S6-SB3 (0.5-2.5) Headspace @ 2.0 ft
3			9.7	SAND, and SILT, some CLAY: (2.5Y 4/2), dk. grayish brown, soft, moist to saturated			Headspace @ 3.50 ft
4				SILT, trace SAND and CLAY: (5Y 2.5/1), black, organic, moist, soft, shells	OL		
5			5.1	SAND, and SILT, some CLAY: (2.5Y 4/2), olive gray, soft, moist, non-cohesive	SM		Headspace @ 5.5 ft
6				SILT, and CLAY, some SAND: (5Y 5/2), olive gray, firm, moist, non-plastic	ML		
7				SILT, and CLAY, some SAND: (5Y 6/3), pale olive, moist, soft, semi-plastic			
8			7.2	SAND, and SILT, some CLAY: mottled (5Y 5/2), olive gray, and (2.5Y 5/4), lt. olive brown, soft, moist to saturated	SM		ID: UANG-S6-SB3 (6.5-9.0) Headspace @ 8.0 ft
9				Total depth=9.0 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 34
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894626.04	DRILLER: Steve Mott
EAST COORDINATE: 1872994.96	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.32 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/09/92 @ 1355 END: 12/09/92 @ 1455	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1					NA		
1				SAND, and SILT, some CLAY: (5Y 3/1), v. dk. gray, moist, soft, crumbly, non-plastic	SM		
2			153	CLAY, and SILT, trace SAND: (5Y 5/3), olive, soft, med plasticity, moist to saturated, mottled w/ (5Y 5/6), olive, @ 3.0 feet	CL		ID: UANG-S6-SB4 (0-2) Headspace @ 1.5 ft
3							Headspace @ 3.50 ft
4			104				
5			67	SILT, some CLAY: (5Y 5/2), olive gray, moist, soft, semi-plastic	ML		Headspace @ 5.0 ft
6							
7			50	CLAY, some SILT: (5Y 5/3), olive, soft, saturated, plastic, some areas more silty, discrete blobs of (2.5Y 3/3), dk. olive brn,	CL		ID: UANG-S6-SB4 (6.0-8.5) Headspace @ 7.0 ft
8							Collected duplicate sample- UANG-S6-SB4 (8.5-11.0)
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 36
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894438.40	DRILLER: Steve Mott
EAST COORDINATE: 1872993.72	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.10 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/10/92 @ 0920 END: 12/10/92 @ 1005	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PTD HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				SAND, and SILT, some CLAY: (5Y 2.5/2), dk. olive, topsoil	SM		
2		☒	6.0	SAND, and SILT, some CLAY: (5Y 5/3), olive, soft to firm with depth, non-plastic, non-cohesive, moist, some rust discoloration,			ID: UANG-S6-SB5 (0-2) Headspace @ 1.5 ft
3			10.0				Headspace @ 3.00 ft
4				SILT, and CLAY, some SAND: (5Y 5/3), olive, saturated, soft, non-plastic, (2.5Y 5/4), lt. olive brown blobs	ML		
5			12				Headspace @ 5.5 ft
6				CLAY, and SAND: (5Y 5/3), olive, mottled w/ (2.5Y 5/4), lt. olive brown zones, soft, non-cohesive, saturated	CL		
7							
8		☒	16.5	CLAY, and SAND: (5BG 5/1), greenish gray, saturated, soft			ID: UANG-S6-SB5 (6.0-8.5) Headspace @ 7.5 ft
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB6

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 36
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894211.10	DRILLER: Steve Mott
EAST COORDINATE: 1872993.34	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.04 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/10/92 @ 1040 END: 12/10/92 @ 1130	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			5.0	SAND, and SILT: (10YR 3/1), v. dk. gray, topsoil	SM		Headspace @ 1.0 ft
2				SILT, and CLAY, some SAND: (5Y 7/3), pale yellow, soft, damp, slightly plastic, some mica grains	ML		
3			5.4	CLAY, and SILT: (5Y 5/3), olive, moist to saturated, soft, (2.5Y 5/4), lt. olive brown discoloration	CL		ID: UANG-S6-SB6 (2-4) Headspace @ 3.00 ft
4				SAND, med to coarse, (5Y 5/3), olive, soft, very loose, quartz and mica, 30% dark mineral grains, clean and well sorted	SP		
5				CLAY, and SILT: (5Y 5/2), olive gray, and thin interbedded rust color sand zones	CL		
6			7.5	SILT, and SAND, fine, some CLAY: (5Y 5/2), olive gray, w/ blobs of (2.5Y 3/2), v. dk. grayish brown, soft, fissile, non-plastic,	ML		Headspace @ 5.5 ft
7			6.9	CLAY, and SILT, some SAND: (5Y 5/2), olive gray, some (2.5Y 3/2), v. dk. grayish brown discoloration, soft, semi-plastic	CL		ID: UANG-S6-SB6 (6.0-8.5) Headspace @ 7.0 ft
8							Collected duplicate sample- UANG-S6-SB6 (8.5-11.0)
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB7

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 37
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893990.37	DRILLER: Steve Mott
EAST COORDINATE: 1872990.81	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.56 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/10/92 @ 1345 END: 12/10/92 @ 1435	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			3.5	SAND, and SILT, some CLAY: (10YR 3/1), dk. brown, topsoil	SM		
2				CLAY, and SILT, some SAND: (5Y 6/3), pale olive, soft, damp, non-plastic, roots	CL		Headspace @ 1.0 ft
3			5.0	SILT, and SAND, fine: (5Y 7/2), lt. gray, dry, firm,	ML		
4				SAND, fine, some SILT, trace CLAY: (5Y 5/2), olive gray, dry, loose,	SM		ID: UANG-S6-SB7 (2-4) Headspace @ 3.00 ft
5				SAND, and SILT, some CLAY: (5Y 5/3), olive, and (2.5Y 4/3), olive brown, soft, moist	SM		
6			2.6	CLAY, some SILT: (5Y 5/3), olive, soft, saturated, med plastic	CL		Headspace @ 5.5 ft
7			1.4	CLAY: (5Y 5/3), olive, and (10YR 2/2), v. dk. brown specks, specks are more lightly colored away from centers, saturated, soft, cohesive	CL		ID: UANG-S6-SB7 (6.0-8.5) Headspace @ 7.0 ft
8				SILT, and SAND, some CLAY: (5Y 5/3), olive	ML		
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB8

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 38
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893778.69	DRILLER: Steve Mott
EAST COORDINATE: 1872992.32	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.81 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/10/92 @ 1510 END: 12/10/92 @ 1540	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2	X		1.7	SILT, and SAND: (5Y 7/2), lt. gray, hard, dry, firm	ML		Headspace @ 1.5 ft
3	X						
4	X	X	0.0	SILT, and SAND: (5Y 5/2), olive gray, soft, moist @ 3.5 ft,			ID: UANG-S6-SB8 (2.5-4.5) Headspace @ 4.00 ft
5	X		0.3	CLAY, and SILT, some SAND: (5Y 5/2), olive gray, soft, saturated @ 5.5 ft	CL		Headspace @ 5.5 ft
6	X						
7	X			SAND, coarse: (2.5Y 4/4), olive brown, loose, clean and well sorted, soft, saturated, v. dk. brown @ contact with underlying clay	SP		
8	X	X	0.3	CLAY, some SILT: (5Y 5/2), olive gray, some areas of interdispersed v. dk. brown and olive brown,	CL		ID: UANG-S6-SB8 (6.5-9.0) Headspace @ 7.5 ft
9				Total depth=9.0 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB9

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 41
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893241.92	DRILLER: Steve Mott
EAST COORDINATE: 1872977.09	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.81 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/11/92 @ 1345 END: 12/11/92 @ 1440	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			0.7	SAND, and SILT, some CLAY: (10YR 3/1), dk. brown, topsoil, roots	SM		ID: UANG-S6-SB9 (0-2) Headspace @ 1.0 ft
2				SAND, and SILT, some CLAY: (2.5Y 5/3), lt. olive brown, soft, moist, non-plastic,			
3			1.8	CLAY, some SAND: (5Y 5/3), olive, soft, saturated, non-plastic	CL		Headspace @ 3.00 ft
4				CLAY: (5Y 5/2), olive gray, mottled w/ (10YR 4/4), dk. yellow brn, soft, saturated, non-plastic	CL		
5			1.5	SAND, coarse, some SILT and CLAY: (5Y 5/3), olive, soft, loose, saturated	SW		Headspace @ 5.0 ft
6					NA		
7			1.2	CLAY: (5Y 5/3), olive, soft, saturated, mottled w/ (10YR 4/4), dk. yellowish brown, and dk. brown inclusions that are hard, brown inclusions do not appear to be organic contamination	CL		ID: UANG-S6-SB9 (6.0-8.5) Headspace @ 6.5 ft Collected duplicate sample- UANG-S6-SB9 (8.5-11.0)
8							
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB10

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 6, Ramp Washdown
PROJECT NUMBER: Ut014	REF. LOGBOOK: 2, pg. 42
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 893013.25	DRILLER: Steve Mott
EAST COORDINATE: 1872975.89	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4216.43 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/11/92 @ 1455 END: 12/11/92 @ 1535	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			1.2	SAND, and SILT: (5Y 3/2), dk. olive gray, topsoil,	ML		ID: UANG-S6-SB10 (0-2) Headspace @ 1.0 ft
2				CLAY, and SILT, some SAND: (2.5Y 4/3), olive brown, soft, moist, non-plastic,	CL		
3			1.1	CLAY, some SAND: (5Y 5/3), olive, with (2.5Y 4/4), olive brown discoloration and dk. brown specks, moist, non-plastic	CL		Headspace @ 3.00 ft
4				CLAY, and SILT, some SAND: (5Y 5/2), olive gray, mottled w/ (10YR 4/4), dk. yellowish brown sand and clay, saturated, non-plastic, soft	CL		Headspace @ 5.0 ft
5			1.5				
6				CLAY, and SILT: same as above	CL		ID: UANG-S6-SB10 (6.0-8.5) Headspace @ 7.0 ft
7			1.3				
8							
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Site 7 - Oil Sludge Pond

Log of Monitoring Well: S7MW1

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 72
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 895090.25
GROUND ELEVATION: 4215.15 ft-MSL	EAST COORDINATE: 1874329.28
WELL DEPTH: 17.26 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.95 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4210.19 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4214.84 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 20.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/04/93	END COMPLETION: 01/05/93

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PTD HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1				ASPHALT	NA		
2				SAND, and SILT, and GRAVEL: fill material, grayish brown, soft	GM		
3				SAND, and CLAY: (5Y 5/3), olive, very moist @ 3.5 feet	SC		
4				SILT: (5Y 2.5/1), black, organic, shells, some mottled olive	OL		
5							
6				CLAY, some SAND and SILT: (5Y 4/1), dk. gray, soft, saturated, shells, organic	OL		
7							
8							
9				CLAY, and SILT, some SAND: (5Y 4/1), dk. gray, soft, some mica, shells, mottled olive and greenish gray zone @ 10.0 feet, organic	OL		
10							
11				CLAY, and SAND: (5Y 4/1), dk. gray, organic, mica	OL		
12				SAND, fine, some SILT: (5Y 4/1), dk. gray	SM		
13				SAND, medium: (5Y 5/1), gray, soft, loose, quartz and mica, moderately well sorted	SW		
14							
15				CUTTINGS: SAND, same as above	SW		
16							
17							
18							
19				CLAY @ 19 ft	CL		
20				Total depth = 20.0 ft.			
21							

Log of Monitoring Well: S7MW2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 72
CLIENT/PROJECT: HAZWRAP/NGB	NORTH COORDINATE: 894891.58
GROUND ELEVATION: 4215.31 ft-MSL	EAST COORDINATE: 1874247.23
WELL DEPTH: 16.84 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5.51 ft-BTOC	DRILLING CONTRACTOR: PC Exploration
GROUNDWATER ELEVATION: 4210.54 ft-MSL	DRILLER: Dave Mott
DATE MEASURED: 1/27/93	DRILLING RIG: Mobile B-57
TOC ELEVATION: 4215.10 ft-MSL	DRILLING METHOD: 6 1/4 in. ID. Hollow Stem Auger
BOREHOLE DEPTH: 20.00 ft-BGL	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon
BEGIN COMPLETION: 01/04/93	END COMPLETION: 01/05/93



Log of Soil Boring: SB1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 20
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 11.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895030.32	DRILLER: Steve Mott
EAST COORDINATE: 1874285.37	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.19 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/03/92 @ 1510	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers
END: 12/03/92 @ 1700	

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
				GRAVEL: fill material	GC		
2			952	SAND, and SILT: (5Y 3/1), v. dk. gray, soft, friable, odor	SM		Headspace @ 2.00 ft
3			1507	SAND, and CLAY, some SILT: (5G 5/1), greenish gray, soft, moist, odor	SC		ID: UANG-S7-SB1 (2.5-4.5) Headspace @ 3.0 ft
4				SILT, some CLAY: (2.5Y 2/0), black, organic, gastropod shells, crumbly, semi-firm, non-plastic	OL		
5			820	SILT: (5Y 3/1), v. dk. gray, crumbly, soft, shells, odor, non-plastic			Headspace @ 5.5 ft
6				SILT, and CLAY: (5G 5/1), greenish gray, moist, semi-plastic, mica	ML		
7			476	SILT: (5Y 3/1), v. dk. gray, plastic, shell fragments, moist	OL		ID: UANG-S7-SB1 (7-9) Headspace @ 7.5 ft
8				SAND, fine, and SILT: (5Y 5/1), gray, moist to saturated, soft, mica, thin gravel zone @ 8.0 feet	SM		
9			93.2	SILT, and CLAY: (5Y 3/1), v. dk. gray, plastic, moist, shells	OL		Headspace @ 9.5 ft
10				SAND, fine, some SILT: (5Y 4/1), dk. gray, moist, soft	SM		
11				Total depth=11.0 ft.			
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER:	REF. LOGBOOK: 2, pg. 22
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. JENSEN	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894987.75	DRILLER: STEVE MOTT
EAST COORDINATE: 1874288.11	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.45 ft-MSL	DRILLING METHOD:
DRILLING BEGIN: 12/04/92 @ 0915 END: 12/04/92 @ 1010	SAMPLING METHOD:

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2					NA		
3				GRAVEL: fill material	GC		
4				SAND, and SILT: (5G 5/1), greenish gray, loose	SC		
5				SILT, and SAND, coarse: (5Y 4/1), dk. gray, interbedded 3 inch layers of coarse sand and silt, soft, very moist, slight odor	ML		
6			54				
7				CLAY, and SILT: (5Y 2.5/1), black, shells, non-plastic, moist, soft	OL		
8				SAND, and SILT: (5Y 3/1), v. dk. gray, soft, moist	OL		
9			56	CLAY, and SILT: (5Y 2.5/1), black, shells, semi-plastic, moist	SC		
10				CLAY, and SAND, some SILT: (5Y 4/1), dk. gray, soft, moist	SM		
11			44	SILT, and SAND, fine: (5Y 5/1), gray, observed hydrocarbon staining, odor, grains cemented, hard			
12				CLAY, and SILT: (5Y 4/1), dk. gray, soft, non-plastic, saturated	CL		
13				Total depth=9.0 ft.			
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 23
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894942.93	DRILLER: Steve Mott
EAST COORDINATE: 1874306.73	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.68 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/04/92 @ 1039 END: 12/04/92 @ 1140	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2				GRAVEL, and CLAY: fill material	GC		
3				SILT, and CLAY: (5Y 3/1), v. dk. gray	ML		
4			0.0	SAND, coarse: (5Y 3/1), v. dk. gray,	SW		
5				SILT: (5Y 5/1), gray, moist, soft	ML		ID: UANG-S7-SB3 (2.5-4.5) Headspace @ 3.50 ft
6				SILT, and CLAY: (5Y 4/1), dk. gray, organic, wood chips soft, moist, non-plastic	OL		
7			0.0	CLAY, and SILT: (5Y 2.5/1), black, organic, shells, semi-plastic, moist	OL		Headspace @ 5.5 ft
8					NA		
9			NA	CLAY, and SILT: (5Y 3/1), v. dk. gray, soft, saturated, semi-plastic	OL		ID: UANG-S7-SB3 (6.5-9.0) Headspace @ 8.5 ft
10				Total depth=9.0 ft.			
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard

SITE LOCATION: Site 7, Oil Sludge Pond

PROJECT NUMBER: UT014

REF. LOGBOOK: 2, pg. 44

CLIENT/PROJECT: HAZWRAP/NGB

TOTAL DEPTH: 9.0 ft-BGL

LOGGED BY: T. M. Jensen

DRILLING CONTRACTOR: PC Exploration

NORTH COORDINATE: 895086.42

DRILLER: Steve Mott

EAST COORDINATE: 1874286.59

DRILLING RIG: Acker Soil Max

GROUND ELEVATION: 4214.87 ft-MSL

DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger

DRILLING BEGIN: 12/14/92 @ 1100 END: 12/14/92 @ 1150

SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2				GRAVEL, and SAND, and SILT: fill material	GM		
3				SAND, and CLAY, some SILT: (2.5Y 5/3), lt olive brown, thin layer of coarse angular sand	SC		
4			0.5	CLAY, and SAND, some SILT: (5Y 5/3), olive, soft, moist, non-plastic	OL		Headspace @ 3.50 ft
5				SILT: (5Y 2.5/1), black, organic, shells, moist, soft, non-plastic	OL		
6			2.0	SILT, and CLAY: (10YR 4/1), dk. gray, organic, shells, soft, non-plastic, small orange seeds, saturated @ about 5.5 feet	OL		ID: UANG-S7-SB4 (4.5-6.5) Headspace @ 5.5 ft
7				SILT, and CLAY: (5Y 4/1), dk. gray, organic, soft, saturated large gastropod shells up to 1 inch long	OL		
8			3.0				Headspace @ 7.5 ft
9				Total depth=9.0 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB5

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 45
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 9.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895006.49	DRILLER: Steve Mott
EAST COORDINATE: 1874331.54	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.39 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/14/92 @ 1400 END: 12/14/92 @ 1450	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2					NA		
2			0.0	SAND, some GRAVEL: fill material	GM		Headspace @ 2.25 ft
3			2.5	SAND, and CLAY: (5Y 3/1), dk. gray, soft, moist, non-plastic	SC		Headspace @ 3.5 ft
4				SILT, and CLAY: (5Y 3/1), v. dk. gray, soft, moist, non-plastic organic, shells, roots	OL		
5				SILT: (5Y 2.5/1), black, organic, shells, moist, soft, non-plastic	OL		ID: UANG-S7-SB5 (4.5-6.5)
6			17.7	SILT, some CLAY: (5Y 3/1), v. dk. gray, soft, moist to saturated, med plasticity	OL		Headspace @ 5.5 ft
7					NA		
8							
8			3.0	SILT, and CLAY: (5Y 3/1), v. dk. gray, soft, saturated	OL		ID: UANG-S7-SB5 (6.5-9.0)
9				Total depth=9.0 ft.			Headspace @ 8.5 ft
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB6

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 45
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894902.57	DRILLER: Steve Mott
EAST COORDINATE: 1874237.16	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4215.00 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/14/92 @ 1500 END: 12/14/92 @ 1550	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	P10 HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			0.3	GRAVEL, and SAND, some SILT: fill material	GM		
2				SAND, and SILT: (2.5Y 4/2), dk. gray brown, soft, moist	SM		Headspace @ 1.00 ft
3				SILT, and CLAY: (5Y 6/3), pale olive, soft, moist, slightly plastic	ML		
4			0.4	SAND, and SILT, some CLAY: mottled (2.5Y 4/2), dk. gray brown, and (2.5Y 6/2), lt. brownish gray, soft, moist, slightly plastic	SM		
5				SILT, some CLAY: (10YR 3/1), v. dk. gray, soft, moist, non-plastic	ML		Headspace @ 3.5 ft
6			0.3	SILT: (5Y 2.5/1), black, organic, shells, moist, soft, non-plastic	OL		
7				SILT, some CLAY: (10YR 4/1), dk. gray, soft, saturated, non-plastic	OL		ID: UANG-S7-SB6 (4-6) Headspace @ 5.5 ft
8			0.5		NA		
9				SILT, and CLAY: (5Y 3/1), v. dk. gray, soft, saturated	OL		Headspace @ 8.0 ft
10				Total depth=8.5 ft.			
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB7

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 95
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 7.0 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 894950.14	DRILLER: Dan Bowden
EAST COORDINATE: 1874220.32	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4214.64 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 2/08/93 @ 1320 END: 2/08/93 @ 1350	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1					NA		
2			1.8	SAND, some SILT, some CLAY, little GRAVEL: (2.5Y 5/3), lt. olive brown, some darker and lighter areas, soft, moist	SC		ID: UANG-S7-SB7 (1-3) Headspace @ 1.50 ft
3				SAND, and SILT: (2.5Y 5/3), lt. olive brown, soft, crumbly	SM		Headspace @ 3.5 ft
4			1.1	CLAY: (5Y 5/2), olive gray, firm, moist, non-plastic, shells	CL		
5				SILT, some CLAY: (2.5Y 5/3), lt. olive brown, shells, moist, soft,	ML		
6				SILT, some CLAY: (5Y 2.5/1), black, organic, shells, soft, moist	OL		ID: UANG-S7-SB7 (5-7) Headspace @ 6.5 ft
7			1.1	SAND, and SILT: (5Y 6/2), lt. olive gray, saturated	SM		
8				Total depth=7.0 ft.			
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB8

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 54
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 6.5 ft-BGL
LOGGED BY: T. M. Jensen	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895044.02	DRILLER: Steve Mott
EAST COORDINATE: 1874212.71	DRILLING RIG: Acker Soil Max
GROUND ELEVATION: 4214.40 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/17/92 @ 0920 END: 12/03/92 @ 1000	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2				GRAVEL, and SAND: fill material	GC		
3			96.6	SILT, and SAND, some CLAY: (5Y 4/2), olive gray, soft, moist	SM		Headspace @ 2.00 ft
4			62.4	CLAY, and SAND, some GRAVEL: (5Y 5/3), olive, soft, moist, non-plastic	SC		
5				CLAY, and SAND: mottled (5Y 2.5/1), black, and (5Y 5/3) olive, soft moist	SC		Headspace @ 3.5 ft
6				SILT: (5Y 2.5/1), black, moist, soft, shells, non-plastic	OL		
7			44.1	CLAY, and SILT: (2.5Y 3/2), v. dk. grayish brown, soft, shells, saturated	CL		ID: UANG-S7-SB8 (4.5-6.5) Headspace @ 5.5 ft
8				Total depth=6.5 ft.			
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB9

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 7, Oil Sludge Pond
PROJECT NUMBER: UT014	REF. LOGBOOK: 2, pg. 69
CLIENT/PROJECT: HAZWRAP/NGB	TOTAL DEPTH: 8.5 ft-BGL
LOGGED BY: J. F. Bernard	DRILLING CONTRACTOR: PC Exploration
NORTH COORDINATE: 895075.46	DRILLER: Dave Mott
EAST COORDINATE: 1874332.57	DRILLING RIG: Mobile B-57
GROUND ELEVATION: 4215.18 ft-MSL	DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger
DRILLING BEGIN: 12/30/92 @ 1115 END: 12/30/92 @ 1230	SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				ASPHALT:	NA		
2				GRAVEL, and SAND: fill material	GC		
3			0.0	SILT, and SAND, some CLAY: (10YR 4/3), dk. brown, moist, semi-plastic	SM		Headspace @ 2.00 ft
4			0.0	SILT, and CLAY, little SAND, fine: (2.5Y 5/3) lt. olive brown, moist	SC		Headspace @ 3.5 ft ID: UANG-S7-SB9 (2.5-4.5) Collected Duplicate UANG-S7-SB9 (8.5-9.5)
5			0.0	SILT, and CLAY: (5Y 3/1), v. dk. gray, shells, moist	OL		
6			0.0	SILT, some CLAY: (5Y 5/1), gray, moist to saturated, slightly plastic	ML		Headspace @ 5.5 ft ID: UANG-S7-SB9 (4.5-6.5) Collected MS and MSD
7			0.0	CLAY, and SILT: (5Y 5/1), gray, moist to saturated	CL		Headspace @ 7.5 ft
8				Total depth=8.5 ft.			
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB10		ENGINEERING-SCIENCE, INC.	
PROJECT LOCATION: Utah Air National Guard		SITE LOCATION: Site 7, Oil Sludge Pond	
PROJECT NUMBER: UT014		REF. LOGBOOK: 2, pg. 68	
CLIENT/PROJECT: HAZWRAP/NGB		TOTAL DEPTH: 8.5 ft-BGL	
LOGGED BY: J. F. Bernard		DRILLING CONTRACTOR: PC Exploration	
NORTH COORDINATE: 895036.91		DRILLER: Dave Mott	
EAST COORDINATE: 1874361.31		DRILLING RIG: Mobile B-57	
GROUND ELEVATION: 4215.36 ft-MSL		DRILLING METHOD: 3 1/4 in. ID. Hollow Stem Auger	
DRILLING BEGIN: 12/29/92 @ 1605 END: 12/29/92 @ 1645		SAMPLING METHOD: 2 1/2 in. ID. Split Spoon w/ ring samplers	


DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1			0.0	ASPHALT:	NA		Headspace @ 2.00 ft
2				GRAVEL, and SAND: fill material	GC		
3							Headspace @ 3.5 ft
4				SAND, fine to coarse, and SILT: (2.5Y 5/4), olive brown, moist	SM		
5				CLAY, and SILT: (5Y 6/4) pale olive, moist, plastic	CL		Headspace @ 5.5 ft ID: UANG-S7-SB10 (4.5-6.5)
6				SILT, and CLAY: (5Y 3/1), v. dk. gray, shells, moist, non-plastic	OL		
7				CLAY, and SILT: (5Y 5/2), olive gray, moist, plastic	CL		Headspace @ 7.5 ft
8				CLAY, and SILT, little SAND, fine, trace GRAVEL: (5Y 5/2), olive gray, saturated	SC		
9				Total depth=8.5 ft.			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Site 10 - Petroleums, Oils, and Lubricants Facility

Log of Monitoring Well: PI-1

ENGINEERING-SCIENCE, INC.


PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 10 - POL
PROJECT NUMBER: UT014	REF. LOGBOOK: 7 pg 2
CLIENT/PROJECT: HAZWRAP/ANGRC	NORTH COORDINATE: 895212.0097
GROUND ELEVATION: 4214.86 ft-MSL	EAST COORDINATE: 1873532.6430
WELL DEPTH: 15 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: ft-MSL	DRILLER: Charles Shorey Jr.
DATE MEASURED: 23 May 94	DRILLING RIG: CME 75
TOC ELEVATION: 4214.68 ft-MSL	DRILLING METHOD: 6.25" I.D. Hollow Stem Auger
BOREHOLE DEPTH: 15 ft-BGL	SAMPLING METHOD: 2.5" I.D. X 2.5' Split Spoon
BEGIN COMPLETION: 1600 23 May 94	END COMPLETION: 23 May 94



Log of Monitoring Well: PI-2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 10 - POL
PROJECT NUMBER: UT014	REF. LOGBOOK: 7 pg 3
CLIENT/PROJECT: HAZWRAP/ANGRC	NORTH COORDINATE: 895506.0492
GROUND ELEVATION: 4214.30 ft-MSL	EAST COORDINATE: 1873772.4404
WELL DEPTH: 15 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: ft-MSL	DRILLER: Charles Shorey Jr.
DATE MEASURED: 24 May 95	DRILLING RIG: CME 75
TOC ELEVATION: 4213.81 ft-MSL	DRILLING METHOD: 6.25" I.D. Hollow Stem Auger
BOREHOLE DEPTH: 15 ft-BGL	SAMPLING METHOD: 2.5" I.D. X 2.5' Split Spoon
BEGIN COMPLETION: 0900 24 May 94	END COMPLETION: 23 May 94



Log of Monitoring Well: PI-3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 10 - POL
PROJECT NUMBER: UT014	REF. LOGBOOK: 7 pg 2
CLIENT/PROJECT: HAZWRAP/ANGRC	NORTH COORDINATE: 895488.8283
GROUND ELEVATION: 4215.66 ft-MSL	EAST COORDINATE: 1873385.7539
WELL DEPTH: 15 ft-BGL	LOGGED BY: T.M. Jensen
WATER LEVEL: 5 ft-BTOC	DRILLING CONTRACTOR: Layne Environmental
GROUNDWATER ELEVATION: ft-MSL	DRILLER: Charles Shorey Jr.
DATE MEASURED: 24 May 94	DRILLING RIG: CME 75
TOC ELEVATION: 4215.41 ft-MSL	DRILLING METHOD: 6.25" I.D. Hollow Stem Auger
BOREHOLE DEPTH: 15 ft-BGL	SAMPLING METHOD: 2.5" I.D. X 2.5' Split Spoon
BEGIN COMPLETION: 1145 24 May 94	END COMPLETION: 24 May 94

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	WELL DIAGRAM
1			0.0	Top is cobble rock (artificial cover) sand, silty gravel and clay (fill material).	NA		<p>Concrete Pad</p> <p>Borehole Diam. 10-1/4 inches</p> <p>Water Level During Installation</p> <p>1-inch I.D. PVC Casing</p> <p>20/40 COLORADO SILICA SAND PACK</p> <p>0.010 SLOTTED PVC SCREEN</p> <p>3-inch end cap</p>
2			0.0	SAND, medium, and CLAY, some GRAVEL: (2.5Y 4/2) dark grayish brown, mottled (5Y 5/2) olive gray and (5Y 6/2) gray, moist, soft, non-plastic.	SC		
3			0.0				
4			0.0	SILT: (5Y 2.5/1) black, soft, non-plastic, rootlets, organic, shells.	OL		
5			0.0	CLAY and SILT, some fine SAND: (5Y 2.5/1) black, saturated, soft, shells.	CL		
6			0.0	Same as above. Except: non-cohesive, moist to wet, sand concentration increasing with depth.			
7			0.0				
8			0.0	CLAY, and SILT, little SAND: (5Y 5/1) gray, saturated, soft.			
9			0.0	SAND, some CLAY, some SILT: (5Y 5/3) olive gray, soft, semi-cohesive.	SC		
10			0.0	SAND, fine, and SILT, some CLAY: (5Y 5/2) olive gray, soft, mica prevalent.	SM		
11			0.0				
12			0.0	SAND, fine, and SILT: (5Y 5/2) olive gray, granitic origin, soft, loose.			
13			0.0				
14			0.0	Not logged.			
15			0.0	Total Depth 15 ft.			
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-1

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 10 - POL
PROJECT NUMBER: UT014	REF. LOGBOOK: 7 pg 5
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 10 ft-BGL
LOGGED BY: T.M. Jensen	DRILLING CONTRACTOR: Layne Environmental
NORTH COORDINATE: 895476.0525	DRILLER: Charles Shorey Jr.
EAST COORDINATE: 1873606.5829	DRILLING RIG: CME 75
GROUND ELEVATION: 4214.06 ft-MSL	DRILLING METHOD: 4.25" I.D. Hollow Stem Auger
DRILLING BEGIN: 08:50 26 May 94	END: 10:30 26 May 94
	SAMPLING METHOD: 2.5" I.D. X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Concrete	NA		
2				Fill - Sand and Gravel, some fines: (10YR 7/8) yellow.	NA		
3			1079				SAMPLE ID: S10-SB1 (2-4) VOA at 3.0 ft.
4				SILT: (5Y 2.5/1) black, moist, non-plastic, organic, shells	OL		Odor and fuel present under concrete.
5			1185	SILT, some SAND, fine (5Y 6/1) gray, saturated, roots.	ML		VOA at 4.5 ft.
6				CLAY, and SILT: (5Y 5/1) gray, damp to moist, firm, semi-plastic.	CL		
7			19.1	SILT, some CLAY: (5Y 5/1), gray, saturated, soft.	ML		SAMPLE ID: S10-SB1 (6-8) VOA at 6.5 ft.
8				SAND, fine: (5Y 5/1) gray, saturated, loose.	SW		
9			25.1	SAND, fine: (5Y 5/1) gray, saturated, loose, mica prevalent.			SAMPLE ID: S10-SB1 (8-10) peculiar odor
10				Total Depth 10 ft. BGS			
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-2

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 10 - POL
PROJECT NUMBER: UT014	REF. LOGBOOK: 7 pg 7
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 6 ft-BGL
LOGGED BY: T.M. Jensen	DRILLING CONTRACTOR: Layne Environmental
NORTH COORDINATE: 895412.2077	DRILLER: Charles Shorey Jr.
EAST COORDINATE: 1873765.8800	DRILLING RIG: CME 75
GROUND ELEVATION: 4213.87 ft-MSL	DRILLING METHOD: 4.25" I.D. Hollow Stem Auger
DRILLING BEGIN: 09:15 26 May 94 END: 10:00 26 May 94	SAMPLING METHOD: 2.5" I.D. X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Concrete	NA		
2				Fill - Sand and gravel, some fines: (10YR 7/8) yellow.	SM		
3				SAND, fine and SILT: (5Y 4/1) dark gray, damp, firm, non-plastic.			
4		164		SAND, and CLAY, some SILT: (5Y 5/1) gray, damp to moist, soft to firm, slightly plastic.	SC		SAMPLE ID: S10-SB2 (2-4)
5		3643		SILT: (5Y 4/1) dark gray, moist to saturated, semi-plastic, fine mica, vitreous sheen on soil.	MH		SAMPLE ID: S10-SB2 (4-6)
6				Total depth 6 ft. BGS.			
7							
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

Log of Soil Boring: SB-3

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 10 - POL
PROJECT NUMBER: UT014	REF. LOGBOOK: 7 pg 8
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 7 ft-BGL
LOGGED BY: T.M. Jensen	DRILLING CONTRACTOR: Layne Environmental
NORTH COORDINATE: 895266.1621	DRILLER: Charles Shorey Jr.
EAST COORDINATE: 1873731.9040	DRILLING RIG: CME 75
GROUND ELEVATION: 4214.63 ft-MSL	DRILLING METHOD: 4.25" I.D. Hollow Stem Auger
DRILLING BEGIN: 10:30 26 May 94 END: 11:15 26 May 94	SAMPLING METHOD: 2.5" I.D. X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Cobble rock.	NA		
2			0.0	SAND and CLAY, some SILT: (5Y 5/2) olive gray mottled (5Y 3/1) very dark gray, damp, soft, non-plastic, non-cohesive.	SC		
3				SILT: (5Y 2.5/1) black, organic, shells.	OL		
4			0.0	SILT: (5Y 6/2) light olive gray, damp, soft, non-plastic, shells.	ML		
5				SILT, and CLAY: (5Y 4/1) dark gray, saturated, soft, plastic, rootlets	MH		
6				SILT and SAND, trace GRAVEL: (5Y 4/2) olive gray, with (5Y 2.5/1) black, and (2.5Y 4/4) olive brown, mottling, saturated, soft, non-plastic.	SM		
7				Total depth 7 ft. BGS.			
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

SAMPLE ID: S10-SB3 (1-3)
VOA at 2.25 ft.

SAMPLE ID: S10-SB3 (3-5)
voa AT 4.25 FT.
Collected MS/MSD:
S10-SB3 (3-5) MS
S10-SB3 (3-5) MSD

Log of Soil Boring: SB-4

ENGINEERING-SCIENCE, INC.

PROJECT LOCATION: Utah Air National Guard	SITE LOCATION: Site 10 - POL
PROJECT NUMBER: UT014	REF. LOGBOOK: 7 pg 9
CLIENT/PROJECT: HAZWRAP/ANGRC	TOTAL DEPTH: 6 ft-BGL
LOGGED BY: T.M. Jensen	DRILLING CONTRACTOR: Layne Environmental
NORTH COORDINATE: 895223.8360	DRILLER: Charles Shorey Jr.
EAST COORDINATE: 1873630.1825	DRILLING RIG: CME 75
GROUND ELEVATION: 4215.31 ft-MSL	DRILLING METHOD: 4.25" I.D. Hollow Stem Auger
DRILLING BEGIN: 13:30 26 May 94 END: 14:10 26 May 94	SAMPLING METHOD: 2.5" I.D. X 2.5' Split Spoon

DEPTH (feet)	INTERVAL RECOVERY	ANALYTICAL SAMPLE	PID HDSP (ppm)	LITHOLOGIC DESCRIPTION	USCS	GRAPHIC LOG	COMMENTS
1				Gravel fill, consisting of sand and gravel and some fines (10YR 7/8) yellow.	NA		
2				SAND, and SILT, some CLAY, little GRAVEL: (5Y 4/1) dark gray, damp to moist, soft, non-cohesive.	SC		
3			4				SAMPLE ID: S10-SB4 (2-4) VOA at 3.25 ft.
4				SILT: (5Y 6/2) light olive gray, saturated, soft, shells.	ML		
5			0.8	CLAY and SILT: (5Y 4/1) dark gray, saturated, soft, semi-plastic.	CL		SAMPLE ID: S10-SB4 (4-6) VOA at 5.25 ft.
6				Total depth 6 ft. BGS.			
7							
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							

TABLE G.1
MONITORING WELL CONSTRUCTION DETAILS
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Station	Land Surface Elevation (feet above MSL)	Top of Casing Elevation (feet above MSL)	Borehole Depth (feet BLS)	Well Depth (feet BLS)	Screened Interval (feet BLS)
BGMW1	4219.11	4218.74	18.0	16.85	4.85-14.85
BGMW2 (1)	4215.54	4218.09	14.5	14.5	4.00-14.00
S1MW1	4218.32	4218.02	18.0	17.35	5.35-15.35
S1MW2	4217.93	4217.63	14.5	14.5	4.00-14.00
S2MW1	4217.43	4217.16	18.0	17.27	5.27-15.27
S2MW2	4217.75	4217.45	14.5	14.5	4.00-14.00
S3MW1 (1)	4213.16	4215.43	19.0	17.13	5.13-15.13
S3MW2 (1)	4216.25	4218.71	21.0	20.74	8.74-18.74
S4MW1	4214.41	4214.06	20.0	17.35	5.35-15.35
S5MW1 (1)	4214.05	4216.47	20.0	17.08	5.08-15.08
S6MW1	4216.92	4216.71	18.0	17.24	5.24-15.24
S6MW2	4216.58	4216.32	18.0	17.26	5.26-15.26
S6MW3 (1)	4216.89	4219.29	18.0	16.75	4.75-14.75
S6MW4	4214.86	4214.69	14.5	14.5	4.00-14.00
S6MW5	4214.78	4214.53	14.0	14.0	3.50-13.50
S7MW1	4215.15	4214.84	20.0	17.26	5.26-15.26
S7MW2	4215.31	4215.10	20.0	16.84	4.84-14.84

MSL = Mean Sea Level

BLS = Below Land Surface

(1) Above Ground Well Casing

APPENDIX H
TARGET COMPOUNDS AND DETECTION LIMITS

APPENDIX H
TABLE OF CONTENTS

Table H.1 (ES Berkeley Laboratory)	H-1
Table H.2 (DataChem Laboratories).....	H-8

TABLE H.1 (ES Berkeley Laboratory)
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	Sample		Sample	
	*Quantitation	Limit	*Quantitation	Limit
(method)	Water		Soil	
	(µg/L)		(µg/kg)	
Volatile Organic Compounds (SW8240)				
Chloromethane	10.0		10.0	
Bromomethane	10.0		10.0	
Vinyl Chloride	10.0		10.0	
Chloroethane	10.0		10.0	
Methylene Chloride	5.0		5.0	
Acetone	10.0		10.0	
Carbon Disulfide	10.0		10.0	
Trichlorofluoromethane	10.0		10.0	
1,1-Dichloroethene	5.0		5.0	
1,1-Dichloroethane	5.0		5.0	
1,2-Dichloroethene (Total)	5.0		5.0	
Chloroform	5.0		5.0	
1,2-Dichloroethane	5.0		5.0	
2-Butanone	10.0		10.0	
1,1,1-Trichloroethane	5.0		5.0	
Carbon Tetrachloride	5.0		5.0	
Vinyl Acetate	10.0		10.0	
Bromodichloromethane	5.0		5.0	
1,2-Dichloropropane	5.0		5.0	
cis-1,3-Dichloropropene	5.0		5.0	
Trichloroethene	5.0		5.0	
Benzene	5.0		5.0	
Dibromochloromethane	5.0		5.0	
1,1,2-Trichloroethane	5.0		5.0	
trans-1,3-Dichloropropene	5.0		5.0	
2-Chloroethylvinylether	10.0		10.0	
Bromoform	5.0		5.0	
2-Hexanone	10.0		10.0	
4-Methyl-2-pentanone	10.0		10.0	
Tetrachloroethene	5.0		5.0	
1,1,2,2-Tetrachloroethane	5.0		5.0	
Toluene	5.0		5.0	
Chlorobenzene	5.0		5.0	
Ethylbenzene	5.0		5.0	
Styrene	5.0		5.0	

**TABLE H.1 (ES Berkeley Laboratory)-Continued
 TARGET COMPOUNDS AND DETECTION LIMITS
 151st AREFG UTAH AIR NATIONAL GUARD
 SALT LAKE CITY INTERNATIONAL AIRPORT
 SALT LAKE CITY, UTAH**

Parameter	(method)	Sample	Sample
		*Quantitation Limit Water (µg/L)	*Quantitation Limit Soil (µg/kg)
Volatile Organic Compounds (SW8240)			
Total Xylenes		5.0	5.0
1,3-Dichlorobenzene		5.0	5.0
1,4-Dichlorobenzene		5.0	5.0
1,2-Dichlorobenzene		5.0	5.0
Halogenated Compounds (SW8010)			
Benzyl Chloride		5.0	5.0
Bromobenzene		5.0	5.0
Bromodichloromethane		1.0	1.0
Bromoform		2.0	2.0
Bromomethane		5.0	5.0
Carbon Tetrachloride		1.0	1.0
Chlorobenzene		1.0	1.0
Chloroethane		5.0	5.0
Chloroform		1.0	1.0
1-Chlorohexane		5.0	5.0
2-Chloroethylvinylether		2.0	2.0
Chloromethane		5.0	5.0
Chlorotoluenes		5.0	5.0
Dibromochloromethane		1.0	1.0
Dibromomethane		5.0	5.0
1,2-Dichlorobenzene		1.0	1.0
1,3-Dichlorobenzene		1.0	1.0
1,4-Dichlorobenzene		1.0	1.0
Dichlorodifluoromethane		18.0	18.0
1,1-Dichloroethane		1.0	1.0
1,2-Dichloroethane		1.0	1.0
1,1-Dichloroethene		1.0	1.0
cis-1,2-Dichloroethene		1.0	1.0
trans-1,2-Dichloroethene		1.0	1.0
Dichloromethane		5.0	5.0
1,2-Dichloropropane		1.0	1.0

**TABLE H.1 (ES Berkeley Laboratory)-Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH**

Parameter	(method)	Sample	Sample
		*Quantitation Limit Water (µg/L)	*Quantitation Limit Soil (µg/kg)
Halogenated Compounds (SW8010)			
1,3-Dichloropropene		2.0	2.0
1,1,2,2-Tetrachloroethane		1.0	1.0
1,1,1,2-Tetrachloroethane		1.0	1.0
Tetrachloroethene		1.0	1.0
1,1,1-Trichloroethane		1.0	1.0
1,1,2-Trichloroethane		1.0	1.0
Trichloroethene		1.0	1.0
Trichlorofluoromethane		1.0	1.0
Trichloropropane		1.0	1.0
Vinyl Chloride		2.0	2.0
Aromatic Compounds (SW8020)			
Benzene		1.0	1.0
Ethylbenzene		1.0	1.0
Toluene		1.0	1.0
Xylenes (Total)		1.0	1.0
Chlorobenzene		2.0	2.0
1,2-Dichlorobenzene		4.0	4.0
1,3-Dichlorobenzene		4.0	4.0
1,4-Dichlorobenzene		4.0	4.0
Semivolatile Organic Compounds (SW8270)			
N-Nitroso-Dimethylamine		10.0	330.0
Phenol		10.0	330.0
bis (2-Chloroethyl) ether		10.0	330.0
2-Chlorophenol		10.0	330.0
1,3-Dichlorobenzene		10.0	330.0
1,4-Dichlorobenzene		10.0	330.0
Benzyl Alcohol		10.0	330.0
1,2-Dichlorobenzene		10.0	330.0

**TABLE H.1 (ES Berkeley Laboratory)-Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH**

Parameter	(method)	Sample		Sample	
		*Quantitation	Limit	*Quantitation	Limit
		Water		Soil	
		(µg/L)		(µg/kg)	
Semivolatile Organic Compounds (SW8270)					
2-Methylphenol		10.0		330.0	
bis (2-Chloroisopropyl) ether		10.0		330.0	
4-Methylphenol		10.0		330.0	
N-Nitroso-Di-n-Propylamine		10.0		330.0	
Hexachloroethane		10.0		330.0	
Nitrobenzene		10.0		330.0	
Isophorone		10.0		330.0	
2-Nitrophenol		10.0		330.0	
2,4-Dimethylphenol		10.0		330.0	
bis (2-Chloroethoxy) methane		10.0		330.0	
2,4-Dichlorophenol		10.0		330.0	
Benzoic Acid		25.0		830.0	
1,2,4-Trichlorobenzene		10.0		330.0	
Napthalene		10.0		330.0	
4-Chloroaniline		10.0		330.0	
Hexachlorobutadiene		10.0		330.0	
4-Chloro-3-Methylphenol		10.0		330.0	
2-Methylnapthalene		10.0		330.0	
Hexachlorocyclopentadiene		10.0		330.0	
2,4,6-Trichlorophenol		10.0		330.0	
2,4,5-Trichlorophenol		25.0		830.0	
2-Chloronapthalene		10.0		330.0	
2-Nitroaniline		25.0		330.0	
Dimethylphthalate		10.0		330.0	
Acenaphylene		10.0		330.0	
2,6-Dinitrotoluene		10.0		330.0	
3-Nitroaniline		25.0		830.0	
Acenaphthene		10.0		330.0	
2,4-Dinitrophenol		25.0		830.0	
Dibenzofuran		10.0		330.0	
4-Nitrophenol		25.0		830.0	
2,4-Dinitrotoluene		10.0		330.0	
Fluorene		10.0		330.0	
Diethylphthalate		10.0		330.0	

**TABLE H.1 (ES Berkeley Laboratory)-Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD BASE
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH**

Parameter	Sample *Quantitation Limit Water (µg/L)	Sample *Quantitation Limit Soil (µg/kg)
(method)		
Semivolatile Organic Compounds (SW8270)		
4-Chlorophenol-phenylether	10.0	330.0
4-Nitroaniline	25.0	830.0
4,6-Dinitro-2-Methylphenol	25.0	830.0
N-Nitrosodiphenylamine	10.0	330.0
4-Bromophenyl-phenylether	10.0	330.0
Hexachlorobenzene	10.0	330.0
Pentachlorophenol	25.0	830.0
Phenanthrene	10.0	330.0
Anthracene	10.0	330.0
Di-n-Butylphthalate	10.0	330.0
Fluoranthene	10.0	330.0
Pyrene	10.0	330.0
Butylbenzylphthalate	10.0	330.0
Benzo (a) Anthracene	10.0	330.0
3,3'-Dichlorobenzadiene	20.0	660.0
Chrysene	10.0	330.0
bis (2-Ethylhexyl) Phthalate	10.0	330.0
Di-n-octylphthalate	10.0	330.0
Benzo (b) Fluoranthene	10.0	330.0
Benzo (k) Fluoranthene	10.0	330.0
Benzo (a) Pyrene	10.0	330.0
Ideno (1,2,3-cd) Pyrene	10.0	330.0
Dibenz (a,h) Anthracene	10.0	330.0
Benzo (g,h,i) Perylene	10.0	330.0
Priority-Pollutant Metals		
Antimony (SW6010)	11.0	1100.0
Arsenic (SW7060)	1.0	2000.0
Beryllium (SW6010)	1.0	330.0
Cadmium (SW6010)	1.0	1000.0
Chromium (SW6010)	2.0	2000.0
Copper (SW6010)	2.0	2000.0

**TABLE H.1 (ES Berkeley Laboratory)-Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH**

Parameter	(method)	Sample	Sample
		*Quantitation Limit	*Quantitation Limit
		Water	Soil
		(µg/L)	(µg/kg)
Priority-Pollutant Metals			
Lead (SW7421)		2.2	2000.0
Mercury (SW7470/7471)		0.03	20.0
Nickel (SW6010)		3.0	3000.0
Selenium (SW7740)		1.0	280.0
Silver (SW6010)		3.0	340.0
Thallium (SW7841)		2.2	390.0
Zinc (SW6010)		1.0	1000.0
TRPH (E418.1)		1000.0	10000.0
Pesticides/PCB (SW8080)			
Aldrin		0.04	1.30
Alpha-BHC		0.03	1.00
Beta-BHC		0.06	2.00
Delta-BHC		0.09	3.00
Gamma-BHC		0.04	1.30
Chlordane		0.14	4.70
4,4'-DDD		0.11	3.70
4,4-DDE		0.04	1.30
4,4-DDT		0.12	4.00
Dieldrin		0.02	0.70
Endosulfan I		0.14	4.70
Endosulfan II		0.04	1.30
Endosulfan Sulfate		0.66	22.00
Endrin		0.06	2.00
Endrin Aldehyde		0.23	7.70
Endrin Keytone		NA	4.00
Heptachlor		0.03	1.00
Heptachlor Epoxide		0.83	27.70
Methoxychlor		1.80	60.00
Toxaphene		2.40	80.00

TABLE H.1 (ES Berkeley Laboratory)-Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	Sample	Sample
		*Quantitation Limit	*Quantitation Limit
Pesticides/PCB (SW8080)		Water	Soil
		(µg/L)	(µg/kg)
PCB-1016		0.10	3.30
PCB-1221		0.40	13.00
PCB-1232		0.30	10.00
PCB-1242		0.20	6.70
PCB-1248		0.20	6.70
PCB-1254		0.20	6.70
PCB-1260		0.20	6.70

* Lowest quantitation limit established by the analytical laboratory. These limits are matrix dependent and were not always achieved due to moisture considerations (soil matrix interference).

TABLE H.2 (DataChem Laboratories)
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	Sample	Sample
		*Quantitation Limit	*Quantitation Limit
		Water	Soil
		(µg/L)	(µg/kg)
Halogenated Compounds (SW8010)			
and Aromatic Compounds (SW8020)			
Chloromethane		0.5	0.5
Bromomethane		0.5	0.5
Dichlorodifluoromethane		0.5	0.5
Vinyl Chloride		0.5	0.5
Chloroethane		0.5	0.5
Methylene Chloride		0.5	0.5
Trichlorofluoromethane		0.5	0.5
1,1-Dichloroethene		0.5	0.5
1,1-Dichloroethane		0.5	0.5
trans-1,2-Dichloroethene		0.5	0.5
Chloroform		0.5	0.5
1,2-Dichloroethane		0.5	0.5
1,1,1-Trichloroethane		0.5	0.5
Carbon Tetrachloride		0.5	0.5
Bromodichloromethane		0.5	0.5
1,2-Dichloropropane		0.5	0.5
trans-1,3-Dichloropropene		0.5	0.5
Trichloroethene		0.5	0.5
Dibromochloromethane		0.5	0.5
1,1,2-Trichloroethane		0.5	0.5
2-Chloroethylvinyl Ether		0.5	0.5
Bromoform		0.5	0.5
1,1,2,2-Tetrachloroethane		0.5	0.5
Tetrachloroethene		0.5	0.5
Chlorobenzene		0.5	0.5
1,1,1,2-Tetrachloroethane		0.5	0.5
Benzene		0.5	0.5
Chlorobenzene		0.5	0.5
1,2-Dichlorobenzene		0.5	0.5
1,3-Dichlorobenzene		0.5	0.5
1,4-Dichlorobenzene		0.5	0.5
Ethylbenzene		0.5	0.5
Toluene		0.5	0.5
m-Xylene and p-Xylene		0.5	0.5

**TABLE H.2 (DataChem Laboratories) -Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH**

Parameter (method)	Sample	Sample
	*Quantitation Limit Water (µg/L)	*Quantitation Limit Soil (µg/kg)
Halogenated Compounds (SW8010) and Aromatic Compounds (SW8020)		
o-Xylene and Styrene	0.5	0.5
Semivolatile Organic Compounds (SW8270)		
N-Nitroso-Dimethylamine	10.0	660.0
Phenol	10.0	660.0
bis (2-Chloroethyl) ether	10.0	660.0
2-Chlorophenol	10.0	660.0
1,3-Dichlorobenzene	10.0	660.0
1,4-Dichlorobenzene	10.0	660.0
Benzyl Alcohol	20.0	1300.0
1,2-Dichlorobenzene	10.0	660.0
2-Methylphenol	10.0	660.0
bis (2-Chloroisopropyl) ether	10.0	660.0
4-Methylphenol	10.0	660.0
N-Nitroso-Di-n-Propylamine	10.0	660.0
Hexachloroethane	10.0	660.0
Nitrobenzene	10.0	660.0
Isophorone	10.0	660.0
2-Nitrophenol	10.0	660.0
2,4-Dimethylphenol	10.0	660.0
bis (2-Chloroethoxy) methane	10.0	660.0
2,4-Dichlorophenol	10.0	660.0
Benzoic Acid	50.0	3300.0
1,2,4-Trichlorobenzene	10.0	660.0
Napthalene	10.0	660.0
4-Chloroaniline	20.0	660.0
Hexachlorobutadiene	10.0	660.0
4-Chloro-3-Methylphenol	20.0	1300.0
2-Methylnapthalene	10.0	660.0
Hexachlorocyclopentadiene	10.0	660.0
2,4,6-Trichlorophenol	10.0	660.0
2,4,5-Trichlorophenol	10.0	660.0

TABLE H.2 (DataChem Laboratories) -Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	Sample	Sample
		*Quantitation Limit	*Quantitation Limit
		Water	Soil
		(µg/L)	(µg/kg)
Semivolatile Organic Compounds (SW8270)			
2-Chloronaphthalene		10.0	660.0
2-Nitroaniline		50.0	3300.0
Dimethylphthalate		10.0	660.0
Acenaphthylene		10.0	660.0
2,6-Dinitrotoluene		10.0	660.0
3-Nitroaniline		50.0	3300.0
Acenaphthene		10.0	660.0
2,4-Dinitrophenol		50.0	3300.0
Dibenzofuran		10.0	660.0
4-Nitrophenol		25.0	3300.0
2,4-Dinitrotoluene		10.0	660.0
Fluorene		10.0	660.0
Diethylphthalate		10.0	660.0
4-Chlorophenol-phenylether		10.0	660.0
4-Nitroaniline		50.0	3300.0
4,6-Dinitro-2-Methylphenol		50.0	3300.0
N-Nitrosodiphenylamine		10.0	660.0
4-Bromophenyl-phenylether		10.0	660.0
Hexachlorobenzene		10.0	660.0
Pentachlorophenol		50.0	3300.0
Phenanthrene		10.0	660.0
Anthracene		10.0	660.0
Di-n-Butylphthalate		10.0	660.0
Fluoranthene		10.0	660.0
Pyrene		10.0	660.0
Butylbenzylphthalate		10.0	660.0
Benzo (a) Anthracene		10.0	660.0
3,3-Dichlorobenzadiene		20.0	1300.0
Chrysene		10.0	660.0
bis (2-Ethylhexyl) Phthalate		10.0	660.0
Di-n-octylphthalate		10.0	660.0
Benzo (b) Fluoranthene		10.0	660.0
Benzo (k) Fluoranthene		10.0	660.0
Benzo (a) Pyrene		10.0	660.0

TABLE H.2 (DataChem Laboratories) -Continued
TARGET COMPOUNDS AND DETECTION LIMITS
151st AREFG UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	(method)	Sample	Sample
		*Quantitation Limit	*Quantitation Limit
		Water	Soil
		(µg/L)	(µg/kg)
Semivolatile Organics (SW8270)			
Ideno (1,2,3-cd) Pyrene		10.0	660.0
Dibenz (a,h) Anthracene		10.0	660.0
Benzo (g,h,i) Perylene		10.0	660.0
Priority-Pollutant Metals			
Antimony (SW6010)		NA	NA
Arsenic (SW7060)		NA	NA
Beryllium (SW6010)		NA	NA
Cadmium (SW6010)		NA	NA
Chromium (SW6010)		NA	NA
Copper (SW6010)		NA	NA
Lead (SW7421)		NA	NA
Mercury (SW7470/7471)		NA	NA
Nickel (SW6010)		NA	NA
Selenium (SW7740)		NA	NA
Silver (SW6010)		NA	NA
Thallium (SW7841)		NA	NA
Zinc (SW6010)		NA	NA
TRPH (E418.1)		100.0	10000.0
Pesticides/PCB (SW8080)			
Parameter			
Aldrin		0.05	1.70
Alpha-BHC		0.05	1.70
Beta-BHC		0.05	1.70
Delta-BHC		0.10	1.70
Lindane		0.05	1.70
Chlordane		0.10	4.70
4,4'-DDD		0.10	3.30

**TABLE H.2 (DataChem Laboratories) -Continued
 TARGET COMPOUNDS AND DETECTION LIMITS
 151st AREFG UTAH AIR NATIONAL GUARD
 SALT LAKE CITY INTERNATIONAL AIRPORT
 SALT LAKE CITY, UTAH**

Parameter (method)	Sample	Sample
	*Quantitation Limit Water (µg/L)	*Quantitation Limit Soil (µg/kg)
Pesticides/PCB (SW8080)		
4,4-DDE	0.05	3.30
4,4-DDT	0.10	3.30
Dieldrin	0.05	3.30
Endosulfan I	0.10	1.70
Endosulfan II	0.05	3.30
Endosulfan Sulfate	0.50	3.30
Endrin	0.10	3.30
Endrin Aldehyde	0.20	3.30
Heptachlor	0.05	1.70
Heptachlor Epoxide	1.00	1.70
Toxaphene	2.00	170.0
Aroclor-1016	1.00	33.0
Aroclor-1221	1.00	33.0
Aroclor-1232	1.00	33.0
Aroclor-1242	1.00	33.0
Aroclor-1248	1.00	33.0
Aroclor-1254	1.00	33.0
Aroclor-1260	1.00	33.0
Methoxychlor	2.00	17.0

* Lowest quantification limits established by the analytical laboratory.

NA Not applicable; detection limits varied, see data tables for limits.

APPENDIX I
HYDROGEOLOGICAL METHODS AND DATA

APPENDIX I

TABLE OF CONTENTS

I.1	Field Methods	I-1
I.2	Methods of Analysis	I-2
I.3	Slug Test Results	I-4
I.4	Hydraulic Conductivity, Flow Rates, and Velocities.....	I-5

LIST OF TABLES

Table I.1	Hydraulic Conductivity of the Porous Media in the Screened Interval of IRP Site Monitoring Wells.....	I-7
Table I.2	Average Hydraulic Conductivity, Hydraulic Gradient, Flow Rate, and Flow Velocity.....	I-8
AQTESOLV Reports		I-9

APPENDIX I

HYDROGEOLOGICAL METHODS AND DATA

I.1 FIELD METHODS

Hydraulic conductivity was measured at 12 monitoring wells installed at seven sites at the UANG Base in March 1993. Slug test data were collected with an In-Situ Inc.-brand Hermit Environmental Data Logger (model 1000C) using an In-Situ Inc. level-type pressure transducer (Model PXD 260). The quadratic coefficients of the transducer used for the slug tests were: scale-19.836, offset-0.168, and linearity-0.105. An accuracy test was performed on the transducer prior to conducting slug tests in the field. The test involved marking one foot intervals on the line, then taking depth readings as the transducer was pulled up to each mark. The total difference after 3 readings, or 3 feet total, was only about 1 %. This difference incorporates human error in the precision of measurement. Human error is probably more significant than the mechanical variation in the transducer.

The pressure transducer was allowed to thermally equilibrate with monitoring well groundwater for about 10 to 15 minutes before conducting the slug tests. The reference datum for the tests was the static water level (SWL). The data logger setting was top of casing (TOC) for the tests and the SWL option was set to zero so that positive displacement was measured into the well from the SWL (0 foot datum). The log time setting was used on the data logger so that early time-recovery data were clearly distinguishable on the resulting graphs (this is important for aquifers anticipated to have relatively high hydraulic conductivity values).

The slug tests were conducted by suddenly removing a volume of water from the wells and then measuring the time-recovery of the static water level using the data logger and pressure transducer. A slug bailer with a volume of approximately 1.1 linear feet in a 2-inch-diameter well was used to remove the volume of water. A removed volume of 1.1 linear feet of well was generally about 10 % of the total well volume (10-foot water column). This volume is in agreement with examples given by Bouwer and Rice (1976). After putting the slug bailer into the wells, the displaced static water level was allowed to equilibrate prior to conducting the tests. Once the water level subsided to the original level, one bailer volume was suddenly removed, and the test was initiated. Only slug withdrawal tests were performed.

I.2 METHODS OF ANALYSIS

The Bouwer and Rice method (1976) was used to generate hydraulic conductivity (K) values from the slug test data. Calculations were automated using AQTESOLV™ computer software version 1.1 (Geraghty and Miller Modeling Group, 1991).

The Bouwer and Rice (1976) slug test method permits measurement of the saturated hydraulic conductivity (K) of aquifer porous media at an effective radial distance from the test well and is based on observations from a single test well. The basis of the method is a time-recovery relationship that measures the response of the aquifer to a sudden withdrawal or injection of a slug of water. The method was developed from a series of analog tests and uses both theory and empirically derived coefficients (Bouwer and Rice, 1976). This method is applicable to a wide range of well geometries and is applicable to completely or partially penetrating wells in an unconfined aquifer. The Bouwer and Rice (1976) method may also be used for slug tests on wells in confined aquifers if water enters the aquifer from the upper confining layer through compression or leakage (Bouwer and Rice, 1976).

The governing equation (1) of the Bouwer and Rice (1976) slug test method is a modification of the Theim (1906) equation of steady state flow to wells. The assumptions are that (1) drawdown of the water table around the well is negligible, (2) flow in the capillary fringe above the saturated zone can be ignored, (3) head losses as water enters the well are negligible, and (4) the aquifer is homogeneous and isotropic. A definition of terms and a schematic for equation (1) follow.

GOVERNING EQUATION:

$$\ln s_o - \ln s_t = \frac{2KLt}{r_c^2 \ln(r_e/r_w)} \quad (1)$$

where:

- s_o = initial drawdown in well due to instantaneous removal of water from well [L]
- s_t = drawdown in well at time (t) [L]
- L = length of well screen [L]
- r_c = radius of well casing [L]
- $\ln(r_e/r_w)$ = empirical "shape factor" determined from tables provided in Bouwer and Rice (1976)
- r_e = equivalent radius over which head loss occurs [L]
- r_w = radius of well (including gravel pack) [L]
- H = static height of water in well [L]
- b = saturated thickness of aquifer [L]

The slug test field data should yield a straight line when plotted as $\ln s_r$ (residual drawdown) versus time (t). The term $(1/t) \ln (s_o/s_r)$ in equation (2) is then obtained from the best-fitting straight line plot of residual drawdown (s_r) versus time (t). The value of $\ln (r_e/r_w)$ is dependent on H , L , b , and r_w and is evaluated from empirically-derived curves and related coefficients (Bouwer and Rice, 1976). The hydraulic conductivity (K) is then obtained from equation (2).

The time-recovery data were imported from the data logger to an input file for AQTESOLV. The Bouwer and Rice (1976) method was chosen for hydraulic conductivity calculations. The data parameters H , L , b , r_w , and r_c are manually input into the AQTESOLV program for each individual test, and the program calculates coefficients and the resulting function $\ln(r_e/r_w)$. The program automatically plots the time-recovery curve on screen and then the best-fit straight line is automatically or manually matched to the curve. After the straight line segment is matched to the time-recovery data, the program is executed, and the hydraulic conductivity is calculated from the input parameters.

The value of hydraulic conductivity is sensitive to the slope of the curve-matched straight line. Therefore, proper orientation of the best fit straight line to the time-recovery data is imperative to obtaining precise and accurate values of hydraulic conductivity. Review of the governing equation (1) and sensitivity tests of Bouwer and Rice (1976) input parameters conducted during AQTESOLV program execution indicates that the analysis is most sensitive to the parameters of well screen length (L) and the well casing radius (r_c), and is less affected by the static height of the water in the well (H), the saturated aquifer thickness (b), and the radius of the well plus gravel pack (r_w).

1.3 SLUG TEST RESULTS

The indication of a good slug test is a definite straight line segment in the initial time-recovery data curve. AQTESOLV generated slug test time-recovery curves and results for the UANG IRP site monitoring wells are presented at the end of this appendix. An examination of the curves indicates that the field slug test results are precise and accurate within the constraints of the analytical method. Some hydraulic conductivity values were also calculated manually as a means of validating the AQTESOLV software. Manual calculations were in agreement with AQTESOLV solutions.

It is possible to get two distinct straight-line segments in the time-recovery curves. This is the result of well borehole effects caused by a higher hydraulic conductivity of the sand or gravel pack relative to the aquifer media (Bouwer, 1989). In this case, the first straight-line segment is steeper (greater slope) than the second straight-line segment. The second straight-line segment is then representative of the aquifer formation hydraulic conductivity. This segment represents the test interval after water contained in the gravel pack reaches equilibrium with the water in the well casing and flow to the well slows down. Separate and distinct straight-line segments are not apparent in the time-recovery curves of the UANG slug tests, and sand pack effects are not manifest on the curves. In

fact, some of the formation hydraulic conductivity values may equal or exceed the hydraulic conductivity of the 20-40 Colorado silica sand pack used in construction of the monitoring wells.

The value of y_0 (s_0 by definition in the equations and schematic above) on the AQTESOLV generated time-recovery curves and results diagrams provided at the end of this appendix is the y-intercept of the curve-matched straight line and represents the best-fit line drawdown at time zero. The value of H_0 on the diagrams is the input value of y_0 (removed slug bailer volume), and has no bearing on the solution. The values of the other input parameters are given on the diagrams. The definition of these terms was discussed above and is presented in the equations and schematic. Where the static height of water in the well (H) of the screen is less than the intake length of the well screen (L), the value of (L) is equal to (H). Generally, the value of (H) was greater than (L) for the tests; ie., the water level was above the top of the screen in the cased portion of the monitoring wells. The saturated thickness of the aquifer (b) is the least-exact input parameter for these analyses, but as stated above, the Bouwer and Rice (1976) solution for the site well geometries is not that sensitive to (b). The saturated thickness (b) is considered to be the vertical distance between the first extensive clay layer beneath the base and the static water level. The top of this clay layer is considered an impermeable boundary for calculations and is contacted at an average depth of approximately 20 feet BLS.

I.4 HYDRAULIC CONDUCTIVITY, FLOW RATES, AND VELOCITIES

Aquifer hydraulic conductivities in the vicinity of UANG IRP site monitoring wells are given in Table I.1. Results of the tests indicate a significant variation in hydraulic conductivity values at the wells, and therefore, variation in aquifer properties at the Base. Although slug tests yield only an estimation of aquifer hydraulic conductivity, the relative difference in hydraulic conductivity values obtained from slug tests at the site wells is considered to represent true spatial variation in aquifer properties.

An examination of Darcy's equation ($Q=KiA$) shows that the value of hydraulic conductivity (K), also called the proportionality constant, is a controlling factor in the determination of volumetric flow rate (Q). Because of the variation in (K) at the Base, the flow rate at the sites is also highly variable. However, since the value of (K) in Darcy's Law is constant and the cross-sectional area of saturated flow (A) is nearly constant, the hydraulic gradient (i) which is variable and is the most dynamic factor, is the driving mechanism of groundwater flow.

The volumetric flow rates (q) per unit width of saturated aquifer thickness (b) were calculated for the sites based on the temporal hydraulic gradients measured on 16 March 1993. Results are presented in Table I.2. The hydraulic conductivity value used in calculating the flow rates is the average (K) of the aquifer between the wells of concern at each site. The hydraulic gradient was established in a flow path perpendicular to

groundwater elevation equipotentials at the monitoring wells. Groundwater flow rates at the Base are subject to change as the hydraulic gradients change.

The velocity of groundwater flow is proportional to the hydraulic gradient and hydraulic conductivity, according to Darcy's Law. Groundwater flow velocities (v) are estimated by the equation ($v=Ki/n$), but velocities may be less accurate than volumetric flow rates due to an assumption for the effective porosity (n). When calculating flow velocities through a porous medium, the effective porosity is used to modify the amount of aquifer surface area available for flow. This is because water only moves through connected pore space making up the surface area. Examination of the equation ($v=Ki/n$) shows that the true velocity, or average linear velocity (v), increases with decreasing effective porosity (n). A generally-assumed value of effective porosity for unconsolidated sediments is 30 %. Fetter (1988) suggests that the effective porosity and total porosity (ratio of the total void volume to total volume) are virtually the same for most sediments. In other words, nearly all of the porosity or void space in a sediment is available for groundwater flow.

Values of average linear velocity were calculated notwithstanding the effective porosity assumption. Estimated groundwater flow velocities (v) for the values of (K) and (i) given in Table I.2 were determined from the equation ($v=Ki/n$); where (n) is the effective porosity. At Site 3 for example, considering the calculated average hydraulic conductivity (K) of 36.9 ft/day and a hydraulic gradient of 2.0×10^{-3} ft/ft, the corresponding average linear velocity was approximately 0.25 ft/day, assuming an effective porosity of 30 %. The actual porosities of sands may be less than 30%, and the porosities of silts and clays may be greater than 30%. Therefore, the actual average linear velocity of groundwater at the sites may be greater (sand) or less than (silts and clays) the calculated values, depending on the actual porosities of the saturated aquifer sediments at each of the sites.

TABLE I.1
HYDRAULIC CONDUCTIVITY OF THE POROUS MEDIA
IN THE SCREENED INTERVAL OF IRP SITE MONITORING WELLS
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Well	Hydraulic Conductivity (K) (ft/min)	Hydraulic Conductivity(K) (ft/day)
BGMW1	3.83E-03	4.26
BGMW2	1.33E-03	1.91
S1MW1	2.29E-03	3.30
S2MW2	3.71E-03	5.34
S2MW1	1.17E-04	0.17
S2MW2	2.38E-03	3.42
S3MW1	1.63E-02	23.40
S3MW2	3.50E-02	50.41
S4MW1	9.99E-04	1.44
S5MW1	1.48E-02	21.28
S6MW1	2.97E-03	4.28
S6MW2	1.42E-03	2.04
S6MW3	3.47E-03	5.00
S6MW4	1.62E-03	2.34
S6MW5	4.90E-03	7.06
S7MW1	7.83E-04	1.13
S7MW2	2.96E-03	5.52
Mean K =	5.82E-03	8.37
St Dev	8.79E-03	12.65

TABLE I.2
AVERAGE HYDRAULIC CONDUCTIVITY,
HYDRAULIC GRADIENT, FLOW RATE, AND FLOW VELOCITY
16 MARCH 1993
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Site	Average Hydraulic Conductivity (K) (ft./day)	Flow Path Distance Between Wells (dl) (ft.)	Change in Head Between Wells (dh) (ft.)	Hydraulic Gradient ($i=dh/dl$) (ft./ft.)	Average Saturated Aquifer Thickness (b) (ft.)	Flow Rate per Unit Width (q) (ft. ³ /day/ft.)	Average Linear Velocity (v) (ft./day)
Fuel Spill (Site 2) S1MW1-S2MW1	1.74	85.0	0.14	1.65×10^{-3}	15.40	4.41×10^{-2}	0.01
Drum Burial (Site 3) S3MW1-S3MW2	36.90	100	0.20	2.0×10^{-3}	18.50	1.37	0.25
Fire TNG - Area 1 (Site 4) S7MW1-S4MW1	1.29	180	0.01	5.56×10^{-5}	15.50	1.11×10^{-3}	2.39×10^{-4}
Ramp Washdown (Site 6) S6MW2-S6MW3	3.52	650	0.99	1.52×10^{-3}	13.75	7.36×10^{-2}	0.02
Oil Sludge Pond (Site 7) S7MW2-S7MW1	3.33	210	0.35	1.67×10^{-3}	15.00	8.34×10^{-2}	0.02

note: $q = (Kib)$; where q = volumetric flow rate per unit width of aquifer,

K = hydraulic conductivity, i = hydraulic gradient, and b = saturated aquifer thickness

$v = K/i/n$; where v = average linear velocity, K = hydraulic conductivity, i = hydraulic gradient, and n = effective porosity; $n = 30\%$ for all calculations.


ENGINEERING-SCIENCE, INC.

Client: MARTIN MARIETTA

Project No.: UT014

Location: UANG IRP SITE 1

UANG SITE 1 MW1 SLUG TEST



DATA SET:
UAGS1MW1.DAT
03/25/93

AQUIFER TYPE:
Unconfined
SOLUTION METHOD:
Bouwer-Rice
TEST DATE:
3/4/93
TEST WELL:
MW1

ESTIMATED PARAMETERS:
 $K = 0.002291$ ft/min
 $y_0 = 0.6978$ ft

TEST DATA:
 $H_0 = 1.$ ft
 $r_c = 0.083$ ft
 $r_w = 0.427$ ft
 $L = 10.$ ft
 $b = 15.$ ft
 $H = 10.$ ft

ENGINEERING-SCIENCE, INC.	Client: MARTIN MARIETTA
Project No.: UT014	Location: UANG IRP SITE 1
<div data-bbox="446 94 1445 577"> <div data-bbox="446 94 475 577"> DATA SET: uags1mw2.aqt 09/08/95 </div> <div data-bbox="475 94 505 577"> AQUIFER TYPE: Unconfined </div> <div data-bbox="505 94 534 577"> SOLUTION METHOD: Bouwer-Rice </div> <div data-bbox="534 94 563 577"> TEST DATE: 9/06/95 </div> <div data-bbox="563 94 592 577"> TEST WELL: MW2 </div> <div data-bbox="592 94 660 577"> ESTIMATED PARAMETERS: K = 0.003706 ft/min y0 = 1.872 ft </div> <div data-bbox="660 94 729 577"> TEST DATA: H0 = 1. ft rc = 0.083 ft rw = 0.344 ft L = 7.66 ft b = 13.8 ft H = 7.66 ft </div> </div> <div data-bbox="446 577 1445 1957"> <div data-bbox="446 577 1445 1957"> </div> </div>	


ENGINEERING—SCIENCE, INC.


Client: MARTIN MARIETTA

Project No.: UT014

Location: UANG IRP SITE 2

UANG SITE 2 MW1 SLUG TEST






ENGINEERING-SCIENCE, INC.

Client: MARTING MARIETTA

Project No.: UT014

Location: UANG IRP SITE 3

UANG SITE 3 MW1 SLUG TEST




DATA SET:
UAGS3MW1.DAT
03/24/93

AQUIFER TYPE:
Unconfined
SOLUTION METHOD:
Bouwer-Rice
TEST DATE:
3/10/93
TEST WELL:
MW1


ESTIMATED PARAMETERS:
 $K = 0.01625 \text{ ft/min}$
 $y_0 = 1.679 \text{ ft}$


TEST DATA:
 $H_0 = 1. \text{ ft}$
 $r_c = 0.083 \text{ ft}$
 $r_w = 0.427 \text{ ft}$
 $L = 10. \text{ ft}$
 $b = 17. \text{ ft}$
 $H = 14.25 \text{ ft}$



ENGINEERING-SCIENCE, INC.	Client: MARTIN MARIETTA
Project No.: UT014	Location: UANG IRP SITE 4


UANG SITE 4 MW1 SLUG TEST





ENGINEERING-SCIENCE, INC.	Client: MARTING MARIETTA
Project No.: UT014	Location: UANG IRP SITE 6

UANG SITE 6 MW1 SLUG TEST



ENGINEERING-SCIENCE, INC.		Client: MARTIN MARIETTA							
Project No.: UT014		Location: UANG IRP SITE 6							
<p align="center">UANG SITE 6 MW2 SLUG TEST</p>									
<table border="1"> <tr> <td> <p>DATA SET: UAGS6MW2.DAT 03/25/93</p> </td> <td rowspan="3"> </td> </tr> <tr> <td> <p>AQUIFER TYPE: Unconfined</p> <p>SOLUTION METHOD: Bouwer-Rice</p> <p>TEST DATE: 3/8/93</p> <p>TEST WELL: MW2</p> </td> </tr> <tr> <td> <p>ESTIMATED PARAMETERS: K = 0.001416 ft/min y0 = 0.7946 ft</p> </td> </tr> <tr> <td colspan="2"> <p>TEST DATA: H0 = 1. ft rc = 0.083 ft rw = 0.427 ft L = 9.6 ft b = 15. ft H = 9.6 ft</p> </td> <td></td> </tr> </table>			<p>DATA SET: UAGS6MW2.DAT 03/25/93</p>		<p>AQUIFER TYPE: Unconfined</p> <p>SOLUTION METHOD: Bouwer-Rice</p> <p>TEST DATE: 3/8/93</p> <p>TEST WELL: MW2</p>	<p>ESTIMATED PARAMETERS: K = 0.001416 ft/min y0 = 0.7946 ft</p>	<p>TEST DATA: H0 = 1. ft rc = 0.083 ft rw = 0.427 ft L = 9.6 ft b = 15. ft H = 9.6 ft</p>		
<p>DATA SET: UAGS6MW2.DAT 03/25/93</p>									
<p>AQUIFER TYPE: Unconfined</p> <p>SOLUTION METHOD: Bouwer-Rice</p> <p>TEST DATE: 3/8/93</p> <p>TEST WELL: MW2</p>									
<p>ESTIMATED PARAMETERS: K = 0.001416 ft/min y0 = 0.7946 ft</p>									
<p>TEST DATA: H0 = 1. ft rc = 0.083 ft rw = 0.427 ft L = 9.6 ft b = 15. ft H = 9.6 ft</p>									

ENGINEERING-SCIENCE, INC.

Client: MARTIN MARIETTA

Project No.: UT014

Location: UANG IRP SITE 6


UANG SITE 6 MW3 SLUG TEST

DATA SET:
UAGS6MW3.DAT
03/25/93

AQUIFER TYPE:
Unconfined
SOLUTION METHOD:
Bouwer-Rice
TEST DATE:
3/8/93
TEST WELL:
MW3

ESTIMATED PARAMETERS:
 $K = 0.003472$ ft/min
 $y_0 = 0.6323$ ft

TEST DATA:
 $H_0 = 1.$ ft
 $r_c = 0.083$ ft
 $r_w = 0.427$ ft
 $L = 7.37$ ft
 $b = 12.5$ ft
 $H = 7.37$ ft



ENGINEERING-SCIENCE, INC.		Client: MARTIN MARIETTA	
Project No.: UT014		Location: UANG IRP SITE 6	
<p align="center">UANG SITE 6 MW4 SLUG TEST</p>			
<p>DATA SET: uags6mw4.aqt 09/08/95</p>		<p>AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: 9/06/95 TEST WELL: MW4</p>	
<p>ESTIMATED PARAMETERS: K = 0.001623 ft/min y0 = 1.708 ft</p>		<p>TEST DATA: H0 = 1. ft rc = 0.083 ft rw = 0.344 ft L = 8.43 ft b = 14. ft H = 8.43 ft</p>	

ENGINEERING-SCIENCE, INC.

Client: MARTIN MARIETTA

Project No.: UT014

Location: UANG IRP SITE 6

UANG SITE 6 MW5 SLUG TEST


DATA SET:
uags6mw5.aqt
09/08/95

AQUIFER TYPE:
Unconfined
SOLUTION METHOD:
Bouwer-Rice

TEST DATE:
9/06/95
TEST WELL:
MW5

ESTIMATED PARAMETERS:
 $K = 0.004904$ ft/min
 $y_0 = 1.537$ ft

TEST DATA:
 $H_0 = 1.$ ft
 $r_c = 0.083$ ft
 $r_w = 0.344$ ft
 $L = 6.89$ ft
 $b = 13.$ ft
 $H = 6.89$ ft



ENGINEERING—SCIENCE, INC.		Client: MARTIN MARIETTA	
Project No.: UT014		Location: UANG IRP SITE 7	
<div>UANG SITE 7 MW1 SLUG TEST</div>			
DATA SET: UAGS7MW1.DAT 03/25/93		AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: 3/9/93 TEST WELL: MW1	
ESTIMATED PARAMETERS: $K = 0.0007826 \text{ ft/min}$ $y_0 = 1.103 \text{ ft}$		TEST DATA: $H_0 = 1. \text{ ft}$ $r_c = 0.083 \text{ ft}$ $r_w = 0.427 \text{ ft}$ $L = 10. \text{ ft}$ $b = 15. \text{ ft}$ $H = 10.45 \text{ ft}$	
<p>Displacement (ft)</p> <p>Time (min)</p>			

ENGINEERING-SCIENCE, INC.		Client: MARTIN MARIETTA						
Project No.: UT014		Location: UANG IRP SITE 7						
<p align="center">UANG SITE 7 MW2 SLUG TEST</p>								
<table border="1"> <tr> <td> DATA SET: UAGS7MW2.DAT 03/25/93 </td> <td> AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: 3/9/93 TEST WELL: MW2 </td> <td> ESTIMATED PARAMETERS: $K = 0.003832 \text{ ft/min}$ $y_0 = 0.5561 \text{ ft}$ </td> </tr> <tr> <td colspan="3"> TEST DATA: $H_0 = 1. \text{ ft}$ $r_c = 0.083 \text{ ft}$ $r_w = 0.427 \text{ ft}$ $L = 10. \text{ ft}$ $b = 15. \text{ ft}$ $H = 10.05 \text{ ft}$ </td> </tr> </table>			DATA SET: UAGS7MW2.DAT 03/25/93	AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: 3/9/93 TEST WELL: MW2	ESTIMATED PARAMETERS: $K = 0.003832 \text{ ft/min}$ $y_0 = 0.5561 \text{ ft}$	TEST DATA: $H_0 = 1. \text{ ft}$ $r_c = 0.083 \text{ ft}$ $r_w = 0.427 \text{ ft}$ $L = 10. \text{ ft}$ $b = 15. \text{ ft}$ $H = 10.05 \text{ ft}$		
DATA SET: UAGS7MW2.DAT 03/25/93	AQUIFER TYPE: Unconfined SOLUTION METHOD: Bouwer-Rice TEST DATE: 3/9/93 TEST WELL: MW2	ESTIMATED PARAMETERS: $K = 0.003832 \text{ ft/min}$ $y_0 = 0.5561 \text{ ft}$						
TEST DATA: $H_0 = 1. \text{ ft}$ $r_c = 0.083 \text{ ft}$ $r_w = 0.427 \text{ ft}$ $L = 10. \text{ ft}$ $b = 15. \text{ ft}$ $H = 10.05 \text{ ft}$								
<p>Displacement (ft)</p> <p>Time (min)</p>								

APPENDIX J
SOIL GAS CORRELATION

APPENDIX J

SOIL GAS CORRELATION

A comparison between the data from the analysis of the soil gas in soil boring samples by the field gas chromatograph (GC) and the actual laboratory analytical data from DataChem and ES Berkeley Laboratories was made to determine if there was a correlation between the GC data and laboratory data. These data were statistically compared to determine a correlation coefficient.

The comparison was made by assembling all of the data into two separate columns. All the data from Sites 1 to 7 were grouped into four tables subdivided by each analyte: benzene, toluene, ethylbenzene, and xylenes. The results of the soil gas analysis were placed in one column and the laboratory analysis for the same interval were placed in the second column. The pairs of data in which both components were zeros were removed from the list. Any datum with either number greater than zero remained on the list.

A variance and standard deviation was calculated on each column of remaining data. The variance is viewed as the average squared deviation of all possible observations from the population mean. The standard deviation provides a statistic that describes dispersion or spread of data around the mean (Davis, 1986). A small standard deviation would indicate little variance around the mean. A large standard deviation would indicate that the observations are widely scattered. Overall, the standard deviations for the soil gas appeared to be relatively small indicating that the majority of the observations are clustered around the mean. However, the soil analytical indicates large deviations from the mean for both ethylbenzene and xylenes.

The covariance was also calculated for both sets of data. The covariance is defined as the joint variation of two variables about their common mean and measures the distribution of values surrounding a common mean. The problem with interpreting variances and covariances is that individual measurements are not very significant because they are dependent on the units of measurement.

The correlation coefficient, denoted as r , is the estimation of a relationship between two variables. This coefficient is independent of measurement. The correlation coefficient is expressed as a ratio and is a unitless number. The covariance can equal but may not exceed the standard deviations of its constituents. Therefore, the correlation coefficient ranges from +1 to -1. A correlation of +1 indicates a perfectly accurate relationship between the constituents; a correlation of -1 indicates that one constituent changes inversely with the other. A correlation of zero indicates that there is no relationship between the constituents whatsoever. Between the endpoints of +1 and -1 exist a number of other possibilities which are less than perfect.

FINAL

The correlation coefficients for benzene, toluene, ethylbenzene, and xylenes ranged between -0.12381 and +0.233943. These show that the correlation is near zero for all constituents. This indicates that there is little or no relationship between the detected soil gas and the soil boring analytical results for the sites.

TABLE J.1
COMPARISON OF SOIL GAS RESULTS FROM SOIL BORING INTERVALS
AND LABORATORY RESULTS FROM CORRESPONDING INTERVALS
151st AREFG, UTAH AIR NATIONAL GUARD
SALT LAKE CITY INTERNATIONAL AIRPORT
SALT LAKE CITY, UTAH

Parameter	Range	Std. Dev.	Variance	Covariance	Corr. Coef.
Benzene					
Soil Gas (ppmv)	0-24.16	8.753509	76.624	-5.87766	-0.12381
Soil Borings (ug/kg)	0-15.0	5.423165	29.411		
Ethylbenzene					
Soil Gas (ppmv)	0-65.2	17.803	316.940	-2204.72	-0.10423
Soil Borings (ug/kg)	0-5200	1188.178	1411766.0		
Toluene					
Soil Gas (ppmv)	0-363.6	92.31373	8521.824	1217.638	0.171706
Soil Borings (ug/kg)	0-450	76.81848	5901.079		
Xylenes					
Soil Gas (ppmv)	0-188.4	59.3356	3520.713	99877.7	0.233943
Soil Borings (ug/kg)	0-30,000	7195.216	51771129.0		

ppmv-Parts per million by volume.